

AD-A231 749

DTIC FILE COPY

INSTALLATION RESTORATION PROGRAM

REMEDIAL INVESTIGATION
REPORT

MINNESOTA AIR NATIONAL GUARD BASE
DULUTH INTERNATIONAL AIRPORT
DULUTH, MINNESOTA

DISTRIBUTION STATEMENT A

Approved for public release
Distribution Unlimited

VOLUME 7

DTIC
SELECTE
FEB 20 1991
S D D



HAZWRAP SUPPORT CONTRACTOR OFFICE

Oak Ridge, Tennessee 37831

Operated by MARTIN MARIETTA ENERGY SYSTEMS, INC

For the U.S. DEPARTMENT OF ENERGY under contract DE-AC05-84OR21400

91 2 11 055

REPORT DOCUMENTATION PAGE

12-11-1989

1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE January 1990		3. REPORT TYPE AND DATES COVERED Final Remedial Investigation Report	
4. TITLE AND SUBTITLE Remedial Investigation Report Minnesota Air National Guard Base Duluth International Airport Duluth, Minnesota Volume 1-final report				5. FUNDING NUMBERS	
6. AUTHOR(S) N/A					
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Engineering-Science 710 South Illinois Ave., Suite F-103 Oak Ridge, TN				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) Hazardous Waste Remedial Actions Program Oak Ridge, TN				10. SPONSORING/MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES Air National Guard Bureau Andrews Air Force Base, Maryland 20331 Volume 2-Appendices Volume 3-Appendices Volume 4-Appendices Volume 5-Appendices Volume 6-Appendices <u>Volume 7-Appendices</u>					
12a. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution is unlimited				12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) The report describes the remedial actions performed on sites confirmed to contain hazardous waste contamination which endangers the human health. The actions performed are described and the potential for future problems. The study was conducted under the Air National Guard's Installation Restoration Program.					
14. SUBJECT TERMS Installation Restoration Program Remedial Investigation Report Minnesota Air National Guard				15. NUMBER OF PAGES	
16. SECURITY CLASSIFICATION OF REPORT Unclassified				17. SECURITY CLASSIFICATION OF THIS PAGE	
18. SECURITY CLASSIFICATION OF ABSTRACT				19. LIMITATION OF ABSTRACT	

"This report has been prepared for the Martin Marietta Energy Systems, Inc. by Engineering-Science, Inc. for the purpose of aiding in the implementation of the Department of Defense Installation Restoration Program. It is not an endorsement of any product. The views expressed herein are those of the Contractor and do not necessarily reflect the official views of the publishing agency, the United States Air National Guard, nor the Department of Defense."

REMEDIAL INVESTIGATION REPORT

MINNESOTA AIR NATIONAL GUARD BASE DULUTH INTERNATIONAL AIRPORT Duluth, Minnesota

VOLUME 7

JANUARY 1990



Prepared By
ENGINEERING-SCIENCE
710 South Illinois Ave., Suite F-103
Oak Ridge, Tennessee

Prepared For
HAZARDOUS WASTE
REMEDIAL ACTIONS PROGRAM
Oak Ridge, Tennessee

Submitted To
MINNESOTA AIR NATIONAL GUARD
Duluth International Airport
Duluth, Minnesota

Accession For	
NTIS CRASH	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution	
Availability Codes	
Dist	Availability or Special
A-1	

This page intentionally left blank.

PREFACE

Engineering-Science (ES) entered into an agreement with the HAZWRAP Support Contractor office operated by Martin Marietta Energy Systems, Inc. for the U.S. Department of Energy (DOE) to perform a Remedial Investigation at the Minnesota Air National Guard Base, Duluth International Airport, Duluth, Minnesota, to be submitted to the National Guard Bureau, Andrews Air Force Base, Maryland. This investigation was initiated in July, 1988 under Task Order Y02, General Order 18B-97387C, which is under DOE contract DE-AC05-84OR21400, with Martin Marietta Energy Systems under Interagency Agreement 1489-1489-A1. The overall objectives of this effort were to define the magnitude, extent, direction, and rate of movement of identified contaminants and to summarize the need for remedial actions based on an assessment of risks to human health and the environment.

This investigation was performed by Engineering-Science personnel from the Oak Ridge, Tennessee office with oversight provided by Martin Marietta Energy Systems. Mr. Larry Janssen, of Martin Marietta Energy Systems was the Technical Monitor for Lt. Col. Michael Washeleski of the National Guard Bureau. Major Joel D. Manns, Minnesota Air National Guard Base, Duluth, Minnesota, provided field support. Engineering-Science personnel included Mr. Robert S. McLeod, P.E., P.G., who served as Project Manager and Mr. John D. Hardeman, P.G., who served as the Field Team Leader. Mr. Robert L. Thoem, P.E. was the ES Technical Director for the project.

Engineering-Science wishes to acknowledge North Star Drilling, Little Falls, Minnesota as the drilling and well installation subcontractor. Salo Engineering, Duluth, Minnesota, provided professional surveying services. ES Berkeley Laboratory, Berkeley, California; ES Atlanta Laboratory, Atlanta, Georgia; MetaTrace, Inc., St. Louis, Missouri; NUS Corporation, Pittsburgh, Pennsylvania; and IT Radiological Sciences Laboratory, Oak Ridge, TN provided analytical laboratory services for sample analyses.

This work was accomplished between July 1988 and March 1989.

This page intentionally left blank.

TABLE OF CONTENTS

VOLUME I

	Page
LIST OF FIGURES	xvii
LIST OF TABLES	xxvii
EXECUTIVE SUMMARY	ES-1
SECTION 1 INTRODUCTION	1-1
1.1 PURPOSE OF REPORT	1-4
1.1.1 Description of Installation Restoration Program	1-4
1.1.2 Report Organization	1-6
1.2 BACKGROUND OF DULUTH AIR NATIONAL GUARD BASE	1-7
1.2.1 Description of Duluth Air National Guard Base	1-7
1.2.1.1 Physiography, Climate and Drainage	1-10
1.2.1.2 Demography and Land Use	1-13
1.2.1.3 Geology	1-16
1.2.1.4 Hydrogeology	1-17
1.2.1.5 Water Quality	1-18
1.2.1.6 Water Use	1-18
1.2.2 History of Duluth Air National Guard Base	1-26
1.2.3 Previous Investigations	1-26
1.2.4 Description and History of Site 2	1-30
1.2.4.1 Description	1-30
1.2.4.2 History	1-31
1.2.4.3 Previous Investigations	1-33
1.2.5 Description and History of Site 3	1-37
1.2.5.1 Description	1-37
1.2.5.2 History	1-43
1.2.5.3 Previous Investigations	1-43
1.2.6 Description and History of Site 4	1-45
1.2.6.1 Description	1-53
1.2.6.2 History	1-53
1.2.6.3 Previous Investigations	1-53
1.2.7 Description and History of Site 8	1-62
1.2.7.1 Description	1-62
1.2.7.2 History	1-62
1.2.7.3 Previous Investigations	1-62

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
1.2.8 Description and History of Site 10	1-68
1.2.8.1 Description	1-68
1.2.8.2 History	1-72
1.2.8.3 Previous Investigations	1-72
SECTION 2 REMEDIAL INVESTIGATION DESCRIPTION	2-1
2.1 AREA LOCATIONS	2-3
2.1.1 Surface Feature Investigation	2-9
2.1.2 Surface Water and Sediment Investigations	2-9
2.1.2.1 Background Surface Drainage Location	2-9
2.1.2.2 Airport Surface Drainage Locations	2-9
2.1.3 Geological Investigation	2-12
2.1.4 Soil Investigation	2-12
2.1.5 Ground-Water Investigation	2-12
2.1.5.1 Water Level Investigation	2-12
2.1.5.2 Ground-Water Sampling Investigation	2-15
2.2 SITE 2	2-15
2.2.1 Surface Feature Investigation	2-20
2.2.2 Surface Water and Sediment Investigations	2-20
2.2.3 Geologic Investigation	2-20
2.2.4 Soil Investigation	2-20
2.2.5 Ground-Water Investigation	2-23
2.2.5.1 Aquifer Investigation	2-23
2.2.5.2 Ground-Water Sampling Investigation	2-25
2.3 SITE 3	2-25
2.3.1 Surface Feature Investigation	2-31
2.3.2 Surface Water and Sediment Investigations	2-31
2.3.3 Geologic Investigation	2-36
2.3.4 Soil Investigations	2-36

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
2.3.5 Ground-Water Investigation	2-38
2.3.5.1 Aquifer Investigation	2-38
2.3.5.2 Ground-Water Sampling Investigation	2-41
2.4 SITE 4	2-41
2.4.1 Surface Feature Investigation	2-47
2.4.2 Surface Water and Sediment Investigations	2-47
2.4.3 Geologic Investigation	2-47
2.4.4 Soil Investigation	2-50
2.4.5 Ground-Water Investigation	2-50
2.4.5.1 Aquifer Investigation	2-50
2.4.5.2 Ground-Water Sampling Investigation	2-50
2.5 SITE 8	2-53
2.5.1 Surface Feature Investigation	2-60
2.5.2 Surface Water and Sediment Investigations	2-60
2.5.3 Geologic Investigation	2-60
2.5.4 Soil Investigations	2-63
2.5.5 Ground-Water Investigation	2-63
2.5.5.1 Aquifer Investigation	2-63
2.5.5.2 Ground-Water Sampling Investigation	2-66
2.6 SITE 10	2-66
2.6.1 Surface Feature Investigation	2-66
2.6.2 Ground-Water Investigation	2-66
2.6.2.1 Aquifer Investigation	2-69
2.6.2.2 Ground-Water Sampling Investigation	2-69
SECTION 3 INVESTIGATION RESULTS	3-1
3.1 AREA LOCATIONS	3-3
3.1.1 Surface Features	3-3
3.1.2 Surface Water Hydrology	3-3

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
3.1.3 Geology	3-7
3.1.4 Hydrogeology	3-11
3.2 SITE 2	3-11
3.2.1 Surface Features	3-11
3.2.2 Surface Water Hydrology	3-18
3.2.3 Geology	3-21
3.2.4 Hydrogeology	3-22
3.3 SITE 3	3-29
3.3.1 Surface Features	3-29
3.3.2 Surface Water Hydrology	3-30
3.3.3 Geology	3-30
3.3.4 Hydrogeology	3-32
3.4 SITE 4	3-41
3.4.1 Surface Features	3-41
3.4.2 Surface Water Hydrology	3-41
3.4.3 Geology	3-43
3.4.4 Hydrogeology	3-44
3.5 SITE 8	3-48
3.5.1 Surface Features	3-50
3.5.2 Surface Water Hydrology	3-50
3.5.3 Geology	3-50
3.5.4 Hydrogeology	3-53
3.6 SITES 3, 4, 8	3-56
3.6.1 Surface Features	3-56
3.6.2 Surface Water Hydrology	3-56

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
3.6.3 Geology	3-65
3.6.4 Hydrogeology	3-67
3.7 SITE 10	3-72
3.7.1 Surface Features	3-72
3.7.2 Surface Water Hydrology	3-78
3.7.3 Geology	3-78
3.7.4 Hydrogeology	3-78
SECTION 4 NATURE AND EXTENT OF CONTAMINATION	4-1
4.1 DEFINITION OF BACKGROUND CONDITIONS	4-3
4.1.1 Surface Water and Sediment Quality	4-4
4.1.2 Soil Quality	4-4
4.1.3 Ground-Water Quality	4-4
4.2 AIRPORT AREA SURFACE WATER AND SEDIMENT SAMPLES	4-8
4.2.1 Airport Area Surface Water and Sediment Quality	4-8
4.2.2 Extent of Airport Area Contamination	4-11
4.3 NATURE AND EXTENT OF CONTAMINATION AT SITE 2	4-11
4.3.1 Source of Contamination	4-14
4.3.2 Surface Water and Sediment Contamination	4-14
4.3.2.1 Surface Water and Sediment Quality	4-14
4.3.2.2 Extent of Surface Water and Sediment Contamination	4-14
4.3.3 Soil Contamination	4-17
4.3.3.1 Soil Quality	4-17
4.3.3.2 Extent of Soil Contamination	4-21
4.3.4 Ground-Water Contamination	4-21
4.3.4.1 Ground-Water Quality	4-21
4.3.4.2 Extent of Ground-water Contamination	4-24

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
4.4 NATURE AND EXTENT OF CONTAMINATION AT SITE 3	4-29
4.4.1 Source of Contamination	4-29
4.4.2 Soil Gas Survey Results	4-29
4.4.3 Surface Water and Sediment Contamination	4-29
4.4.3.1 Surface Water and Sediment Quality	4-30
4.4.3.2 Extent of Surface Water and Sediment Contamination	4-35
4.4.4 Soil Contamination	4-35
4.4.4.1 Soil Quality	4-35
4.4.4.2 Extent of Soil Contamination	4-43
4.4.5 Ground-Water Contamination	4-44
4.4.5.1 Ground-Water Quality	4-44
4.4.5.2 Extent of Ground-Water Contamination	4-46
4.5 NATURE AND EXTENT OF CONTAMINATION AT SITE 4	4-51
4.5.1 Source of Contamination	4-51
4.5.2 Surface Water and Sediment Contamination	4-51
4.5.2.1 Surface Water and Sediment Quality	4-51
4.5.2.2 Extent of Sediment and Surface Water Contamination	4-56
4.5.3 Soil Contamination	4-60
4.5.3.1 Soil Quality	4-60
4.5.3.2 Extent of Soil Contamination	4-60
4.5.4 Ground-Water Contamination	4-60
4.5.4.1 Ground-Water Quality	4-62
4.5.4.2 Extent of Ground-Water Contamination	4-62
4.6 NATURE AND EXTENT OF CONTAMINATION AT SITE 8	4-62
4.6.1 Source of Contamination	4-64
4.6.2 Surface Water and Sediment Contamination	4-64
4.6.2.1 Surface Water and Sediment Quality	4-64
4.6.2.2 Extent of Surface Water and Sediment Contamination	4-64

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
4.6.3 Soil Contamination	4-64
4.6.3.1 Soil Quality	4-64
4.6.3.2 Extent of Soil Contamination	4-69
4.6.4 Ground-Water Contamination	4-69
4.6.4.1 Ground-Water Quality	4-69
4.6.4.2 Extent of Ground-Water Contamination	4-69
4.7 NATURE AND EXTENT OF CONTAMINATION AT SITE 10	4-72
4.7.1 Source of Contamination	4-72
4.7.2 Ground-Water Contamination	4-72
4.7.2.1 Ground-Water Quality	4-72
4.7.2.2 Extent of Ground-Water Contamination	4-75
SECTION 5 CONTAMINANT FATE AND TRANSPORT	5-1
5.1 Introduction	5-3
5.1.1 Contaminant Fate	5-3
5.1.2 Contaminant Transport	5-5
5.2 CONTAMINANT FATE AND TRANSPORT AT SITE 2	5-7
5.2.1 Summary of Contaminants	5-7
5.2.2 Potential Routes of Migration	5-7
5.2.3 Contaminant Persistence	5-8
5.2.4 Contaminant Mobility and Migration	5-9
5.2.4.1 Contaminant Migration in Surface Water	5-9
5.2.4.2 Contaminant Migration in Soil	5-9
5.2.4.3 Contaminant Migration in Ground Water	5-9
5.3 CONTAMINANT FATE AND TRANSPORT AT SITE 3	5-10
5.3.1 Summary of Contaminant	5-11
5.3.2 Potential Routes of Migration	5-11
5.3.3 Contaminant Persistence	5-12
5.3.4 Contaminant Mobility and Migration	5-13
5.3.4.1 Contaminant Migration in Surface Water	5-13
5.3.4.2 Contaminant Migration in Soil	5-13
5.3.4.3 Contaminant Migration in Ground Water	5-14

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
5.4 CONTAMINANT FATE AND TRANSPORT AT SITE 4	5-15
5.4.1 Summary of Contaminants	5-15
5.4.2 Potential Routes of Migration	5-16
5.4.3 Contaminant Persistence	5-16
5.4.4 Contaminant Migration in Surface Water and Ground Water	5-17
5.5 CONTAMINANT FATE AND TRANSPORT AT SITE 8	5-17
5.5.1 Summary of Contaminants	5-17
5.5.2 Potential Routes of Migration	5-17
5.5.3 Contaminant Persistence	5-17
5.5.4 Contaminant Mobility and Migration in Soil	5-18
5.6 CONTAMINANT FATE AND TRANSPORT AT SITE 10	5-18
5.6.1 Summary of Contaminants	5-18
5.6.2 Potential Routes of Migration	5-18
5.6.3 Contaminant Persistence	5-18
5.6.4 Contaminant Mobility and Migration	5-18
SECTION 6 RISK ASSESSMENT	6-1
6.1 EVALUATION METHODOLOGY	6-3
6.1.1 Step 1 Selection of Indicator Chemicals	6-5
6.1.2 Step 2 Estimation of Exposure Point Concentrations	6-9
6.1.2.1 Exposure Pathway Analysis	6-9
6.1.2.2 Exposure Point Concentrations	6-11
6.1.2.3 Applicable and Appropriate Requirements and Other Criteria	6-17
6.1.3 Step 3 Estimation of Chemical Intakes	6-21
6.1.3.1 Fugitive Dust Generation Resulting from Wind Erosion	6-22

TABLE OF CONTENTS (continued)

VOLUME 1 (continued)

	Page
6.1.3.2 Volatilization of Organic Compounds from Surface Water	6-24
6.1.3.3 Dermal Contact with Surface Water	6-27
6.1.3.4 Ingestion of Surface Water During Recreation	6-29
6.1.3.5 Ingestion of Ground Water as Drinking Water	6-30
6.1.3.6 Ingestion of Soil	6-31
6.1.4 Step 4 Toxicity Assessment	6-32
6.1.5 Step 5 Risk Characterization	6-34
6.1.5.1 Noncarcinogenic Effects	6-34
6.1.5.2 Potential Carcinogenic Effects	6-35
6.2 SITE 2 RISK ASSESSMENT	6-36
6.2.1 Selection of Indicator Chemicals	6-36
6.2.2 Estimation of Exposure Point Concentrations or Emission Rates	6-38
6.2.2.1 Exposure Pathway Analysis	6-38
6.2.2.2 Exposure Point Concentrations	6-41
6.2.2.3 Comparison of Exposure Point Concentrations to ARARs	6-42
6.2.3 Estimation of Chemical Intakes	6-44
6.2.4 Toxicity Assessment	6-44
6.2.5 Risk Characterization	6-45
6.2.5.1 Risk Characterization of Noncarcinogenic Compounds	6-45
6.2.5.2 Risk Characterization of Potentially Carcinogenic Compounds	6-45
6.3 SITE 3 RISK ASSESSMENT	6-50
6.3.1 Selection of Indicator Chemicals	6-50
6.3.2 Estimation of Exposure Point Concentrations or Emission Rates	6-50
6.3.2.1 Exposure Pathway Analysis	6-52
6.3.2.2 Exposure Point Concentrations	6-55
6.3.2.3 Comparison of Exposure Point Concentrations to ARARs	6-56
6.3.3 Estimation of Chemical Intakes	6-58
6.3.4 Toxicity Assessment	6-58

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
6.3.5 Risk Characterization	6-59
6.3.5.1 Risk Characterization of Noncarcinogenic Compounds	6-59
6.3.5.2 Risk Characterization of Potentially Carcinogenic Compounds	6-59
6.4 SITE 4 RISK ASSESSMENT	6-62
6.4.1 Selection of Indicator Chemicals	6-62
6.4.2 Estimation of Exposure Point Concentrations or Emission Rates	6-62
6.4.2.1 Exposure Pathway Analysis	6-62
6.4.2.2 Exposure Point Concentrations	6-69
6.4.2.3 Comparison of Exposure Point Concentrations to ARARs	6-71
6.4.3 Estimation of Chemical Intakes	6-72
6.4.4 Toxicity Assessment	6-72
6.4.5 Risk Characterization	6-72
6.4.5.1 Risk Characterization of Noncarcinogenic Compounds	6-73
6.4.5.2 Risk Characterization of Potentially Carcinogenic Compounds	6-73
6.5 SITE 8 RISK ASSESSMENT	6-73
6.5.1 Selection of Indicator Chemicals	6-73
6.5.2 Estimation of Exposure Point Concentrations or Emission Rates	6-73
6.5.2.1 Exposure Pathway Analysis	6-79
6.5.2.2 Exposure Point Concentrations	6-82
6.5.2.3 Comparison of Exposure Point Concentrations to ARARs	6-82
6.5.3 Estimation of Chemical Intakes	6-83
6.5.4 Toxicity Assessment	6-83
6.5.5 Risk Characterization	6-84
6.5.5.1 Risk Characterization of Noncarcinogenic Compounds	6-84
6.5.5.2 Risk Characterization of Potentially Carcinogenic Compounds	6-86
6.6 SUMMARY AND CONCLUSIONS	6-86

TABLE OF CONTENTS (continued)
VOLUME 1 (continued)

	Page
SECTION 7 SUMMARY AND RECOMMENDATIONS	7-1
7.1 INTRODUCTION	7-1
7.2 SIGNIFICANT CONTAMINATION AT SITE 2	7-8
7.3 SIGNIFICANT CONTAMINATION AT SITE 3	7-9
7.4 SIGNIFICANT CONTAMINATION AT SITE 4	7-11
7.5 SIGNIFICANT CONTAMINATION AT SITE 8	7-12
7.6 SIGNIFICANT CONTAMINATION AT SITE 10	7-12
7.7 SUMMARY OF SIGNIFICANT CONTAMINATION AT ALL SITES	7-12
7.8 RECOMMENDATIONS	7-13
SECTION 8 REFERENCES	8-1

VOLUME 2

APPENDIX A	DEFINITIONS, NOMENCLATURE AND UNITS OF MEASUREMENT
APPENDIX B	STATEMENT OF WORK
APPENDIX C	PROJECT TEAM BIOGRAPHICAL SUMMARIES
APPENDIX D	PROCEDURES AND PROTOCOLS
APPENDIX E	DRILLING RECORDS
APPENDIX F	WELL CONSTRUCTION RECORDS
APPENDIX G	AQUIFER SLUG TEST ANALYSIS
APPENDIX H	ALTITUDE AND COORDINATE SURVEY FOR SAMPLING SITES
APPENDIX I	GROUND-WATER LEVEL MEASUREMENT SUMMARY
APPENDIX J	STREAMFLOW MEASUREMENT SUMMARY
APPENDIX K	GRAIN SIZE ANALYSES
APPENDIX L	CHEMICAL ANALYSES RESULTS FOR SOIL, GROUND WATER, SURFACE WATER AND SEDIMENT SAMPLES

TABLE OF CONTENTS (continued)
VOLUME 3

APPENDIX M LABORATORY DATA AND QUALITY ASSURANCE
FORMS, DATA PACKAGES #1 THROUGH #12

VOLUME 4

APPENDIX M LABORATORY DATA AND QUALITY ASSURANCE
FORMS, DATA PACKAGES #13 THROUGH #25

VOLUME 5

APPENDIX M LABORATORY DATA AND QUALITY ASSURANCE
FORMS, DATA PACKAGES #26 THROUGH #41

VOLUME 6

APPENDIX M LABORATORY DATA AND QUALITY ASSURANCE
FORMS, DATA PACKAGES #42 THROUGH #68

→ Volume 7 of this report consists of the following:

~~VOLUME 7~~

APPENDIX N: ^{Quality Assurance} QA REPORT FOR SAMPLE ANALYSES RESULTS.

APPENDIX O: SOIL GAS RESULTS.

APPENDIX P: RISK ASSESSMENT TABLES.

APPENDIX Q: FIELD NOTEBOOKS AND DRILLING LOGS.

→ Included is information obtained from sampling of water wells and ground water and listed in data tables. Data of hazardous materials such as pesticides and chemicals found in soils and in runoff from watersheds is also listed.

LIST OF FIGURES

	Page
1-1 Location Map.	1-8
1-2 Site Vicinity Map.	1-9
1-3 Airport Configuration.	1-12
1-4 St. Louis River Watershed.	1-15
1-5 Location Scheme for Water Wells in the State of Minnesota.	1-20
1-6 Sites Defined and Ranked During IRP Phase I Study.	1-29
1-7 Aerial Photograph of Site 2, April 1988.	1-32
1-8 Site 2 Sampling Locations Utilized During Phase II Investigations.	1-35
1-9 Aerial Photograph of Site 3, April 1988.	1-38
1-10 Site 3 Sampling Locations Utilized During Phase II Investigations.	1-47
1-11 Aerial Photograph of Site 4, April 1988.	1-54
1-12 Site 4 Sampling Locations Utilized During Phase II Investigations.	1-57
1-13 Aerial Photograph of Site 8, April 1988.	1-64
1-14 Site 8 Sampling Locations Utilized During Phase II, Stage 2 Investigations.	1-65
1-15 Site 10 Aerial Photograph, April 1988.	1-70
1-16 Site 10 Sampling Locations Utilized During Phase II, Stage 2 Investigation.	1-73
2-1 Airport Area Sampling Locations Utilized During Remedial Investigations.	2-5
2-2 Site 2 Boreholes, Surface Locations and Trenched Area of Remedial Investigation.	2-16
2-3 Site 2 Sampling Locations Utilized During Remedial Investigation.	2-17
2-4 Site 3 Boreholes, Surface Locations, and Surveyed Soil Gas Grid Points of Remedial Investigation.	2-26
2-5 Site 3 Soil Gas and Shallow Soil Sample Locations.	2-27

LIST OF FIGURES (continued)

	Page
2-6 Site 3 Monitoring Wells Utilized During Remedial Investigation.	2-28
2-7 Site 4 Sampling Locations Established During Remedial Investigation.	2-43
2-8 Site 4 Sampling Locations Utilized During Remedial Investigation.	2-44
2-9 Site 8 Sampling Locations Established During Remedial Investigation.	2-55
2-10 Site 8 Sampling Locations Utilized During Remedial Investigation.	2-56
3-1 Aerial Photograph of the Airport Area, August 1952.	3-5
3-2 Lithologic Logs From Paired Well Points at Site 2.	3-8
3-3 Lithologic Logs From Paired Well Points at Site 8.	3-9
3-4 Bedrock Contour Map of the Airport Area.	3-10
3-5 Geologic Cross-Sections of the Airport Area.	3-13
3-6 Index to Cross-Sections of the Airport Area.	3-14
3-7 Aerial Photograph of Site 2, August 1952.	3-15
3-8 Aerial Photograph of Site 2, October 1965.	3-16
3-9 Aerial Photograph of Site 2, May 1979.	3-17
3-10 Surface Drainage of Site 2.	3-20
3-11 Index to Cross-Section Locations for Site 2.	3-23
3-12 Geologic Cross-Sections for Site 2.	3-24
3-13 Water Table and Direction of Ground Water Movement at Site 2.	3-25
3-14 Variation in Vertical Hydraulic Head in the Glacial Till at Site 2 and Generalized Direction of Ground-Water Movement.	3-26
3-15 Surface Drainage of Site 3.	3-31
3-16 Index to Cross-Sections for Sites 3, 4, and 8.	3-34
3-17 Geologic Cross-Sections for Site 3.	3-35

LIST OF FIGURES (continued)

	Page
3-18 Water Table and Direction of Ground Water Movement for Site 3.	3-38
3-19 Variation in Vertical Hydraulic Head in the Glacial Till at Site 3 and Generalized Direction of Ground-Water Movement.	3-39
3-20 Surface Drainage at Site 4.	3-42
3-21 Geologic Cross-Sections for Site 4.	3-45
3-22 Water Table and Direction of Ground Water Movement for Site 4.	3-46
3-23 Variation in Vertical Hydraulic Head in the Glacial Till at Site 4 and Generalized Direction of Ground-Water Movement.	3-47
3-24 Surface Drainage at Site 8.	3-52
3-25 Geologic Cross-Sections at Site 8.	3-55
3-26 Water Table and Direction of Ground-Water Movement for Site 8.	3-58
3-27 Variation in Vertical Hydraulic Head in the Glacial Till at Site 8 and Generalized Direction of Ground-Water Movement.	3-59
3-28 Aerial Photograph of Sites 3, 4, and 8, April 1988.	3-60
3-29 Aerial Photograph of Sites 3, 4, and 8, August 1952.	3-61
3-30 Aerial Photograph of Sites 3, 4, and 8, October 1965.	3-62
3-31 Aerial Photograph of Sites 3, 4, and 8, May 1979.	3-63
3-32 Bedrock Contour Map of Sites 3, 4, and 8.	3-66
3-33 Geologic Cross-Section for Sites 3, 4 and 8.	3-69
3-34 Water Table and Direction of Ground-Water Movement for Sites 3, 4 and 8.	3-70
3-35 Variation in Vertical Hydraulic Head in the Glacial Till at Sites 3, 4 and 8, and Generalized Direction of Ground-Water Movement.	3-71
3-36 Aerial Photograph of Site 10, August 1952.	3-74
3-37 Aerial Photograph of Site 10, October 1965.	3-75

LIST OF FIGURES (continued)

	Page
3-38 Aerial Photograph of Site 10, May 1979.	3-76
3-39 Aerial Photograph of Site 10, April 1988 Showing Surface Drainage.	3-77
3-40 Water Table and Direction of Ground Water Movement for Site 10.	3-80
4-1 Estimated Areal Extent of Trichloroethene Contamination in Ground Water at Site 2.	4-25
4-2 Estimated Areal Extent of Trans-1,2-Dichloroethene Contamination in Ground Water at Site 2.	4-26
4-3 Distribution of Near Surface Soil Pesticide and PCB Occurrences at Site 3.	4-39
4-4 Estimated Areal Extent of Trichloroethene Contamination in Ground Water at Site 3.	4-48
4-5 Estimated Areal Extent of Tetrachloroethene Contamination in Ground Water at Site 3.	4-49
4-6 Estimated Areal Extent of 1,1,1 Trichloroethane Contamination in Ground Water at Site 3.	4-50
4-7 Vertical Distribution of Trichloroethene Contamination in Ground Water at Site 3	4-52
4-8 Vertical Distribution of Tetrachloroethene Contamination in Ground Water at Site 3.	4-53
4-9 Vertical Distribution of 1,1,1 Trichloroethane Contamination in Ground Water at Site 3.	4-54
4-10 Location of Pesticide and PCB Occurrences in Surface Soils at Site 8.	4-65

LIST OF TABLES

	Page
1-1 Climatic Data for Duluth International Airport	1-14
1-2 Well Data, 1-Mile Radius of Site, Duluth IAP, Duluth, Minnesota	1-21
1-3 Phase I Priority Ranking of Potential Contamination Sources ⁽¹⁾	1-28
1-4 Parameters Analyzed and Detected in Site 2 Ground Water Samples During the Phase II, Stage 1 Investigation	1-36
1-5 Parameters Analyzed in Site 2 Soil Samples During the Phase II, Stage 2 Investigation	1-39
1-6 Parameters Detected in Site 2 Soil Samples During the Phase II, Stage 2 Investigation	1-40
1-7 Parameters Analyzed in Site 2 Water Samples During the Phase II, Stage 2 Study	1-41
1-8 Parameters Detected in Site 2 Water Samples During the Phase II, Stage 2 Investigation	1-42
1-9 Parameters Detected in Site 3 Soil Samples During the Phase II, Stage 1 Investigation	1-44
1-10 Parameters Analyzed in Site 3 Soil and Sediment Samples During the Phase II, Stage 2 Investigation	1-48
1-11 Parameters Detected in Site 3 Soil Samples During the Phase II, Stage 2 Investigation	1-49
1-12 Parameters Detected in Site 3 Sediment Samples During the Phase II, Stage 2 Investigation	1-50
1-13 Parameters Analyzed in Site 3 Water Samples During the Phase II, Stage 2 Investigation	1-51
1-14 Parameters Detected in Site 3 Water Samples During the Phase II, Stage 2 Investigation	1-52
1-15 Parameters Analyzed and Detected in Site 4 Water Samples During the Phase II, Stage 1 Investigation	1-58
1-16 Parameters Analyzed in Site 4 Soil Samples During the Phase II, Stage 2 Investigation	1-59
1-17 Parameters Detected in Site 4 Soil Samples During the Phase II, Stage 2 Investigation	1-60
1-18 Parameters Detected in Site 4 Water Samples During the Phase II, Stage 2 Investigation	1-61

LIST OF TABLES (continued)

		Page
1-19	Parameters Analyzed in Site 8 Soil and Water Samples During the Phase II, Stage 2 Investigation	1-66
1-20	Parameters Detected in Site 8 Soil Samples During the Phase II, Stage 2 Investigation	1-67
1-21	Parameters Detected in Site 8 Water Samples During the Phase II, Stage 2 Investigation	1-71
1-22	Parameters Analyzed and Detected in Site 10 Ground-Water Samples During the Phase II, Stage 2 Investigation	1-74
2-1	Summary of Remedial Investigation Work by Site	2-6
2-2	Drilling and Sampling Summary	2-7
2-3	Summary of Work Performed at Area Locations	2-8
2-4	Chemical Analyses Performed on Background and Airport Area Surface Water Samples	2-10
2-5	Chemical Analyses Performed on Background and Airport Area Sediment Samples	2-11
2-6	Chemical Analyses Performed on Area Background Soil Samples	2-13
2-7	Summary of Water Level Measurement Rounds at Area Background Monitoring Wells	2-14
2-8	Chemical Analysis Performed on Area Background Ground-Water Samples	2-18
2-9	Summary of Work Performed at Site 2 Locations	2-19
2-10	Chemical Analyses Performed on Site 2 Surface Water Samples	2-21
2-11	Chemical Analyses Performed on Site 2 Sediment Samples	2-22
2-12	Chemical Analyses Performed on Site 2 Soil Samples	2-24
2-13	Summary of Site 2 Water Level Measurement Rounds	2-29
2-14	Chemical Analyses Performed on Site 2 Ground-Water Samples	2-30
2-15	Summary of Work Performed at Site 3 Locations	2-32
2-16	Chemical Analyses Performed on Site 3 Surface Water Samples	2-34
2-17	Chemical Analyses Performed on Site 3 Sediment Samples	2-35

LIST OF TABLES (continued)

	Page
2-18 Targeted Compounds for Soil Gas Analysis at Site 3	2-37
2-19 Chemical Analyses Performed on Site 3 Soil Samples	2-39
2-20 Summary of Site 3 Water Level Measurement Rounds	2-40
2-21 Chemical Analysis Performed on Site 3 Ground-Water Samples	2-45
2-22 Summary of Work Performed at Site 4 Locations	2-46
2-23 Chemical Analyses Performed on Site 4 Surface Water Samples	2-48
2-24 Chemical Analyses Performed on Site 4 Sediment Samples	2-49
2-25 Chemical Analyses Performed on Site 4 Soil Samples	2-51
2-26 Summary of Site 4 Water Level Measurement Rounds	2-52
2-27 Chemical Analyses Performed on Site 4 Ground-Water Samples	2-57
2-28 Summary of Work Performed at Site 8 Locations	2-58
2-29 Chemical Analyses Performed on Site 8 Surface Water Samples	2-61
2-30 Chemical Analyses Performed on Site 8 Sediment Samples	2-62
2-31 Chemical Analyses Performed on Site 8 Soil Samples	2-64
2-32 Summary of Site 8 Water Level Measurement Rounds	2-65
2-33 Chemical Analyses Performed on Site 8 Ground-Water Samples	2-67
2-34 Summary of Work Performed at Site 10 Locations	2-68
2-35 Summary of Site 10 Water Level Measurement Rounds	2-70
2-36 Chemical Analyses Performed on Site 10 Ground-Water Samples	2-71
3-1 Streamflow at Three Airport Area Locations	3-6
3-2 Hydraulic Parameters for Site 2	3-28
3-3 Summary of Site 3 Slug Test Results	3-40
3-4 Summary of Site 4 Slug Test Results	3-49
3-5 Summary of Site 8 Slug Test Results	3-64
4-1 Metals Detected in the Background Sediment Sample	4-5
4-2 Metals Detected in Background Soil Samples	4-6

LIST OF TABLES (continued)

	Page
4-3 Metals Detected in Background Ground-Water Samples	4-7
4-4 Radiological Parameters Detected in Background Ground-Water and Surface Water Samples	4-9
4-5 Temperature, pH and Specific Conductance Measurements for Background Location Water Samples	4-10
4-6 Metals Detected in Sediment at Airport Area Locations	4-12
4-7 Temperature, pH and Specific Conductance Measurements for Airport Area Surface Water Samples	4-13
4-8 Metals Detected in Site 2 Sediment Samples	4-15
4-9 Temperature, pH and Specific Conductance Measurements for Site 2 Water Samples	4-16
4-10 Volatile Organic Compounds Detected in Site 2 Soil Samples From Soil Sampling Boreholes	4-18
4-11 Semi-Volatile Organic Compounds Detected in Site 2 Soil Samples	4-19
4-12 Petroleum Hydrocarbons Detected in Site 2 Soil Samples	4-20
4-13 Metals Detected in Site 2 Soil Samples	4-22
4-14 Volatile Organic Compounds Detected in Site 2 Ground-Water Samples	4-27
4-15 Temperature, pH and Specific Conductance Measurements For Site 2 Water Samples	4-28
4-16 Volatile and Semi-Volatile Organic Compounds Detected in Site 3 Surface Water and Sediment Samples	4-31
4-17 Petroleum Hydrocarbons Detected in Site 3 Sediment and Soil Samples	4-32
4-18 Metals Detected in Site 3 Sediment Samples	4-33
4-19 Summary of Temperature, pH and Specific Conductance Measurements For Site 3 Water Samples	4-34
4-20 Volatile Organic Compounds Detected in Site 3 Soil Samples	4-36
4-21 Organochlorine Pesticides and PCBs Detected in Site 3 Soil and Ground-Water Samples	4-40

LIST OF TABLES (continued)

	Page
4-22 Metals Detected in Site 3 Soil Samples	4-41
4-23 Volatile Organic Compounds Detected in Site 3 Ground-Water Samples	4-45
4-24 Volatile Organic Compounds Detected in Site 4 Surface Water and Sediment Samples	4-55
4-25 Petroleum Hydrocarbons Detected in Site 4 Soil Samples	4-57
4-26 Metals Detected in Site 4 Sediment Samples	4-58
4-27 Temperature, pH and Specific Conductance Measurements For Site 4 Water Samples	4-59
4-28 Metals Detected in Site 4 Soil Samples	4-61
4-29 Metals Detected in Site 4 Ground-Water Samples	4-63
4-30 Metals Detected in Site 8 Sediments Samples	4-66
4-31 Temperature, pH and Specific Conductance Measurements For Site 8 Water Samples	4-67
4-32 Organochlorine Pesticides and PCBs Detected in Site 8 Soil Samples	4-68
4-33 Metals Detected in Site 8 Soil Samples	4-70
4-34 Metals Detected in Site 8 Ground-Water Samples	4-71
4-35 Summary of Radiological Results For Ground-Water Samples Taken at Site 10	4-73
4-36 Temperature, pH and Specific Conductance Measurements For Site 10 Water Samples	4-74
5-1 Summary of Chemical and Physical Properties For Organic Compounds Detected at Duluth ANGB ⁽¹⁾	5-4
6-1 Severity Ratings for Noncarcinogens	6-7
6-2 Weight-of-Evidence Categories For Potential Carcinogens	6-8
6-3 Indicator Chemicals and Relevant Physical Properties - Sites 2, 3, 4 and 8	6-10
6-4 Matrix of Potential Exposure Pathways	6-12

LIST OF TABLES (continued)

	Page
6-5 Applicable, Relevant and Appropriate Requirements and Other Criteria For Indicator Chemicals at Sites 2, 3, 4 and 8	6-19
6-6 Sites 2, 3, 4 and 8 Critical Toxicity Values	6-33
6-7 Site 2 Indicator Chemical Concentrations	6-37
6-8 Pathways Contributing to Total Exposure For Each Potential Receptor at Site 2	6-39
6-9 Comparison of Exposure Point Concentrations of Site 2 Indicator Chemicals in Air	6-43
6-10 Summary of Hazard Index Values For Site 2 - Upper Bound	6-46
6-11 Summary of Hazard Index Values For Site 2 - Best Estimate	6-47
6-12 Summary of Risk From Potential Carcinogens For Site 2 - Upper Bound	6-48
6-13 Summary of Risk From Potential Carcinogens For Site 2 - Best Estimate	6-49
6-14 Site 3 Indicator Chemical Concentrations	6-51
6-15 Pathways Contributing to Total Exposure For Each Potential Receptor at Site 3	6-53
6-16 Comparison of Ambient Exposure Point Concentrations With Air Criteria - Site 3	6-57
6-17 Summary of Hazard Index Values for Site 3 - Upper Bound	6-60
6-18 Summary of Hazard Index Values for Site 3 - Best Estimate	6-61
6-19 Summary of Risk From Potential Carcinogens for Site 3 - Upper Bound	6-63
6-20 Summary of Risk From Potential Carcinogens for Site 3 - Best Estimate	6-64
6-21 Site 4 Indicator Chemical Concentrations	6-65
6-22 Pathways Contributing to Total Exposure for Each Potential Receptor at Site 4	6-67
6-23 Comparison of Ambient Exposure Point Concentrations With Air Criteria - Site 4	6-70
6-24 Summary of Hazard Index Values For Site 4 - Upper Bound	6-74

LIST OF TABLES (continued)

	Page
6-25 Summary of Hazard Index Values for Site 4 - Best Estimate	6-75
6-26 Summary of Risk From Potential Carcinogens For Site 4 - Upper Bound	6-76
6-27 Summary of Risk From Potential Carcinogens For Site 4 - Best Estimate	6-77
6-28 Site 8 Indicator Chemical Concentrations	6-78
6-29 Pathways Contributing to Total Exposure For Each Potential Receptor at Site 8	6-80
6-30 Summary of Hazard Index Values For Site 8	6-85
6-31 Summary of Risk From Potential Carcinogens For Site 8	6-87
6-32 Summary of Hazard Index Values for Sites 2, 3, 4 and 8	6-88
6-33 Summary of Risk From Potential Carcinogens For Sites 2, 3, 4 and 8	6-89
6-34 Commonplace Risks	6-91
7-1 Summary of Surface Water Contaminants by Site	7-3
7-2 Summary of Sediment Contaminants by Site	7-6
7-3 Summary of Soil Contaminants by Site	7-7
7-4 Summary of Ground-Water Contaminants by Site	7-8
7-5 Summary of Findings by Site	7-16

This page intentionally left blank.

APPENDIX N
QUALITY ASSURANCE REPORT
FOR SAMPLE ANALYSIS RESULTS

This page intentionally left blank.

APPENDIX N

TABLE OF CONTENTS

	Page
LIST OF TABLES	N-6
N.1 INTRODUCTION	N-9
N.2 HOLDING TIME ANALYSIS	N-13
N.3 SAMPLE CONTAMINATION	N-101
N.3.1 Dichloromethane	N-103
N.3.2 Chloroform	N-103
N.3.3 Toluene	N-103
N.3.4 Bis(2 ethylhexyl)phthalate	N-119
N.4 DATA VALIDATION	N-121
N.4.1 Volatile Organic Analyses	N-123
N.4.1.1 Holding Times	N-123
N.4.1.2 GC/MS Tuning	N-123
N.4.1.3 Calibration	N-123
N.4.1.4 Blanks	N-123
N.4.1.5 Surrogate Recoveries	N-124
N.4.1.6 Matrix Spike/Matrix Spike Duplicate	N-124
N.4.1.7 Compound Identification	N-124
N.4.1.8 System Performance	N-124
N.4.2 Semi-Volatile Organic Analyses	N-125
N.4.2.1 Holding Times	N-125
N.4.2.2 GC/MS Tuning	N-125
N.4.2.3 Calibration	N-125
N.4.2.4 Blanks	N-125
N.4.2.5 Surrogate Recoveries	N-125
N.4.2.6 Matrix Spike/Matrix Spike Duplicate	N-125
N.4.2.7 Compound Identification	N-126
N.4.2.8 System Performance	N-126

APPENDIX N
TABLE OF CONTENTS (continued)

	Page
N.4.3 Pesticide/PCB Data	N-126
N.4.3.1 Holding Times	N-126
N.4.3.2 Pesticide Instrument Performance	N-126
N.4.3.3 Calibration	N-126
N.4.3.4 Blanks	N-126
N.4.3.5 Surrogates	N-126
N.4.3.6 Matrix Spike/Matrix Spike Duplicate	N-127
N.4.3.7 Compound Identification	N-127
N.4.4 Inorganics	N-127
N.4.4.1 Holding Times	N-127
N.4.4.2 Calibration	N-127
N.4.4.3 Blanks	N-128
N.4.4.4 Duplicates	N-128
N.4.4.5 Matrix Spike/Matrix Spike Duplicate	N-128
N.4.5 Metals	N-128
N.4.5.1 Holding Times	N-128
N.4.5.2 Initial and Continuing Calibration	N-128
N.4.5.3 Blanks	N-128
N.4.5.4 ICP Interference Check Samples	N-128
N.4.5.5 Laboratory Control Samples	N-128
N.4.5.6 Duplication	N-128
N.4.5.7 Spikes	N-129
N.5 FIELD QUALITY CONTROL SAMPLES	N-131
N.5.1 Blanks	N-133
N.5.1.1 Trip Blank Results	N-133
N.5.1.2 Field Blank Results	N-134
N.5.2 Duplicate Sample Results	N-134
N.5.2.1 Airport Area and Background Locations	N-134
N.5.2.2 Site 2	N-134
N.5.2.3 Site 3	N-135
N.5.2.4 Site 4	N-135

APPENDIX N
TABLE OF CONTENTS (continued)

	Page
N.5.2.5 Site 8	N-135
N.5.2.6 Site 10	N-136
N.5.3 Bailer Rinseate Results	N-136

APPENDIX N

LIST OF TABLES

	Page
N-1 Area/Background: Summary of Holding Time Data for Surface Water Samples	N-16
N-2 Area/Background: Summary of Holding Time Data for Sediment Samples	N-18
N-3 Area/Background: Summary of Holding Time Data for Soil Samples	N-20
N-4 Area/Background: Summary of Holding Time Data for Ground-Water Samples	N-24
N-5 Site 2: Summary of Holding Time Data for Ground-Water Samples	N-26
N-6 Site 2: Summary of Holding Time Data for Sediment Samples	N-28
N-7 Site 2: Summary of Holding Time Data for Soil Samples	N-30
N-8 Site 2: Summary of Holding Time Data for Ground-Water Samples	N-40
N-9 Site 3: Summary of Holding Time Data for Ground-Water Samples	N-46
N-10 Site 3: Summary of Holding Time Data for Sediment Samples	N-48
N-11 Site 3: Summary of Holding Time Data for Soil Samples	N-50
N-12 Site 3: Summary of Holding Time Data for Ground-Water Samples	N-64
N-13 Site 4: Summary of Holding Time Data for Ground-Water Samples	N-70
N-14 Site 4: Summary of Holding Time Data for Sediment Samples	N-72
N-15 Site 4: Summary of Holding Time Data for Soil Samples	N-74
N-16 Site 4: Summary of Holding Time Data for Ground-Water Samples	N-78
N-17 Site 8: Summary of Holding Time Data for Ground-Water Samples	N-82
N-18 Site 8: Summary of Holding Time Data for Sediment Samples	N-84
N-19 Site 8: Summary of Holding Time Data for Soil Samples	N-86
N-20 Site 8: Summary of Holding Time Data for Ground-Water Samples	N-96
N-21 Dichloromethane and Chloroform Concentrations Detected at all Sites Surface Water and Sediment Samples	N-105
N-22 Toluene Concentrations Detected at All Sites in Surface Water, Sediment and Ground-Water Samples	N-106
N-23 Toluene, Dichloromethane and Chloroform Concentrations Detected in Background Soil Samples	N-107
N-24 Toluene, Dichloromethane and Chloroform Concentrations Detected in Site 2 Soil Samples	N-108

APPENDIX N
LIST OF TABLES (continued)

	Page
N-25 Toluene, Dichloromethane and Chloroform Concentrations Detected in Site 3 Soil Samples	N-110
N-26 Toluene, Dichloromethane and Chloroform Concentrations Detected in Site 4 Soil Samples	N-112
N-27 Toluene, Dichloromethane and Chloroform Concentrations Detected in Site 8 Soil Samples	N-113
N-28 Dichloromethane and Chloroform Concentrations Detected in Area/Background Ground-Water Samples	N-114
N-29 Dichloromethane and Chloroform Concentrations Detected in Site 2 Ground-Water Samples	N-115
N-30 Dichloromethane and Chloroform Concentrations Detected in Site 3 Ground-Water Samples	N-116
N-31 Dichloromethane and Chloroform Concentrations Detected in Site 4 Ground-Water Samples	N-117
N-32 Dichloromethane and Chloroform Concentrations Detected in Site 8 Ground-Water Samples	N-118
N-33 Bis(2-ethylhexyl)phthalate Concentrations Detected in Area/Background, Site 2 and Site 3 Surface Water and Ground-Water Samples	N-120

This page intentionally left blank.

SECTION N.1
INTRODUCTION

This page intentionally left blank.

SECTION N.1 INTRODUCTION

This appendix presents a summary and review of the quality control results for laboratory analyses of surface water, sediment, soil, and ground-water samples collected during the first sampling round as part of the field program for the Remedial Investigation at the Minnesota Air National Guard Base, Duluth, Minnesota. Sample holding times and sample contamination are presented in Sections N.2 and N.3 respectively. Data validation for volatile organic, semi-volatile organic, pesticide, PCB and inorganic analyses are presented in Section N.4. Section N.5 contains field quality control samples including trip blanks, field blanks, field duplicates and bailer rinsewater samples.

Samples were collected from July 1988 through September 1988. Nitrate analyses were performed by MetaTrace Corporation, Earth City, Missouri. Radiological analyses were performed by NUS Corporation, Pittsburgh, Pennsylvania. All other analyses were performed by Engineering-Science, Inc., Berkeley, California.

This page intentionally left blank.

SECTION N.2
HOLDING TIME ANALYSES

This page intentionally left blank.

SECTION N.2

HOLDING TIME ANALYSES

The tables in this Section, Tables N-1 through N-20, give the sample collection date; the laboratory extraction date and elapsed time; and the laboratory analysis date and the elapsed time for each analysis that was performed on each sample. These times can be compared with the maximum holding times which are also given on each table.

If a holding time was missed this is indicated by an exclamation point next to the reported analyte concentration in the corresponding analytical results table in Appendix I.

Explanations of reasons why particular analyses were cancelled is explained in the footnotes to tables in Appendix L which can be found by looking up the analysis for the sample of interest in the corresponding table in Appendix L. The reason for cancellation is usually that the analysis was incorrectly requested.

TABLE N-1
Area/Background
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Surface Water Samples

	SL1 9-24-88 DANGB BG-SL1-GW-1 88092604	SL1 FH 9-24-88 DANGB FH16 88092608	SL2 9-24-88 DANGB BG-SL2-SW-1 88092605	SL3 9-24-88 DANGB BG-SL3-SW-1 88092606	SL4 9-23-88 DANGB BG-SL4-SW-1 88092677	SL4 DUP 9-23-88 DANGB BG-SL4-SW-1 88092678	SL5 9-23-88 DANGB BG-SL5-SW-1 88092681	TB1 9-24-88 DANGB-TB12 88092697
Date Collected	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88	24 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)								
Date Analyzed	28 Sep 88	29 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88
Elapsed Time	4 Days	5 Days	4 Days	4 Days	5 Days	5 Days	5 Days	4 Days
2nd Column	-----	3 Oct 88	3 Oct 88	29 Sep 88	-----	-----	-----	29 Sep 88
Elapsed Time	-----	9 Days	9 Days	5 Days	-----	-----	-----	5 Days
AROMATIC VOLATILE ORGANICS (SW8020)								
Date Analyzed	28 Sep 88	29 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88
Elapsed Time	4 Days	5 Days	4 Days	4 Days	5 Days	5 Days	5 Days	4 Days
2nd Column	-----	-----	-----	29 Sep 88	-----	-----	-----	-----
Elapsed Time	-----	-----	-----	5 Days	-----	-----	-----	-----
PESTICIDES AND PCBs (EPA 608)								
Date Extracted	29 Sep 88	Analysis Not Requested	29 Sep 88	29 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	Analysis Not Requested
Elapsed Time	5 Days		5 Days	5 Days	5 Days	5 Days	5 Days	
Date Analyzed	24 Oct 88	Analysis Not Requested	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	Analysis Not Requested
Elapsed Time	30 Days		30 Days	30 Days	31 Days	31 Days	31 Days	
2nd Column	-----	Analysis Not Requested	-----	-----	-----	-----	-----	Analysis Not Requested
Elapsed Time	-----		-----	-----	-----	-----	-----	
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)								
Date Extracted	10 Oct 88	Analysis Not Requested	10 Oct 88	10 Oct 88	11 Oct 88	11 Oct 88	8 Oct 88	Analysis Not Requested
Elapsed Time	16 Days		16 Days	16 Days	18 Days	18 Days	15 Days	
Date Analyzed	11 Oct 88	Analysis Not Requested	11 Oct 88	12 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	Analysis Not Requested
Elapsed Time	17 Days		17 Days	18 Days	27 Days	27 Days	27 Days	

TABLE N-1
(Continued)

	SL1 9-24-88 DANGB-HG-SL1-GW-1 88072074	SL1 FH 9-24-88 DANGB-FH16 88072498	SL2 9-24-88 DANGB-HG-SL2-SW-1 88072095	SL3 9-24-88 DANGB-HG-SL3-SW-1 88072446/88072724	SL4 9-23-88 DANGB-HG-SL4-SW-1 88072677	SL4 DUP 9-23-88 DANGB-HG-SL4-SW-1 88072678	SL5 9-23-88 DANGB-HG-SL5-SW-1 88072681	TBI 9-24-88 DANGB-TBI2 88072697
Date Collected	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88	24 Sep 88
Arsenic (SW7060)								
Date Analyzed	16 Oct 88	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION 16 Oct 88	21 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	Analysis Not Requested
Elapsed Time	22 Days		22 Days	27 Days	23 Days	23 Days	23 Days	
Barium (SW6010)								
Date Analyzed	13 Oct 88	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION 13 Oct 88	21 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	Analysis Not Requested
Elapsed Time	19 Days		19 Days	28 Days	20 Days	20 Days	20 Days	
Cadmium (SW7131)								
Date Analyzed	26 Oct 88	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION 26 Oct 88	27 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	Analysis Not Requested
Elapsed Time	32 Days		32 Days	33 Days	32 Days	32 Days	32 Days	
Chromium (SW7191)								
Date Analyzed	19 Oct 88	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION 19 Oct 88	21 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	Analysis Not Requested
Elapsed Time	25 Days		25 Days	28 Days	26 Days	26 Days	26 Days	
Lead (SW7421)								
Date Analyzed	24 Oct 88	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION 24 Oct 88	22 Oct 88	21 Oct 88	24 Oct 88	24 Oct 88	Analysis Not Requested
Elapsed Time	30 Days		30 Days	29 Days	28 Days	31 Days	31 Days	
Mercury (SW7471)								
Date Analyzed	22 Oct 88	Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION 22 Oct 88	22 Oct 88	14 Oct 88	22 Oct 88	22 Oct 88	Analysis Not Requested
Elapsed Time	28 Days		28 Days	29 Days	21 Days	29 Days	29 Days	
SEMI-VOLATILE ORGANICS (EPA 625)								
Date Extracted	30 Sep 88	Analysis Not Requested	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION 30 Sep 88	30 Sep 88	29 Sep 88	29 Sep 88	29 Sep 88	Analysis Not Requested
Elapsed Time	6 Days		6 Days	6 Days	6 Days	6 Days	6 Days	
Date Analyzed	9 Nov 88	Analysis Not Requested	9 Nov 88	23 Nov 88	8 Nov 88	8 Nov 88	23 Nov 88	Analysis Not Requested
Elapsed Time	46 Days		46 Days	60 Days	45 Days	46 Days	61 Days	

TABLE N-2
Area/Background
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Sediment Samples

	SL1 9-24-88 DANGB-BG-SL1-SD-1 88092733	SL2 9-24-88 DANGB-BG-SL2-SD-1 88092732	SL3 9-24-88 DANGB-BG-SL3-SD-1 88092731	SL4 9-23-88 DANGB-BG-SL4-SD-1 88092673	SL4 DUP 9-23-88 DANGB-BG-SL4-SD-1 88092674	SL5 9-23-88 DANGB-BG-SL5-SD-1 88092672
Date Collected	24 Sep 88	24 Sep 88	24 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)						
Date Analyzed	5 Oct 88	5 Oct 88	5 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	12 Days	12 Days	12 Days	11 Days	11 Days	11 Days
2nd Column	*****	*****	*****	*****	*****	*****
Elapsed Time	*****	*****	*****	*****	*****	*****
AROMATIC VOLATILE ORGANICS (SW8020)						
Date Analyzed	5 Oct 88	5 Oct 88	5 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	12 Days	12 Days	12 Days	11 Days	11 Days	11 Days
2nd Column	*****	*****	*****	*****	*****	*****
Elapsed Time	*****	*****	*****	*****	*****	*****
PESTICIDES AND PCBs (SW8080)						
Date Extracted	27 Oct 88	7 Oct 88	7 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	34 Days	14 Days	14 Days	11 Days	11 Days	11 Days
Date Analyzed	25 Oct 88	25 Oct 88	25 Oct 88	26 Oct 88	25 Oct 88	25 Oct 88
Elapsed Time	32 Days	32 Days	32 Days	33 Days	32 Days	32 Days
2nd Column	*****	*****	*****	*****	*****	*****
Elapsed Time	*****	*****	*****	*****	*****	*****
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)						
Date Extracted	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88
Elapsed Time	20 Days	21 Days	21 Days	21 Days	21 Days	21 Days
Date Analyzed	22 Oct 88	22 Oct 88	22 Oct 88	22 Oct 88	22 Oct 88	22 Oct 88
Elapsed Time	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days

TABLE N-2
(Continued)

	SL1 9-24-88	SL2 9-24-88	SL3 9-24-88	SL4 9-23-88	SL4 DUP 9-23-88	SL5 9-23-88
	DANGB HG-SL1-SD-1 88092733	DANGB HG-SL2-SD-1 88092732	DANGB HG-SL3-SD-1 88092731	DANGB HG-SL4-SD-1 88092673	DANGB HG-SL5-SD-1 88092674	DANGB HG-SL5-SD-1 88092672
Date Collected	24 Sep 88	24 Sep 88	24 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88
Arsenic (SW7660)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	17 Oct 88	17 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88
Elapsed Time	23 Days	23 Days	22 Days	23 Days	23 Days	23 Days
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88
Elapsed Time	23 Days	23 Days	23 Days	24 Days	24 Days	24 Days
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	18 Oct 88	18 Oct 88	18 Oct 88	20 Oct 88	17 Oct 88	17 Oct 88
Elapsed Time	24 Days	24 Days	24 Days	27 Days	24 Days	24 Days
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88
Elapsed Time	24 Days	24 Days	24 Days	25 Days	25 Days	25 Days
Lead (SW7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	25 Oct 88	16 Oct 88	16 Oct 88	25 Oct 88	25 Oct 88	16 Oct 88
Elapsed Time	31 Days	22 Days	22 Days	32 Days	32 Days	23 Days
Mercury (SW7471)	ANALYZE WITHIN 28 DAYS OF COLLECTION					
Date Analyzed	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88
Elapsed Time	24 Days	24 Days	24 Days	24 Days	24 Days	24 Days
SEMI-VOLATILE ORGANICS (SW8270)	NO HOLDING TIME SPECIFIED					
Date Extracted	7 Oct 88	7 Oct 88	7 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	14 Days	6 Days	14 Days	12 Days	12 Days	12 Days
Date Analyzed	15 Nov 88	30 Nov 88	15 Nov 88	10 Nov 88	11 Nov 88	10 Nov 88
Elapsed Time	53 Days	68 Days	53 Days	58 Days	59 Days	58 Days

TABLE N-3
Area/Background
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Soil Samples

	MW32-SS1 2-3 8-29-88 88082186	MW32-R-SS1 0-1 8-31-88 88092244	MW32-R-SS1 DUP 0-1 8-31-88 88092245	MW32-SS2 11-12 8-29-88 88082187	MW32-SS3 19-20 8-29-88 88082188	MR42-SS1 0-1 8-18-88 DANGB-BG-MW42-SS1 88081970
	DANGB-BG-MW32-SS1 - DANGB-BG-MW32-SS1 DANGB-BG-MW32-SS2 DANGB-BG-MW32-SS3 DANGB-BG-MW42-SS1					
HALOGENATED VOLATILE ORGANICS (SW8910)						
Date Collected	29 Aug 88	31 Aug 88	31 Aug 88	29 Aug 88	29 Aug 88	18 Aug 88
Date Analyzed	7 Sep 88	13 Sep 88	13 Sep 88	7 Sep 88	7 Sep 88	31 Aug 88
Elapsed Time	9 Days	13 Days	13 Days	9 Days	9 Days	13 Days
2nd Column	8 Sep 88	12 Sep 88	12 Sep 88	8 Sep 88	8 Sep 88	30 Aug 88
Elapsed Time	10 Days	12 Days	12 Days	10 Days	10 Days	12 Days
AROMATIC VOLATILE ORGANICS (SW7020)						
Date Analyzed	7 Sep 88	13 Sep 88	13 Sep 88	7 Sep 88	7 Sep 88	31 Aug 88
Elapsed Time	9 Days	13 Days	13 Days	9 Days	9 Days	13 Days
2nd Column	8 Sep 88	11 Sep 88	11 Sep 88	8 Sep 88	8 Sep 88	31 Aug 88
Elapsed Time	10 Days	11 Days	11 Days	10 Days	10 Days	13 Days
PESTICIDES AND PCBs (SW8080)						
Date Extracted	7 Sep 88	9 Sep 88	9 Sep 88	7 Sep 88	7 Sep 88	27 Aug 88
Elapsed Time	9 Days	9 Days	9 Days	9 Days	9 Days	9 Days
Date Analyzed	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	26 Sep 88
Elapsed Time	37 Days	35 Days	35 Days	37 Days	37 Days	39 Days
2nd Column	7 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88	26 Sep 88
Elapsed Time	37 Days	37 Days	37 Days	37 Days	37 Days	39 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)						
Date Extracted	26 Sep 88	22 Sep 88	22 Sep 88	26 Sep 88	26 Sep 88	14 Sep 88
Elapsed Time	28 Days	22 Days	22 Days	28 Days	28 Days	27 Days
Date Analyzed	27 Sep 88	23 Sep 88	23 Sep 88	27 Sep 88	27 Sep 88	15 Sep 88
Elapsed Time	29 Days	23 Days	23 Days	29 Days	29 Days	28 Days

TABLE N-3
(Continued)

	MW42 SS2 7-8 8-18 88	MW42-SS3 14-5-15.5 8-18-88	MW43-SS1 1-2 8-18-88	MW43-SS2 14-15 8-18-88	MW43-SS3 23-24 8-18-88
	DANGIB BG MW42-SS2 88081968	DANGIB HG-MW42-SS3 88081971	DANGIB BG-MW43-SS1 88081967	DANGIB HG-MW43-SS2 88081969	DANGIB HG-MW43-SS3 88081966
Date Collected	18 Aug 88	18 Aug 88	18 Aug 88	18 Aug 88	18 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88
Elapsed Time	13 Days	13 Days	13 Days	13 Days	13 Days
2nd Column	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88
Elapsed Time	12 Days	12 Days	12 Days	12 Days	12 Days
AROMATIC VOLATILE ORGANICS (SW8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88
Elapsed Time	13 Days	13 Days	13 Days	13 Days	13 Days
2nd Column	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88
Elapsed Time	13 Days	13 Days	13 Days	13 Days	13 Days
PESTICIDES AND PCBs (SW8080)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION				
Date Extracted	27 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88
Elapsed Time	9 Days	9 Days	9 Days	9 Days	9 Days
Date Analyzed	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
Elapsed Time	39 Days	39 Days	39 Days	39 Days	39 Days
2nd Column	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
Elapsed Time	39 Days	39 Days	39 Days	39 Days	39 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)	NO HOLDING TIME SPECIFIED				
Date Extracted	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88
Elapsed Time	27 Days	27 Days	27 Days	27 Days	27 Days
Date Analyzed	15 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88
Elapsed Time	28 Days	28 Days	28 Days	28 Days	28 Days

TABLE N-3
(Continued)

	MW32-SS1 2-3 DANGIB BG-MW32 SS1 88082186	MW32-R SS1 0-1 DANGIB-BG-MW32 SS1 88092244	MW32-R SS1 DUP 0-1 DANGIB-BG-MW32-SS4 88092245	MW32-SS2 11-12 DANGIB-BG-MW32-SS2 88082187	MW32-SS3 19-20 DANGIB BG-MW32-SS3 88082188	MW32-SS1 0-1 DANGIB BG MW32 SS1 88081970
Data Collected	29 Aug 88	31 Aug 88	31 Aug 88	29 Aug 88	29 Aug 88	18 Aug 88
Arsenic (SW7060)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	10 Oct 88	11 Oct 88	11 Oct 88	10 Oct 88	10 Oct 88	6 Oct 88
Elapsed Time	42 Days	41 Days	41 Days	42 Days	42 Days	49 Days
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Sept 88
Elapsed Time	52 Days	50 Days	50 Days	52 Days	52 Days	32 Days
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Sept 88
Elapsed Time	52 Days	50 Days	50 Days	52 Days	52 Days	32 Days
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Sept 88
Elapsed Time	52 Days	50 Days	50 Days	52 Days	52 Days	32 Days
Lead (SW7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION					
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	11 Oct 88
Elapsed Time	52 Days	50 Days	52 Days	52 Days	52 Days	54 Days
Mercury (SW7471)	ANALYZE WITHIN 28 DAYS OF COLLECTION					
Date Analyzed	28 Sep 88	22 Sep 88	22 Sep 88	28 Sep 88	28 Sep 88	14 Sep 88
Elapsed Time	30 Days	22 Days	22 Days	30 Days	30 Days	27 Days
PERCENT MOISTURE	PERCENT MOISTURE					
Date Analyzed	7 Sep 88	9 Sep 88	9 Sep 88	7 Sep 88	7 Sep 88	29 Aug 88
Elapsed Time	9 Days	9 Days	9 Days	9 Days	9 Days	11 Days
SEMI-VOLATILE ORGANICS (SW8270)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION					
Date Extracted	8 Sep 88	10 Sep 88	10 Sep 88	8 Sep 88	8 Sep 88	2 Nov 88
Elapsed Time	9 Days	10 Days	10 Days	9 Days	9 Days	76 Days
Date Analyzed	30 Nov 88	21 Oct 88	21 Oct 88	17 Oct 88	17 Oct 88	21 Nov 88
Elapsed Time	93 Days	51 Days	51 Days	49 Days	48 Days	95 Days

TABLE N-3
(Continued)

	MIW42-SV2	MIW42-SS3	MIW43-SS1	MIW43-SS2	MIW43-SS3
	7-8	14-5-15-5	1-2	14-15	23-24
	8-18-88	8-18-88	8-18-88	8-18-88	8-18-88
	DANGB HG-MIW42-SS2	DANGB HG-MIW42-SS1	DANGB HG-MIW43-SS1	DANGB HG-MIW43-SS2	DANGB HG-MIW43-SS3
	88081968	88081971	88081967	88081969	88081966
	18 Aug 88	18 Aug 88	18 Aug 88	18 Aug 88	18 Aug 88
Arzene (SW7060)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	6 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	49 Days	49 Days	49 Days	49 Days	49 Days
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	32 Days	32 Days	32 Days	32 Days	32 Days
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	32 Days	32 Days	32 Days	32 Days	32 Days
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	32 Days	32 Days	32 Days	32 Days	32 Days
Lead (SW7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	11 Oct 88	11 Oct 88	11 Oct 88	11 Oct 88	11 Oct 88
Elapsed Time	54 Days	54 Days	54 Days	54 Days	54 Days
Mercury (SW7471)	ANALYZE WITHIN 28 DAYS OF COLLECTION				
Date Analyzed	13 Sep 88	14 Sep 88	13 Sep 88	14 Sep 88	13 Sep 88
Elapsed Time	26 Days	27 Days	26 Days	27 Days	26 Days
PERCENT MOISTURE					
Date Analyzed	29 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88
Elapsed Time	11 Days	11 Days	11 Days	11 Days	11 Days
SEMI-VOLATILE ORGANICS (SW8270)	NO HOLDING TIME SPECIFIED				
Date Extracted	27 Aug 88	2 Nov 88	27 Aug 88	27 Aug 88	27 Aug 88
Elapsed Time	9 Days	76 Days	9 Days	9 Days	9 Days
Date Analyzed	26 Oct 88	21 Nov 88	5 Oct 88	26 Oct 88	5 Oct 88
Elapsed Time	69 Days	95 Days	48 Days	69 Days	48 Days

TABLE N-4
Area/Background
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Ground-Water Samples

	MW32 9-8-88 DANGB BG-MW32-GW1 88092306	MW42 9-8-88 DANGB BG-MW42-GW1 88092305	MW42 F-H 9-8-88 DANGB F-H2 88092307	MW43 9-7-88 DANGB BG-MW43-GW1 88092293	MW43 DUP 9-7-88 DANGB BG-MW50-GW1 88092292	MW43 FB 9-7-88 DANGB-FB1 88092294	TBI 9-8-88 DANGB-TBI 88092308	TRI 9-7-88 DANGB-TRI 88092291
Date Collected	8 Sep 88	8 Sep 88	8 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	8 Sep 88	7 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)								
Date Analyzed	16 Sep 88	16 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88
Elapsed Time	8 Days	8 Days	6 Days	7 Days	7 Days	7 Days	6 Days	7 Days
2nd Column Elapsed Time	14 Sep 88 6 Days	14 Sep 88 6 Days	16 Sep 88 8 Days	16 Sep 88 9 Days	16 Sep 88 9 Days	16 Sep 88 9 Days	16 Sep 88 8 Days	----- -----
AROMATIC VOLATILE ORGANICS (SW8020)								
Date Analyzed	16 Sep 88	16 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88
Elapsed Time	8 Days	8 Days	6 Days	7 Days	7 Days	7 Days	6 Days	7 Days
2nd Column Elapsed Time	----- -----	----- -----	----- -----	----- -----	----- -----	16 Sep 88 9 Days	----- -----	----- -----
PESTICIDES AND PCBs (TPA 008)								
Date Extracted	14 Sep 88	14 Sep 88	Analysis Not Requested	9 Sep 88	9 Sep 88	Analysis Not Requested	Analysis Not Requested	9 Sep 88
Elapsed Time	6 Days	6 Days	-----	2 Days	2 Days	-----	-----	2 Days
Date Analyzed	6 Oct 88	6 Oct 88	Analysis Not Requested	6 Oct 88	6 Oct 88	Analysis Not Requested	Analysis Not Requested	6 Oct 88
Elapsed Time	28 Days	28 Days	-----	29 Days	29 Days	-----	-----	29 Days
2nd Column Elapsed Time	----- -----	----- -----	Analysis Not Requested	----- -----	----- -----	Analysis Not Requested	Analysis Not Requested	----- -----
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)								
Date Extracted	28 Sep 88	28 Sep 88	Analysis Not Requested	23 Sep 88	23 Sep 88	Analysis Not Requested	Analysis Not Requested	23 Sep 88
Elapsed Time	20 Days	20 Days	-----	16 Days	16 Days	-----	-----	16 Days
Date Analyzed	5 Oct 88	5 Oct 88	Analysis Not Requested	26 Sep 88	26 Sep 88	Analysis Not Requested	Analysis Not Requested	26 Sep 88
Elapsed Time	27 Days	27 Days	-----	19 Days	19 Days	-----	-----	19 Days

TABLE N-4
(Continued)

	MW32 0.8-88 DANGB-HG-MW32 GW-1 88092306	MW42 9-8-88 DANGB-HG-MW42 GW-1 88092305	MW42 FH 0.8-88 DANGB-HG-MW42 GW-1 88092307	MW43 9-7-88 DANGB-HG-MW43 GW-1 88092303	MW43 DUJ 9-7-88 DANGB-HG-MW43 GW-1 88092302	MW43 FB 9-7-88 DANGB-HG-MW43 GW-1 88092304	TBI 9-7-88 DANGB-TBI 88092308	HRI 9-7-88 DANGB-HRI 88092301
Date Collected	8 Sep 88	8 Sep 88	8 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	8 Sep 88	7 Sep 88
Arsenic (SW7060)	ANALYZE WITHIN 180 DAYS OF COLLECTION							
Date Analyzed	4 Nov 88	4 Nov 88	Analysis Not Requested	4 Nov 88	4 Nov 88	Analysis Not Requested	Analysis Not Requested	4 Nov 88
Elapsed Time	57 Days	57 Days		58 Days	58 Days			58 Days
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION							
Date Analyzed	17 Oct 88	17 Oct 88	Analysis Not Requested	17 Oct 88	17 Oct 88	Analysis Not Requested	Analysis Not Requested	17 Oct 88
Elapsed Time	39 Days	39 Days		40 Days	40 Days			40 Days
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION							
Date Analyzed	24 Oct 88	21 Oct 88	Analysis Not Requested	26 Oct 88	26 Oct 88	Analysis Not Requested	Analysis Not Requested	26 Oct 88
Elapsed Time	46 Days	43 Days		49 Days	49 Days			49 Days
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION							
Date Analyzed	28 Oct 88	28 Oct 88	Analysis Not Requested	28 Oct 88	28 Oct 88	Analysis Not Requested	Analysis Not Requested	28 Oct 88
Elapsed Time	50 Days	50 Days		51 Days	51 Days			51 Days
Lead (SW7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION							
Date Analyzed	20 Oct 88	20 Oct 88	Analysis Not Requested	20 Oct 88	20 Oct 88	Analysis Not Requested	Analysis Not Requested	20 Oct 88
Elapsed Time	42 Days	42 Days		43 Days	43 Days			43 Days
Mercury (SW7471)	ANALYZE WITHIN 28 DAYS OF COLLECTION							
Date Analyzed	27 Sep 88	27 Sep 88	Analysis Not Requested	27 Sep 88	27 Sep 88	Analysis Not Requested	Analysis Not Requested	27 Sep 88
Elapsed Time	19 Days	19 Days		20 Days	20 Days			20 Days
SEMI-VOLATILE ORGANICS (EPA 625)	NO HOLDING TIME SPECIFIED							
Date Extracted	11 Sep 88	14 Sep 88	Analysis Not Requested	1 Jan 89	9 Sep 88	Analysis Not Requested	Analysis Not Requested	12 Sep 88
Elapsed Time	6 Days	6 Days		115 Days	2 Days			5 Days
Date Analyzed	23 Oct 88	23 Oct 88	Analysis Not Requested	13 Jan 89	21 Oct 88	Analysis Not Requested	Analysis Not Requested	21 Oct 88
Elapsed Time	45 Days	45 Days		127 Days	44 Days			44 Days

TABLE N-5
Site 2
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Surface Water Samples

	SL6 9-26-88 DANGIB-2-SL6-SW-1 88092769	SL6 DUP 9-26-88 DANGIB-2-SL6-SW-1 88092768	SL6 FB 9-26-88 DANGIB-FB20 88092775	SL7 9-26-88 DANGIB-2-SL7-GW-1 88092770	THI 9-26-88 DANGIB-THI14 88092773
Date Collected	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)					
Date Analyzed	4 Oct 88	4 Oct 88	3 Oct 88	4 Oct 88	3 Oct 88
Elapsed Time	8 Days	8 Days	7 Days	8 Days	7 Days
2nd Column	30 Sep 88	30 Sep 88
Elapsed Time	4 Days	4 Days
AROMATIC VOLATILE ORGANICS (SW8020)					
Date Analyzed	30 Sep 88	30 Sep 88	3 Oct 88	30 Sep 88	3 Oct 88
Elapsed Time	4 Days	4 Days	7 Days	4 Days	7 Days
2nd Column
Elapsed Time
TOTAL PETROLEUM HYDROCARBONS (PPA 418.1)					
Date Extracted	12 Oct 88	12 Oct 88	Analysis Not Requested	12 Oct 88	Analysis Not Requested
Elapsed Time	16 Days	16 Days		16 Days	
Date Analyzed	21 Oct 88	21 Oct 88	Analysis Not Requested	21 Oct 88	Analysis Not Requested
Elapsed Time	25 Days	25 Days		25 Days	

TABLE N-5
(Continued)

	SL6 9-26-88 DANGB 2-SL6-SW-1 88092768	SL6 DUP 9-26-88 DANGB 2-SL6-SW-1 88092768	SL6 FB 9-26-88 DANGB FB20 88092775	SL7 9-26-88 DANGB 2-SL7 GW-1 88092770	TBI 9-26-88 DANGB-TBI4 88092773
Date Collected	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
Barium (SW7010)					
Date Analyzed	21 Oct 88	21 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION	21 Oct 88	Analysis Not Requested
Elapsed Time	25 Days	25 Days	Requested	25 Days	
Cadmium (SW7131)					
Date Analyzed	27 Oct 88	27 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION	27 Oct 88	Analysis Not Requested
Elapsed Time	31 Days	31 Days	Requested	31 Days	
Chromium (SW7191)					
Date Analyzed	21 Oct 88	21 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION	21 Oct 88	Analysis Not Requested
Elapsed Time	25 Days	25 Days	Requested	25 Days	
Lead (SW7421)					
Date Analyzed	22 Oct 88	22 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION	22 Oct 88	Analysis Not Requested
Elapsed Time	26 Days	26 Days	Requested	26 Days	
SEMI-VOLATILE ORGANICS (EPA 625)					
Date Extracted	30 Sep 88	30 Sep 88	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	30 Sep 88	Analysis Not Requested
Elapsed Time	4 Days	4 Days	Requested	4 Days	
Date Analyzed	9 Nov 88	9 Nov 88	Analysis Not Requested	9 Nov 88	Analysis Not Requested
Elapsed Time	44 Days	44 Days	Requested	44 Days	

TABLE N-6
Site 2
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Sediment Samples

	SL6 9/26/88 DANGB-2-SL6-SD-1 88092800	SL6 DUP 9/26/88 DANGB-2-SL6-SD-1 88092801	SL7 9/26/88 DANGB-2-SL7-SD-1 88092799
Date Collected	26 Sep 88	26 Sep 88	26 Sep 88
HAZARDOUS VOLATILE ORGANICS (SW8910)			
Date Analyzed	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	10 Days	10 Days	10 Days
2nd Column	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	10 Days	10 Days	10 Days
AROMATIC VOLATILE ORGANICS (SW8920)			
Date Analyzed	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	10 Days	10 Days	10 Days
2nd Column	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	10 Days	10 Days	10 Days
TOTAL PETROLEUM HYDROCARBONS (16 PAHs)			
Date Extracted	18 Oct 88	18 Oct 88	18 Oct 88
Elapsed Time	22 Days	22 Days	22 Days
Date Analyzed	25 Oct 88	25 Oct 88	25 Oct 88
Elapsed Time	29 Days	29 Days	29 Days

TABLE N-6
(Continued)

	SL6 9-26-88 DANGB 2-SL6-SD-1 88072800	SL6 DUP 9-26-88 DANGB-2-SL7-SD-1 88072801	SL7 9-26-88 DANGB-2-SL7-SD-1 88072799
Date Collected	26 Sep 88	26 Sep 88	26 Sep 88
Arsenic (SW7060)			
Date Analyzed	17 Oct 88	18 Oct 88	17 Oct 88
Elapsed Time	21 Days	22 Days	21 Days
Barium (SW6010)			
Date Analyzed	17 Oct 88	17 Oct 88	17 Oct 88
Elapsed Time	21 Days	21 Days	21 Days
Cadmium (SW7131)			
Date Analyzed	19 Oct 88	20 Oct 88	19 Oct 88
Elapsed Time	23 Days	24 Days	23 Days
Chromium (SW7191)			
Date Analyzed	18 Oct 88	20 Oct 88	18 Oct 88
Elapsed Time	22 Days	24 Days	22 Days
Lead (SW7421)			
Date Analyzed	19 Oct 88	25 Oct 88	18 Oct 88
Elapsed Time	23 Days	29 Days	22 Days
Mercury (SW7471)			
Date Analyzed	17 Oct 88	17 Oct 88	17 Oct 88
Elapsed Time	21 Days	21 Days	21 Days
PERCENT MOISTURE			
Date Analyzed	10 Oct 88	10 Oct 88	10 Oct 88
Elapsed Time	14 Days	14 Days	14 Days
SEMI-VOLATILE ORGANICS (SW8230)			
Date Extracted	Not Given	Not Given	Not Given
Elapsed Time			
Date Analyzed	Not Given	Not Given	Not Given
Elapsed Time			

TABLE N-7
Site 2
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Soil Samples

	BH1-SS1	BH1-SS2	BH1-SS4	BH1-SS5	BH1-SS6	BH12-SS1	BH12-SS4	BH12-SS6	BH12-SS9	BH1-R SS1
	0-2	2-4	6-8	8-10	10-12	0-2	6-8	10-12	16-18	0-2
	7-29 88	7-29 88	7-29 88	7-29 88	7-30 88	7-30 88	7-30 88	7-30 88	7-30 88	8-30 88
	DANGB-2-BH1-SS1	DANGB-2-BH1-SS2	DANGB-2-BH1-SS4	DANGB-2-BH1-SS5	DANGB-2-BH1-SS6	DANGB-2-BH12-SS1	DANGB-2-BH12-SS4	DANGB-2-BH12-SS6	DANGB-2-BH12-SS9	DANGB-2-BH1-SS1
	88071554	88071553	88071552	88071555	88081589	88081590	88081591	88081592	88081593	88092215

Date Collected	29 Jul 88	29 Jul 88	29 Jul 88	29 Jul 88	30 Jul 88	30 Jul 88	30 Jul 88	30 Jul 88	30 Jul 88	30 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)										
Date Analyzed	Sample	Sample	Sample	Sample	Sample	Sample	Sample	Sample	Sample	8 Sep 88
Elapsed Time	Broken	Broken	Broken	Broken	Broken	Broken	Broken	Broken	Broken	9 Days
2nd Column	Sample	Sample	Sample	Sample	Sample	Sample	Sample	Sample	Sample	9 Sep 88
Elapsed Time	Broken	Broken	Broken	Broken	Broken	Broken	Broken	Broken	Broken	10 Days
AROMATIC VOLATILE ORGANICS (SW8020)										
Date Analyzed	Sample	Sample	Sample	Sample	Sample	Sample	Sample	Sample	Sample	8 Sep 88
Elapsed Time	Broken	Broken	Broken	Broken	Broken	Broken	Broken	Broken	Broken	9 Days
2nd Column	Sample	Sample	Sample	Sample	Sample	Sample	Sample	Sample	Sample	9 Sep 88
Elapsed Time	Broken	Broken	Broken	Broken	Broken	Broken	Broken	Broken	Broken	10 Days
PESTICIDES AND PCBs										
Date Extracted	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	Analysis Not Requested
Elapsed Time	6 Days	6 Days	6 Days	6 Days	5 Days	5 Days	5 Days	5 Days	5 Days	
Date Analyzed	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	Analysis Not Requested
Elapsed Time	11 Days	11 Days	11 Days	11 Days	10 Days	10 Days	10 Days	10 Days	10 Days	
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)										
Date Extracted	3 Aug 88	3 Aug 88	3 Aug 88	3 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	Analysis Cancelled
Elapsed Time	5 Days	5 Days	5 Days	5 Days	6 Days	6 Days	6 Days	6 Days	6 Days	
Date Analyzed	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	19 Aug 88	19 Aug 88	19 Aug 88	19 Aug 88	19 Aug 88	Analysis Cancelled
Elapsed Time	6 Days	6 Days	6 Days	6 Days	20 Days	20 Days	20 Days	20 Days	20 Days	

TABLE N-7
Continued

	BH1 R-SS2	BH1 R-SS3	BH1 R-SS4	BH1 R-SS5	BH1 R-SS6	BH1 R-SS7	BH2 R-SS1	BH2 R-SS2	BH2 R-SS3	BH2 R-SS4
	2-4	6-8	8-10	10-12	15-17	22-24	0-2	5-6	10-12	14-15
	8-30-88	8-30-88	8-30-88	8-30-88	8-30-88	8-30-88	8-30-88	8-30-88	8-30-88	8-30-88
	DANGH-2-BH1-SS2	DANGH-2-BH1-SS3	DANGH-2-BH1-SS4	DANGH-2-BH1-SS5	DANGH-2-BH1-SS6	DANGH-2-BH1-SS7	DANGH-2-BH2-SS1	DANGH-2-BH2-SS2	DANGH-2-BH2-SS3	DANGH-2-BH2-SS4
	88092216	88092218	88092217	88092219	88092223	88092224	88092220	88092221	88092222	88092225
Date Collected	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)										
Date Analyzed	8 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	11 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	11 Sep 88
Elapsed Time	9 Days	10 Days	10 Days	10 Days	10 Days	12 Days	10 Days	10 Days	10 Days	12 Days
2nd Column	9 Sep 88	9 Sep 88	9 Sep 88	10 Sep 88	11 Sep 88	9 Sep 88	10 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88
Elapsed Time	10 Days	10 Days	10 Days	11 Days	12 Days	10 Days	11 Days	10 Days	10 Days	10 Days
AROMATIC VOLATILE ORGANICS (SW8020)										
Date Analyzed	8 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	11 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	11 Sep 88
Elapsed Time	9 Days	10 Days	10 Days	10 Days	10 Days	12 Days	10 Days	10 Days	10 Days	12 Days
2nd Column	10 Sep 88	10 Sep 88	10 Sep 88	10 Sep 88	11 Sep 88	9 Sep 88	11 Sep 88	11 Sep 88	11 Sep 88	9 Sep 88
Elapsed Time	11 Days	11 Days	11 Days	11 Days	12 Days	10 Days	12 Days	12 Days	12 Days	10 Days
PESTICIDES AND PCBs (SW8080)										
Date Extracted	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
TOTAL PETROLEUM HYDROCARBONS (EPA 416.1)										
Date Extracted	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested

III2 R-SS5	III2 R-SS6	MW12A-SS1	MW12A-SS1 DUP	MW12A-SS3	MW12A-SS5	MW13A-SS1	MW13A-SS3	MW13A-SS4	MW37-SS1
20-22	21-25	0-2	0-2	5-15	15-20	0-2	8-10	14-15	0-1
8-30-88	8-30 88	8-5 88	8-5-88	8-5 88	8-5-88	8-5-88	8-5-88	8-5-88	8-15 88
DANGB-2 III2-SS5	DANGB-2 III2-SS6	DANGB-2 MW12-SS5	DANGB-2 MW12-SS	DANGB-2 MW12 SS	DANGB-2 MW12-SS	DANGB-2 MW12-SS	DANGB-2 MW13-SS	DANGB-2 MW13-SS	DANGB-2 MW37 SS
88092226	88092226	88081661	88081664	88081662	88081663	88081692	88081693	88081694	88081883

Date Collected	30 Aug 88	30 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	15 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)	Date Analyzed Elapsed Time	10 Sep 88 11 Days	ANALYZE WITHIN 14 DAYS OF COLLECTION						
			16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	23 Aug 88 8 Days
	2nd Column Elapsed Time	11 Sep 88 12 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	23 Aug 88 8 Days
			ANALYZE WITHIN 14 DAYS OF COLLECTION						
	Date Analyzed Elapsed Time	10 Sep 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	23 Aug 88 8 Days
			16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	16 Aug 88 11 Days	24 Aug 88 9 Days
PESTICIDES AND PCB's (SW8080)	Date Extracted Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
			EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION						
	Date Analyzed Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
			NO HOLDING TIME SPECIFIED						
	Date Extracted Elapsed Time	22 Sep 88 23 Days	15 Aug 88 10 Days	15 Aug 88 10 Days	15 Aug 88 10 Days	15 Aug 88 10 Days	15 Aug 88 10 Days	29 Aug 88 24 Days	9 Sep 88 25 Days
			19 Aug 88 14 Days	19 Aug 88 14 Days	19 Aug 88 14 Days	19 Aug 88 14 Days	19 Aug 88 14 Days	31 Aug 88 26 Days	11 Sep 88 27 Days

TABLE N-7
Continued

MW37-SS2 5-6 8-15-88 DANGIB-2-MW37-SS 88081884	MW37-SS2 DUP 5-6 8-15-88 DANGIB-2-MW37-SS 88081887	MW37-SS3 16-17 8-15-88 DANGIB-2-MW37-SS 88081885	MW37-SS4 17-18 8-15-88 DANGIB-2-MW37-SS 88081886	MW38-SS1 0-1-5 8-13-88 DANGIB-2-MW38-SS 88081877	MW38-SS2 9-10-5 8-13-88 DANGIB-2-MW38-SS 88081878	MW38-SS3 17-19 8-13-88 DANGIB-2-MW38-SS 88081879	MW39-SS1 0-1 8-15-88 DANGIB-2-MW39-SS 88081888	MW39-SS2 5-6 8-15-88 DANGIB-2-MW39-SS 88081889	MW39-SS3 21-22 8-15-88 DANGIB-2-MW39-SS 88081890
Date Collected	15 Aug 88	15 Aug 88	15 Aug 88	13 Aug 88	13 Aug 88	13 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION								
Date Analyzed	23 Aug 88	23 Aug 88	23 Aug 88	23 Aug 88	23 Aug 88	23 Aug 88	24 Aug 88	24 Aug 88	25 Aug 88
Elapsed Time	8 Days	8 Days	8 Days	10 Days	10 Days	10 Days	9 Days	9 Days	10 Days
2nd Column	23 Aug 88	24 Aug 88	24 Aug 88	22 Aug 88	22 Aug 88	23 Aug 88	23 Aug 88	24 Aug 88	23 Aug 88
Elapsed Time	8 Days	9 Days	9 Days	9 Days	9 Days	10 Days	8 Days	9 Days	8 Days
AROMATIC VOLATILE ORGANICS (SW8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION								
Date Analyzed	23 Aug 88	23 Aug 88	23 Aug 88	23 Aug 88	23 Aug 88	23 Aug 88	24 Aug 88	23 Aug 88	25 Aug 88
Elapsed Time	8 Days	8 Days	8 Days	10 Days	10 Days	10 Days	9 Days	8 Days	10 Days
2nd Column	23 Aug 88	24 Aug 88	24 Aug 88	23 Aug 88	23 Aug 88	23 Aug 88	24 Aug 88	24 Aug 88	25 Aug 88
Elapsed Time	8 Days	9 Days	9 Days	10 Days	10 Days	10 Days	9 Days	9 Days	10 Days
PESTICIDES AND PCBs (SW8080)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)	NO HOLDING TIME SPECIFIED								
Date Extracted	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88
Elapsed Time	25 Days	25 Days	25 Days	27 Days	27 Days	27 Days	25 Days	25 Days	25 Days
Date Analyzed	11 Sep 88	11 Sep 88	11 Sep 88	11 Sep 88	11 Sep 88	11 Sep 88	11 Sep 88	11 Sep 88	11 Sep 88
Elapsed Time	27 Days	27 Days	27 Days	29 Days	29 Days	29 Days	27 Days	27 Days	27 Days

TABLE N-7
Continued

	MW40-SS1	MW40-SS2	MW40-SS3	MW41-SS1	MW41-SS1 DUP	MW41-SS2	MW41-SS2 DUP	MW41-SS3
	0-1	7-8	15.5-16.5	0-5	0-5	5-15	5-15	15-20
	8-16-88	8-16-88	8-16-88	8-17-88	8-17-88	8-17-88	8-17-88	8-17-88
	DANGIB-2-MW40-SS	DANGIB-2-MW40-SS	DANGIB-2-MW40-SS	DANGIB-2-MW41-SS	DANGIB-2-MW41-SS	DANGIB-2-MW41-SS	DANGIB-2-MW41-SS	DANGIB-2-MW41-SS
	88081878	88081879	88081900	88081918	88081940	88081939	88081942	88081941
Date Collected	16 Aug 88	16 Aug 88	16 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)								
Date Analyzed	26 Aug 88	26 Aug 88	26 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	26 Aug 88	26 Aug 88
Elapsed Time	10 Days	10 Days	10 Days	12 Days	12 Days	12 Days	9 Days	9 Days
2nd Column	22 Aug 88	22 Aug 88	22 Aug 88	25 Aug 88	25 Aug 88	25 Aug 88	30 Aug 88	30 Aug 88
Elapsed Time	6 Days	6 Days	6 Days	8 Days	8 Days	8 Days	13 Days	13 Days
AROMATIC VOLATILE ORGANICS (SW8020)								
Date Analyzed	26 Aug 88	26 Aug 88	26 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	26 Aug 88	26 Aug 88
Elapsed Time	10 Days	10 Days	10 Days	12 Days	12 Days	12 Days	9 Days	9 Days
2nd Column	22 Aug 88	25 Aug 88	22 Aug 88	25 Aug 88	25 Aug 88	25 Aug 88	30 Aug 88	30 Aug 88
Elapsed Time	6 Days	9 Days	6 Days	8 Days	8 Days	8 Days	13 Days	13 Days
PESTICIDES AND PCBs (SW8080)								
Date Extracted	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
TOTAL PETROLIUM HYDROCARBONS (TPH 418.1)								
Date Extracted	12 Sep 88	12 Sep 88	12 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88
Elapsed Time	27 Days	27 Days	27 Days	29 Days	29 Days	29 Days	29 Days	29 Days
Date Analyzed	13 Sep 88	13 Sep 88	13 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88
Elapsed Time	28 Days	28 Days	28 Days	30 Days	30 Days	30 Days	30 Days	30 Days

TABLE N-7
Continued

	BH1-SS1 0-2 7-29-88 DANGB-2-BH1-SS1 88071554	BH1-SS2 2-4 7-29-88 DANGB-2-BH1-SS1 88071553	BH1-SS4 6-8 7-29-88 DANGB-2-BH1-SS2 88071552	BH1-SS5 8-10 7-29-88 DANGB-2-BH1-SS4 88071555	BH1-SS6 10-12 7-30-88 DANGB-2-BH1-SS5 88081589	BH2-SS1 0-2 7-30-88 DANGB-2-BH2-SS1 88081590	BH2-SS4 6-8 7-30-88 DANGB-2-BH2-SS4 88081591	BH2-SS6 10-12 7-30-88 DANGB-2-BH2-SS6 88081592	BH2-SS9 16-18 7-30-88 DANGB-2-BH2-SS9 88081593	BH1 R-SS1 0-2 8-30-88 DANGB-2-BH1-SS1 88092215
Date Collected	29 Jul 88	29 Jul 88	29 Jul 88	29 Jul 88	30 Jul 88	30 Jul 88	30 Jul 88	30 Jul 88	30 Jul 88	30 Aug 88
Arsenic (SW7600)										
Date Analyzed	17 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	Analysis Not Requested
Elapsed Time	19 Days	19 Days	19 Days	19 Days	17 Days	17 Days	17 Days	17 Days	17 Days	
Barium (SW6010)										
Date Analyzed	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	1 Aug 88	1 Aug 88	1 Aug 88	1 Aug 88	1 Aug 88	Analysis Cancelled
Elapsed Time	11 Days	11 Days	11 Days	11 Days	2 Days	2 Days	2 Days	2 Days	2 Days	
Cadmium (SW7131)										
Date Analyzed	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	9 Aug 88	Analysis Cancelled
Elapsed Time	17 Days	17 Days	17 Days	17 Days	10 Days	10 Days	10 Days	10 Days	10 Days	
Chromium (SW7191)										
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Cancelled
Elapsed Time										
Lead (SW7421)										
Date Analyzed	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	Analysis Cancelled
Elapsed Time	17 Days	17 Days	17 Days	17 Days	16 Days	16 Days	16 Days	16 Days	16 Days	
Mercury (SW7471)										
Date Analyzed	12 Aug 88	12 Aug 88	12 Aug 88	12 Aug 88	12 Aug 88	12 Aug 88	12 Aug 88	12 Aug 88	12 Aug 88	Analysis Not Requested
Elapsed Time	14 Days	14 Days	14 Days	14 Days	13 Days	13 Days	11 Days	13 Days	13 Days	
PERCENT MOISTURE										
Date Analyzed	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	4 Aug 88	13 Sep 88
Elapsed Time	6 Days	6 Days	6 Days	6 Days	5 Days	5 Days	5 Days	5 Days	5 Days	14 Days
SEMI-VOLATILE ORGANICS (SW8270)										
Date Analyzed	2 Aug 88	2 Aug 88	2 Aug 88	2 Aug 88	2 Aug 88	2 Aug 88	2 Aug 88	2 Aug 88	2 Aug 88	Analysis Cancelled
Elapsed Time	4 Days	4 Days	4 Days	4 Days	3 Days	3 Days	3 Days	3 Days	3 Days	
Date Analyzed	25 Aug 88	24 Aug 88	24 Aug 88	19 Aug 88	20 Aug 88	25 Aug 88	24 Aug 88	23 Aug 88	24 Aug 88	Analysis Cancelled
Elapsed Time	27 Days	24 Days	26 Days	21 Days	21 Days	26 Days	25 Days	21 Days	25 Days	

TABLE N-7
Continued

	BH1 R-SS2 2-4 8-30-88 DANGB-2-BH1-SS2 88092216	BH1 R-SS3 6-8 8-30-88 DANGB-2-BH1-SS3 88092218	BH1 R-SS4 8-10 8-30-88 DANGB-2-BH1-SS4 88092217	BH1 R-SS5 10-12 8-30-88 DANGB-2-BH1-SS5 88092219	BH1 R-SS6 15-17 8-30-88 DANGB-2-BH1-SS6 88092223	BH1 R-SS7 22-24 8-30-88 DANGB-2-BH1-SS7 88092224	BH2 R-SS1 0-2 8-30-88 DANGB-2-BH2-SS1 88092220	BH2 R-SS2 5-6 8-30-88 DANGB-2-BH2-SS2 88092221	BH2 R-SS3 10-12 8-30-88 DANGB-2-BH2-SS3 88092222	BH2 R-SS4 14-15 8-30-88 DANGB-2-BH2-SS4 88092225
Date Collected	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88
Artenic (SW7060) Date Analyzed Elapsed Time	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested
Barium (SW6010) Date Analyzed Elapsed Time	Analysis Cancelled	Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled
Cadmium (SW7131) Date Analyzed Elapsed Time	Analysis Cancelled	Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled
Chromium (SW7191) Date Analyzed Elapsed Time	Analysis Cancelled	Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled
Lead (SW7421) Date Analyzed Elapsed Time	Analysis Cancelled	Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Cancelled
Mercury (SW7471) Date Analyzed Elapsed Time	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested
PERCENT MOISTURE Date Analyzed Elapsed Time	13 Sep 88 14 Days	13 Sep 88 14 Days	13 Sep 88 14 Days	13 Sep 88 14 Days	9 Sep 88 10 Days	9 Sep 88 10 Days	13 Sep 88 14 Days	13 Sep 88 14 Days	13 Sep 88 14 Days	9 Sep 88 10 Days
SEMI-VOLATILE ORGANICS (SW8270) Date Extracted Elapsed Time	Analysis Cancelled	Analysis Cancelled	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION Analysis Cancelled	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION Analysis Cancelled	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION Analysis Cancelled	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION Analysis Cancelled	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION Analysis Cancelled	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION Analysis Cancelled	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION Analysis Cancelled	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION Analysis Cancelled
Date Analyzed Elapsed Time	Analysis Cancelled	Analysis Cancelled	Analysis Cancelled	Analysis Cancelled	20 Oct 88 51 Days	20 Oct 88 51 Days	20 Oct 88 51 Days	20 Oct 88 51 Days	20 Oct 88 51 Days	20 Oct 88 51 Days

TABLE N-7
Continued

Date Collected	I H2-SS5 R	BH2 R-SS6	MW12A-SSI	MW12A-SSI DUP	MW12A-SS5	MW13A-SSI	MW13A-SS3	M H13A-SS4	MW37-SS1
	20-22 8-30-88 DANGIB-2-BH2-SS5 88092226	24-25 8-30-88 DANGIB-2-BH2-SS6 88092227	0 2 8-5-88 DANGIB-2-MW12-SS5 88081661	0 2 8-5-88 DANGIB-2-MW12-SS5 88081664	15-20 8-5-88 DANGIB-2-MW12-SS5 88081663	0-2 8-5-88 DANGIB-2-MW13-SS5 88081692	8-10 8-5-88 DANGIB-2-MW13-SS5 88081693	14-15 8-5-88 DANGIB-2-MW13-SS5 88081694	0-1 8-15-88 DANGIB-2-MW37-SS5 88081883
Arsenic (SV7060)									
Date Analyzed	30 Aug 88	30 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	5 Aug 88	15 Aug 88
Elapsed Time	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION Analysis Not Requested	Analysis Not Requested
Barium (SV6010)									
Date Analyzed	20 Oct 88	20 Oct 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	18 Sep 88
Elapsed Time	51 Days	51 Days	33 Days	33 Days	33 Days	33 Days	33 Days	33 Days	34 Days
Cadmium (SV7131)									
Date Analyzed	20 Oct 88	20 Oct 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	16 Sep 88
Elapsed Time	51 Days	51 Days	33 Days	33 Days	33 Days	33 Days	33 Days	33 Days	32 Days
Chromium (SV7191)									
Date Analyzed	20 Oct 88	20 Oct 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	16 Sep 88
Elapsed Time	51 Days	51 Days	33 Days	33 Days	33 Days	33 Days	33 Days	33 Days	32 Days
Lead (SV7421)									
Date Analyzed	25 Oct 88	20 Oct 88	12 Sep 88	12 Sep 88	12 Sep 88	13 Sep 88	13 Sep 88	13 Sep 88	23 Sep 88
Elapsed Time	56 Days	51 Days	38 Days	38 Days	38 Days	39 Days	39 Days	39 Days	39 Days
Mercury (SV7471)									
Date Analyzed	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
PERCENT MOISTURE									
Date Analyzed	9 Sep 88	9 Sep 88	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	21 Aug 88
Elapsed Time	10 Days	10 Days	10 Days	10 Days	10 Days	10 Days	10 Days	10 Days	6 Days
SEMI-VOLATILE ORGANICS (SV8270)									
Date Extracted	29 Oct 88	10 Sep 88	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	25 Aug 88
Elapsed Time	60 Days	11 Days	11 Days	11 Days	11 Days	11 Days	11 Days	11 Days	10 Days
Date Analyzed	2 Nov 88	22 Oct 88	14 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88	18 Sep 88	18 Sep 88	1 Oct 88
Elapsed Time	64 Days	53 Days	10 Days	41 Days	41 Days	41 Days	44 Days	44 Days	46 Days

TABLE N-7
Continued

MW37-SS2 5-6 8-15-88 DANGB-2-MW37-SS 88081884	MW37-SS2 DUP 5-6 8-15-88 DANGB-2-MW37-SS 88081887	MW37-SS3 16-17 8-15-88 DANGB-2-MW37-SS 88081885	MW37-SS4 17-18 8-15-88 DANGB-2-MW37-SS 88081886	MW38-SS1 0-1-5 8-13-88 DANGB-2-MW38-SS 88081877	MW38-SS2 9-10-5 8-13-88 DANGB-2-MW38-SS 88081878	MW38-SS3 17-19 8-13-88 DANGB-2-MW38-SS 88081879	MW39-SS1 0-1 8-15-88 DANGB-2-MW39-SS 88081888	MW39-SS2 5-6 8-15-88 DANGB-2-MW39-SS 88081889	MW39-SS3 21-22 8-15-88 DANGB-2-MW39-SS 88081890
15 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88	13 Aug 88	13 Aug 88	13 Aug 88	15 Aug 88	15 Aug 88	15 Aug 88
Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
18 Sep 88 34 Days	18 Sep 88 34 Days	18 Sep 88 34 Days	18 Sep 88 34 Days	18 Sep 88 36 Days	18 Sep 88 36 Days	18 Sep 88 36 Days	18 Sep 88 34 Days	18 Sep 88 34 Days	18 Sep 88 34 Days
16 Sep 88 32 Days	16 Sep 88 32 Days	16 Sep 88 32 Days	16 Sep 88 32 Days	16 Sep 88 34 Days	16 Sep 88 34 Days	16 Sep 88 34 Days	16 Sep 88 32 Days	16 Sep 88 32 Days	16 Sep 88 32 Days
23 Sep 88 39 Days	23 Sep 88 39 Days	23 Sep 88 39 Days	23 Sep 88 39 Days	23 Sep 88 41 Days	23 Sep 88 41 Days	23 Sep 88 41 Days	23 Sep 88 39 Days	23 Sep 88 39 Days	23 Sep 88 39 Days
Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
21 Aug 88 6 Days	21 Aug 88 6 Days	21 Aug 88 6 Days	21 Aug 88 6 Days	21 Aug 88 8 Days	21 Aug 88 8 Days	21 Aug 88 8 Days	21 Aug 88 6 Days	21 Aug 88 6 Days	21 Aug 88 6 Days
25 Aug 88	25 Aug 88	25 Aug 88	25 Aug 88	19 Aug 88 6 Days	19 Aug 88 6 Days	18 Oct 88 66 Days	25 Aug 88 10 Days	26 Aug 88 11 Days	26 Aug 88 11 Days
1 Oct 88 46 Days	2 Nov 88 78 Days	1 Oct 88 46 Days	3 Oct 88 47 Days	30 Aug 88 17 Days	30 Aug 88 17 Days	27 Oct 88 75 Days	3 Oct 88 49 Days	2 Nov 88 78 Days	5 Oct 88 40 Days

TABLE N-7
Continued

MW40-SS1	MW40-SS2	MW10-SS3	MW41-SS1	MW41-SS1 DUP	MW41-SS2	MW41-SS2 DUP	MW41-SS3
0-1	7-8	15-16.5	0-5	0-5	5-15	5-15	15-20
8-16-88	8-16-88	8-16-88	8-17-88	8-17-88	8-17-88	8-17-88	8-17-88
DANGH-2-MW40-SS	DANGH-2-MW40-SS	DANGH-2-MW40-SS	DANGH-2-MW41-SS	DANGH-2-MW41-SS1	DANGH-2-MW41-SS2	DANGH-2-MW41-SS2	DANGH-2-MW41-SS3
88081898	88081899	88081900	88081938	88081940	88081939	88081942	88081941
16 Aug 88	16 Aug 88	16 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88
Arsenic (SW7060)							
Date Analyzed	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Requested	Requested	Requested	Requested	Requested	Requested	Requested
Barium (SW6010)							
Date Analyzed	7 Sep 88	7 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88
Elapsed Time	22 Days	22 Days	32 Days	32 Days	32 Days	32 Days	32 Days
Cadmium (SW7131)							
Date Analyzed	7 Sep 88	7 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88
Elapsed Time	22 Days	22 Days	30 Days	30 Days	30 Days	30 Days	30 Days
Chromium (SW7191)							
Date Analyzed	7 Sep 88	7 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88
Elapsed Time	22 Days	22 Days	30 Days	30 Days	30 Days	30 Days	30 Days
Lead (SW7421)							
Date Analyzed	21 Sep 88	21 Sep 88	3 Oct 88	3 Oct 88	3 Oct 88	3 Oct 88	3 Oct 88
Elapsed Time	36 Days	36 Days	47 Days	47 Days	47 Days	47 Days	47 Days
Mercury (SW7471)							
Date Analyzed	Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Requested	Requested	Requested	Requested	Requested	Requested	Requested
PERCENT MOISTURE							
Date Analyzed	24 Aug 88	24 Aug 88	24 Aug 88	24 Aug 88	24 Aug 88	24 Aug 88	24 Aug 88
Elapsed Time	8 Days	8 Days	7 Days	7 Days	7 Days	7 Days	7 Days
SEMI-VOLATILE ORGANICS (SW8270)							
Date Analyzed	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88
Elapsed Time	10 Days	10 Days	9 Days	9 Days	9 Days	9 Days	9 Days
Date Analyzed	5 Oct 88	5 Oct 88	3 Oct 88	5 Oct 88	21 Nov 88	2 Nov 88	1 Nov 88
Elapsed Time	39 Days	39 Days	47 Days	49 Days	96 Days	77 Days	76 Days

TABLE N-8
Site 2
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Ground-Water Samples

	MW 1	MW 2	MW 4	MW 5	MW 5 + B	MW 6	MW 7	GW 2 A	GW 2-A DUP	GW 2-A FB
	0-19-88	9-19-88	9-21-88	9-22-88	9-22-88	9-22-88	9-22-88	9-21-88	9-21-88	9-21-88
	DANGB-2-MW1-GW-1	DANGB-2-MW1-GW-1	DANGB-2-MW4-GW-1	DANGB-2-MW5-GW-1	DANGB-2-MW5-GW-1	DANGB-2-MW6-GW-1	DANGB-2-MW7-GW-1	DANGB-2-MW2A-GW-1	DANGB-2-MW56-GW-1	DANGB FB13
	88092524	88092523	88092575	88092614	88092618	88092613	88092612	88092573	88092574	88092580
Date Collected	19 Sep 88	19 Sep 88	21 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88
ANALYZE WITHIN 14 DAYS OF COLLECTION										
HALOGENATED VOLATILE ORGANICS (SW8010)										
Date Analyzed	23 Sep 88	27 Sep 88	23 Sep 88	29 Sep 88	29 Sep 88	27 Sep 88	27 Sep 88	23 Sep 88	23 Sep 88	26 Sep 88
Elapsed Time	4 Days	8 Days	2 Days	7 Days	7 Days	5 Days	5 Days	2 Days	2 Days	5 Days
2nd Column
Elapsed Time
ANALYZE WITHIN 14 DAYS OF COLLECTION										
AROMATIC VOLATILE ORGANICS (SW8020)										
Date Analyzed	23 Sep 88	27 Sep 88	23 Sep 88	29 Sep 88	30 Sep 88	30 Sep 88	27 Sep 88	23 Sep 88	23 Sep 88	26 Sep 88
Elapsed Time	4 Days	8 Days	2 Days	7 Days	8 Days	8 Days	5 Days	2 Days	2 Days	5 Days
2nd Column
Elapsed Time
NO HOLDING TIME SPECIFIED										
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)										
Date Extracted	Not	5 Oct 88	1 Oct 88	1 Oct 88	Analysis Not	1 Oct 88	1 Oct 88	4 Oct 88	1 Oct 88	Analysis Not
Elapsed Time	Given	16 Days	10 Days	9 Days	Requested	9 Days	9 Days	13 Days	10 Days	Requested
Date Analyzed	8 Oct 88	8 Oct 88	10 Oct 88	10 Oct 88	Analysis Not	10 Oct 88	10 Oct 88	8 Oct 88	10 Oct 88	Analysis Not
Elapsed Time	19 Days	19 Days	19 Days	18 Days	Requested	18 Days	18 Days	17 Days	19 Days	Requested

TABLE N-8
(Continued)

	GW 2 B	GW 2 C	GW 2 C 1-B	GW 2 D	GW 2 E	MW37	MW38	MW39	MW40	MW40 DUP
	9-22-88	9-21-88	9-21-88	9-21-88	9-20-88	9-20-88	9-22-88	9-21-88	9-20-88	9-20-88
	88092616	88092576	88092581	88092577	88092549	88092547	88092615	88092578	88092550	88092551
	DANGB-2 GW2B GW-1	DANGB-2 GW2C-GW-1	DANGB-2 GW2C-GW-1	DANGB-2 GW2D GW-1	DANGB-2 GW2E-GW-1	DANGB-2-MW37-GW-1	DANGB-2-MW38-GW-1	DANGB-2-MW39-GW-1	DANGB-2-MW40-GW-1	DANGB-2-MW55-GW-1
Date Collected	22 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	20 Sep 88	20 Sep 88	22 Sep 88	21 Sep 88	20 Sep 88	20 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)										
Date Analyzed	27 Sep 88	23 Sep 88	28 Sep 88	23 Sep 88	27 Sep 88	23 Sep 88	29 Sep 88	23 Sep 88	28 Sep 88	23 Sep 88
Elapsed Time	5 Days	2 Days	7 Days	2 Days	7 Days	3 Days	7 Days	2 Days	8 Days	3 Days
2nd Column	-----	-----	30 Sep 88	-----	28 Sep 88	27 Sep 88	-----	-----	26 Sep 88	28 Sep 88
Elapsed Time	-----	-----	9 Days	-----	8 Days	7 Days	-----	-----	6 Days	8 Days
AROMATIC VOLATILE ORGANICS (SW8260)										
Date Analyzed	3 Oct 88	23 Sep 88	28 Sep 88	23 Sep 88	27 Sep 88	23 Sep 88	29 Sep 88	23 Sep 88	28 Sep 88	23 Sep 88
Elapsed Time	11 Days	2 Days	7 Days	2 Days	7 Days	3 Days	7 Days	2 Days	8 Days	3 Days
2nd Column	-----	-----	-----	-----	28 Sep 88	-----	-----	-----	-----	-----
Elapsed Time	-----	-----	-----	-----	8 Days	-----	-----	-----	-----	-----
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)										
Date Extracted	1 Oct 88	1 Oct 88	Analysis Not Requested	1 Oct 88	5 Oct 88	5 Oct 88	1 Oct 88	1 Oct 88	5 Oct 88	5 Oct 88
Elapsed Time	9 Days	10 Days	-----	10 Days	15 Days	15 Days	9 Days	10 Days	15 Days	15 Days
Date Analyzed	10 Oct 88	10 Oct 88	Analysis Not Requested	8 Oct 88	8 Oct 88	8 Oct 88	10 Oct 88	10 Oct 88	8 Oct 88	8 Oct 88
Elapsed Time	18 Days	19 Days	-----	17 Days	18 Days	18 Days	18 Days	19 Days	18 Days	18 Days

TABLE N-8
(Continued)

MIW41 9-20-88		HIR1 9-20-88		HIR2 9-21-88		TIR2 9-22-88	
DANGB-2MIW41-GW-1		DANGB HIR0		DANGB HIR10		DANGB TIR11	
88092548		88092546		88092779		88092582	
20 Sep 88		20 Sep 88		21 Sep 88		16 Sep 88	
Date Collected		Date Collected		Date Collected		Date Collected	
HALOGENATED VOLATILE ORGANICS (SW8010)		ANALYZE WITHIN 14 DAYS OF COLLECTION		ANALYZE WITHIN 14 DAYS OF COLLECTION		ANALYZE WITHIN 14 DAYS OF COLLECTION	
Date Analyzed		26 Sep 88		23 Sep 88		28 Sep 88	
Elapsed Time		3 Days		6 Days		12 Days	
2nd Column		27 Sep 88		28 Sep 88		29 Sep 88	
Elapsed Time		7 Days		7 Days		13 Days	
AROMATIC VOLATILE ORGANICS (SW8020)		ANALYZE WITHIN 14 DAYS OF COLLECTION		ANALYZE WITHIN 14 DAYS OF COLLECTION		ANALYZE WITHIN 14 DAYS OF COLLECTION	
Date Analyzed		23 Sep 88		23 Sep 88		28 Sep 88	
Elapsed Time		3 Days		2 Days		12 Days	
2nd Column		28 Sep 88		28 Sep 88		28 Sep 88	
Elapsed Time		6 Days		6 Days		6 Days	
TOTAL PETROLEUM HYDROCARBONS (FPA 418.1)		NO HOLDING TIME SPECIFIED		NO HOLDING TIME SPECIFIED		NO HOLDING TIME SPECIFIED	
Date Analyzed		5 Oct 88		1 Oct 88		1 Oct 88	
Elapsed Time		15 Days		10 Days		10 Days	
Date Analyzed		8 Oct 88		Not Given		Not Given	
Elapsed Time		18 Days		Not Given		Not Given	

TABLE N-8
(Continued)

	MW 1 9-19-88 DANGB-2-MW1-GW-1 88092524	MW 2 9-19-88 DANGB-2-MW1-GW-1 88092523	MW 4 9-21-88 DANGB-2-MW4-GW-1 88092575	MW 5 9-22-88 DANGB-2-MW5-GW-1 88092614	MW 5 FB 9-22-88 DANGB FB15 88092618	MW 6 9-22-88 DANGB-2-MW6-GW-1 88092613	MW 7 9-22-88 DANGB-2-MW7-GW-1 88092612	GW 2-A 9-21-88 DANGB-2-GW2A-GW-1 88092573	GW 2-A DUP 9-21-88 DANGB-2-MW56-GW-1 88092574	GW 2-A FB 9-21-88 DANGB FB13 88092580
Date Collected	19 Sep 88	19 Sep 88	21 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88
Barium (SW610)										
Date Analyzed	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88
Elapsed Time	24 Days	24 Days	22 Days	21 Days	21 Days	21 Days	21 Days	21 Days	21 Days	Analysis Not Requested
Cadmium (SW7131)										
Date Analyzed	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88
Elapsed Time	37 Days	37 Days	35 Days	34 Days	34 Days	34 Days	34 Days	34 Days	34 Days	Analysis Not Requested
Chromium (SW7191)										
Date Analyzed	16 Oct 88	16 Oct 88	16 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88
Elapsed Time	27 Days	27 Days	25 Days	27 Days	27 Days	27 Days	27 Days	24 Days	24 Days	Analysis Not Requested
Lead (SW7421)										
Date Analyzed	21 Oct 88	21 Oct 88	21 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	21 Oct 88	21 Oct 88	21 Oct 88
Elapsed Time	32 Days	32 Days	30 Days	32 Days	32 Days	32 Days	32 Days	29 Days	29 Days	Analysis Not Requested
SEMI-VOLATILE ORGANICS (EPA 625)										
Date Extracted	24 Sep 88	24 Sep 88	27 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	27 Oct 88	27 Oct 88	27 Oct 88
Elapsed Time	5 Days	5 Days	6 Days	6 Days	6 Days	6 Days	6 Days	36 Days	36 Days	Analysis Not Requested
Date Analyzed	31 Oct 88	31 Oct 88	5 Nov 88	7 Nov 88	7 Nov 88	7 Nov 88	6 Nov 88	5 Nov 88	30 Nov 88	30 Nov 88
Elapsed Time	42 Days	42 Days	45 Days	45 Days	45 Days	45 Days	44 Days	45 Days	61 Days	Analysis Not Requested

TABLE N-8
(Continued)

	GW 2-B 9-22-88 DANGB-2-GW2B-GW-1 88092616	GW 2-C 9-21-88 DANGB-2-GW2C-GW-1 88092576	GW 2-C FIB 9-21-88 DANGB FIB4 88092581	GW 2-D 9-21-88 DANGB-2-GW2D 88092577	GW 2-E 9-20-88 DANGB-2-GW2E 88092549	MW37 9-20-88 DANGB-2-MW37-GW-1 88092547	MW38 9-22-88 DANGB-2-MW38-GW-1 88092615	MW39 9-21-88 DANGB-2-MW39-GW-1 88092576	MW40 9-20-88 DANGB-2-MW40-GW-1 88092550	MW40 DUP 9-20-88 DANGB-2-MW55-GW-1 88092551
Date Collected	22 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	20 Sep 88	20 Sep 88	22 Sep 88	21 Sep 88	20 Sep 88	20 Sep 88
Barium (SW6010)										
Date Analyzed	13 Oct 88	13 Oct 88	Analysis Not Requested	13 Oct 88	13 Oct 88	13 Oct 88	21 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88
Elapsed Time	21 Days	22 Days		22 Days	23 Days	23 Days	29 Days	22 Days	23 Days	23 Days
Cadmium (SW7131)										
Date Analyzed	26 Oct 88	26 Oct 88	Analysis Not Requested	26 Oct 88	26 Oct 88	26 Oct 88	27 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88
Elapsed Time	34 Days	35 Days		35 Days	36 Days	36 Days	35 Days	35 Days	36 Days	36 Days
Chromium (SW7101)										
Date Analyzed	19 Oct 88	16 Oct 88	Analysis Not Requested	16 Oct 88	26 Oct 88	16 Oct 88	21 Oct 88	19 Oct 88	16 Oct 88	16 Oct 88
Elapsed Time	27 Days	25 Days		25 Days	36 Days	26 Days	29 Days	28 Days	26 Days	26 Days
Lead (SW7421)										
Date Analyzed	24 Oct 88	21 Oct 88	Analysis Not Requested	21 Oct 88	21 Oct 88	21 Oct 88	22 Oct 88	21 Oct 88	21 Oct 88	21 Oct 88
Elapsed Time	32 Days	30 Days		30 Days	31 Days	31 Days	30 Days	30 Days	31 Days	31 Days
SEMI-VOLATILE ORGANICS (EPA 625)										
Date Extracted	28 Sep 88	27 Sep 88	Analysis Not Requested	27 Sep 88	24 Sep 88	24 Sep 88	28 Sep 88	27 Sep 88	24 Sep 88	24 Sep 88
Elapsed Time	6 Days	6 Days		6 Days	4 Days	4 Days	6 Days	6 Days	4 Days	4 Days
Date Analyzed	6 Nov 88	30 Nov 88	Analysis Not Requested	5 Nov 88	2 Nov 88	1 Nov 88	7 Nov 88	6 Nov 88	3 Nov 88	23 Nov 88
Elapsed Time	44 Days	68 Days		45 Days	43 Days	42 Days	46 Days	46 Days	44 Days	64 Days

TABLE N-8
(Continued)

	MW41 9-20-88 DANGIB-2 MW41-GW-1 88092548	BR1 9-20-88 DANGIB BR1 88092546	BR2 9-21-88 DANGIB BR2 88092579	TB1 9-21-88 DANGIB-TB1 88092582	TB2 9-22-88 DANGIB-TB2 88092619
Date Collected	20 Sep 88	20 Sep 88	21 Sep 88	16 Sep 88	22 Sep 88
Barium (SW6010)					
Date Analyzed	13 Oct 88	13 Oct 88	13 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	23 Days	23 Days	22 Days		
Cadmium (SW7131)					
Date Analyzed	26 Oct 88	26 Oct 88	26 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	36 Days	36 Days	35 Days		
Chromium (SW7191)					
Date Analyzed	16 Oct 88	16 Oct 88	16 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	26 Days	26 Days	15 Days		
Lead (SW7421)					
Date Analyzed	21 Oct 88	21 Oct 88	21 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	31 Days	31 Days	30 Days		
SEMI-VOLATILE ORGANICS (1 PA 625)					
Date Extracted	24 Sep 88	24 Sep 88	27 Sep 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	4 Days	4 Days	6 Days		
Date Analyzed	1 Nov 88	1 Nov 88	6 Nov 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	42 Days	42 Days	46 Days		

TABLE N-9
Site 3
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Surface Water Samples

	SL8 9-26-88 DANGB-3-SL8-SW-1 88092807/88092766	SL9 9-26-88 DANGB-3-SL9-SW-1 88092772	SL10 9-26-88 DANGB-3-SL10-SW-1 88092767/88092806	SL10 DUP 9-26-88 DANGB-3-SL28-SW-1 88092765	SL10 FB 9-26-88 DANGB-FB19 88092774
Date Collected	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
HALOGENATED AND VOLATILE ORGANICS (SW8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	30 Sep 88	3 Oct 88	3 Oct 88	3 Oct 88	3 Oct 88
Elapsed Time	4 Days	7 Days	7 Days	7 Days	7 Days
2nd Collection	4 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	8 Days	8 Days	8 Days	8 Days	8 Days
AROMATIC VOLATILE ORGANICS (SW8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	30 Sep 88	30 Sep 88	3 Oct 88	3 Oct 88	3 Oct 88
Elapsed Time	4 Days	7 Days	7 Days	7 Days	7 Days
2nd Collection	4 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	8 Days	8 Days	8 Days	8 Days	8 Days
PESTICIDES AND PCBs (EPA 608)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION				
Date Extracted	30 Sep 88	3 Oct 88	3 Oct 88	30 Sep 88	Analysis Not Requested
Elapsed Time	4 Days	7 Days	7 Days	4 Days	
Date Analyzed	25 Oct 88	24 Oct 88	25 Oct 88	24 Oct 88	Analysis Not Requested
Elapsed Time	29 Days	28 Days	29 Days	28 Days	
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION				
Date Extracted	12 Oct 88	12 Oct 88	12 Oct 88	12 Oct 88	Analysis Not Requested
Elapsed Time	16 Days	16 Days	16 Days	16 Days	
Date Analyzed	21 Oct 88	21 Oct 88	21 Oct 88	21 Oct 88	Analysis Not Requested
Elapsed Time	25 Days	25 Days	25 Days	25 Days	

TABLE N-9
(Continued)

	SL8 9-26-88 DANGIR-3 SL8-SW-1 88092807	SL9 9-26-88 DANGIR-3 SL9 SW-1 88092772	SL10 9-26-88 DANGIR-3 SL10-SW-1 88092767/88092806	SL10 DUP 9-26-88 DANGIR-3 SL28-SW-1 88092765	SL10 FB 9-26-88 DANGIR-3 FB19 88092774
Date Collected	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
Analysis (SW700)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	21 Oct 88	21 Oct 88	21 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	25 Days	25 Days	25 Days		
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	2 Nov 88	2 Nov 88	2 Nov 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	37 Days	37 Days	37 Days		
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	31 Oct 88	31 Oct 88	31 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	35 Days	35 Days	35 Days		
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	21 Oct 88	22 Oct 88	21 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	25 Days	26 Days	25 Days		
Lead (SW7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	24 Oct 88	24 Oct 88	24 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	28 Days	28 Days	28 Days		
Mercury (SW7470)	ANALYZE WITHIN 28 DAYS OF COLLECTIONS				
Date Analyzed	22 Oct 88	22 Oct 88	22 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	26 Days	26 Days	26 Days		
SEMI-VOLATILE ORGANICS (EPA 625)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION				
Date Extracted	30 Sep 88	3 Oct 88	4 Oct 88	30 Sep 88	Analysis Not Requested
Elapsed Time	4 Days	7 Days	8 Days	4 Days	
Date Analyzed	9 Nov 88	23 Nov 88	11 Nov 88	10 Nov 88	Analysis Not Requested
Elapsed Time	44 Days	58 Days	46 Days	45 Days	

TABLE N-10
Site 3
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Sediment Samples

	SL8 9-26-88 DANGB-3 SL8-SD-1 88092805	SL9 9-26-88 DANGB-3 SL9-SD-1 88092804	SL10 9-26-88 DANGB-3 SL10-SD-1 88092803	SL10 DUP 9-26-88 DANGB-3 SL10-SD-1 88092802
Date Collected	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)				
Date Analyzed	6 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	10 Days	10 Days	10 Days	10 Days
2nd Column	6 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	10 Days	10 Days	10 Days	10 Days
AROMATIC VOLATILE ORGANICS (SW8020)				
Date Analyzed	6 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	10 Days	10 Days	10 Days	10 Days
2nd Column	6 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	10 Days	10 Days	10 Days	10 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)				
Date Extracted	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88
Elapsed Time	22 Days	22 Days	22 Days	22 Days
Date Analyzed	25 Oct 88	25 Oct 88	25 Oct 88	25 Oct 88
Elapsed Time	29 Days	29 Days	29 Days	29 Days

TABLE N-10
(Continued)

	SL8 9-26-88 DANGB-3-SL8 SD-1 88092805	SL9 9-26-88 DANGB-3-SL9-SD-1 88092804	SL10 9-26-88 DANGB-3-SL10 SD-1 88092803	SL10 DUP 9-26-88 DANGB-3-SL28-SD-1 88092802
Date Collected	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
Arsenic (SW7060)				
Date Analyzed	18 Oct 88	17 Oct 88	17 Oct 88	18 Oct 88
Elapsed Time	22 Days	21 Days	21 Days	22 Days
Barium (SW6010)				
Date Analyzed	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88
Elapsed Time	21 Days	21 Days	21 Days	21 Days
Cadmium (SW7111)				
Date Analyzed	27 Oct 88	19 Oct 88	27 Oct 88	27 Oct 88
Elapsed Time	31 Days	23 Days	31 Days	31 Days
Chromium (SW701)				
Date Analyzed	19 Oct 88	19 Oct 88	19 Oct 88	18 Oct 88
Elapsed Time	23 Days	23 Days	23 Days	22 Days
Lead (SW7421)				
Date Analyzed	18 Oct 88	25 Oct 88	18 Oct 88	25 Oct 88
Elapsed Time	22 Days	29 Days	22 Days	29 Days
Mercury (SW7471)				
Date Analyzed	20 Oct 88	17 Oct 88	20 Oct 88	17 Oct 88
Elapsed Time	24 Days	21 Days	24 Days	21 Days
PERCENT MOISTURE				
Date Analyzed	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88
Elapsed Time	14 Days	14 Days	14 Days	14 Days
SEMI-VOLATILE ORGANICS (SW8270)				
Date Extracted	Missing Data	Missing Data	Missing Data	Missing Data
Elapsed Time				
Date Analyzed	Missing Data	Missing Data	Missing Data	Missing Data
Elapsed Time				

TABLE N-11
Site 3
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Soil Samples

	SGA0	SGA1	SGA2	SGA3	SGA4	SGA4 DUP	SGA5	SGB1	SGB2	SGB3
	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2
	8-16-88	8-16-88	8-16-88	8-16-88	8-16-88	8-17-88	8-17-88	8-16-88	8-17-88	8-16-88
	DANGB-3-SS-A0	DANGB-3-SS-A1	DANGB-3-SS-A2	DANGB-3-SS-A3	DANGB-3-SS-A4	DANGB-3-SS-A4	DANGB-3-SS-A1	DANGB-3-SS-B1	DANGB-3-SS-B2	DANGB-3-SS-B3
	88081912	88081955	88081929	88081954	88081904	88081945	88081946	88081903	88081949	88081905
	88081940							88081961		
Date Collected	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	17 Aug 88	17 Aug 88	16 Aug 88	17 Aug 88	16 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)										
Date Analyzed	26 Aug 88	30 Aug 88	29 Aug 88	29 Aug 88	26 Aug 88	30 Aug 88	30 Aug 88	26 Aug 88	30 Aug 88	26 Aug 88
Elapsed Time	10 Days	14 Days	13 Days	13 Days	10 Days	13 Days	13 Days	10 Days	13 Days	10 Days
2nd Column	25 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	26 Aug 88	29 Aug 88	29 Aug 88	25 Aug 88	-----	26 Aug 88
Elapsed Time	9 Days	13 Days	13 Days	13 Days	10 Days	12 Days	12 Days	9 Days	-----	10 Days
AROMATIC VOLATILE ORGANICS (SW8020)										
Date Analyzed	26 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	26 Aug 88	30 Aug 88	30 Aug 88	26 Aug 88	30 Aug 88	26 Aug 88
Elapsed Time	10 Days	13 Days	13 Days	13 Days	10 Days	13 Days	13 Days	10 Days	13 Days	10 Days
2nd Column	24 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	25 Aug 88	29 Aug 88	29 Aug 88	24 Aug 88	-----	25 Aug 88
Elapsed Time	8 Days	13 Days	13 Days	13 Days	9 Days	12 Days	12 Days	8 Days	-----	9 Days
PESTICIDES AND PCBs (SW8080)										
Date Extracted	25 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	25 Aug 88	26 Aug 88	26 Aug 88	25 Aug 88	26 Aug 88	25 Aug 88
Elapsed Time	9 Days	10 Days	10 Days	10 Days	9 Days	9 Days	9 Days	9 Days	9 Days	9 Days
Date Analyzed	22 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88	22 Sep 88	23 Sep 88	23 Sep 88	22 Sep 88	23 Sep 88	22 Sep 88
Elapsed Time	37 Days	38 Days	38 Days	38 Days	37 Days	37 Days	37 Days	37 Days	37 Days	37 Days
2nd Column	-----	-----	-----	-----	26 Sep 88	-----	-----	-----	26 Sep 88	26 Sep 88
Elapsed Time	-----	-----	-----	-----	41 Days	-----	-----	-----	40 Days	41 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)										
Date Extracted	12 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	12 Sep 88	14 Sep 88	14 Sep 88	12 Sep 88	14 Sep 88	12 Sep 88
Elapsed Time	27 Days	29 Days	29 Days	29 Days	27 Days	28 Days	28 Days	27 Days	28 Days	27 Days
Date Analyzed	13 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	13 Sep 88	14 Sep 88	14 Sep 88	13 Sep 88	14 Sep 88	13 Sep 88
Elapsed Time	28 Days	29 Days	29 Days	29 Days	28 Days	28 Days	28 Days	28 Days	28 Days	28 Days

TABLE N-11
(Continued)

	SGC0	SGC1	SGC2	SGC3	SGC5	SGD0	SGD1	SGD3	SGD3 DUP
	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2
	8-16-88	8-16-88	8-16-88	8-16-88	8-17-88	8-18-88	8-17-88	8-30-88	8-30-88
	DANGB-3-SS C0	DANGB-3-SS C1	DANGB-3-SS C2	DANGB-3-SS C3	DANGB-3-SS C5	DANGB-3-SS D0	DANGB-3-SS D1	DANGB-3-SS D2	DANGB-3-SS D3-SS1
	88081956	88081957	88081901	88081958	88081944	88081973	88081975	88081952	88102200
			88081962						88102201
Date Collected	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	17 Aug 88	18 Aug 88	18 Aug 88	17 Aug 88	30 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)									
Date Analyzed	29 Aug 88	29 Aug 88	26 Aug 88	29 Aug 88	30 Aug 88	31 Aug 88	31 Aug 88	30 Aug 88	8 Sep 88
Elapsed Time	13 Days	13 Days	10 Days	13 Days	13 Days	13 Days	13 Days	9 Days	9 Days
2nd Column	29 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	31 Aug 88	31 Aug 88	30 Aug 88	9 Sep 88
Elapsed Time	13 Days	13 Days	8 Days	13 Days	12 Days	13 Days	13 Days	9 Days	10 Days
AROMATIC VOLATILE ORGANICS (SW8020)									
Date Analyzed	29 Aug 88	29 Aug 88	26 Aug 88	29 Aug 88	30 Aug 88	31 Aug 88	31 Aug 88	30 Aug 88	8 Sep 88
Elapsed Time	13 Days	13 Days	10 Days	13 Days	13 Days	13 Days	13 Days	9 Days	9 Days
2nd Column	29 Aug 88	29 Aug 88	24 Aug 88	29 Aug 88	29 Aug 88	31 Aug 88	31 Aug 88	30 Aug 88	9 Sep 88
Elapsed Time	13 Days	13 Days	8 Days	13 Days	12 Days	13 Days	11 Days	10 Days	10 Days
PESTICIDES AND PCBs (SW8030)									
Date Extracted	26 Aug 88	26 Aug 88	25 Aug 88	26 Aug 88	26 Aug 88	27 Aug 88	27 Aug 88	26 Aug 88	9 Sep 88
Elapsed Time	10 Days	10 Days	9 Days	10 Days	9 Days	9 Days	9 Days	10 Days	10 Days
Date Analyzed	23 Sep 88	23 Sep 88	22 Sep 88	23 Sep 88	23 Sep 88	26 Aug 88	26 Aug 88	23 Sep 88	5 Oct 88
Elapsed Time	38 Days	38 Days	37 Days	38 Days	37 Days	8 Days	8 Days	37 Days	36 Days
2nd Column	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88	3 Oct 88	3 Oct 88	26 Sep 88	-----
Elapsed Time	-----	41 Days	41 Days	-----	-----	46 Days	46 Days	40 Days	-----
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)									
Date Extracted	14 Sep 88	14 Sep 88	12 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	26 Sep 88
Elapsed Time	29 Days	29 Days	27 Days	29 Days	28 Days	27 Days	27 Days	28 Days	27 Days
Date Analyzed	14 Sep 88	14 Sep 88	13 Sep 88	14 Sep 88	14 Sep 88	15 Sep 88	15 Sep 88	14 Sep 88	27 Sep 88
Elapsed Time	29 Days	29 Days	28 Days	29 Days	28 Days	28 Days	28 Days	28 Days	28 Days

TABLE N-11
(Continued)

Date Collected	SG14 0-2 8-17-88 DANGB-3-SS-D4 88031953	SGD5 0-2 8-17-88 DANGB-3-SS-D5 88031943	SG10 0-2 8-18-88 DANGB-3-SS-D0 88081976	SGE1 0-2 8-18-88 DANGB-3-SS-E1 88081977	SGF2 0-2 8-18-88 DANGB-3-SS-E2 88081972	SGE3 0-2 8-30-88 DANGB-3-SS-E3-SS1 88102202	SGE3 DU1P 0-2 8-30-88 DANGB-3-SS-E3-SS1 88102203	SGE4 0-2 8-31-88 DANGB-3-SS-E4-SS2 88092248	SGE4 DU1 0-2 8-31-88 DANGB-3-SS-E4-SS1 88092249	SG49 0-2 8-18-88 DANGB-3-SS-49 88081974
17 Aug 88	17 Aug 88	17 Aug 88	18 Aug 88	18 Aug 88	18 Aug 88	30 Aug 88	30 Aug 88	31 Aug 88	31 Aug 88	18 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION
Date Analyzed	30 Aug 88	30 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	8 Sep 88	8 Sep 88	13 Sep 88	13 Sep 88	31 Aug 88
Elapsed Time	13 Days	13 Days	13 Days	13 Days	13 Days	9 Days	9 Days	13 Days	13 Days	13 Days
2nd Column	30 Aug 88	29 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	9 Sep 88	9 Sep 88	12 Sep 88	12 Sep 88	31 Aug 88
Elapsed Time	13 Days	12 Days	13 Days	13 Days	13 Days	10 Days	10 Days	12 Days	12 Days	13 Days
AROMATIC VOLATILE ORGANICS (SW8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION
Date Analyzed	30 Aug 88	30 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	8 Sep 88	8 Sep 88	13 Sep 88	13 Sep 88	31 Aug 88
Elapsed Time	13 Days	13 Days	13 Days	13 Days	13 Days	9 Days	9 Days	13 Days	13 Days	13 Days
2nd Column	30 Aug 88	29 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	9 Sep 88	9 Sep 88	11 Sep 88	11 Sep 88	31 Aug 88
Elapsed Time	13 Days	12 Days	13 Days	13 Days	13 Days	10 Days	10 Days	11 Days	11 Days	13 Days
PESTICIDES AND PCBs (SW8080)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION
Date Extracted	26 Aug 88	26 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	27 Aug 88
Elapsed Time	9 Days	9 Days	9 Days	9 Days	9 Days	10 Days	10 Days	9 Days	9 Days	9 Days
Date Analyzed	23 Sep 88	23 Sep 88	26 Aug 88	26 Aug 88	26 Aug 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	26 Aug 88
Elapsed Time	37 Days	37 Days	8 Days	8 Days	8 Days	36 Days	36 Days	35 Days	35 Days	8 Days
2nd Column	23 Sep 88	23 Sep 88	4 Oct 88	4 Oct 88	4 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	3 Oct 88
Elapsed Time	37 Days	37 Days	47 Days	47 Days	47 Days	36 Days	36 Days	35 Days	35 Days	46 Days
TOTAL PETROLEUM HYDROCARBONS - EPA 418.1	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED	NO 14 DAY DING TIME SPECIFIED
Date Extracted	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	26 Sep 88	26 Sep 88	22 Sep 88	22 Sep 88	14 Sep 88
Elapsed Time	28 Days	28 Days	27 Days	27 Days	27 Days	27 Days	27 Days	22 Days	22 Days	27 Days
Date Analyzed	14 Sep 88	14 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88	27 Sep 88	27 Sep 88	23 Sep 88	23 Sep 88	15 Sep 88
Elapsed Time	28 Days	28 Days	28 Days	28 Days	28 Days	28 Days	28 Days	23 Days	23 Days	28 Days

TABLE N-11
(Continued)

Date Collected	SG54 0-2 8-17-88 DANGIB-3-SS-72 88081947	SG55 0-2 8-17-88 DANGIB-3-SS-A3.5 88081951	SG56 0-2 8-16-88 DANGIB-3-SS-A3.5 88081906	SG57 0-2 8-17-88 DANGIB-3-SS-A2.5 88081950	SG58 0-2 8-17-88 DANGIB-3-SS-Y2 88081948	SGC4 R-SS1 9-27-88 DANGIB-3-SS1 88072782	SGC4-SS1 DUP 9-27-88 DANGIB-3-SS2 R 88072783	MW25-SS1 0-1 8-26-88 88082146	MW25-SS2 2-3 8-26-88 88082147	MW25-SS3 14-15 8-26-88 DANGIB-3-MW25-SS2 88082148
17 Aug 88	17 Aug 88	17 Aug 88	16 Aug 88	17 Aug 88	17 Aug 88	27 Sep 88	27 Sep 88	26 Aug 88	26 Aug 88	26 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION
Date Analyzed	30 Aug 88	30 Aug 88	26 Aug 88	30 Aug 88	30 Aug 88	16 Oct 88	16 Oct 88	6 Sep 88	6 Sep 88	6 Sep 88
Elapsed Time	13 Days	13 Days	10 Days	13 Days	13 Days	19 Days	19 Days	11 Days	11 Days	11 Days
2nd Column	30 Aug 88	30 Aug 88	25 Aug 88	30 Aug 88	30 Aug 88	16 Oct 88	16 Oct 88	-----	-----	-----
Elapsed Time	13 Days	13 Days	9 Days	13 Days	13 Days	19 Days	19 Days	-----	-----	-----
AROMATIC VOLATILE ORGANICS (SW8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION	ANALYZE WITHIN 14 DAYS OF COLLECTION
Date Analyzed	30 Aug 88	30 Aug 88	26 Aug 88	30 Aug 88	30 Aug 88	16 Oct 88	16 Oct 88	6 Sep 88	6 Sep 88	6 Sep 88
Elapsed Time	13 Days	13 Days	10 Days	13 Days	13 Days	19 Days	19 Days	11 Days	11 Days	11 Days
2nd Column	30 Aug 88	30 Aug 88	25 Aug 88	30 Aug 88	30 Aug 88	16 Oct 88	16 Oct 88	-----	-----	-----
Elapsed Time	13 Days	13 Days	9 Days	13 Days	13 Days	19 Days	19 Days	-----	-----	-----
PESTICIDES AND PCBs (SW8060)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION
Date Extracted	26 Aug 88	26 Aug 88	25 Aug 88	26 Aug 88	26 Aug 88	7 Oct 88	7 Oct 88	1 Sep 88	1 Sep 88	1 Sep 88
Elapsed Time	9 Days	9 Days	9 Days	9 Days	9 Days	10 Days	10 Days	6 Days	6 Days	6 Days
Date Analyzed	23 Sep 88	23 Sep 88	22 Sep 88	23 Sep 88	23 Sep 88	25 Oct 88	25 Oct 88	27 Sep 88	27 Sep 88	27 Sep 88
Elapsed Time	37 Days	37 Days	37 Days	37 Days	37 Days	28 Days	28 Days	32 Days	32 Days	32 Days
2nd Column	-----	-----	-----	-----	-----	26 Oct 88	26 Oct 88	-----	-----	-----
Elapsed Time	-----	-----	-----	-----	-----	29 Days	29 Days	-----	-----	-----
TOTAL PETROLEUM HYDROCARBONS (HPA 4181)	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED	NO HOLDING TIME SPECIFIED
Date Extracted	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	18 Oct 88	18 Oct 88	21 Sep 88	21 Sep 88	21 Sep 88
Elapsed Time	28 Days	28 Days	27 Days	28 Days	28 Days	21 Days	21 Days	26 Days	26 Days	26 Days
Date Analyzed	14 Sep 88	14 Sep 88	13 Sep 88	14 Sep 88	14 Sep 88	25 Oct 88	25 Oct 88	22 Sep 88	22 Sep 88	22 Sep 88
Elapsed Time	28 Days	28 Days	28 Days	28 Days	28 Days	28 Days	28 Days	27 Days	27 Days	27 Days

TABLE N-11
(Continued)

MW27-SS1 0 1 8-31-88 DANGIB-3-MW27-SS1 88082102	MW27-SS2 5-6 8-24-88 DANGIB-3-MW27-SS2 88082103	MW27-SS3 14-15 8-24-88 DANGIB-3-MW27-SS3 88082104	MW28-SS1 0-1 8-27-88 DANGIB-3-MW28-SS1 88082158	MW28-SS2 2-3 8-27-88 DANGIB-3-MW28-SS2 88082159	MW28-SS3 14-15 8-27-88 DANGIB-3-MW28-SS3 88082160	MW29-SS1 0-1 8-30-88 DANGIB-3-MW29-SS1 88082196	MW29-SS2 3-4 8-30-88 DANGIB-3-MW29-SS2 88082197	MW29-SS3 14-15 8-30-88 DANGIB-3-MW29-SS3 88082198	MW29-SS3 DUP 14-15 8-30-88 DANGIB-3-MW29-SS3 88082199
Date Collected	24 Aug 88	24 Aug 88	24 Aug 88	24 Aug 88	27 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION								
Date Analyzed	2 Sep 88	2 Sep 88	2 Sep 88	2 Sep 88	6 Sep 88	8 Sep 88	8 Sep 88	8 Sep 88	8 Sep 88
Elapsed Time	9 Days	9 Days	9 Days	9 Days	10 Days	10 Days	9 Days	9 Days	9 Days
2nd Column	7 Sep 88	7 Sep 88	8 Sep 88	8 Sep 88	8 Sep 88
Elapsed Time	11 Days	11 Days	9 Days	10 Days	9 Days
AROMATIC VOLATILE ORGANICS (SW8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION								
Date Analyzed	1 Sep 88	1 Sep 88	1 Sep 88	1 Sep 88	6 Sep 88	6 Sep 88	8 Sep 88	8 Sep 88	8 Sep 88
Elapsed Time	8 Days	8 Days	8 Days	8 Days	10 Days	10 Days	9 Days	9 Days	9 Days
2nd Column	7 Sep 88	7 Sep 88	8 Sep 88	8 Sep 88	8 Sep 88
Elapsed Time	11 Days	11 Days	9 Days	10 Days	9 Days
PESTICIDES AND PCBs (SW8080)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	1 Sep 88	1 Sep 88	1 Sep 88	1 Sep 88	7 Sep 88	7 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88
Elapsed Time	8 Days	8 Days	8 Days	8 Days	11 Days	11 Days	10 Days	10 Days	10 Days
Date Analyzed	27 Sep 88	27 Sep 88	27 Sep 88	27 Sep 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88
Elapsed Time	34 Days	34 Days	34 Days	34 Days	39 Days	39 Days	36 Days	36 Days	36 Days
2nd Column	7 Oct 88	7 Oct 88	7 Oct 88
Elapsed Time	38 Days	38 Days	38 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)	NO HOLDING TIME SPECIFIED								
Date Extracted	1 Sep 88	17 Sep 88	17 Sep 88	17 Sep 88	21 Sep 88	21 Sep 88	26 Sep 88	26 Sep 88	26 Sep 88
Elapsed Time	8 Days	24 Days	24 Days	24 Days	25 Days	25 Days	27 Days	27 Days	27 Days
Date Analyzed	27 Sep 88	19 Sep 88	19 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	27 Sep 88	27 Sep 88	27 Sep 88
Elapsed Time	34 Days	26 Days	26 Days	26 Days	26 Days	26 Days	28 Days	28 Days	28 Days

TABLE N-11
(Continued)

MW30-SS1 0-1 8-30-88 DANGIB-3-MW30-SS1 89082192	MW30-SS1 DUP 0-1 8-30-88 DANGIB-3-MW30-SS1 89082193	MW30-SS2 9-11 8-30-88 DANGIB-3-MW30-SS2 89082194	MW30-SS3 14-15 8-30-88 DANGIB-3-MW30-SS3 89082195	MW31-SS1 0-1 8-27-88 DANGIB-3-MW31-SS1 89082156	MW31-SS2 9-10 8-27-88 DANGIB-3-MW31-SS2 89082157	MW33-SS1 0-1 8-27-88 DANGIB-3-MW33-SS1 89082161	MW33-SS2 11-12 8-27-88 DANGIB-3-MW33-SS2 89082162	MW33-SS3 20-21 8-27-88 DANGIB-3-MW33-SS3 89082163	MW35-SS1 0-1 8-25-88 DANGIB-3-MW35-SS1 89082132
Date Collected	30 Aug 88	30 Aug 88	30 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	25 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION								
Date Analyzed	8 Sep 88	8 Sep 88	8 Sep 88	6 Sep 88	6 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	3 Sep 88
Elapsed Time	9 Days	9 Days	9 Days	10 Days	10 Days	11 Days	11 Days	11 Days	9 Days
2nd Column	8 Sep 88	8 Sep 88	8 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	8 Sep 88	8 Sep 88	3 Sep 88
Elapsed Time	9 Days	9 Days	9 Days	11 Days	11 Days	11 Days	12 Days	12 Days	9 Days
AROMATIC VOLATILE ORGANICS (SW8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION								
Date Analyzed	8 Sep 88	8 Sep 88	8 Sep 88	6 Sep 88	6 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	3 Sep 88
Elapsed Time	9 Days	9 Days	9 Days	10 Days	10 Days	11 Days	11 Days	11 Days	9 Days
2nd Column	8 Sep 88	8 Sep 88	8 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	8 Sep 88	8 Sep 88	6 Sep 88
Elapsed Time	9 Days	9 Days	9 Days	11 Days	11 Days	11 Days	12 Days	12 Days	12 Days
PESTICIDES AND PCBs (SW8080)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	9 Sep 88	9 Sep 88	9 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	29 Oct 88	29 Oct 88	1 Sep 88
Elapsed Time	10 Days	10 Days	10 Days	11 Days	11 Days	11 Days	63 Days	63 Days	7 Days
Date Analyzed	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	30 Nov 88	2 Nov 88	27 Sep 88
Elapsed Time	36 Days	36 Days	36 Days	39 Days	39 Days	39 Days	95 Days	67 Days	33 Days
2nd Column	7 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88
Elapsed Time	38 Days	38 Days	38 Days	39 Days	39 Days	39 Days	95 Days	67 Days	33 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)	NO HOLDING TIME SPECIFIED								
Date Analyzed	26 Sep 88	26 Sep 88	26 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	19 Sep 88
Elapsed Time	27 Days	27 Days	27 Days	25 Days	25 Days	25 Days	25 Days	25 Days	25 Days
Date Analyzed	27 Sep 88	27 Sep 88	27 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	20 Sep 88
Elapsed Time	28 Days	28 Days	28 Days	26 Days	26 Days	26 Days	26 Days	26 Days	26 Days

TABLE N-11
(Continued)

	MW35-SS2 23 8-25-88 DANGIB-3-MW35-SS2 8/28/2131	MW35-SS3 10-11-5 8-25-88 DANGIB-3-MW35-SS3 8/28/2133	MW35-SS3 DUP 10-11-5 8-25-88 DANGIB-3-MW35-SS3 8/28/2130
Date Collected	24 Aug 88	25 Aug 88	25 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)			
Date Analyzed	3 Sep 88	3 Sep 88	3 Sep 88
Elapsed Time	9 Days	9 Days	9 Days
2nd Column	2 Sep 88	3 Sep 88	2 Sep 88
Elapsed Time	8 Days	9 Days	8 Days
AROMATIC VOLATILE ORGANICS (SW8020)			
Date Analyzed	3 Sep 88	3 Sep 88	3 Sep 88
Elapsed Time	9 Days	9 Days	9 Days
2nd Column	6 Sep 88	6 Sep 88	6 Sep 88
Elapsed Time	12 Days	12 Days	12 Days
PESTICIDES AND PCBs (SW8080)			
Date Extracted	1 Sep 88	1 Sep 88	1 Sep 88
Elapsed Time	7 Days	7 Days	7 Days
Date Analyzed	27 Sep 88	27 Sep 88	27 Sep 88
Elapsed Time	33 Days	33 Days	33 Days
2nd Column
Elapsed Time
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)			
Date Extracted	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	25 Days	25 Days	25 Days
Date Analyzed	20 Sep 88	20 Sep 88	20 Sep 88
Elapsed Time	26 Days	26 Days	26 Days

TABLE N-11
(Continued)

	SGA0	SGA1	SGA2	SGA3	SGA4	SGA4 DUP	SGA5	SGB1	SGB2	SGB3
	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2
	8-16-88	8-16-88	8-16-88	8-16-88	8-16-88	8-17-88	8-17-88	8-16-88	8-17-88	8-16-88
	DANGB-3-SS-A0	DANGB-3-SS-A1	DANGB-3-SS-A2	DANGB-3-SS-A3	DANGB-3-SS-A4	DANGB-3-SS-A4	DANGB-3-SS-A1	DANGB-3-SS-B1	DANGB-3-SS-B2	DANGB-3-SS-B3
	88081902	88081955	88081959	88081954	88381904	88081945	88081946	88081903	88081949	88081905
	88081900							88081961		
Date Collected	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	17 Aug 88	17 Aug 88	16 Aug 88	17 Aug 88	16 Aug 88
Arsenic (SW7800)										
Date Analyzed	4 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88	4 Oct 88	16 Oct 88	16 Oct 88	4 Oct 88	6 Oct 88	4 Oct 88
Elapsed Time	49 Days	51 Days	51 Days	51 Days	49 Days	60 Days	60 Days	49 Days	50 Days	49 Days
Barium (SW6010)										
Date Analyzed	7 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88	7 Sep 88	18 Sep 88	18 Sep 88	7 Sep 88	18 Sep 88	7 Sep 88
Elapsed Time	22 Days	33 Days	33 Days	33 Days	22 Days	32 Days	32 Days	22 Days	32 Days	22 Days
Cadmium (SW7131)										
Date Analyzed	7 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	7 Sep 88	16 Sep 88	16 Sep 88	7 Sep 88	16 Sep 88	7 Sep 88
Elapsed Time	22 Days	31 Days	31 Days	31 Days	22 Days	30 Days	30 Days	22 Days	30 Days	22 Days
Chromium (SW7191)										
Date Analyzed	7 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	7 Sep 88	16 Sep 88	16 Sep 88	7 Sep 88	16 Sep 88	7 Sep 88
Elapsed Time	22 Days	31 Days	31 Days	31 Days	22 Days	30 Days	30 Days	22 Days	30 Days	22 Days
Lead * (SW7421)										
Date Analyzed	23 Sep 88	12 Oct 88	12 Oct 88	12 Oct 88	23 Sep 88	12 Oct 88	12 Oct 88	23 Sep 88	10 Oct 88	23 Sep 88
Elapsed Time	36 Days	57 Days	57 Days	57 Days	38 Days	56 Days	56 Days	38 Days	54 Days	38 Days
Mercury (SW7471)										
Date Analyzed	12 Sep 88	13 Sep 88	13 Sep 88	13 Sep 88	12 Sep 88	13 Sep 88	13 Sep 88	12 Sep 88	13 Sep 88	12 Sep 88
Elapsed Time	27 Days	28 Days	28 Days	28 Days	27 Days	27 Days	27 Days	27 Days	27 Days	27 Days
PERCENT MOISTURE										
Date Analyzed	24 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	24 Aug 88	29 Aug 88	29 Aug 88	24 Aug 88	29 Aug 88	24 Aug 88
Elapsed Time	8 Days	13 Days	13 Days	13 Days	8 Days	12 Days	12 Days	8 Days	12 Days	8 Days
SEMI-VOLATILE ORGANICS (SW8270)										
Date Extracted	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88
Elapsed Time	10 Days	10 Days	10 Days	10 Days	10 Days	9 Days	9 Days	10 Days	9 Days	9 Days
Date Analyzed	5 Oct 88	1 Nov 88	28 Nov 88	29 Nov 88	5 Oct 88	5 Oct 88	5 Oct 88	11 Oct 88	28 Nov 88	11 Oct 88
Elapsed Time	40 Days	77 Days	104 Days	105 Days	40 Days	49 Days	49 Days	46 Days	103 Days	56 Days

	SSC0	SGC1	SGC2	SGC3	SGC5	SGD0	SGD1	SGD2	SGD3	SGD3 DUP
	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2
	8-16-88	8-16-88	8-16-88	8-16-88	8-17-88	8-18-88	8-18-88	8-17-88	8-30-88	8-30-88
	DANGHB-3-SS-C0	DANGHB-3-SS-C1	DANGHB-3-SS-C2	DANGHB-3-SS-C3	DANGHB-3-SS-C5	DANGHB-3-SS-D0	DANGHB-3-SS-D1	DANGHB-3-SS-D2	DANGHB-3-SS-D3	DANGHB-3-SS-D3-SS1
	88081956	88081957	88081901	88081958	88081944	88081973	88081975	88081952	88082200	88082201
			88081962							
Date Collected	16 Aug 88	16 Aug 88	16 Aug 88	16 Aug 88	17 Aug 88	18 Aug 88	18 Aug 88	17 Aug 88	30 Aug 88	30 Aug 88
Arsenic (SW7600)										
Date Analyzed	6 Oct 88	6 Oct 88	4 Oct 88	6 Oct 88	16 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88	10 Oct 88	10 Oct 88
Elapsed Time	51 Days	51 Days	49 Days	51 Days	60 Days	49 Days	49 Days	50 Days	41 Days	41 Days
Barium (SW6010)										
Date Analyzed	18 Sep 88	18 Sep 88	7 Sep 88	18 Sep 88	18 Sep 88	19 Sep 88	19 Sep 88	18 Sep 88	20 Oct 88	20 Oct 88
Elapsed Time	33 Days	33 Days	22 Days	33 Days	32 Days	32 Days	32 Days	32 Days	51 Days	51 Days
Cadmium (SW7131)										
Date Analyzed	16 Sep 88	16 Sep 88	7 Sep 88	16 Sep 88	16 Sep 88	19 Sep 88	19 Sep 88	16 Sep 88	20 Oct 88	20 Oct 88
Elapsed Time	31 Days	31 Days	22 Days	31 Days	30 Days	32 Days	32 Days	30 Days	51 Days	51 Days
Chromium (SW7191)										
Date Analyzed	16 Sep 88	16 Sep 88	7 Sep 88	16 Sep 88	16 Sep 88	19 Sep 88	19 Sep 88	16 Sep 88	20 Oct 88	20 Oct 88
Elapsed Time	31 Days	31 Days	22 Days	31 Days	30 Days	32 Days	32 Days	30 Days	51 Days	51 Days
Lead (SW7421)										
Date Analyzed	12 Oct 88	12 Oct 88	23 Sep 88	12 Oct 88	12 Oct 88	11 Oct 88	11 Oct 88	10 Oct 88	20 Oct 88	20 Oct 88
Elapsed Time	57 Days	57 Days	38 Days	57 Days	56 Days	64 Days	64 Days	54 Days	51 Days	51 Days
Mercury (SW7471)										
Date Analyzed	13 Sep 88	13 Sep 88	12 Sep 88	13 Sep 88	13 Sep 88	14 Sep 88	14 Sep 88	13 Sep 88	22 Sep 88	22 Sep 88
Elapsed Time	28 Days	28 Days	27 Days	28 Days	27 Days	27 Days	27 Days	27 Days	23 Days	23 Days
PERCENT MOISTURE										
Date Analyzed	29 Aug 88	29 Aug 88	24 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	7 Sep 88	7 Sep 88
Elapsed Time	13 Days	13 Days	8 Days	13 Days	12 Days	11 Days	11 Days	12 Days	8 Days	8 Days
SEMI-VOLATILE ORGANICS (SW8270)										
Date Extracted	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	27 Aug 88	2 Nov 88	26 Aug 88	10 Sep 88	10 Sep 88
Elapsed Time	10 Days	10 Days	9 Days	10 Days	9 Days	9 Days	76 Days	9 Days	10 Days	10 Days
Date Analyzed	2 Nov 88	29 Nov 88	11 Oct 88	29 Nov 88	1 Dec 88	28 Nov 88	21 Nov 88	28 Nov 88	19 Oct 88	19 Oct 88
Elapsed Time	78 Days	105 Days	56 Days	105 Days	106 Days	102 Days	95 Days	143 Days	49 Days	49 Days

TABLE N-11
(Continued)

SGD4	SGD5	SGE0	SGE1	SGE2	SGE3	SGE3 DUP	SGE4	SGE4 DUP	SG49
0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2
8-17-88	8-17-88	8-18-88	8-18-88	8-18-88	8-30-88	8-30-88	8-31-88	8-31-88	8-18-88
DANGB-3-SS-D4	DANGB-3-SS-D5	DANGB-3-SS-E0	DANGB-3-SS-E1	DANGB-3-SS-E2	DANGB-3-SS-E3	DANGB-3-SS-E3	DANGB-3-SS-E4	DANGB-3-SS-E4	DANGB-3-SS-49
88081953	88081943	88081976	88081977	88081972	88082202	88082203	88092248	88092249	88081974
Date Collected	17 Aug 88	18 Aug 88	18 Aug 88	18 Aug 88	30 Aug 88	30 Aug 88	31 Aug 88	31 Aug 88	18 Aug 88
Arsenic (SW7060)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	6 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88	10 Oct 88	10 Oct 88	11 Oct 88	11 Oct 88	6 Oct 88
Elapsed Time	50 Days	49 Days	49 Days	49 Days	41 Days	41 Days	41 Days	41 Days	49 Days
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	18 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Sep 88
Elapsed Time	32 Days	32 Days	32 Days	32 Days	51 Days	51 Days	50 Days	50 Days	32 Days
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	16 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Sep 88
Elapsed Time	30 Days	32 Days	32 Days	32 Days	51 Days	51 Days	50 Days	50 Days	32 Days
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	16 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Sep 88
Elapsed Time	30 Days	32 Days	32 Days	32 Days	51 Days	51 Days	50 Days	50 Days	32 Days
Lead (SW7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	12 Oct 88	11 Oct 88	11 Oct 88	11 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	22 Oct 88	11 Oct 88
Elapsed Time	54 Days	64 Days	64 Days	64 Days	51 Days	51 Days	50 Days	52 Days	64 Days
Mercury (SW7471)	ANALYZE WITHIN 28 DAYS OF COLLECTION								
Date Analyzed	13 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	14 Sep 88
Elapsed Time	27 Days	27 Days	27 Days	27 Days	23 Days	23 Days	22 Days	22 Days	27 Days
PERCENT MOISTURE									
Date Analyzed	29 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88	7 Sep 88	7 Sep 88	9 Sep 88	9 Sep 88	29 Aug 88
Elapsed Time	12 Days	12 Days	11 Days	11 Days	8 Days	8 Days	9 Days	9 Days	11 Days
SEMI-VOLATILE ORGANICS (SW8270)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	26 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	10 Sep 88	10 Sep 88	10 Sep 88	10 Sep 88	27 Aug 88
Elapsed Time	9 Days	9 Days	76 Days	9 Days	10 Days	10 Days	10 Days	10 Days	9 Days
Date Analyzed	29 Nov 88	30 Nov 88	30 Nov 88	28 Nov 88	19 Oct 88	19 Oct 88	24 Oct 88	24 Oct 88	27 Oct 88
Elapsed Time	104 Days	103 Days	104 Days	102 Days	49 Days	49 Days	54 Days	54 Days	70 Days

TABLE N-11
(Continued)

SG54 0-2 8-17-88 DANGB-3-SS-72 88081947	SG55 0-2 8-17-88 DANGB-3-SS-A3.5 88081951	SS56 0-2 8-16-88 DANGB-3-SS-A3.5 88081906	SG57 0-2 8-17-88 DANGB-3-SS-A2.5 88081950	SG58 0-2 8-17-88 DANGB-3-SS-Y2 88081948	SGC4IR-221 9-27-88 DANGB-3-SS-A3.5 88092782	SGC4 R-221 DUP 9-27-88 DANGB-3-SS-A3.5 88092783	MW25-SS1 0-1 8-26-88 DANGB-3-MW25-SS1 88082146	MW25-SS2 2-3 8-26-88 DANGB-3-MW25-SS2 88082147	MW25-SS3 14-15 8-26-88 DANGB-3-MW25-SS3 88082148
Date Collected	17 Aug 88	16 Aug 88	17 Aug 88	17 Aug 88	27 Sep 88	27 Sep 88	26 Aug 88	26 Aug 88	26 Aug 88
Arsenic (SW7060)									
Date Analyzed	16 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88	17 Oct 88	17 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88
Elapsed Time	60 Days	49 Days	50 Days	50 Days	20 Days	20 Days	42 Days	43 Days	43 Days
Barium (SW6010)									
Date Analyzed	18 Sep 88	7 Sep 88	18 Sep 88	18 Sep 88	17 Oct 88	17 Oct 88	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	32 Days	22 Days	32 Days	32 Days	20 Days	20 Days	24 Days	24 Days	24 Days
Cadmium (SW7131)									
Date Analyzed	16 Sep 88	7 Sep 88	16 Sep 88	16 Sep 88	27 Oct 88	27 Oct 88	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	30 Days	22 Days	30 Days	30 Days	30 Days	30 Days	24 Days	24 Days	24 Days
Chromium (SW7161)									
Date Analyzed	16 Sep 88	7 Sep 88	16 Sep 88	16 Sep 88	18 Oct 88	18 Oct 88	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	30 Days	22 Days	30 Days	30 Days	21 Days	21 Days	24 Days	24 Days	24 Days
Lead (SW7421)									
Date Analyzed	12 Oct 88	23 Sep 88	10 Oct 88	10 Oct 88	20 Oct 88	20 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	54 Days	38 Days	54 Days	54 Days	23 Days	23 Days	46 Days	46 Days	46 Days
Mercury (SW7471)									
Date Analyzed	13 Sep 88	12 Sep 88	13 Sep 88	13 Sep 88	27 Oct 88	27 Oct 88	21 Sep 88	21 Sep 88	21 Sep 88
Elapsed Time	27 Days	27 Days	27 Days	27 Days	30 Days	30 Days	22 Days	22 Days	22 Days
PERCENT MOISTURE									
Date Analyzed	29 Aug 88	24 Aug 88	29 Aug 88	29 Aug 88	10 Oct 88	10 Oct 88	2 Sep 88	2 Sep 88	2 Sep 88
Elapsed Time	12 Days	8 Days	12 Days	12 Days	13 Days	13 Days	7 Days	7 Days	7 Days
SEMI-VOLATILE ORGANICS (SW8270)									
Date Extracted	26 Aug 88	26 Aug 88	26 Aug 88	26 Aug 88	7 Oct 88	7 Oct 88	25 Oct 88	25 Oct 88	25 Oct 88
Elapsed Time	9 Days	10 Days	9 Days	9 Days	10 Days	10 Days	70 Days	70 Days	70 Days
Date Analyzed	27 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	15 Nov 88	15 Nov 88	2 Nov 88	2 Nov 88	2 Nov 88
Elapsed Time	71 Days	50 Days	49 Days	49 Days	49 Days	49 Days	68 Days	68 Days	68 Days

TABLE N-11
(Continued)

	MW27-SS1	MW27-SS2	MW27-SS3	MW28-SS1	MW28-SS2	MW28-SS3	MW29-SS1	MW29-SS2	MW29-SS3	MW29-SS3 DUP
	Q-1 8-24-88 88082102	5-6 8-24-88 88082103	14-15 8-24-88 88082104	0-1 8-27-88 88082158	2-3 8-27-88 88082159	14-15 8-27-88 88082160	0-1 8-30-88 88082196	7-4 8-30-88 88082197	14-15 8-30-88 88082198	14-15 8-30-88 88082199
	DANGB-3-MW27-SS1 DANGB-3-MW27-SS2 DANGB-3-MW27-SS3 DANGB-3-MW28-SS1 DANGB-3-MW28-SS2 DANGB-3-MW28-SS3 DANGB-3-MW29-SS1 DANGB-3-MW29-SS2 DANGB-3-MW29-SS3									
Date Collected	26 Aug 88	24 Aug 88	24 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88
Arsenic (SW7040)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	7 Oct 88	7 Oct 88	7 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88
Elapsed Time	15 Days	45 Days	45 Days	44 Days	44 Days	44 Days	41 Days	41 Days	41 Days	41 Days
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88
Elapsed Time	26 Days	26 Days	26 Days	54 Days	54 Days	54 Days	51 Days	51 Days	51 Days	51 Days
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	19 Oct 88	19 Oct 88	19 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88
Elapsed Time	26 Days	26 Days	26 Days	53 Days	53 Days	53 Days	51 Days	51 Days	51 Days	51 Days
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	19 Oct 88	19 Oct 88	19 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88
Elapsed Time	26 Days	26 Days	26 Days	53 Days	53 Days	53 Days	51 Days	51 Days	51 Days	51 Days
Lead (SW7321)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	4 Oct 88	4 Oct 88	4 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88
Elapsed Time	48 Days	42 Days	48 Days	47 Days	47 Days	47 Days	51 Days	51 Days	51 Days	51 Days
Mercury (SW7371)	ANALYZE WITHIN 28 DAYS OF COLLECTION									
Date Analyzed	23 Sep 88	20 Sep 88	20 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88
Elapsed Time	27 Days	27 Days	27 Days	25 Days	25 Days	25 Days	23 Days	23 Days	23 Days	23 Days
PERCENT MOISTURE										
Date Analyzed	2 Sep 88	2 Sep 88	2 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88
Elapsed Time	7 Days	9 Days	9 Days	11 Days	11 Days	11 Days	8 Days	8 Days	8 Days	8 Days
SEMI-VOLATILE ORGANICS (SW8270)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION									
Date Extracted	2 Sep 88	2 Sep 88	2 Sep 88	6 Sep 88	6 Sep 88	6 Sep 88	10 Sep 88	10 Sep 88	10 Sep 88	10 Sep 88
Elapsed Time	9 Days	9 Days	26 Days	10 Days	10 Days	10 Days	11 Days	11 Days	11 Days	11 Days
Date Analyzed	13 Oct 88	13 Oct 88	18 Oct 88	14 Oct 88	14 Oct 88	17 Oct 88	20 Oct 88	20 Oct 88	30 Nov 88	18 Oct 88
Elapsed Time	56 Days	50 Days	55 Days	48 Days	48 Days	51 Days	40 Days	51 Days	81 Days	48 Days

TABLE N-11
(Continued)

	MW30-SS1 0-1 8-30-88	MW30-SS1 DUP 0-1 8-30-88	MW30-SS2 9-11 8-30-88	MW30-SS3 14-15 8-30-88	MW31-SS1 0-1 8-27-88	MW31-SS2 9-10 8-27-88	MW33-SS1 0-1 8-27-88	MW33-SS2 11-12 8-27-88	MW33-SS3 20-21 8-27-88	MW35-SS1 0-1 8-25-88
	DANGIB-3-MW30-SS1 89082192	DANGIB-3-MW30-SS1 89082193	DANGIB-3-MW30-SS2 89082194	DANGIB-3-MW30-SS2 89082195	DANGIB-3-MW31-SS1 89082156	DANGIB-3-MW31-SS2 89082157	DANGIB-3-MW33-SS1 89082161	DANGIB-3-MW33-SS2 89082162	DANGIB-3-MW33-SS3 89082163	DANGIB-3-MW35-SS1 89082132
Date Collected	30 Aug 88	30 Aug 88	30 Aug 88	30 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	27 Aug 88	25 Aug 88
Arsenic (SW7060)										
Date Analyzed	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	7 Oct 88
Elapsed Time	41 Days	41 Days	41 Days	41 Days	44 Days	44 Days	44 Days	44 Days	44 Days	43 Days
Barium (SW6010)										
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Sep 88
Elapsed Time	51 Days	51 Days	51 Days	51 Days	54 Days	54 Days	54 Days	54 Days	54 Days	25 Days
Cadmium (SW7131)										
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	19 Sep 88
Elapsed Time	51 Days	51 Days	51 Days	51 Days	53 Days	53 Days	53 Days	53 Days	53 Days	25 Days
Chromium (SW7191)										
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	19 Sep 88
Elapsed Time	51 Days	51 Days	51 Days	51 Days	53 Days	53 Days	53 Days	53 Days	53 Days	25 Days
Lead (SW7421)										
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	4 Oct 88
Elapsed Time	51 Days	51 Days	51 Days	51 Days	47 Days	47 Days	47 Days	47 Days	47 Days	40 Days
Mercury (SW7471)										
Date Analyzed	22 Sep 88	22 Sep 88	22 Sep 88	22 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88
Elapsed Time	23 Days	23 Days	23 Days	23 Days	25 Days	25 Days	25 Days	25 Days	25 Days	27 Days
PERCENT MOISTURE										
Date Analyzed	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	2 Sep 88
Elapsed Time	8 Days	8 Days	8 Days	8 Days	11 Days	11 Days	11 Days	11 Days	11 Days	8 Days
SEMI-VOLATILE ORGANICS (SW8270)										
Date Extracted	10 Sep 88	10 Sep 88	10 Sep 88	10 Sep 88	6 Sep 88	6 Sep 88	6 Sep 88	29 Oct 88	29 Oct 88	2 Sep 88
Elapsed Time	11 Days	11 Days	10 Days	10 Days	10 Days	10 Days	10 Days	63 Days	63 Days	8 Days
Date Analyzed	19 Oct 88	30 Nov 88	18 Oct 88	18 Oct 88	14 Oct 88	14 Oct 88	17 Oct 88	30 Nov 88	2 Nov 88	13 Oct 88
Elapsed Time	49 Days	81 Days	48 Days	48 Days	48 Days	48 Days	51 Days	95 Days	67 Days	49 Days

TABLE N-11
(Continued)

	MW35-SS2 2-3 8-25-88 DANGU-3-MW35-SS2 88082131	MW35-SS3 10-11-5 8-25-88 DANGU-3-MW35-SS3 88082133	MW35-SS3 DUP 10-11-5 8-25-88 DANGU-3-MW35-SS3A 88082130
Date Collected	25 Aug 88	25 Aug 88	25 Aug 88
Arsenic (SW7060)			
Date Analyzed	7 Oct 88	7 Oct 88	7 Oct 88
Elapsed Time	43 Days	43 Days	46 Days
Barium (SW6010)			
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	25 Days	25 Days	25 Days
Cadmium (SW7131)			
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	25 Days	25 Days	25 Days
Chromium (SW7101)			
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	25 Days	25 Days	25 Days
Lead (SW7421)			
Date Analyzed	4 Oct 88	4 Oct 88	20 Oct 88
Elapsed Time	40 Days	40 Days	56 Days
Mercury (SW7471)			
Date Analyzed	21 Sep 88	21 Sep 88	21 Sep 88
Elapsed Time	27 Days	27 Days	27 Days
PERCENT MOISTURE			
Date Analyzed	2 Sep 88	2 Sep 88	2 Sep 88
Elapsed Time	8 Days	8 Days	8 Days
SEMI-VOLATILE ORGANICS (SW8270)			
Date Extracted	2 Sep 88	2 Sep 88	2 Sep 88
Elapsed Time	8 Days	8 Days	8 Days
Date Analyzed	13 Oct 88	13 Oct 88	13 Oct 88
Elapsed Time	49 Days	49 Days	49 Days

TABLE N-12
Site 3
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Ground-Water Samples

GW 3-A 9-17-88 DANGB-3-GW3A-GW-1 88092515		GW 3-B 9-17-88 DANGB-3-GW3B-GW-1 88092513	GW 3-B DUP 9-17-88 DANGB-3-MW54-GW-1 88092514	GW 3-C 9-17-88 DANGB-3-GW3C-GW-1 88092511	GW 3-C FB 9-17-88 DANGB-FB11 88092512	GW 3-D 9-17-88 DANGB-3-GW3D-GW-1 88092516	MW25 9-14-88 DANGB-3-MW25-GW-1 88092423	MW26 9-14-88 DANGB-3-MW26-GW-1 88092426	MW26 DUP 9-14-88 DANGB-3-MW53-GW-1 88092427	MW27 9-16-88 DANGB-3-MW27-GW-1 88092487/88092508
Date Collected		17 Sep 88	17 Sep 88	17 Sep 88	17 Sep 88	17 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	16 Sep 88
HALOGENATED VOLATILE ORGANICS (SV8010)		ANALYZE WITHIN 14 DAYS OF COLLECTION								
Date Analyzed	20 Sep 88	27 Sep 88	27 Sep 88	27 Sep 88	27 Sep 88	27 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88
Elapsed Time	3 Days	10 Days	10 Days	10 Days	10 Days	10 Days	7 Days	7 Days	7 Days	5 Days
2nd Column										
Elapsed Time										
AROMATIC VOLATILE ORGANICS (SV8020)		ANALYZE WITHIN 14 DAYS OF COLLECTION								
Date Analyzed	20 Sep 88	27 Sep 88	27 Sep 88	27 Sep 88	27 Sep 88	27 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88	21 Sep 88
Elapsed Time	3 Days	10 Days	10 Days	10 Days	10 Days	10 Days	7 Days	7 Days	7 Days	5 Days
2nd Column										
Elapsed Time										
PESTICIDES AND PCB'S (EPA 608)		EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	23 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	Not Given
Elapsed Time	6 Days	6 Days	6 Days	6 Days	6 Days	6 Days	5 Days	5 Days	5 Days	
Date Analyzed	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	Not Given
Elapsed Time	37 Days	37 Days	37 Days	37 Days	37 Days	37 Days	32 Days	32 Days	31 Days	
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)		EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	3 Oct 88	3 Oct 88	3 Oct 88	3 Oct 88	3 Oct 88	3 Oct 88	28 Sep 88	28 Sep 88	28 Sep 88	5 Oct 88
Elapsed Time	16 Days	16 Days	16 Days	16 Days	16 Days	16 Days	14 Days	14 Days	14 Days	19 Days
Date Analyzed	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	8 Oct 88
Elapsed Time	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	22 Days

TABLE N-12
(Continued)

Date Collected	19 Sep 88	12 Sep 88	15 Sep 88	16 Sep 88	15 Sep 88	16 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	15 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)										
Date Analyzed	21 Sep 88	20 Sep 88	26 Sep 88	20 Sep 88	21 Sep 88	20 Sep 88	21 Sep 88	27 Sep 88	27 Sep 88	21 Sep 88
Elapsed Time	2 Days	8 Days	11 Days	4 Days	6 Days	4 Days	4 Days	8 Days	8 Days	6 Days
2nd Column		16 Sep 88								
Elapsed Time		4 Days								
AROMATIC VOLATILE ORGANICS (SW8020)										
Date Analyzed	21 Sep 88	20 Sep 88	26 Sep 88	20 Sep 88	21 Sep 88	20 Sep 88	21 Sep 88	27 Sep 88	27 Sep 88	21 Sep 88
Elapsed Time	2 Days	8 Days	11 Days	4 Days	6 Days	4 Days	4 Days	8 Days	8 Days	6 Days
2nd Column										
Elapsed Time										
PESTICIDES AND PCBs (EPA 608)										
Date Analyzed	22 Sep 88	22 Sep 88	Analysis Not Requested	23 Sep 88	22 Sep 88	23 Sep 88	23 Sep 88	23 Sep 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	3 Days	10 Days		7 Days	7 Days	4 Days	4 Days	4 Days	Analysis Not Requested	Analysis Not Requested
2nd Column		16 Oct 88	Analysis Not Requested	16 Oct 88	16 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	27 Days	34 Days		30 Days	31 Days	35 Days	35 Days	35 Days	Analysis Not Requested	Analysis Not Requested
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)										
Date Analyzed	5 Oct 88	Not Given	Analysis Not Requested	29 Sep 88	Missing Data	5 Oct 88	5 Oct 88	5 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	16 Days			13 Days		16 Days	16 Days	16 Days	Analysis Not Requested	Analysis Not Requested
2nd Column		Not Given	Analysis Not Requested	6 Oct 88	Missing Data	8 Oct 88	8 Oct 88	8 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	19 Days			20 Days		19 Days	19 Days	19 Days	Analysis Not Requested	Analysis Not Requested

TABLE N-12
(Continued)

	TR2 9-16-88 DANGIB-TR2 88092493	TR3 9-19-88 DANGIB-TR3 88092532	TR4 9-07-88 DANGIB-TR4 88092536	BR1 9-16-88 DANGIB-BR1 88092492/88092529	BR2 9-19-88 DANGIB-BR2 88092523	BR3 9-14-88 DANGIB-BR3 88092425
Data Collected	16 Sep 88	19 Sep 88	7 Sep 88	16 Sep 88	19 Sep 88	14 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)						
Date Analyzed	23 Sep 88	23 Sep 88	20 Sep 88	21 Sep 88	Not Given	21 Sep 88
Elapsed Time	7 Days	4 Days	13 Days	5 Days	7 Days	7 Days
2nd Column	*****	*****	21 Sep 88	*****	Not Given	*****
Elapsed Time	*****	*****	14 Days	*****	Given	*****
AROMATIC VOLATILE ORGANICS (SW8020)						
Date Analyzed	23 Sep 88	Not Given	20 Sep 88	21 Sep 88	23 Sep 88	21 Sep 88
Elapsed Time	7 Days	Given	13 Days	5 Days	4 Days	7 Days
2nd Column	*****	Not Given	*****	*****	*****	*****
Elapsed Time	*****	Given	*****	*****	*****	*****
PESTICIDES AND PCBs (EPA 608)						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Not Given	23 Sep 88	19 Sep 88
Elapsed Time	Request	Request	Request	Given	4 Days	5 Days
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Not Given	24 Oct 88	16 Oct 88
Elapsed Time	Request	Request	Request	Given	35 Days	32 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	5 Oct 88	5 Oct 88	28 Sep 88
Elapsed Time	Request	Request	Request	19 Days	16 Days	14 Days
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	8 Oct 88	8 Oct 88	5 Oct 88
Elapsed Time	Request	Request	Request	21 Days	19 Days	21 Days

TABLE N-12
(Continued)

	GW 3-A 9-17-88 DANGB-3-GW3A-GW-1 88072515	GW 3-B 9-17-88 DANGB-3-GW3B-GW-1 88072513	GW 3-B DUP 9-17-88 DANGB-3-MW54-GW-1 88072514	GW 3-C 9-17-88 DANGB-3-GW3C-GW-1 88072511	GW 3-C FH 9-17-88 DANGB-3-FH 88072512	GW 3-D 9-17-88 DANGB-3-GW3D-GW-1 88072516	MW25 9-14-88 DANGB-3-MW25-GW-1 88072423	MW26 9-14-88 DANGB-3-MW26-GW-1 88072426	MW26 DUP 9-14-88 DANGB-3-MW53-GW-1 88072427	MW27 9-16-88 DANGB-3-MW27-GW-1 88072487/88072508
Date Collected	17 Sep 88	17 Sep 88	17 Sep 88	17 Sep 88	17 Sep 88	17 Sep 88	14 Sep 88	14 Sep 88	14 Sep 88	16 Sep 88
Arsenic (SW7060)										
Date Analyzed	15 Oct 88	15 Oct 88	15 Oct 88	15 Oct 88	15 Oct 88	15 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	15 Oct 88
Elapsed Time	28 Days	28 Days	28 Days	28 Days	28 Days	28 Days	42 Days	42 Days	42 Days	29 Days
Barium (SW6010)										
Date Analyzed	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	20 Oct 88	20 Oct 88	20 Oct 88	13 Oct 88
Elapsed Time	26 Days	26 Days	26 Days	26 Days	26 Days	26 Days	36 Days	36 Days	36 Days	27 Days
Cadmium (SW7131)										
Date Analyzed	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	20 Oct 88
Elapsed Time	39 Days	39 Days	39 Days	39 Days	39 Days	39 Days	40 Days	40 Days	40 Days	34 Days
Chromium (SW7101)										
Date Analyzed	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	1 Nov 88	1 Nov 88	1 Nov 88	16 Oct 88
Elapsed Time	29 Days	29 Days	29 Days	29 Days	29 Days	29 Days	48 Days	48 Days	48 Days	30 Days
Lead (SW7421)										
Date Analyzed	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	16 Oct 88
Elapsed Time	29 Days	29 Days	29 Days	29 Days	29 Days	29 Days	42 Days	42 Days	42 Days	30 Days
Mercury (SW7570)										
Date Analyzed	14 Oct 88	14 Oct 88	14 Oct 88	14 Oct 88	14 Oct 88	14 Oct 88	7 Oct 88	7 Oct 88	7 Oct 88	14 Oct 88
Elapsed Time	27 Days	27 Days	27 Days	27 Days	27 Days	27 Days	23 Days	23 Days	23 Days	28 Days
SEMI-VOLATILE ORGANICS (EPA 625)										
Date Extracted	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	23 Sep 88
Elapsed Time	7 Days	7 Days	7 Days	7 Days	7 Days	7 Days	5 Days	5 Days	5 Days	7 Days
Date Analyzed	4 Nov 88	31 Oct 88	31 Oct 88	30 Oct 88	30 Oct 88	1 Nov 88	29 Nov 88	29 Nov 88	23 Nov 88	30 Oct 88
Elapsed Time	48 Days	44 Days	44 Days	41 Days	41 Days	48 Days	77 Days	77 Days	71 Days	44 Days

TABLE N-12
(Continued)

	MW28 9-19-88 88092525	MW29 9-12-88 88082490/88092535	MW29 9-12-88 88092491	MW29 9-12-88 88092494	MW31 9-19-88 88092526	MW33 9-15-88 88092488	MW34 9-16-88 88092495	MW35 9-19-88 88092527	MW35 FB 9-19-88 88092531	TBI 9-15-88 DANGIB-T17 88092489
	DANGIB-3-MW28-GW-1	DANGIB-3-MW29-GW-1	DANGIB-3-MW29-GW-1	DANGIB-3-MW29-GW-1	DANGIB-3-MW31-GW-1	DANGIB-3-MW33-GW-1	DANGIB-3-MW34-GW-1	DANGIB-3-MW35-GW-1	DANGIB-FB12	DANGIB-T17
	88092525	88082490/88092535	88092491	88092494	88092526	88092488	88092495	88092527	88092531	88092489
Date Collected	19 Sep 88	12 Sep 88	15 Sep 88	16 Sep 88	19 Sep 88	15 Sep 88	16 Sep 88	19 Sep 88	19 Sep 88	15 Sep 88
Arsenic (SW7060)										
Date Analyzed	15 Oct 88	Not Given	ANALYZE WITHIN 180 DAYS OF COLLECTION	15 Oct 88	15 Oct 88	15 Oct 88	15 Oct 88	16 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	26 Days		Requested	29 Days	26 Days	30 Days	29 Days	27 Days		
Barium (SW6010)										
Date Analyzed	13 Oct 88	19 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	24 Days	37 Days	Requested	27 Days	24 Days	28 Days	27 Days	24 Days		
Cadmium (SW7131)										
Date Analyzed	26 Oct 88	24 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION	20 Oct 88	26 Oct 88	20 Oct 88	20 Oct 88	26 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	37 Days	42 Days	Requested	34 Days	37 Days	35 Days	34 Days	37 Days		
Chromium (SW7191)										
Date Analyzed	16 Oct 88	2 Nov 88	ANALYZE WITHIN 180 DAYS OF COLLECTION	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	16 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	27 Days	51 Days	Requested	30 Days	27 Days	27 Days	30 Days	27 Days		
Lead (SW7421)										
Date Analyzed	21 Oct 88	26 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION	16 Oct 88	21 Oct 88	16 Oct 88	16 Oct 88	21 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	32 Days	44 Days	Requested	30 Days	32 Days	31 Days	30 Days	32 Days		
Mercury (SW7470)										
Date Analyzed	14 Oct 88	Not Given	ANALYZE WITHIN 28 DAYS OF COLLECTION	14 Oct 88	14 Oct 88	14 Oct 88	14 Oct 88	14 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	28 Days		Requested	28 Days	26 Days	29 Days	28 Days	25 Days		
SEMI-VOLATILE ORGANICS (EPA 625)										
Date Extracted	22 Sep 88	22 Sep 88	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	21 Sep 88	24 Sep 88	22 Sep 88	23 Sep 88	24 Sep 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	3 Days	10 Days	Requested	7 Days	5 Days	37 Days	7 Days	5 Days		
Date Analyzed	29 Oct 88	29 Oct 88	Analysis Not Requested	30 Oct 88	31 Sep 88	29 Oct 88	30 Oct 88	31 Oct 88	Analysis Not Requested	Analysis Not Requested
Elapsed Time	40 Days	47 Days	Requested	41 Days	12 Days	44 Days	44 Days	42 Days		

TABLE N-12
(Continued)

	TB2	TB3	TB4	BR1	BR2	BR3
	9-16-88	9-19-88	9-07-88	9-16-88	9-19-88	9-14-88
	DANGB-TB8	DANGB-TB9	DANGB-TB9	DANGB-BR7	DANGB-BR8	DANGB-BR6
	88092493	88092532	88092556	88092592/88092529	88092528	88092425
Date Collected	16 Sep 88	19 Sep 88	7 Sep 88	16 Sep 88	19 Sep 88	14 Sep 88
Arsenic (SW7060)						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Barium (SW7010)						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Cadmium (SW7131)						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Chromium (SW7191)						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Lead (SW7421)						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION	ANALYZE WITHIN 180 DAYS OF COLLECTION
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Mercury (SW7470)						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	ANALYZE WITHIN 28 DAYS OF COLLECTION	ANALYZE WITHIN 28 DAYS OF COLLECTION	ANALYZE WITHIN 28 DAYS OF COLLECTION	ANALYZE WITHIN 28 DAYS OF COLLECTION
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
SEMI-VOLATILE ORGANICS (EPA 625)						
Date Extracted	Analysis Not Requested	Analysis Not Requested	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested

TABLE N-13
Site 4
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Surface Water Samples

	SL11 9-23-88 DANGB-4-SL11-SW-1 88092680	SL12 9-23-88 DANGB-4-SL12-SW-1 88092679	SL13 9-24-88 DANGB-4-SL13-SW-1 88092719	SL13 DUP 9-24-88 DANGB-4-SL13-SW-1 88092720	SL14 9-24-88 DANGB-4-SL14-SW-1 88092723	SL14 FB 9-24-88 DANGB-4-FB17 88092728	SL15 9-24-88 DANGB-4-SL15-SW-1 88092722	SL16 9-27-88 DANGB-4-SL16-SW-1 88092777	TB1 9-27-88 DANGB-TB16 88092776
Date Collected	23 Sep 88	23 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	27 Sep 88	16 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)									
Date Analyzed	30 Sep 88	29 Sep 88	30 Sep 88	30 Sep 88	30 Sep 88	30 Sep 88	30 Sep 88	3 Oct 88	5 Oct 88
Elapsed Time	7 Days	6 Days	6 Days	6 Days	6 Days	6 Days	6 Days	6 Days	19 Days
2nd Column	28 Sep 88	28 Sep 88	29 Sep 88	29 Sep 88	29 Sep 88	4 Oct 88	29 Sep 88	30 Sep 88	7 Oct 88
Elapsed Time	5 Days	5 Days	5 Days	5 Days	5 Days	10 Days	5 Days	3 Days	21 Days
AROMATIC VOLATILE ORGANICS (SW8020)									
Date Analyzed	30 Sep 88	29 Sep 88	30 Sep 88	30 Sep 88	30 Sep 88	30 Sep 88	30 Sep 88	3 Oct 88	5 Oct 88
Elapsed Time	7 Days	6 Days	6 Days	6 Days	6 Days	6 Days	6 Days	6 Days	19 Days
2nd Column	28 Sep 88	28 Sep 88	29 Sep 88	29 Sep 88	29 Sep 88	4 Oct 88	29 Sep 88	30 Sep 88	7 Oct 88
Elapsed Time	5 Days	5 Days	5 Days	5 Days	5 Days	10 Days	5 Days	3 Days	21 Days
TOTAL PETROLEUM HYDROCARBONS (FPA 418.1)									
Date Extracted	8 Oct 88	8 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	Analysis Not Requested	10 Oct 88	12 Oct 88	Analysis Not Requested
Elapsed Time	15 Days	15 Days	16 Days	16 Days	16 Days	Analysis Not Requested	16 Days	15 Days	Analysis Not Requested
Date Analyzed	20 Oct 88	20 Oct 88	12 Oct 88	12 Oct 88	12 Oct 88	Analysis Not Requested	12 Oct 88	21 Oct 88	Analysis Not Requested
Elapsed Time	27 Days	27 Days	18 Days	18 Days	18 Days	Analysis Not Requested	18 Days	24 Days	Analysis Not Requested

TABLE N-13
(Continued)

	SL11 9-23-88 DANGIB-4-SL11-SW-1 8807680	SL12 9-23-88 DANGIB-4-SL12-SW-1 8807679	SL13 9-24-88 DANGIB-4-SL13-SW-1 88092719	SL13 DUP 9-24-88 DANGIB-4-SL13-SW-1 88092720	SL14 9-24-88 DANGIB-4-SL14-SW-1 88092723/88092721	SL14 FB 9-24-88 DANGIB-FB17 88092728	SL15 9-24-88 DANGIB-4-SL15-SW-1 88092722	SL16 9-27-88 DANGIB-4-SL16-SW-1 88092727	TB1 9-27-88 DANGIB-TB16 88092726
Date Collected	23 Sep 88	23 Sep 88	24 Sep 88	24 Sep 88	26 Sep 88	24 Sep 88	24 Sep 88	27 Sep 88	27 Sep 88
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	13 Oct 88	13 Oct 88	13 Oct 88	21 Oct 88	21 Oct 88	Analysis Not Requested	21 Oct 88	2 Nov 88	Analysis Not Requested
Elapsed Time	20 Days	20 Days	19 Days	27 Days	25 Days		27 Days	36 Days	
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	26 Oct 88	26 Oct 88	27 Oct 88	27 Oct 88	31 Oct 88	Analysis Not Requested	27 Oct 88	31 Oct 88	Analysis Not Requested
Elapsed Time	33 Days	33 Days	33 Days	33 Days	35 Days		33 Days	34 Days	
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	19 Oct 88	19 Oct 88	21 Oct 88	21 Oct 88	21 Oct 88	Analysis Not Requested	21 Oct 88	22 Oct 88	Analysis Not Requested
Elapsed Time	26 Days	26 Days	27 Days	27 Days	25 Days		27 Days	25 Days	
Lead (SW7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	24 Oct 88	24 Oct 88	22 Oct 88	22 Oct 88	24 Oct 88	Analysis Not Requested	22 Oct 88	22 Oct 88	Analysis Not Requested
Elapsed Time	31 Days	31 Days	28 Days	28 Days	28 Days		28 Days	25 Days	
SEMI-VOLATILE ORGANICS (EPA 625)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	3 Oct 88	Analysis Not Requested
Elapsed Time								4 Days	
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	11 Nov 88	Analysis Not Requested
Elapsed Time								45 Days	

TABLE N-14
Site 4
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Sediment Samples

	SL11 9-23-88 DANGIB-4-SL11-SD-1 88092675	SL12 9-23-88 DANGIB-4-SL12-SD-1 88092676	SL13 9-24-88 DANGIB-4-SL13-SD-1 88092738	SL13 DUP 9-24-88 DANGIB-4-SL26-SD-1 88092741	SL14 9-24-88 DANGIB-4-SL14-SD-1 88092740	SL15 9-24-88 DANGIB-4-SL15-SD-1 88092739	SL16 9-27-88 DANGIB-4-SL16-SD-1 88092781
Date Collected	23 Sep 88	23 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	27 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION						
Date Analyzed	4 Oct 88	4 Oct 88	9 Oct 88	7 Oct 88	5 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	11 Days	13 Days	15 Days	13 Days	11 Days	12 Days	9 Days
2nd Column	6 Oct 88	6 Oct 88	7 Oct 88	7 Oct 88	6 Oct 88	7 Oct 88	6 Oct 88
Elapsed Time	13 Days	11 Days	13 Days	13 Days	12 Days	13 Days	9 Days
AROMATIC VOLATILE ORGANICS (SW8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION						
Date Analyzed	4 Oct 88	4 Oct 88	7 Oct 88	7 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	11 Days	11 Days	13 Days	13 Days	12 Days	12 Days	9 Days
2nd Column	6 Oct 88	6 Oct 88	7 Oct 88	7 Oct 88	6 Oct 88	7 Oct 88	6 Oct 88
Elapsed Time	13 Days	13 Days	13 Days	13 Days	12 Days	13 Days	9 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION						
Date Extracted	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88	18 Oct 88
Elapsed Time	20 Days	20 Days	19 Days	19 Days	19 Days	19 Days	21 Days
Date Analyzed	22 Oct 88	22 Oct 88	22 Oct 88	22 Oct 88	22 Oct 88	22 Oct 88	25 Oct 88
Elapsed Time	29 Days	29 Days	28 Days	28 Days	28 Days	28 Days	28 Days

TABLE N-14
(Continued)

	SL11 9-23-88 DANGIB-4-SL11-SD-1 88092675	SL12 9-23-88 DANGIB-4-SL12-SD-1 88092676	SL13 9-24-88 DANGIB-4-SL13-SD-1 88092738	SL13 DUP 9-24-88 DANGIB-4-SL13-SD-1 88092741	SL14 9-24-88 DANGIB-4-SL14-SD-1 88092740	SL15 9-24-88 DANGIB-4-SL15-SD-1 88092739	SL16 9-27-88 DANGIB-4-SL16-SD-1 88092781
Date Collected	23 Sep 88	23 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	27 Sep 88
Barium (SW6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION						
Date Analyzed	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88
Elapsed Time	24 Days	24 Days	21 Days	23 Days	23 Days	23 Days	20 Days
Cadmium (SW7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION						
Date Analyzed	17 Oct 88	27 Oct 88	27 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88	19 Oct 88
Elapsed Time	24 Days	34 Days	33 Days	25 Days	25 Days	25 Days	23 Days
Chromium (SW7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION						
Date Analyzed	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88
Elapsed Time	25 Days	25 Days	24 Days	21 Days	24 Days	24 Days	21 Days
Lead (SW7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION						
Date Analyzed	16 Oct 88	16 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88	18 Oct 88
Elapsed Time	23 Days	23 Days	24 Days	24 Days	24 Days	24 Days	21 Days
PERCENT MOISTURE							
Date Analyzed	13 Oct 88	13 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88	10 Oct 88
Elapsed Time	20 Days	20 Days	16 Days	16 Days	16 Days	16 Days	13 Days

TABLE N-15
Site 4
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Soil Samples

MW21-SS1	MW21-SS2	MW21-SS2 DUP	MW21-SS3	MW22-SS1	MW22-SS2	MW22-SS3	MW23-SS1	MW23-SS2	MW23-SS3
0-1	5-7	5-7	18-19	0-1	5-7	30-31	0-1	8-9	30-31
8-20-88	8-20-88	8-20-88	8-20-88	8-20-88	8-20-88	8-20-88	8-19-88	8-19-88	8-19-88
DA	DANGIB-4-MW21-SS2	DANGIB-4-MW21-SS2	DANGIB-4-MW21-SS3	DANGIB-4-MW22-SS1	DANGIB-4-MW22-SS2	DANGIB-4-MW22-SS3	DANGIB-4-MW23-SS1	DANGIB-4-MW23-SS2	DANGIB-4-MW23-SS3
89082046	89082047	89082049	89082048	89082043	89082044	89082045	89082000	89082001	89082002
Date Collected									
20 Aug 88									
ANALYZE WITHIN 14 DAYS OF COLLECTION									
1 Sep 88									
12 Days									
2 Sep 88									
13 Days									
ANALYZE WITHIN 14 DAYS OF COLLECTION									
1 Sep 88									
12 Days									
1 Sep 88									
12 Days									
EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION									
30 Aug 88									
10 Days									
3 Oct 88									
44 Days									
3 Oct 88									
44 Days									
3 Oct 88									
44 Days									
NO HOLDING TIME SPECIFIED									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									
26 Days									
15 Sep 88									

TABLE N-15
(Continued)

MW24-SS1	MW24-IT SS1	MW24-IT-SS1 DUP	MW24-SS2	MW24-SS3
0-1	0-2	0-2	3-4	3-4
8-24-88	8-31-88	8-31-88	8-24-88	8-24-88
DANGIB-4-MW24-SS1	DANGIB-4-MW24-SS1	DANGIB-4-MW24-SS1A	DANGIB-4-MW24-SS2	DANGIB-4-MW24-SS3
8080699	88092254	88092255	88082100	88082101
Date Collected	31 Aug 88	31 Aug 88	24 Aug 88	24 Aug 88
HALOGENATED VOLATILE ORGANICS (SW8010)				
Date Analyzed	1 Sep 88	13 Sep 88	1 Sep 88	1 Sep 88
Elapsed Time	8 Days	13 Days	8 Days	8 Days
2nd Column	2 Sep 88	12 Sep 88	2 Sep 88	2 Sep 88
Elapsed Time	9 Days	12 Days	9 Days	9 Days
AROMATIC VOLATILE ORGANICS (SW8020)				
Date Analyzed	1 Sep 88	13 Sep 88	1 Sep 88	1 Sep 88
Elapsed Time	8 Days	13 Days	8 Days	8 Days
2nd Column	1 Sep 88	12 Sep 88	1 Sep 88	2 Sep 88
Elapsed Time	8 Days	12 Days	8 Days	9 Days
PESTICIDES AND PCBs (SW8060)				
Date Extracted	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time				
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time				
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time				
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)				
Date Extracted	17 Sep 88	22 Sep 88	17 Sep 88	17 Sep 88
Elapsed Time	24 Days	22 Days	21 Days	24 Days
Date Analyzed	19 Sep 88	23 Sep 88	19 Sep 88	19 Sep 88
Elapsed Time	26 Days	23 Days	26 Days	26 Days

TABLE N-15
(Continued)

	MW21-SS1 0-1 8-20-88 DANGB-4-MW21-SS1 88082046	MW21-SS2 5-7 8-20-88 DANGB-4-MW21-SS2 88082047	MW21-SS3 18-19 8-20-88 DANGB-4-MW21-SS3 88082048	MW21-SS2 DUP 5-7 8-20-88 DANGB-4-MW21-SS2 88082049	MW21-SS3 18-19 8-20-88 DANGB-4-MW21-SS3 88082048	MW22-SS1 0-1 8-20-88 DANGB-4-MW22-SS1 88082049	MW22-SS2 5-7 8-20-88 DANGB-4-MW22-SS2 88082044	MW22-SS3 30-31 8-20-88 DANGB-4-MW22-SS3 88082045	MW23-SS1 0-1 8-19-88 DANGB-4-MW23-SS1 88082000	MW23-SS2 8-9 8-19-88 DANGB-4-MW23-SS2 88082001	MW23-SS3 30-31 8-19-88 DANGB-4-MW23-SS3 88082002
Date Collected	20 Aug 88	20 Aug 88	20 Aug 88	20 Aug 88	20 Aug 88	20 Aug 88	20 Aug 88	20 Aug 88	19 Aug 88	19 Aug 88	19 Aug 88
Barium (SW6010)											
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88
Elapsed Time	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days
Cadmium (SW7131)											
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88
Elapsed Time	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	28 Days	28 Days	28 Days
Chromium (SW7191)											
Date Analyzed	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88
Elapsed Time	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	30 Days	28 Days	28 Days	28 Days
Lead (SW7421)											
Date Analyzed	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	5 Oct 88	22 Sep 88	22 Sep 88	22 Sep 88
Elapsed Time	46 Days	46 Days	46 Days	46 Days	46 Days	46 Days	46 Days	46 Days	34 Days	34 Days	34 Days
PERCENT MOISTURE											
Date Analyzed	2 Sep 88	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	31 Aug 88	29 Aug 88	29 Aug 88	29 Aug 88
Elapsed Time	13 Days	11 Days	11 Days	11 Days	11 Days	11 Days	11 Days	11 Days	10 Days	10 Days	10 Days

TABLE N-15
(Continued)

	MW24-SSI 0-2	MW24 R-SSI 0-2	MW24 R-SSI DUF 0-2	MW24-SS2 3-4	MW24-SS3 32-34
	8-24-88	8-31-88	8-31-88	8-20-88	8-24-88
	DANGIB-4-MW24-SSI 88092254	DANGIB-4-MW24-SSI 88092255	DANGIB-4-MW24-SSI 88092255	DANGIB-4-MW24-SS2 88082100	DANGIB-4-MW24-SS3 88082101
Date Collected	24 Aug 88	31 Aug 88	31 Aug 88	24 Aug 88	24 Aug 88
Barium (SW6010)					
Date Analyzed	19 Sep 88				19 Sep 88
Elapsed Time	26 Days				26 Days
Cadmium (SW7131)					
Date Analyzed	19 Sep 88				19 Sep 88
Elapsed Time	26 Days				26 Days
Chromium (SW7191)					
Date Analyzed	19 Sep 88				19 Sep 88
Elapsed Time	26 Days				26 Days
Lead (SW7421)					
Date Analyzed	4 Oct 88				4 Oct 88
Elapsed Time	41 Days				41 Days
PERCENT MOISTURE					
Date Analyzed	2 Sep 88				2 Sep 88
Elapsed Time	9 Days				9 Days

TABLE N-16
Site 4
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Ground-Water Samples

	MW 8 9-13-88 DANGB-4-MW8-GW-1 8807290	MW 9 9-12-88 DANGB-4-MW9-GW-1 8807248	MW 10 9-14-88 DANGB-4-MW10-GW-1 8807212	MW 11 9-14-88 DANGB-4-MW11-GW-1 8807214	GW 4-A 9-13-88 DANGB-4-GW4A-GW-1 8807288	GW 4-B 9-12-88 DANGB-4-GW4B-GW-1 8807249	GW 4-C 9-12-88 DANGB-4-GW4C-GW-1 8807250	GW 4-C DUP 9-12-88 DANGB-4-MW52 - W-1 8807251	GW 4-C FB 9-12-88 DANGB-FB7 8807252
Date Collected	13 Sep 88	12 Sep 88	14 Sep 88	14 Sep 88	13 Sep 88	12 Sep 88	16 Sep 88	16 Sep 88	12 Sep 88
ANALYZE WITHIN 14 DAYS OF COLLECTION									
HALOGENATED VOLATILE ORGANICS (SW8010)									
Date Analyzed	16 Sep 88	20 Sep 88	21 Sep 88	21 Sep 88	16 Sep 88	20 Sep 88	21 Sep 88	21 Sep 88	15 Sep 88
Elapsed Time	3 Days	8 Days	7 Days	7 Days	3 Days	8 Days	5 Days	5 Days	3 Days
2nd Column	19 Sep 88	16 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	19 Sep 88
Elapsed Time	6 Days	4 Days	7 Days	7 Days	6 Days	4 Days	4 Days	4 Days	7 Days
ANALYZE WITHIN 14 DAYS OF COLLECTION									
AROMATIC VOLATILE ORGANICS (SW8010)									
Date Analyzed	16 Sep 88	20 Sep 88	21 Sep 88	21 Sep 88	16 Sep 88	20 Sep 88	21 Sep 88	21 Sep 88	15 Sep 88
Elapsed Time	3 Days	8 Days	7 Days	7 Days	3 Days	8 Days	5 Days	5 Days	3 Days
2nd Column	19 Sep 88	16 Sep 88	19 Sep 88	19 Sep 88	19 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	19 Sep 88
Elapsed Time	6 Days	4 Days	7 Days	7 Days	6 Days	4 Days	4 Days	4 Days	7 Days
EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION									
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1)									
Date Extracted	23 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	23 Sep 88	28 Sep 88	28 Sep 88	28 Sep 88	Analysis Not Requested
Elapsed Time	10 Days	16 Days	14 Days	14 Days	10 Days	16 Days	12 Days	12 Days	Analysis Not Requested
Date Analyzed	26 Sep 88	5 Oct 88	5 Oct 88	5 Oct 88	26 Sep 88	5 Oct 88	5 Oct 88	5 Oct 88	Analysis Not Requested
Elapsed Time	13 Days	23 Days	21 Days	21 Days	13 Days	23 Days	19 Days	19 Days	Analysis Not Requested

TABLE N-16
(Continued)

GW 4-D 9-13-88 DANGB-4-GW4D-GW-1 38022189	MW21 9-10-88 DANGB-4-MW21-GW-1 88022321	MW22 9-10-88 DANGB-4-MW22-GW-1 88022325	MW22 FB 9-10-88 DANGB-FB6 DANGB-4-MW23-GW-1 88022312	MW23 9-10-88 DANGB-4-MW23-GW-1 88022322	T111 9-12-88 DANGB-T114 88022351	TB2 9-13-88 DANGB-TB6 88022391	BR1 9-12-88 DANGB-BR4 88022350	BR2 9-12-88 DANGB-BR5 88022354
Date Collected	13 Sep 88	10 Sep 88	10 Sep 88	10 Sep 88	12 Sep 88	13 Sep 88	12 Sep 88	12 Sep 88
HALOGENATED VOLATILE ORGANICS (SW8010)								
Date Analyzed	16 Sep 88	20 Sep 88	Not	16 Sep 88	15 Sep 88	20 Sep 88	15 Sep 88	20 Sep 88
Elapsed Time	3 Days	10 Days	Given	6 Days	3 Days	7 Days	3 Days	8 Days
2nd Column	19 Sep 88	15 Sep 88	Not	14 Sep 88	19 Sep 88	16 Sep 88	19 Sep 88	21 Sep 88
Elapsed Time	6 Days	5 Days	Given	4 Days	7 Days	3 Days	7 Days	9 Days
AROMATIC VOLATILE ORGANICS (SW8020)								
Date Analyzed	16 Sep 88	20 Sep 88	Not	16 Sep 88	15 Sep 88	20 Sep 88	15 Sep 88	20 Sep 88
Elapsed Time	3 Days	10 Days	Given	6 Days	3 Days	7 Days	3 Days	8 Days
2nd Column	15 Sep 88	15 Sep 88	Not	15 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88	15 Sep 88
Elapsed Time	5 Days	5 Days	Given	5 Days	5 Days	5 Days	5 Days	5 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 4181)								
Date Extracted	23 Sep 88	29 Sep 88	Analysis Not	28 Sep 88	Analysis Not	Analysis Not	28 Sep 88	28 Sep 88
Elapsed Time	10 Days	19 Days	Requested	18 Days	Requested	Requested	16 Days	16 Days
Date Analyzed	26 Sep 88	5 Oct 88	Analysis Not	5 Oct 88	Analysis Not	Analysis Not	5 Oct 88	5 Oct 88
Elapsed Time	13 Days	25 Days	Requested	25 Days	Requested	Requested	23 Days	23 Days

TABLE N-16
(Continued)

	MW 8 9-13-88 DANGB-4-MW8-GW-1 88092390	MW 9 9-12-88 DANGB-4-MW9-GW-1 88092348	MW 9 FB 9-12-88 DANGB-FB8 88092353	MW 10 9-14-88 DANGB-4-MW10-GW-1 88092422	MW 11 9-14-88 DANGB-4-MW11-GW-1 88092424	GW 4-A 9-13-88 DANGB-4-GW4A-GW-1 88092383	GW 4-B 9-12-88 DANGB-4-GW4B-GW-1 88092349	GW 4-C 9-12-88 DANGB-4-GW4C-GW-1 88092509	GW 4-C DUP 9-12-88 DANGB-4-MW52-GW-1 88092510	GW 4-C FB 9-12-88 DANGB-FB7 88092352
Date Collected	13 Sep 88	12 Sep 88	12 Sep 88	14 Sep 88	14 Sep 88	13 Sep 88	12 Sep 88	12 Sep 88	12 Sep 88	12 Sep 88
Barium (SW610)										
Date Analyzed	19 Oct 88	9 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION			19 Oct 88	9 Oct 88	13 Oct 88	13 Oct 88	Analysis Not Requested
Elapsed Time	36 Days	27 Days	Analysis Not Requested	20 Oct 88 36 Days	20 Oct 88 36 Days	36 Days	27 Days	32 Days	32 Days	
Cadmium (SW7131)										
Date Analyzed	24 Oct 88	24 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION			24 Oct 88	24 Oct 88	20 Oct 88	26 Oct 88	Analysis Not Requested
Elapsed Time	41 Days	42 Days	Analysis Not Requested	24 Oct 88 40 Days	24 Oct 88 40 Days	41 Days	42 Days	39 Days	39 Days	
Chromium (SW7191)										
Date Analyzed	7 Nov 88	2 Nov 88	ANALYZE WITHIN 180 DAYS OF COLLECTION			7 Nov 88	2 Nov 88	16 Oct 88	16 Oct 88	Analysis Not Requested
Elapsed Time	55 Days	51 Days	Analysis Not Requested	1 Nov 88 48 Days	1 Nov 88 48 Days	55 Days	51 Days	35 Days	35 Days	
Lead (SW7421)										
Date Analyzed	25 Oct 88	26 Oct 88	ANALYZE WITHIN 180 DAYS OF COLLECTION			25 Oct 88	26 Oct 88	16 Oct 88	16 Oct 88	Analysis Not Requested
Elapsed Time	42 Days	44 Days	Analysis Not Requested	26 Oct 88 42 Days	26 Oct 88 42 Days	42 Days	44 Days	35 Days	35 Days	

TABLE N-16
(Continued)

Date Collected	GW 4-D		MW21		MW22		MW22 FB		MW23		MW24		TBI		TB2		BRI		BR2	
	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time	Date Analyzed	Elapsed Time
Barium (SW6010)	13 Sep 88		10 Sep 88		10 Sep 88		10 Sep 88		10 Sep 88		10 Sep 88		12 Sep 88		13 Sep 88		12 Sep 88		12 Sep 88	
	19 Oct 88	36 Days	18 Oct 88	38 Days	18 Oct 88	38 Days	18 Oct 88	38 Days	17 Oct 88	37 Days	18 Oct 88	38 Days	Analysis Not Requested		Analysis Not Requested		9 Oct 88	27 Days	19 Oct 88	37 Days
Cadmium (SW7131)	24 Oct 88	41 Days	24 Oct 88	44 Days	24 Oct 88	44 Days	24 Oct 88	44 Days	24 Oct 88	44 Days	24 Oct 88	44 Days	Analysis Not Requested		Analysis Not Requested		24 Oct 88	42 Days	24 Oct 88	42 Days
	1 Nov 88	55 Days	1 Nov 88	52 Days	1 Nov 88	52 Days	1 Nov 88	52 Days	28 Oct 88	48 Days	1 Nov 88	52 Days	Analysis Not Requested		Analysis Not Requested		2 Nov 88	51 Days	2 Nov 88	51 Days
Lead (SW7421)	25 Oct 88	12 Days	22 Oct 88	40 Days	22 Oct 88	40 Days	22 Oct 88	40 Days	20 Oct 88	40 Days	22 Oct 88	40 Days	Analysis Not Requested		Analysis Not Requested		26 Oct 88	44 Days	25 Oct 88	43 Days

TABLE N-17
Site 8
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Surface Water Samples

	SL17 9-24-88 DANGH-8-SL17-SW-1 8802721	SL19 9-24-88 DANGH-8-SL19-SW-1 8802726	SL19 FBI 9-24-88 DANGH-FBI8 8802729	SL19 DUP 9-24-88 DANGH-8-SL17-SW-1 8802727	TBI 9-24-88 DANGH-TBI3 8802730
Date Collected	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88
HALOGENATED VOLATILE ORGANICS (SW 8010)	ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	30 Sep 88	30 Sep 88	1 Oct 88	30 Sep 88	1 Oct 88
Elapsed Time	6 Days	6 Days	7 Days	6 Days	7 Days
2nd Column	29 Sep 88	29 Sep 88	4 Oct 88	29 Sep 88	7 Oct 88
Elapsed Time	5 Days	5 Days	10 Days	5 Days	13 Days
AROMATIC VOLATILE ORGANICS (SW 8020)	ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	30 Sep 88	30 Sep 88	1 Oct 88	30 Sep 88	1 Oct 88
Elapsed Time	6 Days	6 Days	7 Days	6 Days	7 Days
2nd Column	29 Sep 88	29 Sep 88	4 Oct 88	29 Sep 88	7 Oct 88
Elapsed Time	5 Days	5 Days	10 Days	5 Days	13 Days
PESTICIDES AND PCB's (EPA 608)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION				
Date Extracted	29 Sep 88	30 Sep 88	Analysis Not Requested	30 Sep 88	Analysis Not Requested
Elapsed Time	5 Days	6 Days		6 Days	
Date Analyzed	24 Oct 88	24 Oct 88	Analysis Not Requested	24 Oct 88	Analysis Not Requested
Elapsed Time	30 Days	30 Days		30 Days	
2nd Column	26 Oct 88	26 Oct 88	Analysis Not Requested	26 Oct 88	Analysis Not Requested
Elapsed Time	32 Days	32 Days			
TOTAL PETROLEUM HYDROCARBONS (EPA 4181)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION				
Date Extracted	10 Oct 88	10 Oct 88	Analysis Not Requested	10 Oct 88	Analysis Not Requested
Elapsed Time	16 Days	16 Days		16 Days	
Date Analyzed	12 Oct 88	12 Oct 88	Analysis Not Requested	12 Oct 88	Analysis Not Requested
Elapsed Time	18 Days	18 Days		18 Days	

TABLE N-17
(Continued)

	SL17 9-24-88	SL19 9-24-88	SL19 FB 9-24-88	SL19 DUP 9-24-88	TBI 9-24-88
	DANGIB-8 SL17-SW-1 88092721	DANGIB-8 SL19-SW-1 88092726	DANGIB-FB18 88092729	DANGIB-8 SL27-SW-1 88092727	DANGIB-TB13 88092730
Date Collected	24 Sep 88	24 Sep 88	24 Sep 88	21 Sep 88	24 Sep 88
Barium (SW 6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	21 Oct 88	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	27 Days				
Caesium (SW 7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	27 Oct 88	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	33 Days				
Chromium (SW 7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	21 Oct 88	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	27 Days				
Lead (SW 7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION				
Date Analyzed	22 Oct 88	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	28 Days				

TABLE N-18
Site 8
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Sediment Samples

	SL17	SL18-8	SL19-8	SL19-8 DUP
	9-24-88	9-24-88	9-24-88	9-24-88
	DANGB 8-SL17-SD-1	DANGB 8-SL18-SD-1	DANGB 8-SL19-SD-1	DANGB 8-SL27-SD-1
	88092735	88092736	88092737	88092734
Date Collected	24 Sep 88	24 Sep 88	24 Sep 88	24 Sep 88
HALOGENATED VOLATILE ORGANICS (SW 8010) ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	5 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	11 Days	12 Days	12 Days	12 Days
2nd Column	4 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	10 Days	10 Days	10 Days	10 Days
AROMATIC VOLATILE ORGANICS (SW 8020) ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	5 Oct 88	6 Oct 88	6 Oct 88	6 Oct 88
Elapsed Time	11 Days	12 Days	12 Days	12 Days
2nd Column	4 Oct 88	4 Oct 88	4 Oct 88	4 Oct 88
Elapsed Time	10 Days	10 Days	10 Days	10 Days
PESTICIDES AND PCB's (SW 8080) NO HOLDING TIME SPECIFIED				
Date Extracted	7 Oct 88	7 Oct 88	6 Oct 88	7 Oct 88
Elapsed Time	13 Days	13 Days	13 Days	13 Days
Date Analyzed	25 Oct 88	25 Oct 88	6 Oct 88	25 Oct 88
Elapsed Time	31 Days	31 Days	31 Days	31 Days
TOTAL PETROLEUM HYDROCARBONS (PPA 4181) NO HOLDING TIME SPECIFIED				
Date Extracted	13 Oct 88	13 Oct 88	13 Oct 88	13 Oct 88
Elapsed Time	29 Days	29 Days	29 Days	29 Days
Date Analyzed	22 Oct 88	22 Oct 88	22 Oct 88	22 Oct 88
Elapsed Time	28 Days	28 Days	28 Days	28 Days

TABLE N-18
(Continued)

	SL17 9-24-88	SL18-8 9-24-88	SL19-8 DUP 9-24-88
	DANGIB-8-SL17-SD-1	DANGIB-8-SL18-SD-1	DANGIB-8-SL17-SD-1
	88092735	88092736	88092737
	24 Sep 88	24 Sep 88	24 Sep 88
	ANALYZE WITHIN 180 DAYS OF COLLECTION		
Barium (SW 6010)	17 Oct 88	17 Oct 88	17 Oct 88
Date Analyzed	23 Days	23 Days	23 Days
Elapsed Time			
	ANALYZE WITHIN 180 DAYS OF COLLECTION		
Cadmium (SW 7131)	19 Oct 88	19 Oct 88	18 Oct 88
Date Analyzed	25 Days	25 Days	24 Days
Elapsed Time			
	ANALYZE WITHIN 180 DAYS OF COLLECTION		
Chromium (SW 7101)	18 Oct 88	18 Oct 88	18 Oct 88
Date Analyzed	24 Days	24 Days	24 Days
Elapsed Time			
	ANALYZE WITHIN 180 DAYS OF COLLECTION		
Lead (SW 7421)	18 Oct 88	20 Oct 88	18 Oct 88
Date Analyzed	24 Days	26 Days	24 Days
Elapsed Time			
	PERCENT MOISTURE		
Date Analyzed	10 Oct 88	10 Oct 88	10 Oct 88
Elapsed Time	16 Days	16 Days	16 Days

TABLE N-19
Site 8
Minnesota Air National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Soil Samples

	MW14-SS1 0-1 8-8-88 DANGB-8-MW14-SS1 88081706	MW14-SS3 10-12 8-8-88 DANGB-8-MW14-SS3 88081707	MW14-SS3 DUP 10-12 8-8-88 DANGB-8-MW14-SS9 88081709	MW14-R-SS3 10-12 8-31-88 DANGB-8-MW14-SS3 88092250	MW14-R-SS3 DUP 10-12 8-31-88 DANGB-8-MW14-SS9 88092251	MW14-SS8 38-40 8-8-88 DANGB-8-MW14-SS8 88081708	MW16-SS1 0-1 8-10-88 DANGB-8-MW16-SS1 88081752	MW16-SS2 4-5 8-10-88 DANGB-8-MW16-SS2 88081753	MW16-SS6 29-30 8-10-88 DANGB-8-MW16-SS6 88081754	MW18A-SS1 0-2 8-5-88 DANGB-8-MW18-SS1 88081695
Date Collected	8 Aug 88	8 Aug 88	8 Aug 88	31 Aug 88	31 Aug 88	8 Aug 88	10 Aug 88	10 Aug 88	10 Aug 88	5 Aug 88
HALOGENATED VOLATILE ORGANICS (SW 8010)										
Date Analyzed	18 Aug 88	17 Aug 88	13 Sep 88	13 Sep 88	13 Sep 88	17 Aug 88	20 Aug 88	21 Aug 88	21 Aug 88	16 Aug 88
Elapsed Time	10 Days	9 Days	13 Days	13 Days	13 Days	9 Days	10 Days	11 Days	11 Days	11 Days
2nd Column	18 Aug 88	18 Aug 88	12 Sep 88	12 Sep 88	12 Sep 88	18 Aug 88	22 Aug 88	22 Aug 88	21 Aug 88	16 Aug 88
Elapsed Time	10 Days	10 Days	12 Days	12 Days	12 Days	10 Days	12 Days	12 Days	11 Days	11 Days
AROMATIC VOLATILE ORGANICS (SW 8020)										
Date Analyzed	18 Aug 88	17 Aug 88	13 Sep 88	13 Sep 88	13 Sep 88	17 Aug 88	20 Aug 88	21 Aug 88	21 Aug 88	16 Aug 88
Elapsed Time	10 Days	9 Days	13 Days	13 Days	13 Days	9 Days	10 Days	11 Days	11 Days	11 Days
2nd Column	21 Aug 88	18 Aug 88	11 Sep 88	11 Sep 88	11 Sep 88	18 Aug 88	22 Aug 88	22 Aug 88	21 Aug 88	16 Aug 88
Elapsed Time	13 Days	10 Days	11 Days	11 Days	11 Days	10 Days	12 Days	12 Days	11 Days	11 Days
PESTICIDES AND PCBs (SW 8030)										
Date Extracted	Not Given	16 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	16 Sep 88	8 Sep 88	8 Sep 88	8 Sep 88	Not Given
Elapsed Time		39 Days	7 Days	7 Days	7 Days	39 Days	29 Days	29 Days	29 Days	
Date Analyzed	18 Sep 88	18 Sep 88	5 Oct 88	5 Oct 88	5 Oct 88	18 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88
Elapsed Time	41 Days	41 Days	35 Days	35 Days	35 Days	41 Days	39 Days	39 Days	39 Days	44 Days
2nd Column										
Elapsed Time										
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1) NO HOLDING TIME SPECIFIED										
Date Extracted	29 Aug 88	Not Given	22 Sep 88	22 Sep 88	22 Sep 88	29 Aug 88	9 Sep 88	9 Sep 88	9 Sep 88	29 Aug 88
Elapsed Time	21 Days		22 Days	22 Days	22 Days	21 Days	30 Days	30 Days	20 Days	24 Days
Date Analyzed	31 Aug 88	Not Given	23 Sep 88	23 Sep 88	23 Sep 88	31 Aug 88	11 Sep 88	11 Sep 88	11 Sep 88	31 Aug 88
Elapsed Time	23 Days		23 Days	23 Days	23 Days	23 Days	32 Days	32 Days	32 Days	26 Days

TABLE N-19
(Continued)

	MW18A-SS2 8-11 8-5-88 DANGB-8-MW18-SS2 88081606	MW18A-SS3 14-15 8-5-88 DANGB-8-MW18-SS3 88081697	MW19A-SS1 0-2 8-10-88 DANGB-8-MW19-SS1 88081749	MW19A-SS2 6-2-7.5 8-10-88 DANGB-8-MW19-SS2 88081750	MW19A-SS3 9-10 8-10-88 DANGB-8-MW19-SS3 88081751	MW20A-SS1 0-2 8-31-88 DANGB-8-MW20-SS1 88081698	MW20A R-SS1 0-2 8-31-88 DANGB-8-MW20-SS1 88081699	MW20A R-SS1 DUP 0-2 8-31-88 DANGB-8-MW20-SS1 88081699	MW20A-SS2 6-8 8-5-88 DANGB-8-MW20-SS2 88081700	MW20A-SS4 15-20.5 8-5-88 DANGB-8-MW20-SS4 88081700
Date Collected	5 Aug 88	5 Aug 88	10 Aug 88	10 Aug 88	10 Aug 88	5 Aug 88	31 Aug 88	31 Aug 88	5 Aug 88	5 Aug 88
HALOGENATED VOLATILE ORGANICS (SW 8010)										
Date Analyzed	16 Aug 88	17 Aug 88	20 Aug 88	20 Aug 88	20 Aug 88	16 Aug 88	13 Sep 88	13 Sep 88	18 Aug 88	17 Aug 88
Elapsed Time	11 Days	12 Days	10 Days	10 Days	10 Days	11 Days	13 Days	13 Days	13 Days	12 Days
2nd Column										
Elapsed Time	12 Days	12 Days	10 Days	10 Days	10 Days	12 Days	12 Days	12 Days	12 Days	12 Days
AROMATIC VOLATILE ORGANICS (SW 8020)										
Date Analyzed	16 Aug 88	17 Aug 88	20 Aug 88	20 Aug 88	20 Aug 88	16 Aug 88	13 Sep 88	13 Sep 88	17 Aug 88	17 Aug 88
Elapsed Time	11 Days	12 Days	10 Days	10 Days	10 Days	11 Days	13 Days	13 Days	12 Days	12 Days
2nd Column										
Elapsed Time	12 Days	12 Days	10 Days	10 Days	10 Days	12 Days	12 Days	12 Days	12 Days	12 Days
PESTICIDES AND PCBs (SW 8030)										
Date Extracted	Not Given	Not Given	8 Sep 88	8 Sep 88	8 Sep 88	Not Given	7 Sep 88	7 Sep 88	Not Given	Not Given
Elapsed Time			29 Days	29 Days	29 Days		7 Days	7 Days		
Date Analyzed	18 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88	18 Sep 88	5 Oct 88	5 Oct 88	18 Sep 88	18 Sep 88
Elapsed Time	44 Days	44 Days	29 Days	29 Days	29 Days	44 Days	35 Days	35 Days	44 Days	44 Days
2nd Column										
Elapsed Time										
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1) NO HOLDING TIME SPECIFIED										
Date Extracted	29 Aug 88	29 Aug 88	9 Sep 88	9 Sep 88	9 Sep 88	Analysis Missing	22 Sep 88	22 Sep 88	29 Aug 88	29 Aug 88
Elapsed Time	24 Days	24 Days	30 Days	30 Days	30 Days		22 Days	22 Days	24 Days	24 Days
Date Analyzed	31 Aug 88	31 Aug 88	11 Sep 88	11 Sep 88	11 Sep 88	Analysis Missing	23 Sep 88	23 Sep 88	31 Aug 88	31 Aug 88
Elapsed Time	26 Days	26 Days	32 Days	32 Days	32 Days		23 Days	23 Days	26 Days	26 Days

TABLE N-19
(Continued)

SSA0 0-2 7-12-88 DANGB-8-SS-A0 88071404	SSA0 DUP 0-2 7-12-88 DANGB-8-SS-G0 88071374	SSA1 0-2 7-12-88 DANGB-8-SS-A1 88071399	SSA2 0-2 7-11-88 DANGB-8-SS-A2 88071387	SSA3 0-2 7-11-88 DANGB-8-SS-A3 88071384	SSB0 0-2 7-12-88 DANGB-8-SS-B0 88071397	SSB1 0-2 7-12-88 DANGB-8-SS-B1 88071403	SSB2 0-2 7-11-88 DANGB-8-SS-B2 88071385	SSB3 0-2 7-10-88 DANGB-8-SS-B3 88071381	SSC0 0-2 7-12-88 DANGB-8-SS-C0 88071395
Date Collected	12 July 88	12 July 88	11 July 88	11 July 88	12 July 88	12 July 88	11 July 88	10 July 88	12 July 88
HALOGENATED VOLATILE ORGANICS (SW 8010)									
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	4 Days	3 Days
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	19 Days	18 Days
AROMATIC VOLATILE ORGANICS (SW 8020)									
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	4 Days	3 Days
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	19 Days	18 Days
PESTICIDES AND PCB's (SW 8080)									
Date Extracted	15 July 88	15 July 88	14 July 88	14 July 88	15 July 88	15 July 88	14 July 88	14 July 88	15 July 88
Elapsed Time	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	4 Days	3 Days
Date Analyzed	30 July 88	30 July 88	29 July 88	29 July 88	30 July 88	30 July 88	29 July 88	29 July 88	30 July 88
Elapsed Time	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	18 Days	19 Days	18 Days
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	30 Days	30 Days	31 Days	31 Days	30 Days	30 Days	31 Days	31 Days	30 Days
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1) NO HOLDING TIME SPECIFIED									
Date Extracted	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88
Elapsed Time	6 Days	6 Days	7 Days	7 Days	6 Days	6 Days	7 Days	8 Days	6 Days
Date Analyzed	20 July 88	20 July 88	19 July 88	19 July 88	20 July 88	20 July 88	19 July 88	19 July 88	20 July 88
Elapsed Time	8 Days	8 Days	8 Days	8 Days	8 Days	8 Days	8 Days	9 Days	8 Days

TABLE N-19
(Continued)

Date Collected	ANALYZE WITHIN 14 DAYS OF COLLECTION									
	SSC1	SSC2	SSC3	SSD0	SSD1	SSD2	SSD2 DUP	SSD3	SSD0	SSD1
	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2	0-2
	7-12-88	7-11-88	7-11-88	7-12-88	7-12-88	7-11-88	7-11-88	7-11-88	7-12-88	7-12-88
	DANGB-8-SS-C1	DANGB-8-SS-C2	DANGB-8-SS-C3	DANGB-8-SS-D0	DANGB-8-SS-D1	DANGB-8-SS-D2	DANGB-8-SS-G2	DANGB-8-SS-D3	DANGB-8-SS-E0	DANGB-8-SS-E1
	8807196	88071390	88071389	88071405	88071391	88071382	88071388	88071383	88071406	88071409
	12 July 88	11 July 88	11 July 88	12 July 88	12 July 88	11 July 88	11 July 88	11 July 88	12 July 88	12 July 88
HALOGENATED VOLATILE ORGANICS (SW 8010)										
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time										
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time										
AROMATIC VOLATILE ORGANICS (SW 8020)										
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time										
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time										
PESTICIDES AND PCB's (SW 8080)										
Date Extracted	15 July 88	14 July 88	14 July 88	15 July 88	15 July 88	14 July 88	14 July 88	14 July 88	15 July 88	15 July 88
Elapsed Time	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days
Date Analyzed	30 July 88	29 July 88	19 July 88	30 July 88	29 July 88	29 July 88	29 July 88	29 July 88	30 July 88	30 July 88
Elapsed Time	18 Days	18 Days	8 Days	18 Days	17 Days	18 Days	18 Days	18 Days	18 Days	18 Days
2nd Column	17 Aug 88	17 Aug 88	-----	-----	11 Aug 88	-----	-----	-----	-----	-----
Elapsed Time	36 Days	37 Days	-----	-----	30 Days	-----	-----	-----	-----	-----
TOTAL PETROLEUM HYDROCARBONS (EPA 418.1) NO HOLDING TIME SPECIFIED										
Date Extracted	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88
Elapsed Time	6 Days	7 Days	7 Days	6 Days	6 Days	7 Days	7 Days	7 Days	6 Days	6 Days
Date Analyzed	20 July 88	19 July 88	19 July 88	20 July 88	19 July 88	19 July 88	19 July 88	19 July 88	20 July 88	20 July 88
Elapsed Time	8 Days	8 Days	8 Days	8 Days	7 Days	8 Days	8 Days	8 Days	8 Days	8 Days

TABLE N-19
(Continued)

SSIE2 0-2 7-12-88 DANGB-8-SS-E2 88071393	SSIE3 0-2 7-11-88 DANGB-8-SS-E3 88071386	SSIF0 0-2 7-12-88 DANGB-8-SS-F0 88071401	SSIF1 0-2 7-12-88 DANGB-8-SS-F1 88071398	SSIF1 DUP 0-2 7-12-88 DANGB-8-SS-G1 88071392	SSIF2 0-2 7-12-88 DANGB-8-SS-F2 88071402	SSIF3 0-2 7-11-88 DANGB-8-SS-F3 88071390
Date Collected	12 July 88	11 July 88	12 July 88	12 July 88	12 July 88	11 July 88
HALOGENATED VOLATILE ORGANICS (SW 8010)						
Date Analyzed	Analysis Not Requested	ANALYZE WITHIN 14 DAYS OF COLLECTION Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Requested	Requested	Requested	Requested	Requested	Requested
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Requested	Requested	Requested	Requested	Requested	Requested
AROMATIC VOLATILE ORGANICS (SW 8020)						
Date Analyzed	Analysis Not Requested	ANALYZE WITHIN 14 DAYS OF COLLECTION Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Requested	Requested	Requested	Requested	Requested	Requested
2nd Column	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Requested	Requested	Requested	Requested	Requested	Requested
PESTICIDES AND PCB'S (SW 8080)						
Date Extracted	15 July 88	14 July 88	15 July 88	15 July 88	15 July 88	14 July 88
Elapsed Time	3 Days	3 Days	3 Days	3 Days	3 Days	3 Days
Date Analyzed	29 July 88	29 July 88	30 July 88	29 July 88	30 July 88	29 July 88
Elapsed Time	17 Days	18 Days	18 Days	17 Days	18 Days	18 Days
2nd Column	11 Aug 88	11 Aug 88
Elapsed Time	30 Days	31 Days
TOTAL PHTHOLEUM HYDROCARBONS (EPA 418.1) NO HOLDING TIME SPECIFIED						
Date Extracted	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88
Elapsed Time	6 Days	7 Days	6 Days	6 Days	6 Days	7 Days
Date Analyzed	19 July 88	19 July 88	20 July 88	19 July 88	20 July 88	19 July 88
Elapsed Time	7 Days	8 Days	8 Days	7 Days	8 Days	8 Days

TABLE N-19
(Continued)

MW14-SS1 0-1 8-8-88 DANGIB-8-MW14-SS1 88081706	MW14-SS3 10-12 8-8-88 DANGIB-8-MW14-SS3 88081707	MW14-SS3 DUP 10-12 8-8-88 DANGIB-8-MW14-SS9 88081709	MW14-R-SS3 10-12 8-31-88 DANGIB-8-MW14-SS3 88092250	MW14-R-SS3 DUP 10-12 8-31-88 DANGIB-8-MW14-SS9 88092251	MW14-SS8 38-40 9-8-88 DANGIB-8-MW14-SS8 88081708	MW16-SS1 0-1 8-10-88 DANGIB-8-MW16-SS1 88081752	MW16-SS2 4-5 8-10-88 DANGIB-8-MW16-SS2 88081753	MW16-SS6 29-30 8-10-88 DANGIB-8-MW16-SS6 88081754	MW18-SS1 0-2 8-5-88 DANGIB-8-MW18-SS1 88081695
Date Collected	8 Aug 88	8 Aug 88	31 Aug 88	31 Aug 88	8 Aug 88	10 Aug 88	10 Aug 88	10 Aug 88	5 Aug 88
Barium (SW 6010)									
Date Analyzed	7 Sep 88	7 Sep 88	17 Oct 88	17 Oct 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88
Elapsed Time	30 Days	30 Days	47 Days	47 Days	30 Days	28 Days	28 Days	28 Days	33 Days
Cadmium (SW 7131)									
Date Analyzed	7 Sep 88	7 Sep 88	17 Oct 88	17 Oct 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88
Elapsed Time	30 Days	30 Days	47 Days	47 Days	30 Days	28 Days	28 Days	28 Days	33 Days
Chromium (SW 7101)									
Date Analyzed	7 Sep 88	7 Sep 88	17 Oct 88	17 Oct 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88
Elapsed Time	30 Days	30 Days	47 Days	47 Days	30 Days	28 Days	28 Days	28 Days	33 Days
Lead (SW 7421)									
Date Analyzed	16 Sep 88	16 Sep 88	17 Oct 88	17 Oct 88	16 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	13 Sep 88
Elapsed Time	39 Days	39 Days	47 Days	47 Days	39 Days	37 Days	37 Days	37 Days	39 Days
PERCENT MOISTURE									
Date Analyzed	12 Aug 88	12 Aug 88	9 Sep 88	9 Sep 88	12 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88	15 Aug 88
Elapsed Time	4 Days	4 Days	6 Days	6 Days	4 Days	7 Days	7 Days	7 Days	10 Days
SEMI-VOLATILE ORGANICS (SW 8270)									
Date Extracted	Analysis cancelled	Not Given	10 Sep 88	10 Sep 88	Analysis cancelled	Analysis cancelled	Analysis cancelled	Analysis cancelled	Not Given
Elapsed Time			10 Days	10 Days					
Date Analyzed	Analysis cancelled	Not Given	21 Oct 88	21 Oct 88	Analysis cancelled	Analysis cancelled	Analysis cancelled	Analysis cancelled	Not Given
Elapsed Time			51 Days	51 Days					

TABLE N-19
(Continued)

MW18A-SS2 8-11 8-5-88 DANGB-8-MW18-SS2 8808165	MW18A-SS3 14-15 8-5-88 DANGB-8-MW18-SS3 8808167	MW19A-SS1 0-2 8-10-88 DANGB-8-MW19-SS1 88081749	MW19A-SS2 6.5-7.5 8-10-88 DANGB-8-MW19-SS2 88081750	MW19A-SS3 9-10 8-10-88 DANGB-8-MW19-SS3 88081751	MW20A-SS1 0-2 8-5-88 DANGB-8-MW20-SS1 88081698	MW20A R-SS1 0-2 8-31-88 DANGB-8-MW20-SS1 88072253	MW20A R-SS1 DUP 0-2 8-31-88 DANGB-8-MW20-SS5 88072252	MW20A-SS2 6-8 8-5-88 DANGB-8-MW20-SS2 88081699	MW20A-SS4 15-20.5 8-5-88 DANGB-8-MW20-SS4 88081700
Date Collected	5 Aug 88	10 Aug 88	10 Aug 88	10 Aug 88	5 Aug 88	31 Aug 88	31 Aug 88	5 Aug 88	5 Aug 88
Barium (SW 6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	Not	20 Oct 88	20 Oct 88	7 Sep 88	7 Sep 88
Elapsed Time	33 Days	28 Days	28 Days	28 Days	Given	50 Days	50 Days	33 Days	33 Days
Cadmium (SW 7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	Not	20 Oct 88	20 Oct 88	7 Sep 88	7 Sep 88
Elapsed Time	33 Days	28 Days	28 Days	28 Days	Given	50 Days	50 Days	33 Days	33 Days
Chromium (SW 7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	7 Sep 88	7 Sep 88	7 Sep 88	7 Sep 88	Not	20 Oct 88	20 Oct 88	7 Sep 88	7 Sep 88
Elapsed Time	33 Days	28 Days	28 Days	28 Days	Given	50 Days	50 Days	33 Days	33 Days
Lead (SW 7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	13 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88	Not	20 Oct 88	20 Oct 88	13 Sep 88	13 Sep 88
Elapsed Time	39 Days	37 Days	37 Days	37 Days	Given	50 Days	50 Days	39 Days	39 Days
PERCENT MOISTURE	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	15 Aug 88	17 Aug 88	17 Aug 88	17 Aug 88	Not	9 Sep 88	9 Sep 88	15 Aug 88	15 Aug 88
Elapsed Time	10 Days	7 Days	7 Days	7 Days	Given	9 Days	9 Days	10 Days	10 Days
SEMI-VOLATILE ORGANICS (SW 8270)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	Not	Not	Not	Not	Analysis	Not	10 Sep 88	Not	Not
Elapsed Time	Given	Given	Analysis cancelled	Analysis cancelled	cancelled	Given	10 Days	Given	Given
Date Analyzed	Not	Not	Analysis cancelled	Analysis cancelled	Analysis	Not	21 Sep 88	Not	Not
Elapsed Time	Given	Given	cancelled	cancelled	cancelled	Given	21 Days	Given	Given

TABLE N-19
(Continued)

SSA0 0-2 7-12-88 DANGB-8-SS-A0 88071404	SSA0 DUP 0-2 7-12-88 DANGB-8-SS-G0 88071394	SSA1 0-2 7-12-88 DANGB-8-SS-A1 88071399	SSA2 0-2 7-11-88 DANGB-8-SS-A2 88071387	SSA3 0-2 7-11-88 DANGB-8-SS-A3 88071384	SSB0 0-2 7-12-88 DANGB-8-SS-B0 88071397	SSB1 0-2 7-12-88 DANGB-8-SS-B1 88071403	SSB2 0-2 7-11-88 DANGB-8-SS-B2 88071385	SSB3 0-2 7-10-88 DANGB-8-SS-B3 88071381	SSC0 0-2 7-12-88 DANGB-8-SS-C0 88071395
Date Collected	12 July 88	12 July 88	11 July 88	11 July 88	12 July 88	12 July 88	11 July 88	10 July 88	12 July 88
Barium (SW 6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time									
Cadmium (SW 7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time									
Chromium (SW 7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time									
Lead (SW 7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time									
PERCENT MOISTURE									
Date Analyzed	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88
Elapsed Time	6 Days	6 Days	7 Days	7 Days	6 Days	6 Days	7 Days	8 Days	6 Days
SEMI-VOLATILE ORGANICS (SW 8270)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time									
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time									

TABLE N-19
(Continued)

SSC1 0-2 7-12-88 DANGB-8-SS-C1 8807196	SSC2 0-2 7-11-88 DANGB-8-SS-C2 8807190	SSC3 0-2 7-11-88 DANGB-8-SS-C3 8807190	SSD0 0-2 7-12-88 DANGB-8-SS-D0 88071405	SSD1 0-2 7-12-88 DANGB-8-SS-D1 88071391	SSD2 0-2 7-11-88 DANGB-8-SS-D2 88071382	SSD2 DUPI 0-2 7-11-88 DANGB-8-SS-G2 88071388	SSD3 0-2 7-11-88 DANGB-8-SS-D3 88071383	SSD0 0-2 7-12-88 DANGB-8-SS-E0 88071406	SSEI 0-2 7-12-88 DANGB-8-SS-EI 88071400
Date Collected	12 July 88	11 July 88	12 July 88	12 July 88	11 July 88	11 July 88	11 July 88	12 July 88	12 July 88
Barium (SW 6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Cadmium (SW 7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Chromium (SW 7191)	ANALYZE WITHIN 28 DAYS OF COLLECTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Lead (SW 7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION								
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
PERCENT MOISTURE	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Analyzed	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88
Elapsed Time	6 Days	7 Days	6 Days	6 Days	7 Days	7 Days	7 Days	6 Days	6 Days
SEMI-VOLATILE ORGANICS (SW 8270)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION								
Date Extracted	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested

TABLE N-19
(Continued)

SSF2 0-2 7-12-88 DANGB-8-SS-E2 88071393	SSIF3 0-2 7-11-88 DANGB-8-SS-F3 88071380	SSIF2 0-2 7-12-88 DANGB-8-SS-F2 88071402	SSIF1 DUP 0-2 7-12-88 DANGB-8-SS-G1 88071392	SSIF1 0-2 7-12-88 DANGB-8-SS-F1 88071398	SSIF0 0-2 7-12-88 DANGB-8-SS-F0 88071401	SSIF3 0-2 7-11-88 DANGB-8-SS-E3 88071386	SSIF2 0-2 7-12-88 DANGB-8-SS-E2 88071393
Date Collected	11 July 88	12 July 88	12 July 88	12 July 88	12 July 88	11 July 88	12 July 88
Barium (SW 6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Cadmium (SW 7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Chromium (SW 7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Lead (SW 7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION						
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
PERCENT MOISTURE							
Date Analyzed	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88	18 July 88
Elapsed Time	6 Days	6 Days	6 Days	6 Days	6 Days	7 Days	7 Days
SEMI-VOLATILE ORGANICS (SW 8270)	EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION						
Date Extracted	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Date Analyzed	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested
Elapsed Time	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested	Analysis Not Requested

TABLE N-20
Site 8
Minneapolis National Guard Base
Duluth, Minnesota
Summary of Holding Time Data for Ground-Water Samples

	MW14 9-8-88 DANGB-8-MW14-GW-1 88092303	MW14 DUP 9-8-88 DANGB-8-MW14-GW-1 88092304	MW14 FB 9-8-88 DANGB-FB1 88092309	MW15 9-9-88 DANGB-8-MW15-GW-1 88092317	MW15 FB 9-9-88 DANGB-FB1 88092318	MW16 9-9-88 DANGB-8-MW16-GW-1 88092315	MW17 9-9-88 DANGB-8-MW17-GW-1 88092314	MW17 FB 9-9-88 DANGB-FB1 88092332	GW 8-A 9-10-88 DANGB-8-GW8A-GW-1 88092327	GW 8-B 9-10-88 DANGB-8-GW8B-GW-1 88092323
Date Collected	8 Sep 88	8 Sep 88	8 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	10 Sep 88	10 Sep 88
HALOGENATED VOLATILE ORGANICS (ANALYZE WITHIN 14 DAYS OF COLLECTION)										
Date Analyzed	16 Sep 88	15 Sep 88	15 Sep 88	16 Sep 88	15 Sep 88	16 Sep 88	16 Sep 88	15 Sep 88	20 Sep 88	20 Sep 88
Elapsed Time	8 Days	7 Days	7 Days	7 Days	6 Days	7 Days	7 Days	6 Days	10 Days	10 Days
2nd Column	14 Sep 88	14 Sep 88	16 Sep 88	15 Sep 88	19 Sep 88	15 Sep 88	15 Sep 88	19 Sep 88	15 Sep 88	15 Sep 88
Elapsed Time	6 Days	6 Days	8 Days	6 Days	10 Days	6 Days	6 Days	10 Days	5 Days	5 Days
AROMATIC VOLATILE ORGANICS (SW 8 ANALYZE WITHIN 14 DAYS OF COLLECTION)										
Date Analyzed	16 Sep 88	15 Sep 88	15 Sep 88	16 Sep 88	15 Sep 88	16 Sep 88	16 Sep 88	15 Sep 88	20 Sep 88	20 Sep 88
Elapsed Time	8 Days	7 Days	7 Days	7 Days	6 Days	7 Days	7 Days	6 Days	10 Days	10 Days
2nd Column	14 Sep 88	14 Sep 88	16 Sep 88	15 Sep 88	19 Sep 88	15 Sep 88	15 Sep 88	19 Sep 88	15 Sep 88	15 Sep 88
Elapsed Time	6 Days	6 Days	8 Days	6 Days	10 Days	6 Days	6 Days	10 Days	5 Days	5 Days
PESTICIDES AND PCB's (EPA 608)										
Date Extracted	14 Sep 88	14 Sep 88	Analysis Not Requested	15 Sep 88	Analysis Not Requested	15 Sep 88	15 Sep 88	Analysis Not Requested	15 Sep 88	15 Sep 88
Elapsed Time	6 Days	6 Days	Analysis Not Requested	6 Days	Analysis Not Requested	6 Days	6 Days	Analysis Not Requested	5 Days	5 Days
Date Analyzed	6 Oct 88	6 Oct 88	Analysis Not Requested	16 Oct 88	Analysis Not Requested	16 Oct 88	16 Oct 88	Analysis Not Requested	16 Oct 88	16 Oct 88
Elapsed Time	18 Days	18 Days	Analysis Not Requested	37 Days	Analysis Not Requested	37 Days	37 Days	Analysis Not Requested	36 Days	36 Days
2nd Column	14 Sep 88	14 Sep 88	Analysis Not Requested	19 Oct 88	Analysis Not Requested	19 Oct 88	19 Oct 88	Analysis Not Requested	19 Oct 88	19 Oct 88
Elapsed Time	6 Days	6 Days	Analysis Not Requested	40 Days	Analysis Not Requested	40 Days	40 Days	Analysis Not Requested	39 Days	39 Days
TOTAL PETROLEUM HYDROCARBONS (EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION)										
Date Extracted	28 Sep 88	28 Sep 88	Analysis Not Requested	28 Sep 88	Analysis Not Requested	28 Sep 88	28 Sep 88	Analysis Not Requested	29 Sep 88	29 Sep 88
Elapsed Time	20 Days	20 Days	Analysis Not Requested	19 Days	Analysis Not Requested	19 Days	19 Days	Analysis Not Requested	19 Days	19 Days
Date Analyzed	5 Oct 88	5 Oct 88	Analysis Not Requested	5 Oct 88	Analysis Not Requested	5 Oct 88	5 Oct 88	Analysis Not Requested	5 Oct 88	5 Oct 88
Elapsed Time	17 Days	17 Days	Analysis Not Requested	26 Days	Analysis Not Requested	26 Days	26 Days	Analysis Not Requested	25 Days	25 Days

TABLE N-20
(Continued)

GW 8-C		TBI	IRI	BR2
9-9-88		9-9-88	9-10-88	9-9-88
DANGB-GW8C-GW4		DANGB-TBI2	DANGB-IRI3	DANGB-BR2
88092317/88092620		88092330	88092324	88092316
Date Collected	9 Sep 88	9 Sep 88	10 Sep 88	9 Sep 88
HALOGENATED VOLATILE ORGANICS (ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	16 Sep 88	14 Sep 88	14 Sep 88	16 Sep 88
Elapsed Time	7 Days	5 Days	4 Days	7 Days
2nd Column	14 Sep 88	16 Sep 88	16 Sep 88	15 Sep 88
Elapsed Time	5 Days	7 Days	6 Days	6 Days
AROMATIC VOLATILE ORGANICS (SW 8 ANALYZE WITHIN 14 DAYS OF COLLECTION				
Date Analyzed	16 Sep 88	14 Sep 88	14 Sep 88	16 Sep 88
Elapsed Time	7 Days	5 Days	4 Days	7 Days
2nd Column	16 Sep 88	16 Sep 88	16 Sep 88	16 Sep 88
Elapsed Time	7 Days	7 Days	6 Days	6 Days
PESTICIDES AND PCB's (EPA 608) EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION				
Date Extracted	15 Sep 88	Analysis Not Requested	15 Sep 88	15 Sep 88
Elapsed Time	6 Days		5 Days	6 Days
Date Analyzed	16 Oct 88	Analysis Not Requested	16 Sep 88	16 Oct 88
Elapsed Time	37 Days		6 Days	37 Days
2nd Column	19 Oct 88	Analysis Not Requested	19 Oct 88	19 Oct 88
Elapsed Time	40 Days		39 Days	40 Days
TOTAL PETROLEUM HYDROCARBONS (EXTRACT WITHIN 14 DAYS OF COLLECTION AND ANALYZE WITHIN 40 DAYS OF EXTRACTION				
Date Extracted	1 Oct 88	Analysis Not Requested	29 Sep 88	28 Sep 88
Elapsed Time	23 Days		19 Days	19 Days
Date Analyzed	10 Oct 88	Analysis Not Requested	5 Oct 88	5 Oct 88
Elapsed Time	32 Days		25 Days	26 Days

TABLE N-20
(Continued)

	MW11 9-8-88 DANGB-8-MW14-GW-1 88092301	MW14 DUP 9-8-88 DANGB-8-MW51-GW-1 88092304	MW14 FB 9-8-88 DANGB-FB3 DANGB-8-MW15 GW-1 88092309	MW15 9-9-88 DANGB-8-MW15 GW-1 88092317	MW15 FB 9-9-88 DANGB-FB4 DANGB-8-MW16-GW-1 88092311	MW16 9-9-88 DANGB-8-MW16-GW-1 88092315	MW17 9-9-88 DANGB-8-MW17-GW-1 88092314	MW17 FB 9-9-88 DANGB-FB5 DANGB-8-GW8A-GW-1 88092312	GW 8-A 9-10-88 DANGB-8-GW8B-GW-1 88092327	GW 8-B 9-10-88 DANGB-8-GW8B-GW-1 88092323
Date Collected	8 Sep 88	8 Sep 88	8 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	9 Sep 88	10 Sep 88	10 Sep 88
Barium (SW 6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	17 Oct 88	18 Oct 88	18 Oct 88
Elapsed Time	29 Days	29 Days	Analysis Not Requested	38 Days	Analysis Not Requested	38 Days	38 Days	Analysis Not Requested	38 Days	38 Days
Cadmium (SW 7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	24 Oct 88	21 Oct 88	21 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88	24 Oct 88
Elapsed Time	36 Days	33 Days	Analysis Not Requested	45 Days	Analysis Not Requested	45 Days	45 Days	Analysis Not Requested	44 Days	44 Days
Chromium (SW 7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	28 Oct 88	28 Oct 88	28 Oct 88	28 Oct 88	28 Oct 88	28 Oct 88	28 Oct 88	28 Oct 88	1 Nov 88	1 Nov 88
Elapsed Time	40 Days	40 Days	Analysis Not Requested	49 Days	Analysis Not Requested	49 Days	49 Days	Analysis Not Requested	52 Days	52 Days
Lead (SW 7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION									
Date Analyzed	20 Oct 88	20 Oct 88	20 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	26 Oct 88	20 Oct 88	20 Oct 88
Elapsed Time	32 Days	32 Days	Analysis Not Requested	47 Days	Analysis Not Requested	41 Days	41 Days	Analysis Not Requested	40 Days	40 Days

TABLE N-20
(Continued)

	GW 8-C 9-9-88	TBI 9-9-88	BRI 9-10-88	BR2 9-9-88
	DANGB-GW8C-GW-1	DANGB-TB2	DANGB-BR2	DANGB-BR2
	88092313	88092330	88092324	88092316
Date Collected	9 Sep 88	9 Sep 88	10 Sep 88	9 Sep 88
Barium (SW 6010)	ANALYZE WITHIN 180 DAYS OF COLLECTION			
Date Analyzed	17 Oct 88	Analysis Not Requested	18 Oct 88	17 Oct 88
Elapsed Time	38 Days		38 Days	38 Days
Cadmium (SW 7131)	ANALYZE WITHIN 180 DAYS OF COLLECTION			
Date Analyzed	24 Oct 88	Analysis Not Requested	24 Oct 88	24 Oct 88
Elapsed Time	45 Days		44 Days	44 Days
Chromium (SW 7191)	ANALYZE WITHIN 180 DAYS OF COLLECTION			
Date Analyzed	28 Oct 88	Analysis Not Requested	1 Nov 88	28 Oct 88
Elapsed Time	49 Days		52 Days	49 Days
Lead (SW 7421)	ANALYZE WITHIN 180 DAYS OF COLLECTION			
Date Analyzed	20 Oct 88	Analysis Not Requested	20 Oct 88	20 Oct 88
Elapsed Time	41 Days		40 Days	41 Days

This page intentionally left blank.

SECTION N.3
SAMPLE CONTAMINATION

This page intentionally left blank.

SECTION N.3

SAMPLE CONTAMINATION

Several compounds were detected which are thought to be non-representative of on-site contamination. These compounds are dichloromethane, chloroform, toluene, and bis(2-ethylhexyl)phthalate. Tables N-21 through N-32 give the detection of these compounds at all sites in all media. Each of these compounds is discussed in the following sections.

N.3.1 Dichloromethane

Dichloromethane was found at low levels in surface water, sediment, soil and ground-water samples from all sites and from airport area and background locations (Tables N-21 through N-32). It was also detected in the laboratory blank for each sample in which it was detected. Laboratory contamination would appear to be the source of this compound.

N.3.2 Chloroform

Chloroform was detected at low levels in the surface water at Site 3 (Table N-21); in the sediment at an Area location, Site 4 and Site 8 (Table N-21); and in the soil and ground water at area background locations (Tables N-23 and N-28), Site 2 (Tables N-24 and N-29), Site 3 (Tables N-25 and N-30), Site 4 (Tables N-26 and N-31) and Site 8 (Tables N-27 and N-32).

With a few exceptions, chloroform was also found in the laboratory blanks of the samples in which it was detected. The exceptions are one surface water sample from Site 4 at 3 ug/L, a sediment sample from one airport area location at 1.5 ug/L, one sediment sample from Site 4 at 16 ug/L and three sediment samples from Site 8 at 14, 14, and 27 ug/L; five soil samples from Site 3 at 0.20, 0.50, 3.50, 1.10, and 0.56 ug/L; two ground-water samples from Site 3 at 1.3, 0.25, 1.4 ug/L and one ground-water sample from Site 4 at 0.18 ug/L. All these levels, including the three from the sediment samples at Site 8 are very low and are thought to be a result of laboratory contamination.

N.3.3 Toluene

The distribution of the occurrence of toluene is unusual. The detections of toluene in surface water, sediment and ground-water samples are given in Table N-22.

In the Area/Background samples, toluene was detected only in one surface water sample which is most likely associated with a small localized spill

(Section 4.2.1). At Site 2 toluene was not detected in the surface water, sediment or ground-water samples.

At Site 3 toluene was detected in samples from two wells and in the duplicate sample from one of them. These detections are due to contamination at the Site 3 storage pad (Section 4.4.5.1).

At Site 4 toluene was detected at very low levels in two surface water samples and at amounts which varied from undetected to 54,000 ug/L in the sediment samples. This contamination is to be expected from a fuel spill (Section 4.5.2.1).

At Site 8 toluene was not detected.

The detection of toluene in soil are given in Tables N-23 through N-27. These detections occur at various sample depths and do not appear to be related to other contaminants, known contaminant sources or to laboratory contamination. However, all soil samples were obtained during the first part of the field program, during which time almost all of the soil samples were obtained. During this time period black electrical tape was used to seal the sample containers. The field personnel used white tape to seal surface water, sediment and ground-water sample containers all of which were collected during the last few weeks of the field period. It was noted during its use that the black tape had a strong odor. Subsequent qualitative testing of the black tape on a field GC instrument has substantiated that the black tape did show high levels of toluene. This leads to the conclusion that the toluene levels reported in the soil samples are probably due to the black tape used to seal the sample bottles.

TABLE N-21
DICHLOROMETHANE AND CHLOROFORM CONCENTRATIONS
DETECTED AT ALL SITES SURFACE WATER AND SEDIMENT SAMPLES
(Sediment results in micrograms per kilogram;
water results in micrograms per liter.)

Sample Location	Dichloromethane		Chloroform	
	Water	Sediment	Water	Sediment
DANGB-BG-SL1	U	34 B	U	U
DANGB-BG-SL2	U	69 B	U	U
DANGB-BG-SL3	6.9 B	0.77 B	U	U
DANGB-BG-SL4	U	42 B	U	1.5
DANGB-BG-SL5	U	62 B	U	U
DANGB-2-SL6	U	65 B	U	U
DANGB-2-SL7	0.24 B	52 B	U	U
DANGB-3-SL8	0.26 B	23 B	U	U
DANGB-3-SL9	0.58 B	26 B	U	U
DANGB-3-SL10	U	37 B	U	U
DANGB-4-SL11	1.0 B ⁽¹⁾	60 B	U ⁽²⁾	U
DANGB-4-SL12	1.0 B	27 B	U	U
DANGB-4-SL13	45.0 B	46 B	U	U
DANGB-4-SL14	1.6 B	59 B	U	14 B
DANGB-4-SL15	36.0 B	40 B	3	U
DANGB-4-SL16	0.5 B	50 B	U	16
DANGB-8-SL17	1.7 B	36 B	U	14
DANGB-8-SL18	U	34 B	U	14
DANGB-8-SL19	1.9 B	98 B	U	27

1. B indicates the compound was detected in the laboratory blank.
2. U indicates that the compound was analyzed for but not detected.

TABLE N-22
TOLUENE CONCENTRATIONS DETECTED
AT ALL SITES IN SURFACE WATER,
SEDIMENT AND GROUND-WATER SAMPLES
(Sediment results in micrograms per kilogram;
water results in micrograms per liter.)

Location	Medium	Concentration
<u>Airport Area</u>		
DANGB-BG-SL3	Surface Water	19
<u>Background</u>		
None		
<u>Site 2</u>		
None		
<u>Site 3</u>		
GW 3-B	Ground Water	21
GW 3-B DUP	Ground Water	20
GW 3-D	Ground Water	2.9
<u>Site 4</u>		
DANGB-4-SL11	Surface Water	4.3
DANGB-4-SL13 DUP	Surface Water	2.3
DANGB-4-SL11	Sediment	970
DANGB-4-SL12	Sediment	360
DANGB-4-SL13	Sediment	54,000
DANGB-4-SL13 DUP	Sediment	26,000
DANGB-4-SL14	Sediment	U
DANGB-4-SL15	Sediment	5.5
DANGB-4-SL16	Sediment	U
<u>Site 8</u>		
None		

TABLE N-23
TOLUENE, DICHLOROMETHANE AND CHLOROFORM
CONCENTRATIONS DETECTED IN
AREA/BACKGROUND SOIL SAMPLES
(Results in micrograms per kilogram.)

Sample Location	Toluene	Dichloromethane	Chloroform
DANGB-BG-MW32			
SS1 2 to 3 feet	28	4.1 B ⁽¹⁾	U ⁽²⁾
SS2 11 to 12 feet	47	4.0 B	U
SS3 19 to 20 feet	31	1.5 B	U
DANGB-BG-MW42			
SS1 0 to 1 foot	1.8 B	1.3 B	U
SS2 7 to 8 feet	(1)	0.29 B	U
SS3 14.5 to 15.5 feet	198 B	2.2 B	0.22 B
DANGB-BG-MW43			
SS1 1 to 2 feet	25 B	3.1 B	U
SS2 14 to 15 feet	8.3 B	4.8 B	0.12 B
SS3 23 to 24 feet	160 B	7.4 B	U

1. B indicates the compound was detected in the laboratory blank.
2. U indicates that the compound was analyzed for but was not detected.

TABLE N-24
TOLUENE, DICHLOROMETHANE AND CHLOROFORM
CONCENTRATIONS DETECTED IN SITE 2 SOIL SAMPLES
(Results in micrograms per kilogram.)

Sample Location	Toluene	Dichloromethane	Chloroform
DANGB-BG-MW12A			
SS1 2 to 3 feet	3.1	1.0 B ⁽¹⁾	0.06 B
SS3 5 to 15 feet	2.1	1.6 B	U ⁽²⁾
SS5 15 to 20 feet	2.3	1.7 B	0.12 B
DANGB-2-MW13A			
SS1 0 to 2 feet	19	9.9 B	U
SS3 8 to 10 feet	13	4.3 B	U
SS4 14 to 15 feet	4.9	4.4 B	U
DANGB-2-MW37			
SS1 0 to 1 foot	38	6.0 B	0.17 B
SS2 5 to 6 feet	90	2.9 B	U
SS3 16 to 17 feet	64	2.1 B	U
SS4 17.5 to 18 feet	56	2.2 B	U
DANGB-2-MW39			
SS1 0 to 1 foot	1.4	18.0 B	U
SS2 9 to 10.5 feet	520	4.6 B	U
SS4 17 to 19 feet	12	49.0 B	U
DANGB-2-MW40			
SS1 0 to 1 foot	37	4.4 B	1.30 B
SS2 5 to 6 feet	8.8	0.9 B	U
SS3 15.5 to 16.5 feet	8.9	4.4 B	0.10 B
DANGB-2-MW41			
SS1 0 to 5 feet	4.2	6.8 B	0.60 B
SS2 5 to 15 feet	57	5.4 B	0.50 B
SS3 15 to 20 feet	47	3.4 B	U
DANGB-2-BH1 R			
SS1 0 to 2 feet	2,000 B	5.2 B	U
SS2 2 to 4 feet	640 B	2.6 B	U
SS3 6 to 8 feet	15,000	12.0 B	1.70 B
SS4 8 to 10 feet	1,700	2.2 B	0.90 B
SS5 10 to 12 feet	1,100	7.3 B	0.60 B
SS6 15 to 17 feet	200	21.0 B	0.44 B
SS7 22 to 24 feet	1.7	2.1 B	1.40 B

TABLE N-24 (continued)

Sample Location	Toluene	Dichloromethane	Chloroform
DANGB-2-BH2 R			
SS1 0 to 2 feet	36,000	7.8 B	1.30 B
SS2 5 to 6 feet	7,200	19.0 B	U
SS3 10 to 12 feet	570	4.0 B	33.00 B
SS4 14 to 15 feet	U	1.5 B	1.70 B
SS5 20 to 22 feet	4.0	3.2 B	0.43 B
SS6 24 to 25 feet	11	1.9 B	0.33 B

1. B indicates that the compound was detected in the laboratory blank.
2. U indicates that the compound was analyzed for but was not detected.

TABLE N-25
TOLUENE, DICHLOROMETHANE AND CHLOROFORM
CONCENTRATIONS DETECTED IN SITE 3 SOIL SAMPLES
(Results in micrograms per kilogram.)

Sample Location	Toluene	Dichloromethane	Chloroform
DANGB-3-MW25			
SS1 0 to 1 foot	U(1)	2.50B(2)	U
SS2 2 to 3 feet	U	U	U
SS3 14 to 15 feet	U	U	U
DANGB-3-MW27			
SS1 0 to 1 foot	610	3.00 B	U
SS2 5 to 6 feet	740	1.90 B	U
SS3 14 to 15 feet	100	120 B	U
DANGB-3-MW28			
SS1 0 to 1 foot	5.5	3.10 B	U
SS2 2 to 3 feet	60	2.20 B	U
SS3 14 to 15 feet	23	1.70 B	0.24 B
DANGB-3-MW29			
SS1 0 to 1 foot	18	0.94 B	U
SS2 3 to 4 feet	38	0.57 B	U
SS3 14 to 15 feet	7.0	0.67 B	U
DANGB-3-MW30			
SS1 0 to 1 foot	U	1.20 B	U
SS2 9 to 11 feet	U	U	U
SS3 14 to 15 feet	20	1.20 B	U
DANGB-3-MW31			
SS1 0 to 1 foot	9.8	5.90 B	U
SS2 9 to 10 feet	60	2.30 B	0.43 B
DANGB-3-MW33			
SS1 0 to 1 foot	150	3.90 B	U
SS2 11 to 12 feet	28	2.60 B	U
SS3 20 to 21 feet	9.4	4.10 B	U
DANGB-3-MW35			
SS1 0 to 1 foot	18	9.20 B	U
SS2 2 to 3 feet	13	81.00 B	U
SS3 10 to 11.5 feet	79	8.60 B	0.09 B
DANGB-3-SGA0	17	3.40 B	0.20 B
DANGB-3-SGA1	8.5	8.80 B	U
DANGB-3-SGA2	3.4	2.00 B	U
DANGB-3-SGA3	12	2.50 B	0.80 B

TABLE N-25 (continued)

Sample Location	Toluene	Dichloromethane	Chloroform
DANGB-3-SGA4	1.6	12.00 B	0.20 B
DANGB-3-SGA5	39	25.00 B	0.20
DANGB-3-SGB1	4.5	5.70 B	2.60 B
DANGB-3-SGB2	U	U	U
DANGB-3-SGB3	36	5.80 B	1.10 B
DANGB-3-SGC0	6.7	3.90 B	U
DANGB-3-SGC1	8.1	1.90 B	U
DANGB-3-SGC2	5.3	12.0 B	0.20 B
DANGB-3-SGC3	4.2	1.70 B	U
DANGB-3-SGC5	190	11.0 B	U
DANGB-3-SGD0	20 B	1.30 B	U
DANGB-3-SGD1	12 B	1.40 B	U
DANGB-3-SGD2	U	3.40 B	U
DANGB-3-SGD4	8.6	6.60 B	U
DANGB-3-SGD5	12	5.80 B	0.50
DANGB-3-SGE0	3.1 B	1.40 B	U
DANGB-3-SGE1	53 B	3.50 B	U
DANGB-3-SGE2	38 B	1.30 B	0.23 B
DANGB-3-SGE3	8.8	5.40 B	U
DANGB-3-SGE4	140	4.60 B	3.50
DANGB-3-SG49	1,300 B	2.40 B	U
DANGB-3-SG54	12	9.10 B	U
DANGB-3-SG55	U	4.30 B	0.20 B
DANGB-3-SG58	U	U	0.30 B

1. U indicates that the compound was undetected above the level of the practical quantitation limit.
2. B indicates the compound was detected in the laboratory blank.

TABLE N-26
TOLUENE, DICHLOROMETHANE AND CHLOROFORM
CONCENTRATIONS DETECTED IN SITE 4 SOIL SAMPLES
(Results in micrograms per kilogram)

Sample Location	Toluene	Dichloromethane	Chloroform
DANGB-4-MW21			
SS1 0 to 1 foot	330	6.7 B ⁽¹⁾	U ⁽²⁾
SS2 5 to 7 feet	120	3.5 B	U
SS3 18 to 19 feet	53	2.8 B	U
DANGB-4-MW22			
SS1 0 to 1 foot	120	17.0 B	U
SS2 5 to 7 feet	100	4.6 B	1.10
SS3 30 to 31 feet	830	6.0 B	0.56
DANGB-4-MW23			
SS1 0 to 1 foot	1.2	8.4 B	U
SS2 8 to 9 feet	25	3.2 B	0.40 B
SS3 30 to 31 feet	13	5.4 B	0.08 B
DANGB-4-MW24			
SS1 0 to 2 feet	39	2.9 B	U
SS2 3 to 4 feet	150	4.3 B	U
SS3 32 to 34 feet	950	3.6 B	U

1. B indicates the compound was detected in the laboratory blank.
2. U indicates that the compound was analyzed for but not detected.

TABLE N-27
TOLUENE, DICHLOROMETHANE AND CHLOROFORM
CONCENTRATIONS DETECTED IN SITE 8 SOIL SAMPLES
(Results in micrograms per kilogram.)

Sample Location	Toluene	Dichloromethane	Chloroform
DANGB-8-MW14			
SS1 0 to 1 foot	1,400	13.00 B ⁽¹⁾	U ⁽²⁾
SS3 10 to 12 feet	9.4	3.00 B	U
SS8 38 to 40 feet	23.0	4.30 B	U
DANGB-8-MW16			
SS1 0 to 1 foot	15.0	5.10 B	U
SS2 4 to 5 feet	41.0	10.00 B	U
SS6 29 to 30 feet	7.5	4.10 B	U
DANGB-8-MW18			
SS1 0 to 2 feet	2.0	3.30 B	U
SS2 8 to 11 feet	84.0	5.10 B	U
SS3 14 to 15 feet	81.0	4.40 B	U
DANGB-8-MW19			
SS1 0 to 2 feet	10.0	10.00 B	0.50 B
SS2 6.5 to 7.5 feet	1.7	3.20 B	0.05 B
SS3 9 to 10 feet	4.4	3.20 B	0.04 B
DANGB-8-MW20			
SS1 0 to 2 feet	15.0	3.40 B	U
SS2 6 to 8 feet	120.0	0.35 B	U
SS4 15 to 20.5 feet	720.0	3.60 B	U

1. B indicates the compound was detected in the laboratory blank.
2. U indicates that the compound was analyzed for but not detected.

TABLE N-28
DICHLOROMETHANE AND CHLOROFORM CONCENTRATIONS
DETECTED IN AREA/BACKGROUND GROUND-WATER SAMPLES
(Results are in micrograms per liter.)

Sample Location	Dichloromethane	Chloroform
DANGB-BG-MW32	2.2 B ⁽¹⁾	U ⁽²⁾
DANGB-BG-MW42	0.98 B	1.0 B
DANGB-BG-MW43	1.6 B	U

1. B indicates the compound was detected in the laboratory blank.
2. U indicates compound was analyzed for but not detected.

TABLE N-29
DICHLOROMETHANE AND CHLOROFORM CONCENTRATIONS
DETECTED IN SITE 2 GROUND-WATER SAMPLES
(Results are in micrograms per liter.)

Sample Location	Dichloromethane	Chloroform
MW 2	0.42 B ⁽¹⁾	U ⁽²⁾
MW 5	0.53 B	U
GW 2-D	0.80 B	U
DANGB-2-MW37	U	0.32 B
DANGB-2-MW38	0.96 B	0.86 B
DANGB-2-MW40	0.85 B	U
DANGB-2-MW41	U	0.15 B

1. B indicates the compound was detected in the laboratory blank.
2. U indicates compound was analyzed for but not detected.

TABLE N-30
DICHLOROMETHANE AND CHLOROFORM CONCENTRATIONS
DETECTED IN SITE 3 GROUND-WATER SAMPLES

(Results are in micrograms per liter.)

Sample Location	Dichloromethane	Chloroform
GW 3-B	0.50 B ⁽¹⁾	U ⁽²⁾
GW 3-C	U	2.8 B
GW 3-D	0.29 B	U
DANGB-3-MW25	1.6 B	U
DANGB-3-MW26	0.93 B	U
DANGB-3-MW27	0.50 B	U
DANGB-3-MW29	0.32 B	U
DANGB-3-MW30	U	1.3
DANGB-3-MW31	U	0.33 B
DANGB-3-MW33	0.50 B	0.25
DANGB-3-MW34	0.51 B	1.4

1. B indicates the compound was detected in the laboratory blank.
2. U indicates compound was analyzed for but not detected.

TABLE N-31
DICHLOROMETHANE AND CHLOROFORM
CONCENTRATIONS DETECTED IN SITE 4 GROUND-WATER SAMPLES
(Results are in micrograms per liter.)

Sample Location	Dichloromethane	Chloroform
MW 8	0.67 B ⁽¹⁾	U ⁽²⁾
MW 9	0.37 B	U
MW 10	0.04 B	U
MW 11	0.37 B	U
GW 4-A	0.31 B	U
GW 4-B	0.50 B	U
GW 4-D	0.49 B	U
DANGB-4-MW21	2.60 B	U
DANGB-4-MW22	0.69 B	0.23 B
DANGB-4-MW23	5.30 B	U
DANGB-4-MW24	4.10 B	0.18

1. B indicates the compound was detected in the laboratory blank.
2. U indicates that the compound was analyzed for but not detected.

TABLE N-32
DICHLOROMETHANE AND CHLOROFORM CONCENTRATIONS
DETECTED IN SITE 8 GROUND-WATER SAMPLES
(Results are in micrograms per liter.)

Sample Location	Dichloromethane	Chloroform
GW 8-A	1.60 B ⁽¹⁾	U ⁽²⁾
GW 8-B	0.46 B	U
GW 8-C	2.20 B	U
DANGB-8-MW14	1.70 B	U
DANGB-8-MW15	2.80 B	U
DANGB-8-MW16	0.12 B	0.14 B
DANGB-8-MW17	0.77 B	0.16 B

1. B indicates the compound was detected in the laboratory blank.
2. U indicates compound was analyzed for but was not detected.

N.3.4 Bis(2-ethylhexyl)phthalate

The surface water and ground-water samples in which bis(2-ethylhexyl)phthalate was detected also had, with one exception, this compound detected in the laboratory blank (Table N-33). On the other hand, detections of this compound in either sediment or soil did not have detections in the associated laboratory blanks. Therefore, the detections in water appear to be due to laboratory contamination. Bis(2-ethylhexyl)phthalate does appear to be present in the sediment and soil.

TABLE N-33
 BIS(2-ETHYLHEXYL)PHTHALATE
 CONCENTRATIONS DETECTED IN
 AREA/BACKGROUND, SITE 2 AND SITE 3 SURFACE WATER
 AND GROUND-WATER SAMPLES
 (results in micrograins per liter.)

Sample Location	Medium	Concentration
<u>Area/Background</u>		
MW42	Ground Water	10 B
MW43	Ground Water	13
<u>Site 2</u>		
MW 1	Ground Water	15 B
MW 2	Ground Water	10 B
MW 5	Ground Water	14 B
MW 39	Ground Water	100 B
<u>Site 3</u>		
SL 10 DUP	Surface Water	10 B
GW 3-B	Ground Water	17 B
GW 3-B DUP	Ground Water	19 B
MW 27	Ground Water	42 B
MW 28	Ground Water	23 B
MW 31	Ground Water	62 B

SECTION N.4
DATA VALIDATION

This page intentionally left blank.

SECTION N.4

DATA VALIDATION

The data validation is presented in this section. Data validations are presented in the following sections by type of compound. The quality control data on which the validation was done is located in the Data Packages in Appendix M.

N.4.1 Volatile Organic Analyses

Results were validated against U. S. Environmental Protection Agency, Laboratory Data Validation, Functional Guidelines for Evaluating Organic Analyses, May 28 1985.

N.4.1.1 Holding Times

All volatile organic compounds were validated against a 14-day holding time as required by the SW-846 8010/8020 methods. The holding time data are given in Tables N-1 through N-20. All samples met the required holding times.

N.4.1.2 GC/MS Tuning

The volatile organic analyses were performed by GC methods and did not require tuning of the instrument.

N.4.1.3 Calibration

Initial and continuing calibration checks documented satisfactory maintenance and adjustment of the instrument on a day-to-day basis in the 10% of samples checked.

N.4.1.4 Blanks

Two volatile organic compounds, dichloromethane and chloroform were frequently detected in varying concentrations in numerous soil and water samples. Several other volatile organic compounds were detected less frequently. In addition, many of these same compounds were detected in varying concentrations in laboratory blanks, field blanks, rinseate blanks, and trip blanks. This variation was in a randomly distributed pattern. This same random pattern was also evident in duplicates and background samples. This supports the hypothesis that these frequently detected compounds are the result of common laboratory contamination, and the presence of the other compounds in the blanks is the result of isolated occurrences. Neither of these should affect other data.

All blanks were evaluated against the guidelines and results were flagged as per the guidelines. Field blank, bailer rinseate blank and trip blank data are

presented in Appendix L.

N.4.1.5 Surrogate Recoveries

The surrogate used for methods SW 601/8010 was 1-chloro-2-bromopropane and the surrogate used for methods 602/8020 was a-a-a-trifluorotoluene. Temporary control limits were established for these surrogates based on the results of surrogate recoveries on the blank spikes. Control limits established on blank spikes will actually be tighter than those established by multiple laboratories on multiple matrices. The control limits were set at ± 3 standard deviations from the mean, and are as follows:

Method 601	67-117% Recovery (water)
Method 602	65-133% Recovery (water)
Method 8010	43-124% Recovery (soil)
Method 8020	31-148% Recovery (soil)

All surrogates were validated against these criteria, and samples outside these recovery limits were flagged.

N.4.1.6 Matrix Spike/Matrix Spike Duplicate

All matrix spikes/matrix spike duplicates (MS/MSD) were evaluated in conjunction with other QC criteria. Anytime a MS or MSD was outside recovery limits, the MS/MSD on the associated blank spike was reviewed. If the blank spike showed the laboratory to be in control, the results were accepted. If the blank spike showed the laboratory to be out of control, the sample(s) were reanalyzed.

N.4.1.7 Compound Identification

Roughly 10% of the positive values were reviewed with no problems detected. Second column confirmation was performed on all positive results as required. Instances where second column confirmations were conducted are given in Tables N-1 through N-20.

N.4.1.8 System Performance

One problem appeared that could not be explained or corrected through data validation. A large portion of soil samples showed varying levels of toluene. It was noted by field personnel that black electrical tape was used to seal the bottles containing the soil samples, while a white tape was used to seal all of the other samples. It was also noted in the field that the black tape had a strong odor. Subsequent qualitative testing of the tape on a field GC instrument has substantiated that the black tape did indeed show high levels of toluene. This leads to the conclusion that the toluene levels reported

in the soil samples are probably a result of the black tape used to seal the sample bottles.

N.4.2 Semi-Volatile Organic Analyses

Results were validated against U. S. Environmental Protection Agency, Laboratory Data Validation, Functional Guidelines for Evaluating Organic Analyses, May 28 1985.

N.4.2.1 Holding Times

All semi-volatile organic analyses were validated against a 7-day holding time for extraction of water samples; a 14-day holding time for extraction of soil and sediment samples; and a 40-day holding time for analysis from verified time of sample receipt. The holding time data are given in Tables N-1 through N-20. A major portion of the semi-volatile organic analyses missed holding times and were flagged according to the guidelines. Most of the samples missed holding times because the samples had to be re-extracted and re-analyzed due to QC values outside control limits.

N.4.2.2 GC/MS Tuning

Batches of data were analyzed with associated DFTPP tunes that met ion abundance criteria in the 10% of samples checked.

N.4.2.3 Calibration

Initial and continuing calibration checks documented satisfactory maintenance and adjustment of the instrument on a day-to-day basis in the 10% of samples checked.

N.4.2.4 Blanks

One semi-volatile organic compound was frequently detected in varying concentrations in both soil and water samples. That compound was bis(2-ethylhexyl)phthalate. Many phthalate esters are common laboratory contaminants and there are precise reporting criteria for them. All blanks were evaluated against these guidelines, and results were flagged as per the guidelines.

N.4.2.5 Surrogate Recoveries

All semi-volatile organic surrogates were validated against the "Laboratory Data Validation, Function Guidelines for Evaluating Organic Analyses", May 1985, and data were flagged according to these guidelines.

N.4.2.6 Matrix Spike/Matrix Spike Duplicate

All matrix spike/matrix spike duplicates (MS/MSD) were evaluated in conjunction with other QC criteria. Anytime a MS or MSD was outside

recovery limits, the MS/MSD on the associated blank spike was reviewed. If the blank spike showed the laboratory to be in control, the results were accepted. If the blank spike showed the laboratory to be out of control, the samples were reanalyzed.

N.4.2.7 Compound Identification

The positive values were reviewed with no problems detected. Instances where second column confirmations were conducted can be identified using Tables N-1 through N-20.

N.4.2.8 System Performance

The major problem that occurred was that many samples had to be re-extracted and re-analyzed outside of holding times.

N.4.3 Pesticide/PCB Data Validation

Results were validated against U. S. Environmental Protection Agency, Laboratory Data Validation, Functional Guidelines for Evaluating Pesticides/PCBs Analyses, May 28 1985.

N.4.3.1 Holding Times

All pesticide and PCB analyses were validated against a 7-day holding time for extraction of water samples; a 14-day holding time for extraction of soil and sediment samples; and a 40-day holding time for analysis from verified time of receipt. The holding time data are given in Tables N-1 through N-20. Several of the pesticide and PCB samples missed holding times because they had to be re-extracted and re-analyzed due to QC values outside of control limits. The samples that missed holding times were flagged according to protocol.

N.4.3.2 Pesticide Instrument Performance

Roughly 10% of the retention time window data was reviewed with no evidence of significant problems.

N.4.3.3 Calibration

Initial and continuing calibration checks were reviewed and there were no apparent problems.

N.4.3.4 Blanks

All of the pesticide and PCB blanks were reviewed. None of the blanks showed any compounds above detection limits.

N.4.3.5 Surrogates

All surrogate recoveries were reviewed. Although some recoveries were outside of control limits, the surrogate is for advisory purposes only and no

data were flagged. The results were evaluated by the laboratory at the time of analysis, and in most cases the blank spike showed the laboratory to be in control; other validation parameters were also within acceptable control limits.

N.4.3.6 Matrix Spike/Matrix Spike Duplicate

All of the matrix spike/matrix spike duplicates were evaluated against criteria. Several problems existed, however, none of these should affect data quality. The problems were as follows:

- a) The relative percent difference (RPD) and/or the percent recoveries (PR) for several spikes exceed the control limits, however, a blank spike analysis showed the laboratory to be in control in each case.
- b) Heptachlor epoxide was inadvertently used instead of heptachlor in the matrix spiking solution.
- c) In several samples, endrin aldehyde and kepone were not recoverable because they were removed by the alumina column clean-up that had to be used on the samples.
- d) In several cases, the samples were apparently double-spiked with matrix compounds.

N.4.3.7 Compound Identification

Retention time windows were reviewed on samples that showed positive values and required second column confirmation. No problems were observed. Instances where second column confirmations were conducted are given in Tables N-1 through N-20.

N.4.4 Total Petroleum Hydrocarbon Analyses Validation

Total petroleum hydrocarbon results were evaluated against U. S. Environmental Protection Agency, Laboratory Data Validation, Functional Guidelines for Evaluating Inorganic Analyses, May 28 1985.

N.4.4.1 Holding Times

All total petroleum hydrocarbon analyses were evaluated against a 28-day holding time for water samples, and no specified holding time for soil and sediment samples. The Remedial Investigation Work Plan (ES, 1988) specified a 14-day holding time for soil samples. This is incorrect, as there is no specified holding time for soil samples for the 418.1 method. The holding time data are given in Tables N-1 through N-20. All of the samples met holding times.

N.4.4.2 Calibration

All initial and continuing calibration data was reviewed. All of the

continuous calibration verification (CCV) values were within the required 80-120% window.

N.4.4.3 Blanks

All of the blanks were evaluated and found to be less than detection limits.

N.4.4.4 Duplicates

All of the duplicates were within the $\pm 20\%$ relative percent difference (RPD) required.

N.4.4.5 Matrix Spike/Matrix Spike Duplicate

All of the spikes were reviewed. Several spike recoveries were low, but in every case the blank spike was within limits, thus showing the laboratory to be in control. In several cases, there was insufficient volume of sample provided for spikes, so blank spikes were used for quality control purposes in these incidences.

N.4.5 Metals Analyses Validation

Metals results were validated against U. S. Environmental Protection Agency, Laboratory Data Validation, Functional Guidelines for Evaluation Inorganic Analyses, May 28 1985.

N.4.5.1 Holding Times

All metals analyses except for several mercury analyses met holding times. The holding time data are also given in Tables N-1 through N-20. These samples were flagged according to protocol.

N.4.5.2 Initial and Continuing Calibration

All sample batches were within calibration limits.

N.4.5.3 Blanks

All blanks were less than the Contract Required Detection Limit (CRDL).

N.4.5.4 ICP Interference Check Samples

All samples for ICP Analysis were within the ICP Interference Check Sample Limits.

N.4.5.5 Laboratory Control Samples

Several Laboratory Control Samples (LCS) were outside control limits, however, those samples were reanalyzed. All samples reported were analyzed in batches in which the LCSs met criteria, or the blank spike showed the laboratory to be in control.

N.4.5.6 Duplicates

Only two duplicates exceeded the 50% RPD level. However, all of the

analytes reported for the associated samples were less than 5 times the CRDL. No action is necessary.

N.4.5.7 Spikes

Several spikes were outside of control limits; however, post-digestion spikes of the same samples were within limits on all but 3 samples. This is an indication of digestion problems and the method of standard additions was performed as required for quantitation. The post-digestion spikes on the other 3 samples were similar to the original spikes. This indicates a matrix interference and no action was required.

This page intentionally left blank.

SECTION N.5
FIELD QUALITY CONTROL SAMPLES

This page intentionally left blank.

SECTION N.5

FIELD QUALITY CONTROL SAMPLES

Field quality control samples consisted of trip blanks (TB), field blanks (FB), coded field duplicates (DUP) and bailer rinseate (BR) samples. They can be identified in Tables L-1 through L-21 in which the laboratory results are presented by the designators TB, FB, DUP and BR.

N.5.1 Blanks

Blanks are artificial samples used to monitor the introduction of artifacts into aqueous samples. Two types of blanks were used in this Remedial Investigation. Trip blanks are organic-free, American Society for Testing Materials (ASTM) Type II reagent water samples that are sealed in sample containers at the laboratory. They are taken to the field where they remain sealed and are present during sampling and accompany field samples during transport to the laboratory. Field blanks are analyte-free water samples that are poured into sample containers while on site and are handled like samples. The water used is the same water used for final equipment decontamination rinses. Field blanks are used to monitor the introduction of analytes into sample containers during sampling.

N.5.1.1 Trip Blank Results

Fourteen trip blanks were analyzed for halogenated volatile organic compounds (SW 8010) and aromatic volatile organic compounds (SW 8020).

Bromodichloromethane and Chloroform were each detected in one trip blank at 0.27 and 0.2 ug/L respectively.

Bromoform was detected in six trip blanks at concentrations ranging from 8.1 to 30 ug/L.

Dibromoethane was detected in two trip blanks at concentrations of from 3.1 and 3.6 ug/L.

Dichloromethane was detected in all trip blanks at concentrations ranging from 0.61 to 4.5 ug/L. In each case, dichloromethane was detected in the associated laboratory blank as well as the trip blank, indicating that dichloromethane, was present as a laboratory contaminant.

Dibromochloromethane was detected in four trip blanks at concentrations ranging from 1.3 to 4.7 ug/L.

No aromatic volatile organics were detected in any of the trip blanks.

N.5.1.2 Field Blank Results

Nineteen field blanks were analyzed for halogenated volatile organic compounds (SW 8010) and aromatic volatile organic compounds (SW 8020). Five of the field blanks were filled while taking surface water samples and fourteen were filled while taking ground-water samples. No analytes were detected in the surface water field blanks. Chloroform, a suspected laboratory contaminant, was detected in nine of the field blanks filled during ground-water sampling at concentrations ranging from 13 to 16 ug/L. No other analytes were detected.

N.5.2 Duplicate Sample Results

Coded field duplicates were submitted to the laboratory with bottle labels and chain of custody identifiers different from the actual sample identification. In Tables L-1 through L-21, the field duplicates can be identified by the designation "DUP" following their identifiers. The criteria and considerations by which analyses results from samples and their respective duplicates are acceptably reproduced are similar to that required by laboratory precision evaluation and relative percent difference.

N.5.2.1 Airport Area and Background Locations

At the area locations, one duplicate sample from each media: surface water, sediment, soil and ground water was taken.

Toluene was detected at 1.0 ug/L in the soil duplicate sample but not the soil sample. All other analytes were acceptably reproduced.

All analytes detected in the surface water sample were acceptably reproduced from the duplicate sample.

Chloroform was detected at 14 ug/L in the ground-water duplicate sample, but not the ground-water sample. Butyl benzyl phthalate at 10 ug/L and bis(2-ethylhexyl)phthalate at 13 ug/L were detected in the ground-water sample but not in the duplicate sample. All other analytes were acceptably reproduced.

Chloroform was detected at 1.5 ug/L in the sediment sample but not in the duplicate sample. All other analytes were acceptably reproduced.

N.5.2.2 Site 2

At Site 2 one duplicate each was taken from the surface water and sediment, four duplicate samples were taken from the soil, and two duplicate samples were taken from the ground water.

Diethyl phthalate was detected at 144 ug/L in the Site 4 ground-water

sample but not in the duplicate sample. All other analytes were acceptably reproduced.

All analytes detected in the Site 2 surface water, sediment and soil sample/duplicate pairs were acceptably reproduced.

N.5.2.3 Site 3

At Site 3 one duplicate each was taken from the surface water and sediment, seven duplicate samples were taken from the soil, and two duplicate samples were taken from the ground water.

Chloroform at 3.5 ug/kg, dichlorodifluoromethane at 0.25 ug/kg, toluene at 1.6 ug/kg, 4,4'-DDE at 33 ug/kg, 4,4'-DDT at 75 ug/kg, and total petroleum hydrocarbons at 600 mg/L were detected in the soil samples but not in their respective duplicate samples. Tetrachloroethene at 0.41 ug/kg, and diethyl phthalate at 1500 ug/kg were detected in the duplicate samples but not in their respective soil samples. All other analytes were acceptably reproduced.

Chloroform at 1.8 ug/kg was detected in one of the ground-water samples but not in its respective duplicate sample. All other analytes were acceptably reproduced.

N.5.2.4 Site 4

At Site 4 one duplicate sample each was taken from the surface water and sediment, two duplicate samples were taken from soil, and one duplicate sample was taken from the ground water.

All analytes detected in the sediment sample/duplicate pair were acceptably reproduced.

Xylenes at 4.1 ug/kg were detected in one of the duplicate soil samples but not in its respective sample. All other analytes were acceptably reproduced.

Trichloroethene at 0.98 ug/kg was detected in the surface water sample but not in its respective duplicate. Toluene at 23 ug/L and petroleum hydrocarbons at 2.5 mg/L were detected in the surface water duplicate but not in its respective sample. All other analytes were acceptably reproduced.

All analytes detected in the ground water sample/duplicate pairs were acceptably reproduced.

N.5.2.5 Site 8

At Site 8 one sample each was taken from the surface water and sediment, six duplicate samples were taken from soil and one duplicate sample was taken from the ground water.

All analytes detected in the ground-water sample/duplicate pair were acceptably reproduced.

Chloroform at 120 ug/kg and toluene at 220 ug/kg were detected in a Site 8 soil sample duplicate but not in the respective sample. All other analytes were acceptably reproduced.

All analytes detected in the surface water and sediment sample/duplicate pairs were acceptably reproduced.

N.5.2.6 Site 10

At Site 10, one duplicate sample was taken from the ground water during each sampling round.

N.5.3 Bailer Rinseate Results

Sampling device cleanliness is monitored using bailer rinseate samples. After decontamination, sampling equipment was rinsed using analyte-free water. The rinseate was collected and treated as a sample from the site where the sampling equipment was used. One bailer rinseate sample was collected during area/background sampling activities, two bailer rinseate samples were collected during Site 2 sampling activities, one was collected during Site 3 sampling activities, and two samples each were collected during Site 4 and Site 8 sampling activities.

No analytes were detected in the Site 2 bailer rinseate sample.

Chloroform at 14 ug/L and diethyl phthalate at 15 ug/L were detected in the background bailer rinseate sample.

Chloroform at 11 and 0.87 ug/L was detected in two of the three Site 3 bailer rinseate samples.

Chloroform at 15 ug/L was detected in one of the Site 4 bailer rinseate samples.

No analytes were detected from the Site 8 bailer rinseate samples.

APPENDIX O
SOIL GAS SURVEY

This page intentionally left blank.

APPENDIX O
TABLE OF CONTENTS

	Page
O.1 INTRODUCTION	O-7
O.2 SOIL GAS SURVEY METHODS	O-11
O.3 QUALITY CONTROL PROCEDURES	O-17
O.4 RESULTS	O-21
O.4.1 Benzene	O-23
O.4.2 Chlorobenzene	O-23
O.4.3 Cis-1,2-Dichloroethene (DCE)	O-23
O.4.4 Tetrachloroethene (PCE)	O-30
O.4.5 Toluene	O-30
O.4.6 Trichloroethene (TCE)	O-30
O.4.7 Xylene	O-30
O.5 DISCUSSION OF ANALYTICAL RESULTS	O-35

APPENDIX O
LIST OF FIGURES

	Page
O-1 Soil Gas Sampling Locations at Site 3	O-14
O-2 Concentration of Benzene in Soil Gas at Site 3	O-24
O-3 Concentration of Chlorobenzene in Soil Gas at Site 3	O-25
O-4 Concentration of Cis-1,2-Dichloroethene in Soil Gas at Site 3	O-26
O-5 Concentration of Tetrachloroethene in Soil Gas at Site 3	O-31
O-6 Concentration of Toluene in Soil Gas at Site 3	O-32
O-7 Concentration of Trichloroethene in Soil Gas at Site 3	O-33
O-8 Concentration of Xylene in Soil Gas at Site 3	O-34

LIST OF TABLES

	Page
O-1 Soil Gas Survey Results	O-27

This page intentionally left blank.

SECTION 0.1
INTRODUCTION

This page intentionally left blank.

SECTION O.1 INTRODUCTION

As part of the Remedial Investigation conducted at the Duluth Air National Guard Base (ANGE), a soil gas survey (SGS) was performed at Site 3 (DPDO Storage Area C). The purpose of this survey was to optimize the placement of ground water monitoring wells, soil borings, and other sampling points at the site. The objectives of the survey were to:

- (1) determine the most probable source of sources of contamination impacting the subsurface soil, ground water, and surface water in the vicinity of the site;
- (2) attempt to quantify the concentrations of contaminants present in the soil and ground water beneath the site; and
- (3) define the approximate lateral extent and migration direction of the contamination in subsurface soil and ground water.

This appendix includes a summary of the methods used in the collection and analysis of samples followed by a discussion of the results and their implications at the site.

This page intentionally left blank.

SECTION 0.2
SOIL GAS SURVEY METHODS

This page intentionally left blank.

SECTION O.2

SOIL GAS SURVEY METHODS


The soil gas survey was conducted at Site 3 between July 7 and 13, 1988. The horizontal extent of volatile organic contamination was investigated by a 57 point soil gas survey over an approximately 600- by 600- foot area. A 49 point grid was established with columns lettered A through G oriented northwest-southeast and rows numbered 0 to 6 oriented northeast to southwest (Figure O-1). Additional points were taken outside the grid structure and are numbered 49, and 53 through 59 on Figure O-1.

Sampling depths were determined by conducting depth profiles at two initial points, points DANGB-3-SGB2 and DANGB-3-SGB3. The profiles were conducted by collecting and analyzing samples at depths ranging from 1 to 8 feet. The purpose of the depth profiling was to identify the contact between the aerobic and anaerobic soil zones. Soil gas samples should be collected below this contact depth where possible for optimal results since aromatic hydrocarbons rapidly decrease in concentration in the aerobic zone due to biodegradation.

Based on the depth profile results, remaining soil gas samples were collected from a depth of 7 feet whenever possible.

Soil gas samples were collected using hollow 0.75-inch stainless steel (type 316) sampling probes inserted mechanically into the soil. After installation of the sampling probe, a vacuum pump was used to withdraw soil gases through the probe into a one liter Tedlar sampling bag. The bags were equipped with septa through which gas samples were withdrawn using a gas-tight syringe. Samples were then injected into a portable gas chromatograph (GC).

Two Photovac portable GC units, model number 10S50 and using photoionization detectors (PIDs) with 10.6 electron-volt (eV) light sources, were used for on-site analysis. The GCs were equipped with isothermal ovens and were set up with precolumn/backflush configurations using CPSil 5CB packed columns. These columns are useful for non-polar hydrocarbons and are recommended by the Photovac corporation for separation of compounds containing 4 to 8 carbon atoms.



EXPLANATION

+ Soil gas sampling location

Figure O-1 Soil Gas Sampling Locations at Site 3.

The following compounds were suspected to occur at the sites and were targeted for calibration and analysis: benzene, toluene, chlorobenzene, m-xylene, o-xylene, 1,1-dichloroethene (DCE), cis-1,2-dichloroethene, trichloroethene (TCE), tetrachloroethene (PCE), and vinyl chloride.

Calibration of the GCs was done in one of two ways. Commercially prepared 1 part per million (ppm) standards were used for calibration of benzene, toluene, chlorobenzene, and o-xylene using a standard prepared by Scott Specialty Gases (mix no. 6670). A second 1 ppm standard (Scott Specialty Gases mix no. 6675) was used for calibration of vinyl chloride, cis-1,2-DCE, and PCE. The remaining two compounds, m-xylene and TCE, were calibrated using a 10 ppm mixture prepared on-site several times daily. This standard was prepared by diluting vapors obtained from the headspace above a volume of pure liquid compound in an airtight vial. The amount of headspace vapor needed to prepare the standard was determined using a table of standard vapor pressures adjusted to the prevailing temperature and barometric pressure. Instrument response was checked by preparing standards for each target compound at higher and lower concentrations in order to construct three-point calibration curves at concentrations approximating those expected in the samples.

Injection volumes and instrument gain settings were adjusted to accommodate the range of concentrations encountered. This was done by prescreening the samples prior to injection into the GCs using a portable organic vapor detector (Photovac TIP), which uses a PID to give an indication of total organic vapors present. The readings obtained were used to adjust injection volumes such that the injections did not saturate the detectors in the GCs. Injection volumes varied from 5 to as much as 2,000 microliters (uL).

This page intentionally left blank.

SECTION 0.3
QUALITY CONTROL PROCEDURES

This page left intentionally blank.

SECTION O.3

QUALITY CONTROL PROCEDURES

A number of quality control procedures were followed to insure the validity of the data obtained during sampling. Three-point calibration curves and data from equipment blanks were used to determine practical detection limits and instrument response. Several types of blanks were routinely analyzed, including instrument, syringe, and bag blanks. Background air was analyzed to determine possible interferences. Decontamination procedures were checked by analyzing samples taken through some or all portions of the sampling train. Spikes were analyzed using particular analytes of interest. A minimum of 10 percent duplicates were analyzed, both by repeating the analysis done on a particular bag and by resampling selected locations at different times. A minimum of 20 percent of the analyses run over the course of a day were for quality control documentation, including all duplicates, spikes, and blanks. Where problems were observed, immediate remedial action was taken to allow sampling to proceed.

This page intentionally left blank.

SECTION O.4
RESULTS

This page intentionally left blank.

SECTION O.4

RESULTS

The data collected from the soil gas survey were used to generate graphic representations of contaminants in soil gases at the site. Vinyl chloride and 1,1-DCE were not detected at any of the 57 sampling points and are therefore not considered further. The results for the remaining compounds are given in Table O.1 and addressed below.

O.4.1 BENZENE


Benzene was detected at four sampling points (Figure O-2). With the exception of point DANGB-3-SGG2, a benzene anomaly extended two hundred feet to the northwest from point DANGB-3-SGB2. Concentrations of benzene ranged from 0.03 ppm at DANGB-3-SGB4 and DANGB-3-SGG2 to 1.4 ppm at point DANGB-3-SGB2. However, four duplications were run from a 3-foot deep sample at DANGB-3-SGB2 and the concentrations ranged from 0.04 to 1.4 ppm. In samples collected from 5-foot, 6-foot, and 8-foot depths at DANGB-3-SGB2, benzene was not detected in the 5 and 8-foot samples and had a concentration of only 0.02 ppm in the 6-foot sample.

O.4.2 CHLOROBENZENE

Chlorobenzene was detected at concentrations ranged from 0.03 ppm at point DANGB-3-SGD2 to 0.76 ppm at point 49. Chlorobenzene exhibited an anomaly centered near point DANGB-3-SGB2 (Figure O-3) which extended in a southwesterly direction. Secondary anomalies were detected near the center of the site and along the eastern boundary.

O.4.3 CIS-1,2-DICHLOROETHENE (DCE)

Cis-1,2-Dichloroethene was detected only at point DANGB-3-SGB2. The concentration shown in Figure O-4 (6.4 ppm) was the highest concentration observed among seven samples taken from the 3 foot to 8 foot depth intervals. The average concentration in these seven samples was 1.2 ppm.




EXPLANATION

0.029 + Probe point with concentration in ppm.
Where no concentration is shown, compound
was not detected.

Contour interval = 10x
Contours dashed where interred

Figure O-2 Concentration of Benzene in Soil Gas at Site 3.




EXPLANATION

0.036 + Probe point with concentration in ppm.
Where no concentration is shown, compound¹
was not detected.

Contour interval = 10x
Contours dashed where inferred

Figure O-3 Concentration of Chlorobenzene in Soil Gas at Site 3.



EXPLANATION

64 +

Probe point with concentration in ppm
Where no concentration is shown, compound
was not detected.

Contour interval = 10x
Contours dashed where inferred

Figure O-4 Concentration of Cis-1,2-Dichloroethene in Soil Gas at Site 3.

TABLE O-1
MINNESOTA AIR NATIONAL GUARD BASE, DULUTH, MINNESOTA
SOIL GAS SURVEY RESULTS
(Results in parts per million unless otherwise noted.)

Sample	Soil Gas (SG) Date	Injection Volume (ul)	Vinyl Chloride 50 ^a	1,1 DCE 50 ^a	CIS 1,2 DCE 10 ^a	Benzene 10 ^a	Toluene 10 ^a	O- Xylene 10 ^a	M- Xylene 10 ^a	Chloro Benzene 30 ^a	TCE 5 ^a	PCE 10 ^a
SG A-0	7/11/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG A-1	7/11/88	1,000	ND	ND	ND	ND	ND	0.0496	0.0307	0.2040	ND	ND
SG A-2	7/08/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG A-2D	7/08/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG A-3	7/11/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG A-4	7/11/88	1,000	ND	ND	ND	ND	ND	0.0272	0.0389	ND	ND	ND
SG A-5	7/11/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG A-6	7/11/88	1,000	ND	ND	ND	ND	ND	ND	0.0337	ND	ND	ND
SG B-0	7/11/88	1,000	ND	ND	ND	ND	ND	0.9084	ND	ND	ND	ND
SG B-1	7/11/88	1,000	ND	ND	ND	ND	ND	ND	0.3310	ND	ND	0.0151
SG B-2-3'	7/07/88	5	ND	ND	ND	0.8092	ND	ND	79.9	ND	14.5	ND
SG B-2-3'D	7/07/88	15	ND	ND	ND	1.4	ND	ND	191.5	ND	16.3	ND
SG B-2-3'D2	7/07/88	200	ND	ND	0.384	0.0524	ND	ND	0.2255	ND	ND	0.0547
SG B-2-3'D3	7/07/88	1,000	ND	ND	1.7	0.0406	ND	ND	0.4532	0.4012	ND	0.2124
SG B-2-5'	7/07/88	1,000	ND	ND	6.4	ND	0.3944	ND	0.0412	ND	ND	ND
SG B-2-6	7/07/88	1,000	ND	ND	0.0293	0.0229	0.4628	ND	0.2024	0.1888	ND	0.0968
SG B-2-8'	7/07/88	1,000	ND	ND	0.1895	ND	0.9866	ND	0.1121	ND	ND	ND
SG B-3	7/08/88	2,000	ND	ND	ND	0.3458	ND	ND	ND	0.0737	ND	ND
SG B-3D	7/08/88	1,000	ND	ND	ND	0.5544	ND	ND	ND	0.0801	ND	ND
SG B-4	7/08/88	2,000	ND	ND	ND	0.0327	ND	0.0396	ND	ND	ND	ND
SG B-4D	7/08/88	200	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG B-5	7/08/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG B-5D	7/08/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG B-6	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG C-0	7/10/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG C-0D	7/10/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG C-1	7/11/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG C-2-3'	7/08/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG C-2-6'	7/08/88	1,000	ND	ND	ND	ND	ND	ND	0.0109	ND	ND	ND

Sample	Soil Gas (SG) Date	Injection Volume (ul)	Vinyl Chloride 50 ^a	1,1 DCE 50 ^a	1,2 DCE 10 ^a	Benzene 10 ^a	Toluene 10 ^a	o- Xylene 10 ^a	m- Xylene 10 ^a	Chloro Benzene 30 ^a	TCE 5 ^a	PCE 10 ^a
SG F-4	7/08/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG F-4D	7/08/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG F-5	7/09/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG F-5D	7/09/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG F-6	7/13/88	1,000	ND	ND	ND	ND	ND	ND	0.0166	ND	ND	ND
SG G-0	7/10/83	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG G-1	7/10/83	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG G-2	7/09/83	2,000	ND	ND	0.0290	0.0373	ND	ND	0.0159	ND	ND	ND
SG G-3	7/09/83	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG G-4	7/09/83	2,000	ND	ND	ND	ND	ND	ND	ND	0.0358	ND	ND
SG G-4D	7/09/83	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG G-5	7/09/83	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG G-5D	7/09/83	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG G-6	7/13/83	500	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG G-6D	7/13/83	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG 49	7/12/83	500	ND	ND	ND	ND	ND	ND	0.3177	0.0758	ND	0.0754
SG 53	7/13/83	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG 54	7/13/83	1,000	ND	ND	ND	ND	ND	0.1165	ND	ND	ND	ND
SG 55	7/13/83	1,000	ND	ND	ND	ND	ND	0.1401	ND	ND	ND	ND
SG 56	7/13/83	1,000	ND	ND	ND	ND	ND	0.0123	0.0104	0.6830	ND	ND
SG 57	7/13/83	1,000	ND	ND	ND	ND	1.8	0.0136	ND	0.0493	ND	ND
SG 57D	7/13/83	1,000	ND	ND	ND	ND	1.2	0.0435	0.0183	0.5450	ND	ND
SG 58	7/13/83	1,000	ND	ND	ND	ND	ND	0.0115	ND	ND	ND	ND
SG 59	7/13/83	1,000	ND	ND	ND	ND	ND	0.1977	ND	ND	ND	ND

*ND - Not Detected.

ID indicates duplicate sample.

^aDetection limit in ppb.

TABLE O-1 (Continued)

Sample	Soil Gas (SG) Date	Injection Volume (ul)	Vinyl Chloride 50 ^a	1,1 DCE 50 ^a	CIS 1,2 DCE 10 ^a	Benzene 10 ^a	Toluene 10 ^a	0- Xylene 10 ^a	M- Xylene 10 ^a	Chloro Benzene 30 ^a	TCE 5 ^a	PCE 10 ^a
SG C-6D	7/08/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG C-3	7/08/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG C-4	7/12/88	1,000	ND	ND	ND	ND	0.0717	0.5448	ND	0.2576	ND	ND
SG C-4D	7/12/88	1,000	ND	ND	ND	ND	0.0529	1.2	ND	0.1654	0.0153	ND
SG C-5	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG C-6	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG D-0	7/10/88	2,000	ND	ND	ND	ND	ND	ND	0.0119	ND	ND	ND
SG D-1	7/11/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG D-2	7/08/88	2,000	ND	ND	ND	ND	ND	ND	ND	0.0336	0.5073	ND
SG D-2D	7/08/88	1,000	ND	ND	ND	ND	ND	ND	ND	0.2475	0.1968	ND
SG D-3	7/08/88	2,000	ND	ND	ND	ND	0.0972	ND	ND	ND	ND	ND
SG D-3D	7/08/88	200	ND	ND	ND	ND	0.0884	0.0314	ND	ND	0.0087	ND
SG D-4	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG D-5	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG D-6	7/07/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG D-6D	7/07/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG E-0	7/10/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	0.1555	ND
SG E-0A	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG E-0B	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG E-1	7/11/88	1,000	ND	ND	ND	ND	ND	ND	0.0111	ND	ND	ND
SG E-2	7/09/88	2,000	ND	ND	ND	ND	ND	0.0137	ND	ND	ND	ND
SG E-3	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG E-4	7/12/88	1,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG E5	7/09/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG E-5D	7/09/88	1,000	1.3	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG E-6	7/13/88	1,000	ND	ND	ND	ND	ND	ND	0.0424	ND	ND	ND
SG F-0	7/10/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG F-0D	7/10/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG F-1	7/10/88	2,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
SG F-2	7/09/88	2,000	ND	ND	ND	ND	0.0102	ND	ND	ND	ND	ND
SG F-3	7/09/88	2,000	ND	ND	ND	ND	0.0111	ND	ND	ND	ND	ND

O.4.4 TETRACHLOROETHENE (PCE)

A PCE anomaly was centered around point DANGB-3-SGB2 as shown in Figure O-5. Detected concentrations ranged from 0.015 to 0.21 ppm.

O.4.5 TOLUENE

Toluene was detected in three anomalies at Site 3 as shown in Figure O-6. The highest concentrations (0.93-1.5 ppm) were centered on point DANGB-3-SGB2. A second anomaly (0.06-0.09 ppm) was detected under the asphalt storage yard, and a third anomaly (0.01-0.04 ppm) was detected at the midpoint of the eastern boundary of the study grid.

O.4.6 TRICHLOROETHENE (TCE)

Four TCE anomalies were detected at Site 3 during this investigation (Figure O-7). The highest concentration TCE (16.3 ppm) was detected at point DANGB-3-SGB2. A second anomaly, centered on point DANGB-3-SGD2, had a maximum concentration of 0.5 ppm in the soil gas. The third anomaly centered on point DANGB-3-SGE0, had a maximum concentration of 0.16 in the soil gas.

At point DANGB-3-SGB2, four duplicate samples were run from the 3-foot depth along with samples from 5, 6, and 8 foot depths. Two of the analyses from the 3 foot interval gave high concentrations (14-16 ppm). In contrast, TCE was not detected in the rest of the samples from DANGB-3-SGB2.

O.4.7 XYLENE

Xylene is the most widespread contaminant at Site 3 based on the soil gas survey. Concentrations presented in Figure O-8 represent the highest concentration of either o-xylene or m-xylene detected at a particular sampling point. The highest concentration, 191 ppm, was found at point DANGB-3-SGB2. The 191 and 80 ppm values at point DANGB-3-SGB2 represent the highest detected concentration of four samples taken from the 3 foot depth interval while the other two samples had only 0.22-0.45 ppm. The xylene concentrations in the 5, 6, and 8 foot samples at DANGB-3-SGB2 were 0.04 to 0.20 ppm.




EXPLANATION

0.21 +

Probe point with concentration in ppm
Where no concentration is shown, compound
was not detected

Contour interval = 10x
Contours dashed where inferred

Figure O-5 Concentration of Tetrachloroethene in Soil Gas at Site 3.




EXPLANATION

0.093 + Probe point with concentration in ppm.
Where no concentration is shown, compound
was not detected

Contour interval = 10x
Contours dashed where inferred

Figure O-6 Concentration of Toluene in Soil Gas at Site 3.




EXPLANATION

0.5073 + Probe point with concentration in ppm
Where no concentration is shown, compound
was not detected.

Contour interval = 10x
Contours dashed where inferred

Figure O-7 Concentration of Trichloroethene in Soil Gas at Site 3.



EXPLANATION

0.031 +

Probe point with concentration in ppm
Where no concentration is shown, compound
was not detected.

Contour interval = 10x
Contours dashed where inferred

Figure O-8 Concentration of Xylene in Soil Gas at Site 3.

SECTION 0.5
DISCUSSION OF ANALYTICAL RESULTS

This page intentionally left blank.

SECTION O.5

DISCUSSION OF ANALYTICAL RESULTS

Waste petroleum oils and lubricants, waste solvents, and chemicals were stored at Site 3 from 1965 to 1980. Minor drum leaks are known to have occurred in the past, although no major spills were recorded. The primary area of contamination appears to be centered around point DANGB-3-SGB2 located within Storage Area C.

Several compounds were detected in this anomaly including benzene, chlorobenzene, cis-1,2-dichloroethene, tetrachloroethene, toluene, trichloroethene, and xylene. However, the concentrations of benzene, trichloroethene, and xylene at point DANGB-3-SGB2 are uncertain since widely differing analytical results (16.3 ppm to undetected for trichloroethene; 191 to 0.04 ppm for xylene; 1.4 to 0.04 ppm for benzene) were obtained from four samples collected at a depth of 3 feet. The actual concentrations at DANGB-3-SGB2 for benzene, trichloroethene, and xylene are probably the lower values reported for the 3-foot depth samples since a larger injection size (1,000 vs. 5 uL) was used to determine those results. A larger injection size lowers the detection limit and lessens the chance of ambient air and contaminated syringes affecting the results. In addition, the lower values for benzene, toluene, and trichloroethene are supported by chemical results from this study and previously published soil and ground water analyses (Dames & Moore, 1987).

Other minor anomalies were detected elsewhere on the site, as depicted in Figures O-2 through O-8. The anomaly under the existing storage yard, near point DANGB-3-SGC2, was suspected by the field team to be representative of surface contamination. The minor hydrocarbon anomalies probably reflect relatively small surface spills throughout the area since the total amount of volatile hydrocarbons present at the anomalies shown on Figures O-2, O-6, and O-8 is low.

The glacial till with locally occurring clay layers and perched water tables can mask soil gas anomalies. Consequently, soil gas results, which indicate only minor localized contamination, may be distorted by geologic conditions. However, the tetrachloroethene anomaly centered near point DANGB-3-SGB2 defines the source area of ground-water contamination

determined by Dames & Moore (1987). Consequently, the soil gas data can be interpreted to be representative of source areas of chlorinated solvent contamination present at the site. Localized trichloroethene soil gas anomalies shown on Figure O-7 may represent separate point sources of contamination.

APPENDIX P
RISK ASSESSMENT TABLES

This page intentionally left blank.

APPENDIX P

TABLE OF CONTENTS

P.1	INTRODUCTION	Page
P.1.1	Indicator Chemical Selection	P-11
P.1.2	Estimation of Chemical Intake for Each Pathway	P-13
P.1.3	Estimation of Total Chemical Intake for Each Exposure Route	P-14
P.1.4	Characterization of Risk from Noncarcinogens	P-15
P.1.5	Characterization of Risk from Potential Carcinogens	P-16
P.2	Site 2 Risk Assessment Tables	P-19
P.2.1	Site 2 Indicator Chemical Selection	P-21
P.2.2	Site 2 Estimation of Chemical Intake for Each Pathway	P-21
P.2.3	Site 2 Estimation of Total Chemical Intake for Each Exposure Route	P-21
P.2.4	Site 2 Characterization of Risk from Noncarcinogens	P-21
P.2.5	Site 2 Characterization of Risk from Potential Carcinogens	P-21
P.3	Site 3 Risk Assessment Tables	P-59
P.3.1	Site 3 Indicator Chemical Selection	P-61
P.3.2	Site 3 Estimation of Chemical Intake for Each Pathway	P-61
P.3.3	Site 3 Estimation of Total Chemical Intake for Each Exposure Route	P-61
P.3.4	Site 3 Characterization of Risk from Noncarcinogens	P-61
P.3.5	Site 3 Characterization of Risk from Potential Carcinogens	P-61
P.4	Site 4 Risk Assessment Tables	P-97
P.4.1	Site 4 Indicator Chemical Selection	P-99
P.4.2	Site 4 Estimation of Chemical Intake for Each Pathway	P-99
P.4.3	Site 4 Estimation of Total Chemical Intake for Each Exposure Route	P-99
P.4.4	Site 4 Characterization of Risk from Noncarcinogens	P-99
P.4.5	Site 4 Characterization of Risk from Potential Carcinogens	P-99

APPENDIX P
TABLE OF CONTENTS (continued)

	Page
P.5 Site 8 Risk Assessment Tables	P-133
P.5.1 Site 8 Indicator Chemical Selection	P-135
P.5.2 Site 8 Estimation of Chemical Intake for Each Pathway	P-135
P.5.3 Site 8 Estimation of Total Chemical Intake for Each Exposure Route	P-135
P.5.4 Site 8 Characterization of Risk from Noncarcinogens	P-135
P.5.5 Site 8 Characterization of Risk from Potential Carcinogens	P-135

APPENDIX P

LIST OF TABLES

	Page
P-1 Maximum and Representative Chemical Concentrations at Site 2	P-22
P-2 Toxicity Data For Compounds Detected at Site 2	P-23
P-3 CT Values For Noncarcinogenic Compounds Detected at Site 2	P-25
P-4 CT Values For Potentially Carcinogenic Compounds Detected at Site 2	P-26
P-5 Indicator Scores and Tentative Ranking For Compounds Detected at Site 2	P-27
P-6 Future Exposure Point Intake Via Ingestion of Soil at Depth For Workers at Site 2	P-28
P-7 Future Exposure Point Intake Via Ingestion of Ground Water as Drinking Water For Onsite Adult Residents or Workers at Site 2	P-29
P-8 Future Exposure Point Intake Via Ingestion of Ground Water as Drinking Water for Onsite Child Residents at Site 2	P-30
P-9 Current Exposure Point Intake Via Ingestion of Surface Soils for Workers at Site 2	P-31
P-10 Current Exposure Point Intake Via Fugitive Dust Generation (FDG) For Workers at Site 2	P-32
P-11 Current Exposure Point Intake Via Ingestion of Surface Soils For Nearby Adults Visiting Site 2	P-33
P-12 Current Exposure Point Intake Via Fugitive Dust Generation (FDG) For Nearby Adults Visiting Site 2	P-34
P-13 Current Exposure Point Intake Via Ingestion of Surface Soils For Nearby Children Visiting Site 2	P-35
P-14 Current Exposure Point Intake Via Fugitive Dust Generation (FDG) For Nearby Children Visiting Site 2	P-36
P-15 Future Total Chronic Intake - Onsite Adult Residents or Workers at Site 2	P-37
P-16 Future Total Chronic Intake - Onsite Child Residents at Site 2	P-38
P-17 Total Chronic Intake For Workers at Site 2 - Current	P-39
P-18 Total Chronic Intake For Adults Near Site 2 - Current	P-40
P-19 Total Chronic Intake for Children Near Site 2 - Current	P-41
P-20 Chronic Hazard Index - Onsite Adult Residents or Workers at Site 2 - Future	P-42
P-21 Chronic Hazard Index - Onsite Child Residents at Site 2 - Future	P-43

APPENDIX P (continued)
LIST OF TABLES

	Page
P-22 Chronic Hazard Index For Workers on Site 2 - Current - Upper Bound	P-44
P-23 Chronic Hazard Index For Workers on Site 2 - Current - Best Estimate	P-45
P-24 Chronic Hazard Index For Adults Near Site 2 - Current - Upper Bound	P-46
P-25 Chronic Hazard Index For Adults Near Site 2 - Current - Best Estimate	P-47
P-26 Chronic Hazard Index For Children Near Site 2 - Current - Upper Bound	P-48
P-27 Chronic Hazard Index For Children Near Site 2 - Current - Best Estimate	P-49
P-28 Risk From Potential Carcinogens - Onsite Adult Residents or Workers at Site 2 - Future	P-50
P-29 Risk From Potential Carcinogens - Onsite Child Residents at Site 2 - Future	P-51
P-30 Risk From Potential Carcinogens For Workers on Site 2 - Current - Upper Bound	P-52
P-31 Risk From Potential Carcinogens For Workers on Site 2 - Current - Best Estimate	P-53
P-32 Risk From Potential Carcinogens For Adults Near Site 2 - Current - Upper Bound	P-54
P-33 Risk From Potential Carcinogens For Adults Near Site 2 - Current - Best Estimate	P-55
P-34 Risk From Potential Carcinogens For Children Near Site 2 - Current - Upper Bound	P-56
P-35 Risk From Potential Carcinogens For Children Near Site 2 - Current - Best Estimate	P-57
P-36 Maximum and Representative Chemical Concentrations at Site 3	P-63
P-37 Toxicity Data For Compounds Detected at Site 3	P-65
P-38 CT Values For Noncarcinogenic Compounds Detected at Site 3	P-67
P-39 CT Values For Potentially Carcinogenic Compounds Detected at Site 3	P-69
P-40 Indicator Scores and Tentative Ranking For Compounds Detected at Site 3	P-71
P-41 Future Exposure Point Intake Via Ingestion of Soil at Depth For Workers at Site 3	P-73

APPENDIX P (continued)

LIST OF TABLES

		Page
P-42	Future Exposure Point Intake Via Ingestion of Ground Water as Drinking Water For Onsite Residents or Workers at Site 3	P-74
P-43	Future Exposure Point Intake Via Ingestion of Ground Water as Drinking Water for Child Residents at Site 3	P-75
P-44	Current Exposure Point Intake Via Ingestion of Surface Soils For Workers at Site 3	P-76
P-45	Current Exposure Point Intake Via Volatilization of Surface Water For Workers at Site 3	P-77
P-46	Current Exposure Point Intake Via Ingestion of Surface Water During Recreation For Adults Near Site 3	P-78
P-47	Current Exposure Point Intake Via Ingestion of Surface Water During Recreation For Children Near Site 3	P-79
P-48	Future Total Chronic Intake - Onsite Adult Residents or Workers at Site 3	P-80
P-49	Future Total Chronic Intake - Onsite Child Residents at Site 3	P-81
P-50	Total Chronic Intake For Workers at Site 3 - Current	P-82
P-51	Total Chronic Intake For Adults Near Site 3 - Current	P-83
P-52	Total Chronic Intake for Children Near Site 3 - Current	P-84
P-53	Chronic Hazard Index - Onsite Adult Residents or Workers at Site 3 - Future	P-85
P-54	Chronic Hazard Index - Onsite Child Residents at Site 3 - Future	P-86
P-55	Chronic Hazard Index For Workers on Site 3 - Current - Upper Bound	P-87
P-56	Chronic Hazard Index For Workers on Site 3 - Current - Best Estimate	P-88
P-57	Chronic Hazard Index For Adults Near Site 3 - Current	P-89
P-58	Chronic Hazard Index For Children Near Site 3 - Current	P-90
P-59	Risk From Potential Carcinogens - Onsite Adult Residents or Workers at Site 3 - Future	P-91
P-60	Risk From Potential Carcinogens - Onsite Child Residents at Site 3 - Future	P-92
P-61	Risk From Potential Carcinogens For Workers on Site 3 - Current - Upper Bound	P-93
P-62	Risk From Potential Carcinogens For Workers on Site 3 - Current - Best Estimate	P-94

APPENDIX P (continued)
LIST OF TABLES

	Page
P-63 Risk From Potential Carcinogens For Adults Near Site 3 - Current	P-95
P-64 Risk From Potential Carcinogens For Children Near Site 3 - Current	P-96
P-65 Maximum and Representative Chemical Concentrations at Site 4	P-101
P-66 Toxicity Data For Compounds Detected at Site 4	P-102
P-67 CT Values For Noncarcinogenic Compounds Detected at Site 4	P-103
P-68 CT Values For Potentially Carcinogenic Compounds Detected at Site 4	P-104
P-69 Indicator Scores and Tentative Ranking For Compounds Detected at Site 4	P-105
P-70 Future Exposure Point Intake Via Ingestion of Ground Water as Drinking Water For Adult Onsite Residents or Workers at Site 4	P-106
P-71 Future Exposure Point Intake Via Ingestion of Ground Water as Drinking Water for Onsite Child Residents at Site 4	P-107
P-72 Future Exposure Point Intake Via Ingestion of Soil at Depth For Workers at Site 4	P-108
P-73 Current Exposure Point Intake Via Ingestion of Surface Soils For Workers at Site 4	P-109
P-74 Current Exposure Point Intake Via Volatilization of Surface Water For Workers at Site 4	P-110
P-75 Current Exposure Point Intake Via Ingestion of Surface Water During Recreation For Adults Near Site 4	P-111
P-76 Current Exposure Point Intake Via Dermal Contact with Surface Water During Recreation For Adults Near Site 4	P-112
P-77 Current Exposure Point Intake Via Ingestion of Surface Water During Recreation For Children Near Site 4	P-113
P-78 Current Exposure Point Intake Via Dermal Contact with Surface Water During Recreation For Children Near Site 4	P-114
P-79 Future Total Chronic Intake - Onsite Adult Residents or Workers at Site 4	P-115
P-80 Future Total Chronic Intake - Onsite Child Residents at Site 4	P-116
P-81 Total Chronic Intake For Workers at Site 4 - Current	P-117
P-82 Total Chronic Intake For Adults Near Site 4 - Current	P-118
P-83 Total Chronic Intake for Children Near Site 4 - Current	P-119

APPENDIX P (continued)
LIST OF TABLES

	Page
P-84 Chronic Hazard Index - Onsite Adult Residents or Workers on Site 4 - Future	P-120
P-85 Chronic Hazard Index - Onsite Child Residents at Site 4 - Future	P-121
P-86 Chronic Hazard Index for Workers at Site 4 - Current - Upper Bound	P-122
P-87 Chronic Hazard Index For Workers on Site 4 - Current - Best Estimate	P-123
P-88 Chronic Hazard Index For Adults Near Site 4 - Current	P-124
P-89 Chronic Hazard Index For Children Near Site 4 - Current	P-125
P-90 Risk From Potential Carcinogens - Onsite Adult Residents or Workers at Site 4 - Future	P-126
P-91 Risk From Potential Carcinogens - Onsite Child Residents at Site 4 - Future	P-127
P-92 Risk From Potential Carcinogens For Workers on Site 4 - Upper Bound	P-128
P-93 Risk From Potential Carcinogens For Workers on Site 4 - Best Estimate	P-129
P-94 Risk From Potential Carcinogens For Adults Near Site 4 - Current	P-130
P-95 Risk From Potential Carcinogens For Children Near Site 4 - Current	P-131
P-96 Maximum and Representative Chemical Concentrations at Site 8	P-137
P-97 Toxicity Data For Compounds Detected at Site 8	P-138
P-98 CT Values For Noncarcinogenic Compounds Detected at Site 8	P-139
P-99 CT Values For Potentially Carcinogenic Compounds Detected at Site 8	P-140
P-100 Indicator Scores and Tentative Ranking For Compounds Detected at Site 8	P-141
P-101 Future Exposure Point Intake Via Ingestion of Soil at Depth For Workers at Site 8	P-142
P-102 Future Exposure Point Intake Via Ingestion of Ground Water as Drinking Water For Adult Onsite Residents or Workers at Site 8	P-143
P-103 Future Exposure Point Intake Via Ingestion of Ground Water as Drinking Water For Child Residents at Site 8	P-144
P-104 Current Exposure Point Intake Via Ingestion of Surface Soils For Workers at Site 8	P-145

APPENDIX P (continued)
LIST OF TABLES

	Page
P-105 Current Exposure Point Intake Via Ingestion of Surface Water During Recreation For Adults Near Site 8	P-146
P-106 Current Exposure Point Intake Via Dermal Contact with Surface Water During Recreation For Adults Near Site 8	P-147
P-107 Current Exposure Point Intake Via Ingestion of Surface Water During Recreation For Children Near Site 8	P-148
P-108 Current Exposure Point Intake Via Dermal Contact with Surface Water During Recreation For Children Near Site 8	P-149
P-109 Future Total Chronic Intake - Onsite Adult Residents or Workers at Site 8	P-150
P-110 Future Total Chronic Intake - Onsite Child Residents at Site 8	P-151
P-111 Total Chronic Intake For Workers at Site 8 - Current	P-152
P-112 Total Chronic Intake For Adults Near Site 8 - Current	P-153
P-113 Total Chronic Intake for Children Near Site 8 - Current	P-154
P-114 Chronic Hazard Index - Onsite Adult Residents or Workers at Site 8 - Future	P-155
P-115 Chronic Hazard Index - Onsite Child Residents at Site 8 - Future	P-156
P-116 Chronic Hazard Index For Workers on Site 8 - Current	P-157
P-117 Chronic Hazard Index For Adults Near Site 8 - Current	P-158
P-118 Chronic Hazard Index For Children Near Site 8 - Current	P-159
P-119 Risk From Potential Carcinogens - Onsite Adult Residents or Workers at Site 8 - Future	P-160
P-120 Risk From Potential Carcinogens - Onsite Child Residents at Site 8 - Future	P-161
P-121 Risk From Potential Carcinogens For Workers on Site 8 - Current	P-162
P-122 Risk From Potential Carcinogens For Adults Near Site 8 - Current	P-163
P-123 Risk From Potential Carcinogens For Children Near Site 8 - Current	P-164

SECTION P.1
INTRODUCTION

This page intentionally left blank.

SECTION P.1 INTRODUCTION

Backup data used to perform the risk assessment in Section 6 is presented in this Appendix. Sections P.2, P.3, P.4 and P.5 contain the risk assessment worksheets for Sites 2, 3, 4 and 8, respectively.

Each section contains five subsections of Tables. These are:

- indicator chemical selection,
- estimation of chemical intake for each pathway,
- estimation of total chemical intake for each exposure route,
- characterization of risk from noncarcinogens, and
- characterization of risk from potential carcinogens.

The table headings are described and explained below.

P.1.1 Indicator Chemical Selection

The column headings for the indicator chemical selection are defined as follows:

Parameter:	The chemical of interest.
CAS Number:	Chemical identifier provided by the Chemical Abstracts Service.
Maximum Value:	The maximum concentration of a chemical that was detected by the referenced studies for a particular site.
Representative Value:	The average concentration of a chemical that was detected by the referenced studies for a particular site; determined by taking the arithmetic mean of the values from samples in which the compound was detected above the Method Detection Limit or the reporting limit.
# Detected/# Analyzed:	The number of samples in which the compound was detected, compared to the total number of samples which were subjected to analysis for the compound. These numbers include duplicates.
Toxicologic Class:	This class indicates whether a compound has been identified as a potential carcinogen (PC) or noncarcinogen (NC).

Severity Rating:	A pseudo-quantitative indication of the noncarcinogenic health effects associated with a given compound. Table 6.1 presents the severity rating categories and their associated health effects.
Carcinogen Assessment Group (CAG):	A classification which indicates the amount of evidence for carcinogenicity of a compound. Table 6.2 presents the rationale used to assign CAGs.
Toxicity Constant:	A potency factor provided by USEPA based on either carcinogenic or noncarcinogenic endpoints for soil, water and air. Toxicity constants for air were not included since no air sampling data was collected during the studies referenced for each site.
CT Value:	A value calculated by multiplying the toxicity constant by the maximum or representative concentration for a particular compound.
Indicator Score (IS):	The sum of the CT values of all media for a particular chemical. The IS is evaluated separately for maximum and representative concentrations, and only the higher CT value is used in the IS calculation for surface water and ground water.

P.1.2 Estimation of Chemical Intake for Each Pathway

The column headings for pathway specific chemical intake estimation are defined as follows:

Indicator Chemical:	A group of 10 to 15 compounds used to represent the overall potential risk to human health from a given site. These indicator chemicals are selected after evaluating the indicator score, toxicological class, chemical properties, availability of toxicological data and frequency of detection of each detected compound.
Fraction Absorbed:	The fraction of the indicator chemical's concentration which would be absorbed via a specific pathway, as suggested by previous research.
Human Intake Factor:	A factor which is multiplied by the exposure point concentration for an indicator chemical in order to

	obtain the chronic daily intake by a human receptor. This factor is determined by assuming values such as the length of time a potential receptor spends at the exposure point, the skin area of the receptor, the body weight of the receptor, the ingestion rate, or the inhalation rate.
Chronic Daily Intake:	The daily chemical intake of an indicator chemical by humans, in units of milligram of contaminant per kg body weight per day.
Upper Bound:	The chronic daily intake calculated from the maximum indicator chemical concentrations.
Best Estimate:	The chronic daily intake calculated from the representative chemical concentrations.
Emission Rate:	The rate which an indicator chemical is emitted from a source such as soil or water, in units of milligram of contaminant per unit time.
Exposure Point Concentration:	The concentration of the indicator chemical at the human exposure point, in units of milligram of contaminant per unit volume.
Permeability Constant:	The rate at which an indicator chemical penetrates the skin, in units of centimeter per hour. This value is not available for most compounds, and is based on previous research.
Exposed Skin Area:	The surface area of a human receptors's skin which is available for potential absorption of an indicator chemical, in centimeters squared.

P.1.3 Estimation of Total Chemical Intake for Each Exposure Route

The chronic daily intake values calculated previously are summed for each exposure route in these worksheets. The column headings for route specific chemical intake estimation are therefore self explanatory. Total chronic daily intake is formally defined as follows:

The summation of chronic daily intakes for a specific route and human population. Exposure routes can be through ingestion, dermal contact or inhalation of an indicator chemical, and potential populations are adult onsite workers, adult nearby residents and

child nearby residents. Total chronic daily intake is calculated for current exposure or future exposure.

P.1.4 Characterization of Risk from Noncarcinogens

Column headings used in worksheets which characterize risk from indicator chemicals which are classified as noncarcinogens are defined as follows:

AIC: Acceptable Chronic Intake, a compound specific value provided by the USEPA, in units of milligrams of contaminant per kilogram body weight per day. The AIC for a compound is ideally based on a chronic study where the test animal or human population was exposed to the compound over a major portion of the subject's lifespan.

CDI:AIC The chronic hazard index for a noncarcinogenic indicator chemical, calculated by dividing the chronic daily intake by the acceptable chronic intake for the indicator chemical. This value has no dimensions, and is calculated separately for oral and inhalation pathways of exposure for each potentially exposed population.

P.1.5 Characterization of Risk from Potential Carcinogens

Column headings used in worksheets which characterize risk from indicator chemicals which are classified as potential carcinogens are defined as follows:

Potency Factor: A compound specific value derived only for compounds which have been shown to cause an increased incidence of tumors in either human or animal studies, in units of inverse {milligrams of contaminant per kilogram body weight per day}. The potency factor is an upper 95 percent confidence limit on lifetime risk and is determined by low dose extrapolation modeling of animal or human data. Potency factors in this risk assessment were provided by USEPA.

Route-Specific
Risk:

The probability that a human receptor will contract cancer as a direct result of being exposed to an indicator chemical, calculated by multiplying the chronic daily intake by the compound specific potency factor.

This value has no dimensions, and is calculated separately for oral and inhalation pathways of exposure for each potentially exposed population.

This page intentionally left blank.

SECTION P.2
SITE 2 RISK ASSESSMENT TABLES

This page intentionally left blank.

SECTION P.2

SITE 2 RISK ASSESSMENT TABLES

This section contains the risk assessment worksheets for Site 2.

P.2.1 Site 2 Indicator Chemical Selection

Data used in the selection of indicator chemicals were compiled from both the Remedial Investigation performed at the Base by ES in 1988 and the 1986 study (Dames & Moore, 1987). These data are summarized in Table P-1, while Tables P-2 through P-5 step through the USEPA selection process.

P.2.2 Site 2 Estimation of Chemical Intake for Each Pathway

Tables P-6 through P-14 summarize the upper bound and best estimate chronic daily intakes from each potential pathway for each population at risk, as calculated from the maximum and average indicator chemical concentrations, respectively.

P.2.3 Site 2 Estimation of Total Chemical Intake for Each Exposure Route

Chronic daily intakes for pathways categorized as oral or inhalation routes are summed to yield total chronic daily intake via a particular route for a target population. Tables P-15 through P-19 present the total chemical intake for each exposure route.

P.2.4 Site 2 Characterization of Risk From Noncarcinogens

Tables P-20 through P-27 present the chronic hazard index values for each target population.

P.2.5 Site 2 Characterization of Risk From Potential Carcinogens

Tables P-28 through P-35 present the risk from potential carcinogens for each target population.

TABLE P-1

MAXIMUM AND REPRESENTATIVE CHEMICAL CONCENTRATIONS AT SITE 2

Parameter	CAS (a) Number	Ground Water (mg/L)			Surface Water (mg/L)			Soils (mg/kg)			Soils Below 2 Feet (mg/kg)		
		Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed
Arsenic	7440-38-2	ND (b)	ND	0/0	ND	1.30E+00	3/3	3.70E+00	2.70E+00	2/2	2.70E+00	1.66E+00	7/7
Barium	7440-39-3	ND	ND	0/18	ND	5.39E+01	3/3	2.95E+02	8.72E+01	11/11	2.62E+02	5.69E+01	29/29
Benzene	71-43-2	1.20E-03	6.00E-04	1/23	ND	ND	0/6	2.50E+00	1.24E+00	3/12	3.10E+00	1.34E+00	8/37
Cadmium	7140-43-9	ND	ND	0/18	ND	ND	0/3	1.33E+01	9.02E+00	11/11	1.22E+01	7.58E+00	29/29
Chlorobenzene	108-90-7	ND	ND	0/18	ND	ND	0/3	8.00E+02	4.50E+02	1/11	ND	ND	0/28
Chromium	7440-47-3	ND	ND	0/18	ND	2.19E+01	3/3	3.79E+01	3.16E+01	9/9	3.46E+01	2.54E+01	22/22
Diethyl Phthalate	84-74-2	ND	ND	0/14	ND	ND	0/2	ND	ND	0/11	2.00E+00	1.65E+00	3/25
1,2 Dichlorobenzene	95-50-1	ND	ND	0/14	ND	ND	0/2	ND	ND	0/11	2.00E+00	1.65E+00	3/25
1,2 Dichloroethane	107-06-2	2.20E-04	1.10E-04	1/23	ND	ND	0/3	1.80E+03	9.00E+04	1/11	ND	ND	0/28
1,1 Dichloroethylethene	75-35-4	6.10E-04	3.05E-04	1/23	ND	ND	0/6	ND	ND	0/11	ND	ND	0/37
Trans-1,2 Dichloroethylethene	540-59-0	1.20E+00	2.31E-01	7/23	2.60E-03	1.30E-03	0/6	9.00E+02	4.50E+02	1/11	8.00E+04	4.00E+04	1/23
Diethyl Phthalate	84-66-2	1.44E-01	1.21E-02	2/14	ND	ND	0/1	ND	ND	0/8	ND	ND	0/25
Ethyl Benzene	100-41-4	ND	ND	0/18	ND	ND	0/3	5.20E+00	3.33E+00	3/12	2.50E+01	8.81E+00	8/37
Lead	7439-92-1	ND	ND	0/16	ND	5.26E+00	3/3	5.40E+01	1.32E+01	11/11	1.02E+02	8.01E+00	29/29
Mercury	7439-97-6	ND	ND	0/18	ND	ND	0/3	2.00E+01	1.00E+01	1/2	1.00E+01	5.00E+02	1/7
Pyrene	129-00-0	ND	ND	0/14	ND	ND	0/2	3.70E+00	1.85E+00	1/8	6.20E+01	3.10E+01	1/25
1,1,1,2,2 Tetrachloroethane	79-34-5	ND	ND	0/18	ND	ND	0/3	ND	ND	0/10	1.70E+02	8.50E+03	1/28
Tetrachloroethylethene	127-18-4	4.30E-04	2.15E-04	1/23	ND	ND	0/3	2.30E+00	1.15E+00	2/11	1.50E+01	2.54E+02	6/36
Toluene	108-88-3	ND	ND	0/18	ND	2.50E+02	1/6	3.60E+01	3.23E+00	12/12	1.50E+01	9.89E+01	28/37
1,1,1 Trichloroethane	71-55-6	ND	ND	0/18	ND	2.40E+01	6/9	ND	ND	0/11	ND	ND	0/37
Trichloroethylethene	79-01-6	3.30E-02	1.71E-02	4/23	ND	2.60E-04	1/6	1.60E+00	8.01E+01	2/11	7.10E+02	2.94E+02	6/36
Vinyl Chloride	75-01-4	3.10E-03	1.55E-03	1/23	ND	ND	0/3	ND	ND	0/11	ND	ND	0/28
Xylenes	1330-20-7	ND	ND	0/23	ND	ND	0/3	1.80E+02	6.86E+01	3/12	7.10E+01	2.13E+01	7/37

a. CAS = Chemical Abstract Service

b. ND = Not Detected

Source: Engineering-Science, Inc. (1988) and Dames & Moore (1987)

TABLE P-2

TOXICITY DATA FOR COMPOUNDS DETECTED AT SITE 2

Parameter	CAS (a) Number	Toxicologic Class	Severity Rating (RfC) (b)		Carcinogen Assessment Group (CA6) (c)	Toxicity Constants (d)			
						Noncarcinogens		Potential Carcinogens	
			Oral Route	Inhalation Route		Water ($\mu\text{g/l}$) (e)	Soil ($\mu\text{g/kg}$) (f)	Water ($\mu\text{g/l}$) (g)	Soil ($\mu\text{g/kg}$) (h)
Arsenic	7440-38-2	NC, PC (g)	9	9	A	1.80E+01	9.00E-04	4.07E+00	2.03E-04
Barium	7440-39-3	NC	10	10	D	4.08E+00	2.04E-04	- (h)	-
Benzene	71-43-2	NC, PC	5	10	A	1.17E-01	5.85E-06	7.71E-03	3.86E-07
Cadmium	7740-43-9	NC, PC	-	8	-	NA (i)	NA	NA	NA
Chlorobenzene	108-90-7	NC	4	1	D	1.43E-01	7.14E-06	-	-
Chromium	7440-47-3	NC, PC	-	8	-	NA	NA	NA	NA
Dibutyl Phthalate	84-74-2	NC	8	8	D	3.81E-02	1.90E-06	-	-
1,2 Dichlorobenzene	95-50-1	NC	4	5	D	5.19E-02	2.60E-06	-	-
1,2 Dichloroethane	107-06-2	NC, PC	10	8	B2	1.76E-02	8.80E-07	5.86E-02	2.93E-06
1,1 Dichloroethylene	75-35-4	NC, PC	7	5	C	3.71E-01	1.86E-05	1.23E-01	6.14E-06
Trans-1,2 Dichloroethylene	540-59-0	NC	5	5	D	5.29E-02	2.65E-06	-	-
Diethyl Phthalate	84-66-2	NC	4	4	D	2.67E-04	1.34E-08	-	-
Ethyl Benzene	100-41-4	NC	4	4	D	1.10E-02	5.52E-07	-	-
Lead	7439-92-1	NC, PC	10	10	B2	8.93E-01	4.46E-05	NA	NA
Mercury	7439-97-6	NC	7	8	D	1.84E+01	9.21E-04	-	-
Pyrene	129-00-0	NC, PC	-	-	-	NA	NA	NA	NA
1,1,2,2 Tetrachloroethane	79-34-5	NC, PC	5	5	C	4.55E-01	2.27E-05	4.74E-02	2.37E-06
Tetrachloroethylene	127-18-4	NC, PC	7	10	B2	9.62E-03	4.81E-07	8.86E-03	4.43E-07
Toluene	108-88-3	NC	7	10	D	5.26E-03	2.60E-07	NA	NA
1,1,1 Trichloroethane	71-55-6	NC	2	2	D	7.33E-04	3.67E-08	-	-

TABLE P-2 (CONTINUED)

TOXICITY DATA FOR COMPOUNDS DETECTED AT SITE 2

Parameter	CAS (a) Number	Toxicologic Class	Severity Rating (RfD) (b)		Carcinogen Assessment Group (CMG) (c)		Toxicity Constants (d)			
							Noncarcinogens		Potential Carcinogens	
			Oral Route	Inhalation Route	Oral Route	Inhalation Route	Water (L/mg)	Soil (sf) (f) (kg/mg)	Water (L/mg)	Soil (sf) (kg/mg)
Trichloroethylene	79-01-6	NC, PC	5	4	B2	B2	1.05E+00	5.26E-05	4.29E-03	2.14E-07
Vinyl Chloride	75-01-4	NC, PC	10	10	A	A	8.77E-02	4.39E-06	4.29E-03	2.14E-07
Xylenes	1330-20-7	NC	8	8	D	D	1.07E-01	5.33E-06	-	-

a. CAS = Chemical Abstracts Service

b. Rating Value = RfD = USEPA health effect rating value for noncarcinogens

c. Carcinogen Assessment Group = CMG = USEPA classification of carcinogenicity

d. Toxicity Constant = USEPA potency factor based on either carcinogenic or noncarcinogenic endpoints for a given medium

e. WT = Water toxicity constant

f. SF = Soil toxicity constant

g. NC = Noncarcinogenic effects PC = Potential Carcinogen

h. Not applicable to parameter

i. NA = No data available

Source: U.S. Environmental Protection Agency (1986a)

TABLE P-3

CT VALUES FOR NONCARCINOGENIC COMPOUNDS DETECTED AT SITE 2

Parameter	CAS (a) Number	Ground Water CT Value (b)		Surface Water CT Value		Sediment CT Value		CT Values for Soils			
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	0 to 2 feet		Below 2 feet	
								Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value
Arsenic	7440-38-2	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.17E-06	9.18E-07	3.33E-06	2.43E-06	2.43E-06	1.49E-06
Barium	7440-39-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.10E-05	1.03E-05	6.02E-05	1.78E-05	5.34E-05	1.16E-05
Benzene	71-43-2	1.40E-04	7.02E-05	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.46E-05	7.24E-06	1.81E-05	7.83E-06
Cadmium	7740-43-9	- (c)	-	-	-	-	-	-	-	-	-
Chlorobenzene	108-90-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	5.71E-07	3.21E-07	0.00E+00	0.00E+00
Chromium	7440-47-3	-	-	-	-	-	-	-	-	-	-
Diethyl Phthalate	84-74-2	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	3.80E-06	3.13E-06
1,2 Dichlorobenzene	95-50-1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	5.20E-06	4.28E-06
1,2 Dichloroethane	107-66-2	3.87E-06	1.94E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.58E-09	7.92E-10	0.00E+00	0.00E+00
1,1 Dichloroethylene	75-35-4	2.26E-04	1.13E-04	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	540-59-0	6.35E-02	1.22E-02	1.28E-04	6.88E-05	0.00E+00	0.00E+00	2.38E-07	1.19E-07	2.12E-09	1.06E-09
Diethyl Phthalate	84-66-2	3.84E-05	3.24E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	100-41-4	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	2.87E-06	1.84E-06	1.38E-05	4.87E-06
Lead	7439-92-1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	2.99E-07	4.55E-08	2.41E-06	5.89E-07	4.46E-06	3.57E-07
Mercury	7439-97-6	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.84E-07	9.21E-08	9.21E-08	4.61E-08
Pyrene	129-00-0	-	-	-	-	-	-	-	-	-	-
1,1,1,2,2 Tetrachloroethane	79-34-5	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	3.86E-07	1.93E-07
Tetrachloroethylene	127-18-4	4.14E-06	2.07E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.11E-06	5.54E-07	7.72E-08	1.72E-08
Toluene	108-88-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	6.50E-09	3.25E-09	9.36E-06	8.39E-07	3.90E-06	2.57E-07
1,1,1 Trichloroethane	71-55-6	0.00E+00	0.00E+00	0.00E+00	0.00E+00	8.81E-09	1.68E-09	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trichloroethylene	79-01-6	3.47E-02	1.82E-02	0.00E+00	0.00E+00	1.37E-08	6.84E-09	4.94E-05	8.42E-05	0.00E+00	1.54E-06
Vinyl Chloride	75-01-4	2.72E-04	1.36E-04	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	1330-20-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	9.59E-04	3.66E-04	3.78E-04	1.13E-04

a. CAS = Chemical Abstracts Service
b. CT Value = Concentration x Toxicity. CT values equaling zero are the result of nondetected compounds.
c. No toxicity data available.

TABLE P-4

CT VALUES FOR POTENTIALLY CARCINOGENIC COMPOUNDS DETECTED AT SITE 2

Parameter	CAS (a) Number	Ground Water CT Value (b)	Surface Water CT Value			Sediment CT Value			CT Values for Soils				
			Maximum Value	Represent- ative Value	n ^a Value	Maximum Value	Represent- ative Value	0 to 2 Feet		Below 2 Feet			
								Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value		
Arsenic	7440-38-2	0.00E+00	0.00E+00	0.00E+00	0.00E+00	2.64E-07	2.07E-07	7.51E-07	5.48E-07	5.48E-07	5.48E-07	3.36E-07	3.36E-07
Barium	7440-39-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Benzene	71-43-2	9.25E-06	4.63E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	9.65E-07	4.78E-07	1.20E-06	5.16E-07	5.16E-07	5.16E-07
Cadmium	7740-43-9	- (c)	-	-	-	-	-	-	-	-	-	-	-
Chlorobenzene	106-90-7	-	-	-	-	-	-	-	-	-	-	-	-
Chromium	7440-47-3	-	-	-	-	-	-	-	-	-	-	-	-
Dibutyl Phthalate	84-74-2	-	-	-	-	-	-	-	-	-	-	-	-
1,2-Dichlorobenzene	95-50-1	-	-	-	-	-	-	-	-	-	-	-	-
1,2-Dichloroethane	107-06-2	1.29E-05	6.45E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	5.27E-09	2.64E-09	0.00E+00	0.00E+00	0.00E+00	0.00E+00
1,1-Dichloroethylene	75-35-4	7.50E-05	3.75E-05	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trans-1,2-Dichloroethylene	540-59-0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Dibutyl Phthalate	84-65-2	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	100-41-4	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Lead	7439-92-1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Miscar7	7439-97-6	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Pyrene	129-00-0	-	-	-	-	-	-	-	-	-	-	-	-
1,1,1,2,2-Tetrachloroethane	79-34-5	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	4.03E-03	2.01E-03	2.01E-03	2.01E-03
Tetrachloroethylene	127-18-4	3.31E-06	1.90E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.02E-06	5.11E-07	6.64E-08	1.12E-08	1.12E-08	1.12E-08
Toluene	108-88-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
1,1,1-Trichloroethane	71-55-6	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trichloroethylene	79-01-6	1.42E-04	7.43E-05	0.00E+00	0.00E+00	5.56E-11	2.78E-11	2.01E-07	3.42E-07	0.00E+00	6.28E-09	6.28E-09	6.28E-09
Vinyl Chloride	75-01-4	1.33E-05	6.65E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	1330-20-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00

a. CAS = Chemical Abstracts Service

b. CT Value = Concentration x Toxicity. CT values equaling zero are the result of nondetected compounds.

c. No toxicity data available.

TABLE P-5

INDICATOR SCORES AND TENTATIVE RANKING FOR COMPOUNDS DETECTED AT SITE 2

Parameter	CAS (a) Number	Indicator Score for Noncarcinogenic Effects		Tentative Rank for Noncarcinogenic Effects		Indicator Score for Potential Carcinogens		Tentative Rank for Potential Carcinogens	
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value
Arsenic	7440-38-2	6.93E-03	4.84E-03	5	4	1.56E-03	1.09E-03	1	1
Barium	7440-39-3	1.25E-01	3.97E-02	1	1	0.00E+00	0.00E+00		
Benzene	71-43-2	1.73E-04	8.53E-05	10	10	1.14E-05	5.62E-06	6	6
Cadmium	7740-43-9	0.00E+00	0.00E+00			0.00E+00	0.00E+00		
Chlorobenzene	108-90-7	5.71E-07	3.21E-07	18	18	0.00E+00	0.00E+00		
Chromium	7440-47-3	0.00E+00	0.00E+00			0.00E+00	0.00E+00		
Dibutyl Phthalate	84-74-2	3.80E-06	3.13E-06	17	14	0.00E+00	0.00E+00		
1,2 Dichlorobenzene	95-50-1	5.20E-06	4.28E-06	15	12	0.00E+00	0.00E+00		
1,2 Dichloroethane	107-06-2	3.87E-06	1.94E-06	16	16	1.29E-05	6.45E-06	5	5
1,1 Dichloroethylene	75-35-4	2.26E-04	1.13E-04	9	9	7.50E-05	3.75E-05	3	3
Trans-1,2 Dichloroethylene	540-59-0	6.35E-02	1.22E-02	2	3	0.00E+00	0.00E+00		
Diethyl Phthalate	84-66-2	3.84E-05	3.24E-05	11	13	0.00E+00	0.00E+00		
Ethyl Benzene	100-41-4	1.67E-05	6.70E-06	12	11	0.00E+00	0.00E+00		
Lead	7439-92-1	7.19E-03	1.24E-03	4	5	0.00E+00	0.00E+00		
Mercury	7439-97-6	2.76E-04	1.38E-04	7	7	0.00E+00	0.00E+00		
Pyrene	129-00-0	0.00E+00	0.00E+00			0.00E+00	0.00E+00		
1,1,2,2 Tetrachloroethane	79-34-5	3.86E-07	1.93E-07	19	19	4.03E-08	2.01E-08	8	8
Tetrachloroethylene	127-18-4	5.32E-06	2.63E-06	14	15	4.90E-06	2.43E-06	7	7
Toluene	108-88-3	1.33E-05	1.10E-06	13	17	0.00E+00	0.00E+00		
1,1,1 Trichloroethane	71-55-6	8.81E-09	1.68E-09	20	20	0.00E+00	0.00E+00		
Trichloroethylene	79-01-6	3.47E-02	1.83E-02	3	2	1.42E-04	7.47E-05	2	2
Vinyl Chloride	75-01-4	2.72E-04	1.36E-04	8	8	1.33E-05	6.55E-06	4	4
Xylenes	1330-20-7	1.34E-03	4.79E-04	6	6	0.00E+00	0.00E+00		

a. CAS = Chemical Abstracts Service

TABLE P-6

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF SOIL AT DEPTH
FOR WORKERS AT SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	2.70E+00	1.66E+00	1.00E+00	1.68E-09	4.53E-09	2.78E-09
Barium	2.62E+02	5.69E+01	5.00E-01	8.39E-10	2.20E-07	4.77E-08
Benzene	3.10E+00	1.34E+00	1.00E+00	1.68E-09	5.20E-09	2.24E-09
Dibutyl Phthalate	2.00E+00	1.65E+00	1.00E+00	1.68E-09	3.35E-09	2.76E-09
1,1 Dichloroethylene	ND (b)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	8.00E-04	4.00E-04	1.00E+00	1.68E-09	1.34E-12	6.71E-13
Diethyl Phthalate	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Ethyl Benzene	2.50E+01	8.81E+00	1.00E+00	1.68E-09	4.19E-08	1.48E-08
Lead	1.02E+02	8.01E+00	1.50E-01	2.52E-10	2.57E-08	2.02E-09
Mercury	1.00E-01	5.00E-02	7.00E-02	1.17E-10	1.17E-11	5.87E-12
Tetrachloroethylene	1.50E-01	2.54E-02	1.00E+00	1.68E-09	2.52E-10	4.26E-11
Toluene	1.50E+01	9.89E-01	1.00E+00	1.68E-09	2.52E-08	1.66E-09
Trichloroethylene	7.10E-02	2.94E-02	1.00E+00	1.68E-09	1.19E-10	4.92E-11
Vinyl Chloride	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Xylenes	7.10E+01	2.13E+01	1.00E+00	1.68E-09	1.19E-07	3.57E-08

a. ND = Not Detected

TABLE P-7

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF GROUND WATER AS DRINKING WATER
FOR ONSITE ADULT RESIDENTS OR WORKERS AT SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	ND (a)	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Barium	ND	ND	5.00E-01	1.43E-02	0.00E+00	0.00E+00
Benzene	1.20E-03	6.00E-04	1.00E+00	2.86E-02	3.43E-05	1.71E-05
Dibutyl Phthalate	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
1,1 Dichloroethylene	6.10E-04	3.05E-04	1.00E+00	2.86E-02	1.74E-05	8.71E-06
Trans-1,2 Dichloroethylene	1.20E+00	2.31E-01	1.00E+00	2.86E-02	3.43E-02	6.60E-03
Diethyl Phthalate	1.44E-01	1.21E-02	1.00E+00	2.86E-02	4.11E-03	3.47E-04
Ethyl Benzene	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Lead	ND	ND	1.50E-01	4.29E-03	0.00E+00	0.00E+00
Mercury	ND	ND	7.00E-02	2.00E-03	0.00E+00	0.00E+00
Tetrachloroethylene	4.30E-04	2.15E-04	1.00E+00	2.86E-02	1.23E-05	6.14E-06
Toluene	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Trichloroethylene	3.30E-02	1.73E-02	1.00E+00	2.86E-02	9.43E-04	4.95E-04
Vinyl Chloride	3.10E-03	1.55E-03	1.00E+00	2.86E-02	8.86E-05	4.43E-05
Xylenes	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-8

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF GROUND WATER AS DRINKING WATER
FOR ONSITE CHILD RESIDENTS AT SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	ND (a)	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Barium	ND	ND	5.00E-01	1.07E-02	0.00E+00	0.00E+00
Benzene	1.20E-03	6.00E-04	1.00E+00	2.14E-02	2.57E-05	1.29E-05
Dibutyl Phthalate	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
1,1 Dichloroethylene	6.10E-04	3.05E-04	1.00E+00	2.14E-02	1.31E-05	6.54E-06
Trans-1,2 Dichloroethylene	1.20E+00	2.31E-01	1.00E+00	2.14E-02	2.57E-02	4.95E-03
Diethyl Phthalate	1.44E-01	1.21E-02	1.00E+00	2.14E-02	3.09E-03	2.60E-04
Ethyl Benzene	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Lead	ND	ND	4.00E-01	8.57E-03	0.00E+00	0.00E+00
Mercury	ND	ND	7.00E-02	1.50E-03	0.00E+00	0.00E+00
Tetrachloroethylene	4.30E-04	2.15E-04	1.00E+00	2.14E-02	9.21E-06	4.61E-06
Toluene	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Trichloroethylene	3.30E-02	1.73E-02	1.00E+00	2.14E-02	7.07E-04	3.71E-04
Vinyl Chloride	3.10E-03	1.55E-03	1.00E+00	2.14E-02	6.64E-05	3.32E-05
Xylenes	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-9

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE SOILS
FOR WORKERS AT SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	3.70E+00	2.70E+00	1.00E+00	1.68E-09	6.21E-09	4.53E-09
Barium	2.95E+02	8.72E+01	5.00E-01	8.39E-10	2.47E-07	7.31E-08
Benzene	2.50E+00	1.24E+00	1.00E+00	1.68E-09	4.19E-09	2.08E-09
Dibutyl Phthalate	ND (a)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
1,1 Dichloroethylene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	9.00E-02	4.50E-02	1.00E+00	1.68E-09	1.51E-10	7.55E-11
Diethyl Phthalate	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Ethyl Benzene	5.20E+00	3.33E+00	1.00E+00	1.68E-09	8.72E-09	5.58E-09
Lead	5.40E+01	1.32E+01	1.50E-01	2.52E-10	1.36E-08	3.32E-09
Mercury	2.00E-01	1.00E-01	7.00E-02	1.17E-10	2.35E-11	1.17E-11
Tetrachloroethylene	2.30E+00	1.15E+00	1.00E+00	1.68E-09	3.86E-09	1.93E-09
Toluene	3.60E+01	3.23E+00	1.00E+00	1.68E-09	6.04E-08	5.41E-09
Trichloroethylene	1.60E+00	8.01E-01	1.00E+00	1.68E-09	2.68E-09	1.34E-09
Vinyl Chloride	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Xylenes	1.80E+02	6.86E+01	1.00E+00	1.68E-09	3.02E-07	1.15E-07

a. ND = Not Detected

TABLE P-10

CURRENT EXPOSURE POINT INTAKE VIA FUGITIVE DUST GENERATION (FDG)
FOR WORKERS AT SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Emission Rate Due to Wind Erosion (mg/hr)			Exposure Point Concentration (mg/m ³)		Human Intake Factor (m ³ /day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative	Upper Bound	Best Estimate		Upper Bound	Best Estimate		Upper Bound	Best Estimate
Arsenic	3.70E+00	2.70E+00	5.16E-04	3.77E-04		9.02E-11	6.58E-11	1.94E-03	1.75E-13	1.28E-13
Barium	2.95E+02	8.72E+01	4.12E-02	1.22E-02		7.19E-09	2.12E-09	1.94E-03	1.40E-11	4.13E-12
Benzene	2.50E+00	1.24E+00	3.49E-04	1.73E-04		6.09E-11	3.02E-11	1.94E-03	1.18E-13	5.86E-14
Dibutyl Phthalate	ND (a)	ND	0.00E+00	0.00E+00		0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
1,1 Dichloroethylene	ND	ND	0.00E+00	0.00E+00		0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	9.00E-02	4.50E-02	1.26E-05	6.28E-06		2.19E-12	1.10E-12	1.94E-03	4.26E-15	2.13E-15
Diethyl Phthalate	ND	ND	0.00E+00	0.00E+00		0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Ethyl Benzene	5.20E+00	3.33E+00	7.25E-04	4.64E-04		1.27E-10	8.11E-11	1.94E-03	2.46E-13	1.58E-13
Lead	5.40E+01	1.32E+01	7.53E-03	1.84E-03		1.32E-09	3.22E-10	1.94E-03	2.56E-12	6.25E-13
Mercury	2.00E-01	1.00E-01	2.79E-05	1.40E-05		4.87E-12	2.44E-12	1.94E-03	9.47E-15	4.74E-15
Tetrachloroethylene	2.30E+00	1.15E+00	3.21E-04	1.61E-04		5.65E-11	2.81E-11	1.94E-03	1.09E-13	5.46E-14
Toluene	3.60E+01	3.23E+00	5.02E-03	4.50E-04		8.77E-10	7.86E-11	1.94E-03	1.71E-12	1.53E-13
Trichloroethylene	1.60E+00	8.01E-01	2.23E-04	1.12E-04		3.90E-11	1.95E-11	1.94E-03	7.58E-14	3.79E-14
Vinyl Chloride	ND	ND	0.00E+00	0.00E+00		0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Xylenes	1.80E+02	6.86E+01	2.51E-02	9.58E-03		4.39E-09	1.67E-09	1.94E-03	8.53E-12	3.25E-12

a. ND = Not Detected

TABLE P-11

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE SOILS
FOR NEARBY ADULTS VISITING SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	3.70E+00	2.70E+00	1.00E+00	1.68E-09	6.21E-09	4.53E-09
Barium	2.95E+02	8.72E+01	5.00E-01	8.39E-10	2.47E-07	7.31E-08
Benzene	2.50E+00	1.24E+00	1.00E+00	1.68E-09	4.19E-09	2.08E-09
Dibutyl Phthalate	ND (a)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
1,1 Dichloroethylene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	9.00E-02	4.50E-02	1.00E+00	1.68E-09	1.51E-10	7.55E-11
Diethyl Phthalate	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Ethyl Benzene	5.20E+00	3.33E+00	1.00E+00	1.68E-09	8.72E-09	5.58E-09
Lead	5.40E+01	1.32E+01	1.50E-01	2.52E-10	1.36E-08	3.32E-09
Mercury	2.00E-01	1.00E-01	7.00E-02	1.17E-10	2.35E-11	1.17E-11
Tetrachloroethylene	2.30E+00	1.15E+00	1.00E+00	1.68E-09	3.86E-09	1.93E-09
Toluene	3.60E+01	3.23E+00	1.00E+00	1.68E-09	6.04E-08	5.41E-09
Trichloroethylene	1.60E+00	8.01E-01	1.00E+00	1.68E-09	2.68E-09	1.34E-09
Vinyl Chloride	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Xylenes	1.80E+02	6.86E+01	1.00E+00	1.68E-09	3.02E-07	1.15E-07

a. ND = Not Detected

TABLE P-12
CURRENT EXPOSURE POINT INTAKE VIA FUGITIVE DUST GENERATION (FDG)
FOR NEARBY ADULTS VISITING SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Emission Rate Due to Wind Erosion (mg/hr)			Exposure Point Concentration (mg/m ³)		Human Intake Factor (m ³ /day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative	Upper Bound	Best Estimate		Upper Bound	Best Estimate		Upper Bound	Best Estimate
Arsenic	3.70E+00	2.70E+00	5.16E-04	3.77E-04		1.88E-11	1.37E-11	1.94E-03	3.65E-14	2.66E-14
Barium	2.95E+02	8.72E+01	4.12E-02	1.22E-02		1.50E-09	4.43E-10	1.94E-03	2.91E-12	8.60E-13
Benzene	2.50E+00	1.24E+00	3.49E-04	1.73E-04		1.27E-11	6.29E-12	1.94E-03	2.47E-14	1.22E-14
Dibutyl Phthalate	ND (a)	ND	0.00E+00	0.00E+00		0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
1,1 Dichloroethylene	ND	ND	0.00E+00	0.00E+00		0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	9.00E-02	4.50E-02	1.26E-05	6.28E-06		4.57E-13	2.28E-13	1.94E-03	8.88E-16	4.44E-16
Diethyl Phthalate	ND	ND	0.00E+00	0.00E+00		0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Ethyl Benzene	5.20E+00	3.33E+00	7.25E-04	4.64E-04		2.64E-11	1.69E-11	1.94E-03	5.13E-14	3.28E-14
Lead	5.40E+01	1.32E+01	7.53E-03	1.84E-03		2.74E-10	6.70E-11	1.94E-03	5.33E-13	1.30E-13
Mercury	2.00E-01	1.00E-01	2.79E-05	1.40E-05		1.02E-12	5.08E-13	1.94E-03	1.97E-15	9.87E-16
Tetrachloroethylene	2.30E+00	1.15E+00	3.21E-04	1.61E-04		1.17E-11	5.85E-12	1.94E-03	2.27E-14	1.14E-14
Toluene	3.60E+01	3.23E+00	5.02E-03	4.50E-04		1.83E-10	1.64E-11	1.94E-03	3.55E-13	3.18E-14
Trichloroethylene	1.60E+00	8.01E-01	2.23E-04	1.12E-04		8.12E-12	4.07E-12	1.94E-03	1.58E-14	7.90E-15
Vinyl Chloride	ND	ND	0.00E+00	0.00E+00		0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Xylenes	1.80E+02	6.86E+01	2.51E-02	9.58E-03		9.14E-10	3.48E-10	1.94E-03	1.78E-12	6.77E-13

a. ND = Not Detected

TABLE P-13

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE SOILS
FOR NEARBY CHILDREN VISITING SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	3.70E+00	2.70E+00	1.00E+00	1.76E-09	6.52E-09	4.76E-09
Barium	2.95E+02	8.72E+01	5.00E-01	8.81E-10	2.60E-07	7.68E-08
Benzene	2.50E+00	1.24E+00	1.00E+00	1.76E-09	4.40E-09	2.18E-09
Dibutyl Phthalate	ND (a)	ND	1.00E+00	1.76E-09	0.00E+00	0.00E+00
1,1 Dichloroethylene	ND	ND	1.00E+00	1.76E-09	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	9.00E-02	4.50E-02	1.00E+00	1.76E-09	1.59E-10	7.93E-11
Diethyl Phthalate	ND	ND	1.00E+00	1.76E-09	0.00E+00	0.00E+00
Ethyl Benzene	5.20E+00	3.33E+00	1.00E+00	1.76E-09	9.16E-09	5.86E-09
Lead	5.40E+01	1.32E+01	4.00E-01	7.05E-10	3.80E-08	9.30E-09
Mercury	2.00E-01	1.00E-01	7.00E-02	1.23E-10	2.47E-11	1.23E-11
Tetrachloroethylene	2.30E+00	1.15E+00	1.00E+00	1.76E-09	4.05E-09	2.03E-09
Toluene	3.60E+01	3.23E+00	1.00E+00	1.76E-09	6.34E-08	5.68E-09
Trichloroethylene	1.60E+00	8.01E-01	1.00E+00	1.76E-09	2.82E-09	1.41E-09
Vinyl Chloride	ND	ND	1.00E+00	1.76E-09	0.00E+00	0.00E+00
Xylenes	1.80E+02	6.86E+01	1.00E+00	1.76E-09	3.17E-07	1.21E-07

a. ND = Not Detected

TABLE P-14

CURRENT EXPOSURE POINT INTAKE VIA FUGITIVE DUST GENERATION (FDG)
FOR NEARBY CHILDREN VISITING SITE 2

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Emission Rate Due to Wind Erosion (mg/hr)		Exposure Point Concentration (mg/m ³)		Human Intake Factor (m ³ /day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative	Upper Bound	Best Estimate	Upper Bound	Best Estimate		Upper Bound	Best Estimate
Arsenic	3.70E+00	2.70E+00	5.16E-04	3.77E-04	1.88E-11	1.37E-11	1.28E-03	2.40E-14	1.75E-14
Barium	2.95E+02	8.72E+01	4.12E-02	1.22E-02	1.50E-09	4.43E-10	1.28E-03	1.91E-12	5.65E-13
Benzene	2.50E+00	1.24E+00	3.49E-04	1.73E-04	1.27E-11	6.29E-12	1.28E-03	1.62E-14	8.02E-15
Dibutyl Phthalate	ND (a)	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.28E-03	0.00E+00	0.00E+00
1,1 Dichloroethylene	ND	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.28E-03	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	9.00E-02	4.50E-02	1.26E-05	6.28E-06	4.57E-13	2.28E-13	1.28E-03	5.83E-16	2.91E-16
Diethyl Phthalate	ND	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.28E-03	0.00E+00	0.00E+00
Ethyl Benzene	5.20E+00	3.33E+00	7.25E-04	4.64E-04	2.64E-11	1.69E-11	1.28E-03	3.37E-14	2.15E-14
Lead	5.40E+01	1.32E+01	7.53E-03	1.84E-03	2.74E-10	6.70E-11	1.28E-03	3.50E-13	8.55E-14
Mercury	2.00E-01	1.00E-01	2.79E-05	1.40E-05	1.02E-12	5.08E-13	1.28E-03	1.30E-15	6.48E-16
Tetrachloroethylene	2.30E+00	1.15E+00	3.21E-04	1.61E-04	1.17E-11	5.85E-12	1.28E-03	1.49E-14	7.46E-15
Toluene	3.60E+01	3.23E+00	5.02E-03	4.50E-04	1.83E-10	1.64E-11	1.28E-03	2.33E-13	2.09E-14
Trichloroethylene	1.60E+00	8.01E-01	2.23E-04	1.12E-04	8.12E-12	4.07E-12	1.28E-03	1.04E-14	5.19E-15
Vinyl Chloride	ND	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.28E-03	0.00E+00	0.00E+00
Xylenes	1.80E+02	6.86E+01	2.51E-02	9.58E-03	9.14E-10	3.48E-10	1.28E-03	1.17E-12	4.44E-13

a. ND = Not Detected

TABLE P-15

FUTURE TOTAL CHRONIC INTAKE
ONSITE ADULT RESIDENTS OR WORKERS AT SITE 2

Indicator Chemical	Ingestion of Soil at Depth (mg/kg/day)		Ingestion of Ground Water (mg/kg/day)		Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Arsenic	4.53E-09	2.78E-09	0.00E+00	0.00E+00	4.53E-09	2.78E-09
Barium	2.20E-07	4.77E-08	0.00E+00	0.00E+00	2.20E-07	4.77E-08
Benzene	5.20E-09	2.24E-09	3.43E-05	1.71E-05	3.43E-05	1.71E-05
Dibutyl Phthalate	3.35E-09	2.76E-09	0.00E+00	0.00E+00	3.35E-09	2.76E-09
1,1 Dichloroethylene	0.00E+00	0.00E+00	1.74E-05	8.71E-06	1.74E-05	8.71E-06
Trans-1,2 Dichloroethylene	1.34E-12	6.71E-13	3.43E-02	6.60E-03	3.43E-02	6.60E-03
Diethyl Phthalate	0.00E+00	0.00E+00	4.11E-03	3.47E-04	4.11E-03	3.47E-04
Ethyl Benzene	4.19E-08	1.48E-08	0.00E+00	0.00E+00	4.19E-08	1.48E-08
Lead	2.57E-08	2.02E-09	0.00E+00	0.00E+00	2.57E-08	2.02E-09
Mercury	1.17E-11	5.87E-12	0.00E+00	0.00E+00	1.17E-11	5.87E-12
Tetrachloroethylene	2.52E-10	4.26E-11	1.23E-05	6.14E-06	1.23E-05	6.14E-06
Toluene	2.52E-08	1.66E-09	0.00E+00	0.00E+00	2.52E-08	1.66E-09
Trichloroethylene	1.19E-10	4.92E-11	9.43E-04	4.95E-04	9.43E-04	4.95E-04
Vinyl Chloride	0.00E+00	0.00E+00	8.86E-05	4.43E-05	8.86E-05	4.43E-05
Xylenes	1.19E-07	3.57E-08	0.00E+00	0.00E+00	1.19E-07	3.57E-08

TABLE P-16

FUTURE TOTAL CHRONIC INTAKE
ONSITE CHILD RESIDENTS AT SITE 2

Indicator Chemical	Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate
Arsenic	0.00E+00	0.00E+00
Barium	0.00E+00	0.00E+00
Benzene	2.57E-05	1.29E-05
Dibutyl Phthalate	0.00E+00	0.00E+00
1,1 Dichloroethylene	1.31E-05	6.54E-06
Trans-1,2 Dichloroethylene	2.57E-02	4.95E-03
Diethyl Phthalate	3.09E-03	2.60E-04
Ethyl Benzene	0.00E+00	0.00E+00
Lead	0.00E+00	0.00E+00
Mercury	0.00E+00	0.00E+00
Tetrachloroethylene	9.21E-06	4.61E-06
Toluene	0.00E+00	0.00E+00
Trichloroethylene	7.07E-04	3.71E-04
Vinyl Chloride	6.64E-05	3.32E-05
Xylenes	0.00E+00	0.00E+00

TABLE P-17

TOTAL CHRONIC INTAKE FOR WORKERS AT SITE 2
CURRENT

Indicator Chemical	Total Chronic Daily Intakes Oral Route (mg/kg/day)		Total Chronic Daily Intakes Inhalation Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Arsenic	6.21E-09	4.53E-09	1.75E-13	1.28E-13
Barium	2.47E-07	7.31E-08	1.40E-11	4.13E-12
Benzene	4.19E-09	2.08E-09	1.18E-13	5.86E-14
Dibutyl Phthalate	0.00E+00	0.00E+00	0.00E+00	0.00E+00
1,1 Dichloroethylene	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	1.51E-10	7.55E-11	4.26E-15	2.13E-15
Diethyl Phthalate	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	8.72E-09	5.58E-09	2.46E-13	1.58E-13
Lead	1.36E-08	3.32E-09	2.56E-12	6.25E-13
Mercury	2.35E-11	1.17E-11	9.47E-15	4.74E-15
Tetrachloroethylene	3.86E-09	1.93E-09	1.09E-13	5.46E-14
Toluene	6.04E-08	5.41E-09	1.71E-12	1.53E-13
Trichloroethylene	2.68E-09	1.34E-09	7.58E-14	3.79E-14
Vinyl Chloride	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	3.02E-07	1.15E-07	8.53E-12	3.25E-12

TABLE P-18

TOTAL CHRONIC INTAKE FOR ADULTS NEAR SITE 2
CURRENT

Indicator Chemical	Total Chronic Daily Intake Oral Route (mg/kg/day)		Total Chronic Daily Intake Inhalation Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Arsenic	6.21E-09	4.53E-09	3.65E-14	2.66E-14
Barium	2.47E-07	7.31E-08	2.91E-12	8.60E-13
Benzene	4.19E-09	2.08E-09	2.47E-14	1.22E-14
Dibutyl Phthalate	0.00E+00	0.00E+00	0.00E+00	0.00E+00
1,1 Dichloroethylene	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	1.51E-10	7.55E-11	8.88E-16	4.44E-16
Diethyl Phthalate	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	8.72E-09	5.58E-09	5.13E-14	3.28E-14
Lead	1.36E-08	3.32E-09	5.33E-13	1.30E-13
Mercury	2.35E-11	1.17E-11	1.97E-15	9.87E-16
Tetrachloroethylene	3.86E-09	1.93E-09	2.27E-14	1.14E-14
Toluene	6.04E-08	5.41E-09	3.55E-13	3.18E-14
Trichloroethylene	2.68E-09	1.34E-09	1.58E-14	7.90E-15
Vinyl Chloride	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	3.02E-07	1.15E-07	1.78E-12	6.77E-13

TABLE P-19

TOTAL CHRONIC INTAKE FOR CHILDREN NEAR SITE 2
CURRENT

Indicator Chemical	Total Chronic Daily Intake Oral Route (mg/kg/day)		Total Chronic Daily Intake Inhalation Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Arsenic	6.52E-09	4.76E-09	2.40E-14	1.75E-14
Barium	2.60E-07	7.68E-08	1.91E-12	5.65E-13
Benzene	4.40E-09	2.18E-09	1.62E-14	8.02E-15
Dibutyl Phthalate	0.00E+00	0.00E+00	0.00E+00	0.00E+00
1,1 Dichloroethylene	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	1.59E-10	7.93E-11	5.83E-16	2.91E-16
Diethyl Phthalate	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	9.16E-09	5.86E-09	3.37E-14	2.15E-14
Lead	3.80E-08	9.30E-09	3.50E-13	8.55E-14
Mercury	2.47E-11	1.23E-11	1.30E-15	6.48E-16
Tetrachloroethylene	4.05E-09	2.03E-09	1.49E-14	7.46E-15
Toluene	6.34E-08	5.68E-09	2.33E-13	2.09E-14
Trichloroethylene	2.82E-09	1.41E-09	1.04E-14	5.19E-15
Vinyl Chloride	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	3.17E-07	1.21E-07	1.17E-12	4.44E-13

TABLE P-20

CHRONIC HAZARD INDEX
ONSITE ADULT RESIDENTS OR WORKERS AT SITE 2
FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	4.53E-09	NA (c)	0.00E+00	2.78E-09	NA	0.00E+00
Barium	2.20E-07	5.10E-02	4.31E-06	4.77E-08	5.10E-02	9.36E-07
Benzene	3.43E-05	NA	0.00E+00	1.71E-05	NA	0.00E+00
Dibutyl Phthalate	3.35E-09	1.00E-01	3.35E-08	2.76E-09	1.00E-01	2.76E-08
1,1 Dichloroethylene	1.74E-05	9.00E-03	1.94E-03	8.71E-06	9.00E-03	9.68E-04
Trans-1,2 Dichloroethylene	3.43E-02	2.00E-02	1.71E+00	6.60E-03	2.00E-02	3.30E-01
Diethyl Phthalate	4.11E-03	1.30E+01	3.16E-04	3.47E-04	1.30E+01	2.67E-05
Ethyl Benzene	4.19E-08	1.00E-01	4.19E-07	1.48E-08	1.00E-01	1.48E-07
Lead	2.57E-08	NA	0.00E+00	2.02E-09	NA	0.00E+00
Mercury	1.17E-11	2.00E-03	5.87E-09	5.87E-12	2.00E-03	2.94E-09
Tetrachloroethylene	1.23E-05	1.00E-02	1.23E-03	6.14E-06	1.00E-02	6.14E-04
Toluene	2.52E-08	3.00E-01	8.39E-08	1.66E-09	3.00E-01	5.53E-09
Trichloroethylene	9.43E-04	1.30E-02	7.25E-02	4.95E-04	1.30E-02	3.81E-02
Vinyl Chloride	8.86E-05	NA	0.00E+00	4.43E-05	NA	0.00E+00
Xylenes	1.19E-07	1.00E-02	1.19E-05	3.57E-08	1.00E-02	3.57E-06

- a. CDI = Chronic Daily Intake
b. AIC = Acceptable Chronic Intake
c. NA = Data not available.

TABLE P-21
CHRONIC HAZARD INDEX
ONSITE CHILD RESIDENTS AT SITE 2
FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Barium	0.00E+00	5.10E-02	0.00E+00	0.00E+00	5.10E-02	0.00E+00
Benzene	2.57E-05	NA	0.00E+00	1.29E-05	NA	0.00E+00
Dibutyl Phthalate	0.00E+00	1.00E-01	0.00E+00	0.00E+00	1.00E-01	0.00E+00
1,1 Dichloroethylene	1.31E-05	9.00E-03	1.45E-03	6.54E-06	9.00E-03	7.26E-04
Trans-1,2 Dichloroethylene	2.57E-02	2.00E-02	1.29E+00	4.95E-03	2.00E-02	2.48E-01
Diethyl Phthalate	3.09E-03	1.30E+01	2.37E-04	2.60E-04	1.30E+01	2.00E-05
Ethyl Benzene	0.00E+00	1.00E-01	0.00E+00	0.00E+00	1.00E-01	0.00E+00
Lead	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Mercury	0.00E+00	2.00E-03	0.00E+00	0.00E+00	2.00E-03	0.00E+00
Tetrachloroethylene	9.21E-06	1.00E-02	9.21E-04	4.61E-06	1.00E-02	4.61E-04
Toluene	0.00E+00	3.00E-01	0.00E+00	0.00E+00	3.00E-01	0.00E+00
Trichloroethylene	7.07E-04	1.30E-02	5.44E-02	3.71E-04	1.30E-02	2.86E-02
Vinyl Chloride	6.64E-05	NA	0.00E+00	3.32E-05	NA	0.00E+00
Xylenes	0.00E+00	1.00E-02	0.00E+00	0.00E+00	1.00E-02	0.00E+00

a. CDI = Chronic Daily Intake
b. AIC = Acceptable Chronic Intake
c. NA = Data not available.

TABLE P-22

CHRONIC HAZARD INDEX FOR WORKERS ON SITE 2
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	1.75E-13	NA (c)	0.00E+00	6.21E-09	NA	0.00E+00
Barium	1.40E-11	1.40E-04	9.98E-08	2.47E-07	5.10E-02	4.85E-06
Benzene	1.18E-13	NA	0.00E+00	4.19E-09	NA	0.00E+00
Dibutyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.00E-01	0.00E+00
1,1 Dichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	9.00E-03	0.00E+00
Trans-1,2 Dichloroethylene	4.26E-15	NA	0.00E+00	1.51E-10	2.00E-02	7.55E-09
Diethyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.33E-01	0.00E+00
Ethyl Benzene	2.46E-13	NA	0.00E+00	8.72E-09	1.00E-01	8.72E-08
Lead	2.56E-12	NA	0.00E+00	1.36E-08	NA	0.00E+00
Mercury	9.47E-15	5.10E-05	1.86E-10	2.35E-11	2.00E-03	1.17E-08
Tetrachloroethylene	1.09E-13	NA	0.00E+00	3.86E-09	1.00E-02	3.86E-07
Toluene	1.71E-12	1.50E+00	1.14E-12	6.04E-08	3.00E-01	2.01E-07
Trichloroethylene	7.58E-14	NA	0.00E+00	2.68E-09	1.30E-02	2.06E-07
Vinyl Chloride	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	8.53E-12	4.00E-01	2.13E-11	3.02E-07	1.00E-02	3.02E-05

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-23

CHRONIC HAZARD INDEX FOR WORKERS ON SITE 2
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	1.28E-13	NA (c)	0.00E+00	4.53E-09	NA	0.00E+00
Barium	4.13E-12	1.40E-04	2.95E-08	7.31E-08	5.10E-02	1.43E-06
Benzene	5.86E-14	NA	0.00E+00	2.08E-09	NA	0.00E+00
Dibutyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.00E-01	0.00E+00
1,1 Dichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	9.00E-03	0.00E+00
Trans-1,2 Dichloroethylene	2.13E-15	NA	0.00E+00	7.55E-11	2.00E-02	3.77E-09
Diethyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.30E+01	0.00E+00
Ethyl Benzene	1.58E-13	NA	0.00E+00	5.58E-09	1.00E-01	5.58E-08
Lead	6.25E-13	NA	0.00E+00	3.32E-09	NA	0.00E+00
Mercury	4.74E-15	5.10E-05	9.29E-11	1.17E-11	2.00E-03	5.87E-09
Tetrachloroethylene	5.46E-14	NA	0.00E+00	1.93E-09	1.00E-02	1.93E-07
Toluene	1.53E-13	1.50E+00	1.02E-13	5.41E-09	3.00E-01	1.80E-08
Trichloroethylene	3.79E-14	NA	0.00E+00	1.34E-09	1.30E-02	1.03E-07
Vinyl Chloride	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	3.25E-12	4.00E-01	8.13E-12	1.15E-07	1.00E-02	1.15E-05

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-24

CHRONIC HAZARD INDEX FOR ADULTS NEAR SITE 2
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	3.65E-14	NA (c)	0.00E+00	6.21E-09	NA	0.00E+00
Barium	2.91E-12	1.40E-04	2.08E-08	2.47E-07	5.10E-02	4.85E-06
Benzene	2.47E-14	NA	0.00E+00	4.19E-09	NA	0.00E+00
Dibutyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.00E-01	0.00E+00
1,1 Dichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	9.00E-03	0.00E+00
Trans-1,2 Dichloroethylene	8.88E-16	NA	0.00E+00	1.51E-10	2.00E-02	7.55E-09
Diethyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.30E+01	0.00E+00
Ethyl Benzene	5.13E-14	NA	0.00E+00	8.72E-09	1.00E-01	8.72E-08
Lead	5.33E-13	NA	0.00E+00	1.36E-08	NA	0.00E+00
Mercury	1.97E-15	5.10E-05	3.87E-11	2.35E-11	2.00E-03	1.17E-08
Tetrachloroethylene	2.27E-14	NA	0.00E+00	3.86E-09	1.00E-02	3.86E-07
Toluene	3.55E-13	1.50E+00	2.37E-13	6.04E-08	3.00E-01	2.01E-07
Trichloroethylene	1.58E-14	NA	0.00E+00	2.68E-09	1.30E-02	2.06E-07
Vinyl Chloride	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	1.78E-12	4.00E-01	4.44E-12	3.02E-07	1.00E-02	3.02E-05

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-25

CHRONIC HAZARD INDEX FOR ADULTS NEAR SITE 2
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	2.66E-14	NA (c)	0.00E+00	4.53E-09	NA	0.00E+00
Barium	8.60E-13	1.40E-04	6.15E-09	7.31E-08	5.10E-02	1.43E-06
Benzene	1.22E-14	NA	0.00E+00	2.08E-09	NA	0.00E+00
Dibutyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.00E-01	0.00E+00
1,1 Dichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	9.00E-03	0.00E+00
Trans-1,2 Dichloroethylene	4.44E-16	NA	0.00E+00	7.55E-11	2.00E-02	3.77E-09
Diethyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.30E+01	0.00E+00
Ethyl Benzene	3.28E-14	NA	0.00E+00	5.58E-09	1.00E-01	5.58E-08
Lead	1.30E-13	NA	0.00E+00	3.32E-09	NA	0.00E+00
Mercury	9.87E-16	5.10E-05	1.93E-11	1.17E-11	2.00E-03	5.87E-09
Tetrachloroethylene	1.14E-14	NA	0.00E+00	1.93E-09	1.00E-02	1.93E-07
Toluene	3.18E-14	1.50E+00	2.12E-14	5.41E-09	3.00E-01	1.80E-08
Trichloroethylene	7.90E-15	NA	0.00E+00	1.34E-09	1.30E-02	1.03E-07
Vinyl Chloride	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	6.77E-13	4.00E-01	1.69E-12	1.15E-07	1.00E-02	1.15E-05

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-26

CHRONIC HAZARD INDEX FOR CHILDREN NEAR SITE 2
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation-Child			Oral-Child		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	2.40E-14	NA (c)	0.00E+00	6.52E-09	NA	0.00E+00
Barium	1.91E-12	1.40E-04	1.36E-08	2.60E-07	5.10E-02	5.09E-06
Benzene	1.62E-14	NA	0.00E+00	4.40E-09	NA	0.00E+00
Dibutyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.00E-01	0.00E+00
1,1 Dichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	9.00E-03	0.00E+00
Trans-1,2 Dichloroethylene	5.83E-16	NA	0.00E+00	1.59E-10	2.00E-02	7.93E-09
Diethyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.30E+01	0.00E+00
Ethyl Benzene	3.37E-14	NA	0.00E+00	9.16E-09	1.00E-01	9.16E-08
Lead	3.50E-13	NA	0.00E+00	3.80E-08	NA	0.00E+00
Mercury	1.30E-15	5.10E-05	2.54E-11	2.47E-11	2.00E-03	1.23E-08
Tetrachloroethylene	1.49E-14	NA	0.00E+00	4.05E-09	1.00E-02	4.05E-07
Toluene	2.33E-13	1.50E+00	1.55E-13	6.34E-08	3.00E-01	2.11E-07
Trichloroethylene	1.04E-14	NA	0.00E+00	2.82E-09	1.30E-02	2.17E-07
Vinyl Chloride	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	1.17E-12	4.00E-01	2.91E-12	3.17E-07	1.00E-02	3.17E-05

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-27

CHRONIC HAZARD INDEX FOR CHILDREN NEAR SITE 2
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation-Child			Oral-Child		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	1.75E-14	NA (c)	0.00E+00	4.76E-09	NA	0.00E+00
Barium	5.65E-13	1.40E-04	4.03E-09	7.68E-08	5.10E-02	1.51E-06
Benzene	8.02E-15	NA	0.00E+00	2.18E-09	NA	0.00E+00
Dibutyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.00E-01	0.00E+00
1,1 Dichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	9.00E-03	0.00E+00
Trans-1,2 Dichloroethylene	2.91E-16	NA	0.00E+00	7.93E-11	2.00E-02	3.96E-09
Diethyl Phthalate	0.00E+00	NA	0.00E+00	0.00E+00	1.30E+01	0.00E+00
Ethyl Benzene	2.15E-14	NA	0.00E+00	5.86E-09	1.00E-01	5.86E-08
Lead	8.55E-14	NA	0.00E+00	9.30E-09	NA	0.00E+00
Mercury	6.48E-16	5.10E-05	1.27E-11	1.23E-11	2.00E-03	6.16E-09
Tetrachloroethylene	7.46E-15	NA	0.00E+00	2.03E-09	1.00E-02	2.03E-07
Toluene	2.09E-14	1.50E+00	1.39E-14	5.68E-09	3.00E-01	1.89E-08
Trichloroethylene	5.19E-15	NA	0.00E+00	1.41E-09	1.30E-02	1.09E-07
Vinyl Chloride	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	4.44E-13	4.00E-01	1.11E-12	1.21E-07	1.00E-02	1.21E-05

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-28

RISK FROM POTENTIAL CARCINOGENS
 ONSITE ADULT RESIDENTS OR WORKERS AT SITE 2
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	4.53E-09	1.50E+01	6.79E-08	2.78E-09	1.50E+01	4.18E-08
Barium	2.20E-07	- (b)	0.00E+00	4.77E-08	-	0.00E+00
Benzene	3.43E-05	2.90E-02	9.94E-07	1.71E-05	2.90E-02	4.97E-07
Dibutyl Phthalate	3.35E-09	-	0.00E+00	2.76E-09	-	0.00E+00
1,1 Dichloroethylene	1.74E-05	6.00E-01	1.05E-05	8.71E-06	6.00E-01	5.23E-06
Trans-1,2 Dichloroethylene	3.43E-02	-	0.00E+00	6.60E-03	-	0.00E+00
Diethyl Phthalate	4.11E-03	-	0.00E+00	3.47E-04	-	0.00E+00
Ethyl Benzene	4.19E-08	-	0.00E+00	1.48E-08	-	0.00E+00
Lead	2.57E-08	NA (c)	0.00E+00	2.02E-09	NA	0.00E+00
Mercury	1.17E-11	-	0.00E+00	5.87E-12	-	0.00E+00
Tetrachloroethylene	1.23E-05	-	0.00E+00	6.14E-06	-	0.00E+00
Toluene	2.52E-08	-	0.00E+00	1.66E-09	-	0.00E+00
Trichloroethylene	9.43E-04	1.10E-02	1.04E-05	4.95E-04	1.10E-02	5.45E-06
Vinyl Chloride	8.86E-05	2.30E+00	2.04E-04	4.43E-05	2.30E+00	1.02E-04
Xylenes	1.19E-07	-	0.00E+00	3.57E-08	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to compound

c. NA = Data not available.

TABLE P-29

RISK FROM POTENTIAL CARCINOGENS
 ONSITE CHILD RESIDENTS AT SITE 2
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	0.00E+00	1.50E+01	0.00E+00	0.00E+00	1.50E+01	0.00E+00
Barium	0.00E+00	- (b)	0.00E+00	0.00E+00	-	0.00E+00
Benzene	2.57E-05	2.90E-02	7.46E-07	1.29E-05	2.90E-02	3.73E-07
Dibutyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
1,1 Dichloroethylene	1.31E-05	6.00E-01	7.84E-06	6.54E-06	6.00E-01	3.92E-06
Trans-1,2 Dichloroethylene	2.57E-02	-	0.00E+00	4.95E-03	-	0.00E+00
Diethyl Phthalate	3.09E-03	-	0.00E+00	2.60E-04	-	0.00E+00
Ethyl Benzene	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Mercury	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Tetrachloroethylene	9.21E-06	-	0.00E+00	4.61E-06	-	0.00E+00
Toluene	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Trichloroethylene	7.07E-04	1.10E-02	7.78E-06	3.71E-04	1.10E-02	4.08E-06
Vinyl Chloride	6.64E-05	2.30E+00	1.53E-04	3.32E-05	2.30E+00	7.64E-05
Xylenes	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to compound

c. NA = Data not available.

TABLE P-30

RISK FROM POTENTIAL CARCINOGENS FOR WORKERS ON SITE 2
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	1.75E-13	5.00E+01	8.76E-12	6.21E-09	1.50E+01	9.31E-08
Barium	1.40E-11	- (b)	0.00E+00	2.47E-07	-	0.00E+00
Benzene	1.18E-13	2.90E-02	3.43E-15	4.19E-09	2.90E-02	1.22E-10
Dibutyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
1,1 Dichloroethylene	0.00E+00	1.16E+00	0.00E+00	0.00E+00	6.00E-01	0.00E+00
Trans-1,2 Dichloroethylene	4.26E-15	-	0.00E+00	1.51E-10	-	0.00E+00
Diethyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Ethyl Benzene	2.46E-13	-	0.00E+00	8.72E-09	-	0.00E+00
Lead	2.56E-12	NA (c)	0.00E+00	1.36E-08	NA	0.00E+00
Mercury	9.47E-15	-	0.00E+00	2.35E-11	-	0.00E+00
Tetrachloroethylene	1.09E-13	-	0.00E+00	3.86E-09	-	0.00E+00
Toluene	1.71E-12	-	0.00E+00	6.04E-08	-	0.00E+00
Trichloroethylene	7.58E-14	NA	0.00E+00	2.68E-09	1.10E-02	2.95E-11
Vinyl Chloride	0.00E+00	2.50E-02	0.00E+00	0.00E+00	2.30E+00	0.00E+00
Xylenes	8.53E-12	-	0.00E+00	3.02E-07	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to compound

c. NA = Data not available

TABLE P-31

RISK FROM POTENTIAL CARCINOGENS FOR WORKERS ON SITE 2
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	4.13E-12	5.00E+01	2.06E-10	4.53E-09	1.50E+01	6.79E-08
Barium	5.86E-14	- (b)	0.00E+00	7.31E-08	-	0.00E+00
Benzene	0.00E+00	2.90E-02	0.00E+00	2.08E-09	2.90E-02	6.02E-11
Dibutyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
1,1 Dichloroethylene	2.13E-15	1.16E+00	2.47E-15	0.00E+00	6.00E-01	0.00E+00
Trans-1,2 Dichloroethylene	0.00E+00	-	0.00E+00	7.55E-11	-	0.00E+00
Diethyl Phthalate	1.58E-13	-	0.00E+00	0.00E+00	-	0.00E+00
Ethyl Benzene	6.25E-13	-	0.00E+00	5.58E-09	-	0.00E+00
Lead	4.74E-15	NA (c)	0.00E+00	3.32E-09	NA	0.00E+00
Mercury	5.46E-14	-	0.00E+00	1.17E-11	-	0.00E+00
Tetrachloroethylene	1.53E-13	-	0.00E+00	1.93E-09	-	0.00E+00
Toluene	3.79E-14	-	0.00E+00	5.41E-09	-	0.00E+00
Trichloroethylene	0.00E+00	NA	0.00E+00	1.34E-09	1.10E-02	1.48E-11
Vinyl Chloride	3.25E-12	2.50E-02	8.13E-14	0.00E+00	2.30E+00	0.00E+00
Ylenes	0.00E+00	-	0.00E+00	1.15E-07	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to compound

c. NA = Data not available

TABLE P-32

RISK FROM POTENTIAL CARCINOGENS FOR ADULTS NEAR SITE 2
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	3.65E-14	5.00E+01	1.83E-12	6.21E-09	1.50E+01	9.31E-08
Barium	2.91E-12	- (b)	0.00E+00	2.47E-07	-	0.00E+00
Benzene	2.47E-14	2.50E-02	7.15E-16	4.19E-09	2.90E-02	1.22E-10
Dibutyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
1,1 Dichloroethylene	0.00E+00	1.16E+00	0.00E+00	0.00E+00	6.00E-01	0.00E+00
Trans-1,2 Dichloroethylene	8.88E-16	-	0.00E+00	1.51E-10	-	0.00E+00
Diethyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Ethyl Benzene	5.13E-14	-	0.00E+00	8.72E-09	-	0.00E+00
Lead	5.33E-13	NA (c)	0.00E+00	1.36E-08	NA	0.00E+00
Mercury	1.97E-15	-	0.00E+00	2.35E-11	-	0.00E+00
Tetrachloroethylene	2.27E-14	-	0.00E+00	3.86E-09	-	0.00E+00
Toluene	3.55E-13	-	0.00E+00	6.04E-08	-	0.00E+00
Trichloroethylene	1.58E-14	NA	0.00E+00	2.68E-09	1.10E-02	2.95E-11
Vinyl Chloride	0.00E+00	2.50E-02	0.00E+00	0.00E+00	2.30E+00	0.00E+00
Xylenes	1.78E-12	-	0.00E+00	3.02E-07	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to compound

c. NA = Data not available.

TABLE P-33

RISK FROM POTENTIAL CARCINOGENS FOR ADULTS NEAR SITE 2
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	2.66E-14	5.00E+01	1.33E-12	4.53E-09	1.50E+01	6.79E-08
Barium	8.60E-13	- (b)	0.00E+00	7.31E-08	-	0.00E+00
Benzene	1.22E-14	2.90E-02	3.54E-16	2.08E-09	2.90E-02	6.02E-11
Dibutyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
1,1 Dichloroethylene	0.00E+00	1.16E+00	0.00E+00	0.00E+00	6.00E-01	0.00E+00
Trans-1,2 Dichloroethylene	4.44E-16	-	0.00E+00	7.55E-11	-	0.00E+00
Diethyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Ethyl Benzene	3.28E-14	-	0.00E+00	5.58E-09	-	0.00E+00
Lead	1.30E-13	NA (c)	0.00E+00	3.32E-09	NA	0.00E+00
Mercury	9.87E-16	-	0.00E+00	1.17E-11	-	0.00E+00
Tetrachloroethylene	1.14E-14	-	0.00E+00	1.93E-09	-	0.00E+00
Toluene	3.18E-14	-	0.00E+00	5.41E-09	-	0.00E+00
Trichloroethylene	7.90E-15	NA	0.00E+00	1.34E-09	10E-02	1.43E-11
Vinyl Chloride	0.00E+00	2.50E-02	0.00E+00	0.00E+00	2.30E+00	0.00E+00
Xylenes	6.77E-13	-	0.00E+00	1.15E-07	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to compound

c. NA = Data not available.

TABLE P-34

RISK FROM POTENTIAL CARCINOGENS FOR CHILDREN NEAR SITE 2
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation-Child			Oral-Child		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	2.40E-14	5.00E+01	1.20E-12	6.52E-09	1.50E+01	9.77E-08
Barium	1.91E-12	- (b)	0.00E+00	2.60E-07	-	0.00E+00
Benzene	1.62E-14	2.90E-02	4.69E-16	4.40E-09	2.90E-02	1.28E-10
Dibutyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
1,1 Dichloroethylene	0.00E+00	1.16E+00	0.00E+00	0.00E+00	6.00E-01	0.00E+00
Trans-1,2 Dichloroethylene	5.83E-16	-	0.00E+00	1.59E-10	-	0.00E+00
Diethyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Ethyl Benzene	3.37E-14	-	0.00E+00	9.16E-09	-	0.00E+00
Lead	3.50E-13	NA (c)	0.00E+00	3.80E-08	NA	0.00E+00
Mercury	1.30E-15	-	0.00E+00	2.47E-11	-	0.00E+00
Tetrachloroethylene	1.49E-14	-	0.00E+00	4.05E-09	-	0.00E+00
Toluene	2.33E-13	-	0.00E+00	6.34E-08	-	0.00E+00
Trichloroethylene	1.04E-14	NA	0.00E+00	2.82E-09	1.10E-02	3.10E-11
Vinyl Chloride	0.00E+00	2.50E-02	0.00E+00	0.00E+00	2.30E+00	0.00E+00
Xylenes	1.17E-12	-	0.00E+00	3.17E-07	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to compound

c. NA = Data not available.

TABLE P-35

RISK FROM POTENTIAL CARCINOGENS FOR CHILDREN NEAR SITE 2
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation-Child			Oral-Child		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	1.75E-14	5.00E+01	8.74E-13	4.76E-09	1.50E+01	7.13E-08
Barium	5.65E-13	- (b)	0.00E+00	7.68E-08	-	0.00E+00
Benzene	8.02E-15	2.90E-02	2.33E-16	2.18E-09	2.90E-02	6.32E-11
Dibutyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
1,1 Dichloroethylene	0.00E+00	1.16E+00	0.00E+00	0.00E+00	6.00E-01	0.00E+00
Trans-1,2 Dichloroethylene	2.91E-16	-	0.00E+00	7.93E-11	-	0.00E+00
Diethyl Phthalate	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Ethyl Benzene	2.15E-14	-	0.00E+00	5.86E-09	-	0.00E+00
Lead	8.55E-14	NA (c)	0.00E+00	9.30E-09	NA	0.00E+00
Mercury	6.48E-16	-	0.00E+00	1.23E-11	-	0.00E+00
Tetrachloroethylene	7.46E-15	-	0.00E+00	2.03E-09	-	0.00E+00
Toluene	2.09E-14	-	0.00E+00	5.68E-09	-	0.00E+00
Trichloroethylene	5.19E-15	NA	0.00E+00	1.41E-09	1.10E-02	1.55E-11
Vinyl Chloride	0.00E+00	2.50E-02	0.00E+00	0.00E+00	2.30E+00	0.00E+00
Xylenes	4.44E-13	-	0.00E+00	1.21E-07	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to compound

c. NA = Data not available.

This page intentionally left blank.

SECTION P.3
SITE 3 RISK ASSESSMENT TABLES

This page intentionally left blank.

SECTION P.3

SITE 3 RISK ASSESSMENT TABLES

This section contains the risk assessment work sheets for Site 3.

P.3.1 Site 3 Indicator Chemical Selection

Data used in the selection of indicator chemicals were compiled from the Remedial Investigation performed at the Base by ES in 1988, the 1986 Phase II Stage 2 study (Dames & Moore, 1987) and the 1983 Phase II Stage 1 study (Weston, 1984). These data are summarized in Table P-36, while Tables P-37 through P-40 step through the USEPA selection process.

P.3.2 Site 3 Estimation of Chemical Intake for Each Pathway

Tables P-41 through P-47 summarize the upper bound and best estimate chronic daily intakes from each potential pathway for each population at risk, as calculated from the maximum and average indicator chemical concentrations, respectively.

P.3.3 Site 3 Estimation of Total Chemical Intake for Each Exposure Route

Chronic daily intakes for pathways categorized as oral or inhalation routes were summed to yield total chronic daily intake via a particular route for a target population. Tables P-48 through P-52 present the total chemical intake for each exposure route.

P.3.4 Site 3 Characterization of Risk From Noncarcinogens

Tables P-53 through P-58 present the chronic hazard index values for each target population.

P.3.5 Site 3 Characterization of Risk From Potential Carcinogens

Tables P-59 through P-64 present the risk from potential carcinogens for each target population.

This page intentionally left blank.

TABLE P-36
MAXIMUM AND REPRESENTATIVE CHEMICAL CONCENTRATIONS AT SITE 3

Parameter	CAS (a) Number	Ground Water (mg/L)			Surface Water (mg/L)			Sediment (mg/kg)			Soils at 0 to 2 Feet (mg/kg)			Soils Below 2 Feet (mg/kg)		
		Maximum Value	Represent- ative Value	# Detected/ # Analyzed	Maximum Value	Represent- ative Value	# Detected/ # Analyzed	Maximum Value	Represent- ative Value	# Detected/ # Analyzed	Maximum Value	Represent- ative Value	# Detected/ # Analyzed	Maximum Value	Represent- ative Value	# Detected/ # Analyzed
Arsenic	7440-38-2	ND (b)	ND	0/20	2.00E-02	1.00E-02	1/7	5.90E+01	3.23E+01	3/7	ND	ND	0/17	ND	ND	0/26
Barium	7440-39-3	1.00E+00	6.33E-01	3/19	6.00E-01	3.50E-01	2/7	3.10E+02	8.90E+01	7/7	1.21E+02	6.98E+01	47/47	1.20E+02	4.85E+01	26/26
Benzene	71-43-2	3.60E-02	1.02E-02	4/20	ND	ND	0/7	ND	ND	0/7	9.00E-01	4.50E-01	1/47	ND	ND	0/26
Codolium	7740-43-9	ND	ND	0/20	1.40E-01	1.00E-01	2/7	9.03E+00	7.88E+00	4/7	1.94E+01	1.04E+01	45/47	1.10E+01	8.99E+00	17/26
Chromium	7440-47-3	7.10E-01	3.05E-01	4/20	2.00E-01	1.00E-01	1/7	7.80E+01	3.49E+01	7/7	4.43E+01	3.19E+01	47/47	3.80E+01	2.82E+01	26/26
4,4' DDB	72-54-8	ND	ND	0/20	ND	ND	0/7	ND	ND	0/7	4.90E-01	2.13E-01	4/47	ND	ND	0/26
4,4' DDE	72-55-9	ND	ND	0/16	ND	ND	0/4	ND	ND	0/7	6.10E-02	3.37E-02	3/47	2.90E-02	1.45E-02	2/26
4,4' DDT	50-29-3	ND	ND	0/20	ND	ND	0/7	ND	ND	0/7	5.00E-01	8.94E-02	10/47	1.10E-01	4.88E-02	4/26
Beta BHC	319-86-8	ND	ND	0/16	ND	ND	0/4	ND	ND	0/7	ND	ND	0/47	2.00E-03	1.00E-03	2/21
1,4 Dichlorobenzene	106-46-7	9.10E-04	4.55E-04	9/16	ND	ND	0/4	ND	ND	0/4	ND	ND	0/44	ND	ND	0/17
1,1 Dichloroethane	75-34-3	3.10E-01	1.11E-01	9/29	3.70E-02	2.04E-02	4/7	5.60E-03	3.29E-03	3/9	2.20E-02	1.35E-02	4/67	2.50E-04	1.25E-04	1/26
1,2 Dichloroethane	107-06-2	4.70E-03	3.46E-03	5/20	3.00E-03	2.90E-03	2/7	ND	ND	0/6	1.80E-02	6.75E-03	4/67	ND	ND	0/17
1,1 Dichloroethylene	75-35-4	5.80E-02	2.16E-02	9/20	3.50E-02	1.68E-02	4/7	2.40E-02	2.10E-02	3/9	3.70E-02	1.95E-02	6/67	ND	ND	0/26
Trans-1,2 Dichloroethylene	540-59-0	4.50E-01	1.23E-01	8/20	8.20E-02	5.41E-02	4/7	5.00E-01	3.15E-01	3/9	1.40E-02	1.00E-02	2/67	ND	ND	0/26
Diethyl Phthalate	84-66-2	1.60E-02	8.00E-03	1/16	ND	ND	0/4	ND	ND	0/4	1.50E+00	1.02E+00	2/47	ND	ND	0/17
Endosulfan Sulfate	115-29-7	ND	ND	0/16	ND	ND	0/4	9.70E-02	5.50E-02	2/4	ND	ND	0/47	ND	ND	0/26
Ethyl Benzene	100-41-4	ND	ND	0/16	ND	ND	0/4	ND	ND	0/4	2.60E-01	1.30E-01	1/47	ND	ND	0/26
Lead	7439-92-1	3.00E-02	1.50E-02	1/20	7.60E-01	3.13E-01	3/7	4.78E+02	1.26E+02	6/7	3.03E+01	9.70E+00	45/47	8.20E+00	4.27E+00	17/26
Mercury	7439-97-6	ND	ND	0/20	ND	ND	0/7	5.80E-01	4.40E-01	2/7	2.80E-01	1.40E-01	1/47	ND	ND	0/26
PCB's	1336-36-3	4.50E-02	3.46E-02	5/16	ND	ND	0/4	3.40E+00	1.22E+00	3/4	ND	ND	0/47	ND	ND	0/26
Tetrachloroethylene	127-18-4	1.00E+00	4.06E-01	9/20	1.00E-02	7.30E-03	4/7	5.10E-03	3.80E-03	2/9	3.00E+00	8.23E-02	7/67	4.10E-04	2.05E-04	1/26

TABLE P-36 (CONTINUED)
MAXIMUM AND REPRESENTATIVE CHEMICAL CONCENTRATIONS AT SITE 3

Parameter	CAS (a) Number	Ground Water (mg/L)			Surface Water (mg/L)			Sediment (mg/kg)			Soils at 0 to 2 Feet (mg/kg)			Soils Below 2 Feet (mg/kg)		
		Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed
Toluene	108-88-3	2.10E-02	1.46E-02	3/20	ND	ND	0/7	8.40E-02	4.20E-02	1/7	1.30E+00	8.39E-02	34/47	7.40E-02	7.97E-02	9/26
1,1,1 Trichloroethane	71-55-6	3.10E+00	1.08E+00	10/20	1.40E+00	6.01E-01	4/7	2.40E-01	4.58E-02	6/9	2.10E-01	4.89E-02	4/67	ND	ND	0/26
Trichloroethylene	79-01-6	7.90E-01	8.89E-02	10/20	7.40E-01	3.56E-01	5/7	1.40E-01	4.63E-02	5/9	9.40E-01	1.93E-01	6/67	4.40E-03	3.75E-02	2/26
Vinyl Chloride	75-01-4	9.10E-03	4.98E-03	4/20	6.00E-03	4.60E-03	3/7	4.20E-03	8.40E-03	1/7	ND	ND	0/47	ND	ND	0/26
Xylenes	1330-20-7	ND	ND	0/20	ND	ND	0/7	ND	ND	0/7	2.00E+00	1.11E+00	2/47	ND	ND	0/26

a. CAS = Chemical Abstracts Service

b. ND = Not Detected

Source: Engineering Science, Inc. (1985), Dumas & Moore (1987) and Weston (1984)

TABLE P-3/

TOXICITY DATA FOR COMPOUNDS DETECTED AT SITE 3

Parameter	CAS (a) Number	Toxicologic Class	Severity Rating (R _{va}) (b)		Carcinogen Assessment Group (CAG) (c)		Toxicity Constants (d)			
							Noncarcinogens		Potential Carcinogens	
			Oral Route	Inhalation Route	Oral Route	Inhalation Route	Water (μ T) (e) (L/mg)	Soil (μ T) (f) (kg/mg)	Water (μ T) (g) (L/mg)	Soil (μ T) (h) (kg/mg)
Arsenic	7440-38-2	NC, PC (g)	9	9	A	A	1.80E+01	9.00E-04	4.07E+00	2.03E-04
Barium	7440-39-3	NC	10	10	D	D	4.08E+00	2.04E-04	- (h)	-
Benzene	71-43-2	NC, PC	5	10	A	A	1.17E-01	5.85E-06	7.71E-03	3.86E-07
Cadmium	7740-43-9	NC, PC	-	8	-	B1	NA (i,	NA	NA	NA
Chromium	7440-47-3	NC, PC	-	8	-	A	NA	NA	NA	NA
4,4' DDD	72-54-8	NC, PC	-	-	B2	B2	NA	NA	3.71E-02	1.86E-06
4,4' DDE	72-55-9	NC, PC	-	-	B2	B2	NA	NA	1.13E-01	5.64E-06
4,4' DDT	50-29-3	NC, PC	-	-	B2	B2	NA	NA	1.59E-01	7.97E-06
Delta BHC	319-86-8	NC	-	-	D	D	NA	NA	-	-
1,4 Dichlorobenzene	106-46-7	NC	4	5	D	D	5.19E-02	2.60E-06	-	-
1,1 Dichloroethane	75-34-3	NC	7	7	D	D	2.58E-02	1.29E-06	-	-
1,2 Dichloroethane	107-06-2	NC, PC	10	8	B2	B2	1.76E-02	8.80E-07	5.86E-02	2.93E-06
1,1 Dichloroethylene	75-35-4	NC, PC	7	5	C	C	3.71E-01	1.86E-05	1.23E-01	6.14E-06
Trans-1,2 Dichloroethylene	540-59-0	NC	5	5	D	D	5.29E-02	2.65E-06	-	-
Diethyl Phthalate	84-66-2	NC	4	4	D	D	2.67E-04	1.34E-08	-	-
Endosulfan sulfate	115-29-7	NC	-	-	D	D	NA	NA	-	-
Ethyl Benzene	100-41-4	NC	4	4	D	D	1.10E-02	5.52E-07	-	-
Lead	7439-92-1	NC, PC	10	10	B2	B2	8.93E-01	4.46E-05	NA	NA
Mercury	7439-97-6	NC	7	8	D	D	1.84E+01	9.21E-04	-	-
PCB's	1336-36-3	NC, PC	-	-	B2	B2	NA	NA	5.71E-01	2.86E-05

TABLE P-27 (CONTINUED)

TOXICITY DATA FOR COMPOUNDS DETECTED AT SITE 3

Parameter	CAS (a) Number	Toxicologic Class	Severity Rating (RfC) (b)		Carcinogen Assessment Group (CAG) (c)		Toxicity Constants (d)			
			Oral Route	Inhalation Route	Oral Route	Inhalation Route	Noncarcinogens		Potential Carcinogens	
							Water (WT) (e) (L/kg)	Soil (ST) (f) (kg/mg)	Water (WT) (L/kg)	Soil (ST) (kg/mg)
Tetrachloroethylene	127-18-4	NC, PC	7	10	B2	B2	9.62E-03	4.81E-07	8.86E-03	4.43E-07
Toluene	108-88-3	NC	7	10	D	D	5.20E-03	2.60E-07	-	-
1,1,1 Trichloroethane	71-55-6	NC	2	2	D	D	7.33E-04	3.67E-08	-	-
Trichloroethylene	79-01-6	NC, PC	5	4	B2	B2	1.05E+00	5.26E-05	4.29E-03	2.14E-07
Vinyl Chloride	75-01-4	NC, PC	10	10	A	A	8.77E-02	4.39E-06	4.29E-03	2.14E-07
Xylenes	1330-20-7	NC	8	8	D	D	1.07E-01	5.33E-06	-	-

a. CAS = Chemical Abstracts Service

b. Rating Value : RfC = USEPA health effect rating value for noncarcinogens

c. Carcinogen Assessment Group = CAG = USEPA classification of carcinogenicity

d. Toxicity Constant = USEPA potency factor based on either carcinogenic or noncarcinogenic endpoints for a given medium

e. WT = Water toxicity constant

f. ST = Soil toxicity constant

g. NC = Noncarcinogenic effects PC = Potential Carcinogen

h. Not applicable to parameter

i. NA = No data available

Source: U.S. Environmental Protection Agency (1986a)

TABLE P-38

CT VALUES FOR NONCARCINOGENIC COMPOUNDS DETECTED AT SITE 3

Parameter	CAS (a) Number	Ground Water CT Value (b)			Surface Water CT Value			Sediment CT Value			CT Values for Soils					
		Maximum Value	Represent- ative Value	-	Maximum Value	Represent- ative Value	-	Maximum Value	Represent- ative Value	-	0 to 2 Feet		Below 2 Feet		Represent- ative Value	
											Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value		
Arsenic	7440-38-2	0.00E+00	0.00E+00	-	3.60E-01	1.80E-01	-	5.31E-05	2.91E-05	-	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Barium	7440-39-3	4.08E+00	2.58E+00	-	2.45E+00	1.43E+00	-	6.32E-05	1.81E-05	-	2.47E-05	1.42E-05	2.45E-05	2.45E-05	9.89E-06	
Benzene	71-43-2	4.21E-13	1.19E-03	-	0.00E+00	0.00E+00	-	0.00E+00	0.00E+00	-	5.27E-06	2.63E-06	0.00E+00	0.00E+00	0.00E+00	
Cadmium	7740-43-9	- (c)	-	-	-	-	-	-	-	-	-	-	-	-	-	
Chromium	7440-47-3	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4,4' DDD	72-54-8	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4,4' DDE	72-55-9	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4,4' DDT	50-29-3	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Delta BHC	319-86-8	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1,4 Dichlorobenzene	106-46-7	4.72E-05	2.34E-05	-	0.00E+00	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
1,1 Dichloroethane	75-34-3	8.00E-03	2.85E-03	-	9.55E-04	5.26E-04	-	7.22E-09	4.24E-09	-	2.84E-08	1.74E-08	3.22E-10	3.22E-10	1.61E-10	
1,2 Dichloroethane	107-06-2	8.27E-05	6.09E-05	-	5.28E-05	5.10E-05	-	0.00E+00	0.00E+00	-	1.58E-08	5.94E-09	0.00E+00	0.00E+00	0.00E+00	
1,1 Dichloroethylene	75-35-4	2.15E-02	8.03E-03	-	1.30E-02	6.24E-03	-	4.46E-07	3.91E-07	-	6.88E-07	3.63E-07	0.00E+00	0.00E+00	0.00E+00	
Trans-1,2 Dichloroethylene	540-59-6	2.33E-02	6.53E-03	-	4.34E-03	2.86E-03	-	1.33E-06	8.34E-07	-	3.71E-08	2.65E-08	0.00E+00	0.00E+00	0.00E+00	
Diethyl Phthalate	84-66-2	4.27E-06	2.14E-06	-	0.00E+00	0.00E+00	-	0.00E+00	0.00E+00	-	2.01E-08	1.37E-08	0.00E+00	0.00E+00	0.00E+00	
Endosulfan Sulfate	115-29-7	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Ethyl Benzene	100-41-4	0.00E+00	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00	0.00E+00	-	1.44E-07	7.18E-08	0.00E+00	0.00E+00	0.00E+00	
Lead	7439-92-1	2.68E-02	1.34E-02	-	6.79E-01	2.80E-01	-	2.13E-05	5.64E-06	-	1.35E-06	4.33E-07	3.65E-07	3.65E-07	1.90E-07	
Mercury	7439-97-6	0.00E+00	0.00E+00	-	0.00E+00	0.00E+00	-	5.34E-07	4.03E-07	-	2.58E-07	1.29E-07	0.00E+00	0.00E+00	0.00E+00	
PCB's	1336-36-3	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Tetrachloroethylene	127-18-4	9.62E-03	3.91E-03	-	9.62E-05	7.02E-05	-	2.45E-09	1.83E-09	-	1.44E-06	3.96E-08	1.97E-10	1.97E-10	9.86E-11	

TABLE P-18 (CONTINUED)
CT VALUES FOR NONCARCINOGENIC COMPOUNDS DETECTED AT SITE 3

Parameter	CAS (a) Number	Ground Water CT Value (b)		Surface Water CT Value		Sediment CT Value		CT Values for Soils			
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	0 to 2 Feet		Below 2 Feet	
Toluene	108-88-3	1.09E-04	7.61E-05	0.00E+00	0.00E+00	2.18E-08	1.06E-08	3.38E-07	2.22E-08	1.92E-07	2.70E-08
1,1,1 Trichloroethane	71-55-6	2.27E-03	7.93E-04	1.03E-03	4.40E-04	8.81E-09	1.6E-09	7.71E-09	1.80E-09	0.00E+00	0.00E+00
Trichloroethylene	79-01-6	8.30E-01	9.33E-02	7.77E-01	3.74E-01	7.36E-06	2.44E-06	4.94E-05	1.02E-05	2.10E-07	1.97E-06
Vinyl Chloride	75-01-4	7.98E-04	4.36E-04	5.26E-04	4.03E-04	1.84E-08	3.62E-08	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	1330-20-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.07E-05	5.92E-06	0.00E+00	0.00E+00

a. CAS = Chemical Abstracts Service
b. CT Value = Concentration x Toxicity. CT values equaling zero are the result of nondetected compounds.
c. No toxicity data available.

TABLE P-39

CT VALUES FOR POTENTIALLY CARCINOGENIC COMPOUNDS DETECTED AT SITE 3

Parameter	CAS (a) Number	Ground Water CT Value (b)			Surface Water CT Value			Sediment CT Value			CT Values for Soils					
		Maximum Value			Maximum Value			Maximum Value			0 to 2 Feet		Below 2 Feet		Representative Value	
											Maximum Value	Representative Value	Maximum Value	Representative Value		
Arsenic	7440-38-2	0.00E+00	0.00E+00	0.00E+00	8.14E-02	4.07E-02	1.20E-05	6.56E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Barium	7440-39-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Benzene	71-43-2	2.78E-04	7.83E-05	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	3.47E-07	1.74E-07	0.00E+00	0.00E+00	0.00E+00	
Cadmium	7740-43-9	- (c)	-	-	-	-	-	-	-	-	-	-	-	-	-	
Chromium	7440-47-3	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4,4' DDD	72-54-8	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	9.11E-07	3.96E-07	0.00E+00	0.00E+00	0.00E+00	
4,4' DDE	72-55-9	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	3.44E-07	2.46E-07	1.64E-07	8.18E-08	0.00E+00	
4,4' DDT	50-29-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	3.98E-06	7.13E-07	8.77E-07	3.89E-07	0.00E+00	
Delta BHC	319-86-8	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1,4 Dichlorobenzene	106-46-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
1,1 Dichloroethane	75-34-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
1,2 Dichloroethane	107-06-2	2.75E-04	2.03E-04	1.76E-04	1.76E-04	1.70E-04	0.00E+00	0.00E+00	0.00E+00	0.00E+00	5.27E-08	1.98E-08	0.00E+00	0.00E+00	0.00E+00	
1,1 Dichloroethylene	75-35-4	7.13E-03	2.66E-03	4.31E-03	4.31E-03	2.07E-03	1.47E-07	1.29E-07	2.27E-07	2.27E-07	2.27E-07	1.20E-07	0.00E+00	0.00E+00	0.00E+00	
Trans-1,2 Dichloroethylene	540-59-0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Diethyl Phthalate	84-66-2	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Endosulfan Sulfate	115-29-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Ethyl Benzene	100-41-4	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Lead	7439-92-1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Mercury	7439-97-6	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
PCB's	1336-36-3	2.57E-02	1.98E-02	0.00E+00	0.00E+00	0.00E+00	9.72E-05	3.50E-05	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Tetrachloroethylene	127-18-4	8.86E-03	3.60E-03	8.86E-05	8.86E-05	6.47E-05	2.26E-09	1.68E-09	1.33E-06	3.65E-08	1.87E-10	9.08E-11	1.87E-10	9.08E-11	1.87E-10	

TABLE P-39 (CONTINUED)

[illegible]

a. CAS = Chemical Abstracts Service
b. CT Value = Concentration x Toxicity. CT values equaling zero are the result of nondetected compounds.
c. No toxicity data available.

TABLE P-40
INDICATOR SCORES AND TENTATIVE RANKING FOR COMPOUNDS DETECTED AT SITE 3

Parameter	CAS (a) Number	Indicator Score for Noncarcinogenic Effects		Tentative Rank for Noncarcinogenic Effects		Indicator Score for Potential Carcinogens		Tentative Rank for Potential Carcinogens	
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value
Arsenic	7440-38-2	5.31E-02	2.91E-02	3	3	1.20E-02	6.56E-03	2	2
Barium	7440-39-3	4.19E+00	2.62E+00	1	1				
Benzene	71-43-2	4.72E-03	1.19E-03	9	9	2.78E-04	7.85E-05	6	7
Cadmium	7740-43-9								
Chromium	7440-47-3								
4,4' DDD	72-54-8					9.11E-07	3.96E-07	10	10
4,4' DDE	72-55-9					5.08E-07	3.28E-07	11	11
4,4' DDT	50-29-3					4.86E-06	1.10E-06	9	9
Delta BHC	319-86-8								
1,4 Dichlorobenzene	106-46-7	4.72E-05	2.36E-05	15	15				
1,1 Dichloroethane	75-34-3	8.00E-03	2.85E-03	8	8				
1,2 Dichloroethane	107-06-2	8.27E-05	6.09E-05	14	14	2.75E-04	2.03E-04	7	6
1,1 Dichloroethylene	75-35-4	2.15E-02	8.03E-03	6	5	7.13E-03	2.66E-03	4	4
Trans-1,2 Dichloroethylene	540-59-0	2.38E-02	6.53E-03	5	6				
Diethyl Phthalate	84-66-2	4.29E-06	2.15E-06	17	17				
Endosulfan Sulfate	115-29-7								
Ethyl Benzene	100-41-4	1.44E-07	7.18E-08	18	18				
Lead	7439-92-1	4.98E-02	1.97E-02	4	4				
Mercury	7439-97-6	7.92E-04	5.34E-04	12	11				
PCB's	1336-36-3					2.58E-02	1.98E-02	1	1
Tetrachloroethylene	127-18-4	9.62E-03	3.91E-03	7	7	8.86E-03	3.60E-03	3	3

TABLE P-40 (CONTINUED)

INDICATOR SCORES AND TENTATIVE RANKING FOR COMPOUNDS DETECTED AT SITE 3

Parameter	CAS (a) Number	Indicator Score for Noncarcinogenic Effects		Tentative Rank for Noncarcinogenic Effects		Indicator Score for Potential Carcinogens		Tentative Rank for Potential Carcinogens	
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value
Toluene	108-88-3	1.10E-04	7.61E-05	13	13				
1,1,1 Trichloroethane	71-55-6	2.27E-03	7.93E-04	10	10				
Trichloroethylene	79-01-6	8.30E-01	3.74E-01	2	2	3.39E-03	1.53E-03	5	5
Vinyl Chloride	75-01-4	7.98E-04	4.36E-04	11	12	3.90E-05	2.13E-05	8	8
Xylenes	1330-20-7	1.07E-05	5.97E-06	16	16				

a. CAS = Chemical Abstracts Service

TABLE P-41

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF SOIL AT DEPTH
FOR WORKERS AT SITE 3

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	ND (b)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Barium	1.20E+02	4.85E+01	5.00E-01	8.39E-10	1.01E-07	4.07E-08
Benzene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Cadmium	1.10E+01	8.99E+00	8.00E-02	1.34E-10	1.48E-09	1.21E-09
Chromium	3.80E+01	2.82E+01	5.00E-01	8.39E-10	3.19E-08	2.37E-08
4,4' DDT	1.10E-01	4.88E-02	1.00E+00	1.68E-09	1.85E-10	8.18E-11
1,1 Dichloroethane	2.50E-04	1.25E-04	1.00E+00	1.68E-09	4.19E-13	2.10E-13
1,1 Dichloroethylene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Lead	8.20E+00	4.27E+00	1.50E-01	2.52E-10	2.06E-09	1.07E-09
Mercury	ND	ND	7.00E-02	1.17E-10	0.00E+00	0.00E+00
Tetrachloroethylene	4.10E-04	2.05E-04	1.00E+00	1.68E-09	6.88E-13	3.44E-13
1,1,1 Trichloroethane	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Trichloroethylene	4.00E-03	3.75E-02	1.00E+00	1.68E-09	6.71E-12	6.29E-11
Vinyl Chloride	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-42

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF GROUND WATER AS DRINKING WATER
FOR ONSITE ADULT RESIDENTS OR WORKERS AT SITE 3

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	ND (a)	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Barium	1.00E+00	6.33E-01	5.00E-01	1.43E-02	1.43E-02	9.04E-03
Benzene	3.60E-02	1.02E-02	1.00E+00	2.86E-02	1.03E-03	2.90E-04
Cadmium	ND	ND	8.00E-02	2.29E-03	0.00E+00	0.00E+00
Chromium	7.10E-01	3.05E-01	5.00E-01	1.43E-02	1.01E-02	4.36E-03
4,4' DDT	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
1,1 Dichloroethane	3.10E-01	1.11E-01	1.00E+00	2.86E-02	8.86E-03	3.16E-03
1,1 Dichloroethylene	5.80E-02	2.16E-02	1.00E+00	2.86E-02	1.66E-03	6.18E-04
Trans-1,2 Dichloroethylene	4.50E-01	1.23E-01	1.00E+00	2.86E-02	1.29E-02	3.53E-03
Lead	3.00E-02	1.50E-02	1.50E-01	4.29E-03	1.29E-04	6.43E-05
Mercury	ND	ND	7.00E-02	2.00E-03	0.00E+00	0.00E+00
Tetrachloroethylene	1.00E+00	4.06E-01	1.00E+00	2.86E-02	2.86E-02	1.16E-02
1,1,1 Trichloroethane	3.10E+00	1.08E+00	1.00E+00	2.86E-02	8.86E-02	3.09E-02
Trichloroethylene	7.90E-01	8.89E-02	1.00E+00	2.86E-02	2.26E-02	2.54E-03
Vinyl Chloride	9.10E-03	4.98E-03	1.00E+00	2.86E-02	2.60E-04	1.42E-04

a. ND = Not Detected

TABLE P-43

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF GROUND WATER AS DRINKING WATER
FOR CHILD RESIDENTS AT SITE 3

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	ND (a)	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Barium	1.00E+00	6.33E-01	5.00E-01	1.07E-02	1.07E-02	6.78E-03
Benzene	3.60E-02	1.02E-02	1.00E+00	2.14E-02	7.71E-04	2.18E-04
Cadmium	ND	ND	8.00E-02	1.71E-03	0.00E+00	0.00E+00
Chromium	7.10E-01	3.05E-01	5.00E-01	1.07E-02	7.61E-03	3.27E-03
4,4' DDT	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
1,1 Dichloroethane	3.10E-01	1.11E-01	1.00E+00	2.14E-02	6.64E-03	2.37E-03
1,1 Dichloroethylene	5.80E-02	2.16E-02	1.00E+00	2.14E-02	1.24E-03	4.64E-04
Trans-1,2 Dichloroethylene	4.50E-01	1.23E-01	1.00E+00	2.14E-02	9.64E-03	2.65E-03
Lead	3.03E-02	1.50E-02	4.00E-01	8.57E-03	2.57E-04	1.29E-04
Mercury	ND	ND	7.00E-02	1.50E-03	0.00E+00	0.00E+00
Tetrachloroethylene	1.00E+00	4.06E-01	1.00E+00	2.14E-02	2.14E-02	8.71E-03
1,1,1 Trichloroethane	3.10E+00	1.08E+00	1.00E+00	2.14E-02	6.64E-02	2.32E-02
Trichloroethylene	7.90E-01	8.89E-02	1.00E+00	2.14E-02	1.69E-02	1.90E-03
Vinyl Chloride	9.10E-03	4.98E-03	1.00E+00	2.14E-02	1.95E-04	1.07E-04

a. ND = Not Detected

TABLE P-44

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE SOILS
FOR WORKERS AT SITE 3

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	ND (a)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Barium	1.21E+02	6.98E+01	5.00E-01	8.39E-10	1.01E-07	5.85E-08
Benzene	9.00E-01	4.50E-01	1.00E+00	1.68E-09	1.51E-09	7.55E-10
Cadmium	1.94E+01	1.04E+01	8.00E-02	1.34E-10	2.60E-09	1.40E-09
Chromium	4.43E+01	3.19E+01	5.00E-01	8.39E-10	3.72E-08	2.67E-08
4,4' DDT	5.00E-01	8.94E-02	1.00E+00	1.68E-09	8.39E-10	1.50E-10
1,1 Dichloroethane	2.20E-02	1.35E-02	1.00E+00	1.68E-09	3.69E-11	2.26E-11
1,1 Dichloroethylene	3.70E-02	1.95E-02	1.00E+00	1.68E-09	6.21E-11	3.27E-11
Trans-1,2 Dichloroethylene	1.40E-02	1.00E-02	1.00E+00	1.68E-09	2.35E-11	1.68E-11
Lead	3.03E+01	9.70E+00	1.50E-01	2.52E-10	7.62E-09	2.44E-09
Mercury	2.80E-01	1.40E-01	7.00E-02	1.17E-10	3.29E-11	1.64E-11
Tetrachloroethylene	3.00E+00	8.23E-02	1.00E+00	1.68E-09	5.03E-09	1.38E-10
1,1,1 Trichloroethane	2.10E-01	4.89E-02	1.00E+00	1.68E-09	3.52E-10	8.21E-11
Trichloroethylene	9.40E-01	1.93E-01	1.00E+00	1.68E-09	1.58E-09	3.24E-10
Vinyl Chloride	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-45

CURRENT EXPOSURE POINT INTAKE VIA VOLATILIZATION OF SURFACE WATER
FOR WORKERS AT SITE 3

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Emission Rate From Water Surface (mg/hr)		Exposure Point Concentration (mg/m ³)		Human Intake Factor (m ³ /day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative	Upper Bound	Best Estimate	Upper Bound	Best Estimate		Upper Bound	Best Estimate
Arsenic	2.00E-02	1.00E-02	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Barium	6.00E-01	3.50E-01	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Benzene	ND (a)	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Cadmium	1.40E-01	1.00E-01	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Chromium	2.00E-01	1.00E-01	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
4,4' DDT	ND	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
1,1 Dichloroethane	3.70E-02	2.04E-02	4.98E-02	2.75E-02	7.76E-09	4.28E-09	1.94E-03	1.51E-11	8.32E-12
1,1 Dichloroethylene	3.50E-02	1.68E-02	4.76E-02	2.29E-02	7.42E-09	3.56E-09	1.94E-03	1.44E-11	6.93E-12
Trans-1,2 Dichloroethylene	8.20E-02	5.41E-02	1.11E-01	7.35E-02	1.74E-08	1.15E-08	1.94E-03	3.38E-11	2.23E-11
Lead	7.60E-01	3.13E-01	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Mercury	ND	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Tetrachloroethylene	1.00E-02	7.30E-03	1.04E-02	7.59E-03	1.62E-09	1.18E-09	1.94E-03	3.15E-12	2.30E-12
1,1,1 Trichloroethane	1.40E+00	6.01E-01	1.63E+00	6.98E-01	2.53E-07	1.09E-07	1.94E-03	4.93E-10	2.11E-10
Trichloroethylene	7.40E-01	3.56E-01	8.66E-01	4.15E-01	1.35E-07	6.49E-08	1.94E-03	2.62E-10	1.26E-10
Vinyl Chloride	6.00E-03	4.60E-03	1.01E-02	7.76E-03	1.58E-09	1.21E-09	1.94E-03	3.07E-12	2.35E-12

a. ND = Not Detected

TABLE P-46

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE WATER DURING RECREATION
FOR ADULTS NEAR SITE 3

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	2.00E-02	1.00E-02	1.00E+00	3.63E-05	7.27E-07	3.63E-07
Barium	6.00E-01	3.50E-01	5.00E-01	1.82E-05	1.09E-05	6.36E-06
Benzene	ND (a)	ND	1.00E+00	3.63E-05	0.00E+00	0.00E+00
Cadmium	1.40E-01	1.00E-01	8.00E-02	2.91E-06	4.07E-07	2.91E-07
Chromium	2.00E-01	1.00E-01	5.00E-01	1.82E-05	3.63E-06	1.82E-06
4,4' DDT	ND	ND	1.00E+00	3.63E-05	0.00E+00	0.00E+00
1,1 Dichloroethane	3.70E-02	2.04E-02	1.00E+00	3.63E-05	1.34E-06	7.41E-07
1,1 Dichloroethylene	3.50E-02	1.68E-02	1.00E+00	3.63E-05	1.27E-06	6.11E-07
Trans-1,2 Dichloroethylene	8.20E-02	5.41E-02	1.00E+00	3.63E-05	2.98E-06	1.97E-06
Lead	7.60E-01	3.13E-01	1.50E-01	5.45E-06	4.14E-06	1.71E-06
Mercury	ND	ND	7.00E-02	2.54E-06	0.00E+00	0.00E+00
Tetrachloroethylene	1.00E-02	7.30E-03	1.00E+00	3.63E-05	3.63E-07	2.65E-07
1,1,1 Trichloroethane	1.40E+00	6.01E-01	1.00E+00	3.63E-05	5.09E-05	2.18E-05
Trichloroethylene	7.40E-01	3.56E-01	1.00E+00	3.63E-05	2.69E-05	1.29E-05
Vinyl Chloride	6.00E-03	4.60E-03	1.00E+00	3.63E-05	2.18E-07	1.67E-07

a. ND = Not Detected

TABLE P-47

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE WATER DURING RECREATION
FOR CHILDREN NEAR SITE 3

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Arsenic	2.00E-02	1.00E-02	1.00E+00	1.91E-04	3.82E-06	1.91E-06
Barium	6.00E-01	3.50E-01	5.00E-01	9.54E-05	5.72E-05	3.34E-05
Benzene	ND (a)	ND	1.00E+00	1.91E-04	0.00E+00	0.00E+00
Cadmium	1.40E-01	1.00E-01	8.00E-02	1.53E-05	2.14E-06	1.53E-06
Chromium	2.00E-01	1.00E-01	5.00E-01	9.54E-05	1.91E-05	9.54E-06
4,4' DDT	ND	ND	1.00E+00	1.91E-04	0.00E+00	0.00E+00
1,1 Dichloroethane	3.70E-02	2.04E-02	1.00E+00	1.91E-04	7.06E-06	3.89E-06
1,1 Dichloroethylene	3.50E-02	1.68E-02	1.00E+00	1.91E-04	6.68E-06	3.21E-06
Trans-1,2 Dichloroethylene	8.20E-02	5.41E-02	1.00E+00	1.91E-04	1.56E-05	1.03E-05
Lead	7.60E-01	3.13E-01	4.00E-01	7.63E-05	5.80E-05	2.39E-05
Mercury	ND	ND	7.00E-02	1.34E-05	0.00E+00	0.00E+00
Tetrachloroethylene	1.00E-02	7.30E-03	1.00E+00	1.91E-04	1.91E-06	1.39E-06
1,1,1 Trichloroethane	1.40E+00	6.01E-01	1.00E+00	1.91E-04	2.67E-04	1.15E-04
Trichloroethylene	7.40E-01	3.56E-01	1.00E+00	1.91E-04	1.41E-04	6.79E-05
Vinyl Chloride	6.00E-03	4.60E-03	1.00E+00	1.91E-04	1.14E-06	8.78E-07

a. ND = Not Detected

TABLE P-48

FUTURE TOTAL CHRONIC INTAKE
ONSITE ADULT RESIDENTS OR WORKERS AT SITE 3

Indicator Chemical	Ingestion of Soil at Depth (mg/kg/day)		Ingestion of Ground Water (mg/kg/day)		Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Arsenic	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Barium	1.01E-07	4.07E-08	1.43E-02	9.04E-03	1.43E-02	9.04E-03
Benzene	0.00E+00	0.00E+00	1.03E-03	2.90E-04	1.03E-03	2.90E-04
Cadmium	1.48E-09	1.21E-09	0.00E+00	0.00E+00	1.48E-09	1.21E-09
Chromium	3.19E-08	2.37E-08	1.01E-02	4.36E-03	1.01E-02	4.36E-03
4,4' DDT	1.85E-10	8.18E-11	0.00E+00	0.00E+00	1.85E-10	8.18E-11
1,1 Dichloroethane	4.19E-13	2.10E-13	8.86E-03	3.16E-03	8.86E-03	3.16E-03
1,1 Dichloroethylene	0.00E+00	0.00E+00	1.66E-03	6.18E-04	1.66E-03	6.18E-04
Trans-1,2 Dichloroethylene	0.00E+00	0.00E+00	1.29E-02	3.53E-03	1.29E-02	3.53E-03
Lead	2.06E-09	1.07E-09	1.29E-04	6.43E-05	1.29E-04	6.43E-05
Mercury	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Tetrachloroethylene	6.88E-13	3.44E-13	2.86E-02	1.16E-02	2.86E-02	1.16E-02
1,1,1 Trichloroethane	0.00E+00	0.00E+00	8.86E-02	3.09E-02	8.86E-02	3.09E-02
Trichloroethylene	6.71E-12	6.29E-11	2.26E-02	2.54E-03	2.26E-02	2.54E-03
Vinyl Chloride	0.00E+00	0.00E+00	2.60E-04	1.42E-04	2.60E-04	1.42E-04

TABLE P-49

FUTURE TOTAL CHRONIC INTAKE
 ONSITE CHILD RESIDENTS AT SITE 3

Indicator Chemical	Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate
Arsenic	0.00E+00	0.00E+00
Barium	1.07E-02	6.78E-03
Benzene	7.71E-04	2.18E-04
Cadmium	0.00E+00	0.00E+00
Chromium	7.61E-03	3.27E-03
4,4' DDT	0.00E+00	0.00E+00
1,1 Dichloroethane	6.64E-03	2.37E-03
1,1 Dichloroethylene	1.24E-03	4.64E-04
Trans-1,2 Dichloroethylene	9.64E-03	2.65E-03
Lead	2.57E-04	1.29E-04
Mercury	0.00E+00	0.00E+00
Tetrachloroethylene	2.14E-02	8.71E-03
1,1,1 Trichloroethane	6.64E-02	2.32E-02
Trichloroethylene	1.69E-02	1.90E-03
Vinyl Chloride	1.95E-04	1.07E-04

TABLE P-50

TOTAL CHRONIC INTAKE FOR WORKERS AT SITE 3
CURRENT

Indicator Chemical	Total Chronic Daily Intakes Oral Route (mg/kg/day)		Total Chronic Daily Intakes Inhalation Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Arsenic	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Barium	1.01E-07	5.85E-08	0.00E+00	0.00E+00
Benzene	1.51E-09	7.55E-10	0.00E+00	0.00E+00
Cadmium	2.60E-09	1.40E-09	0.00E+00	0.00E+00
Chromium	3.72E-08	2.67E-08	0.00E+00	0.00E+00
4,4' DDT	8.39E-10	1.50E-10	0.00E+00	0.00E+00
1,1 Dichloroethane	3.69E-11	2.26E-11	1.51E-11	8.32E-12
1,1 Dichloroethylene	6.21E-11	3.27E-11	1.44E-11	6.93E-12
Trans-1,2 Dichloroethylene	2.35E-11	1.68E-11	3.38E-11	2.23E-11
Lead	7.62E-09	2.44E-09	0.00E+00	0.00E+00
Mercury	3.29E-11	1.64E-11	0.00E+00	0.00E+00
Tetrachloroethylene	5.03E-09	1.38E-10	3.15E-12	2.30E-12
1,1,1 Trichloroethane	3.52E-10	8.21E-11	4.93E-10	2.11E-10
Trichloroethylene	1.58E-09	3.24E-10	2.62E-10	1.26E-10
Vinyl Chloride	0.00E+00	0.00E+00	3.07E-12	2.35E-12

TABLE P-51

TOTAL CHRONIC INTAKE FOR ADULTS NEAR SITE 3
CURRENT

Indicator Chemical	Total Chronic Daily Intake Oral Route (mg/kg/day)	
	Upper Bound	Best Estimate
Arsenic	7.27E-07	3.63E-07
Barium	1.09E-05	6.36E-06
Benzene	0.00E+00	0.00E+00
Cadmium	4.07E-07	2.91E-07
Chromium	3.63E-06	1.82E-06
4,4' DDT	0.00E+00	0.00E+00
1,1 Dichloroethane	1.34E-06	7.41E-07
1,1 Dichloroethylene	1.27E-06	6.11E-07
Trans-1,2 Dichloroethylene	2.98E-06	1.97E-06
Lead	4.14E-06	1.71E-06
Mercury	0.00E+00	0.00E+00
Tetrachloroethylene	3.63E-07	2.65E-07
1,1,1 Trichloroethane	5.09E-05	2.18E-05
Trichloroethylene	2.69E-05	1.29E-05
Vinyl Chloride	2.18E-07	1.67E-07

TABLE P-52

TOTAL CHRONIC INTAKE FOR CHILDREN NEAR SITE 3
CURRENT

Indicator Chemical	Total Chronic Daily Intake Oral Route (mg/kg/day)	
	Upper Bound	Best Estimate
Arsenic	3.82E-06	1.91E-06
Barium	5.72E-05	3.34E-05
Benzene	0.00E+00	0.00E+00
Cadmium	2.14E-06	1.53E-06
Chromium	1.91E-05	9.54E-06
4,4' DDT	0.00E+00	0.00E+00
1,1 Dichloroethane	7.06E-06	3.89E-06
1,1 Dichloroethylene	6.68E-06	3.21E-06
Trans-1,2 Dichloroethylene	1.56E-05	1.03E-05
Lead	5.80E-05	2.39E-05
Mercury	0.00E+00	0.00E+00
Tetrachloroethylene	1.91E-06	1.39E-06
1,1,1 Trichloroethane	2.67E-04	1.15E-04
Trichloroethylene	1.41E-04	6.79E-05
Vinyl Chloride	1.14E-06	8.78E-07

TABLE P-53

CHRONIC HAZARD INDEX
 ONSITE ADULT RESIDENTS OR WORKERS AT SITE 3
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Barium	1.43E-02	5.10E-02	2.80E-01	9.04E-03	5.10E-02	1.77E-01
Benzene	1.03E-03	NA	0.00E+00	2.90E-04	NA	0.00E+00
Cadmium	1.48E-09	2.90E-04	5.09E-06	1.21E-09	2.90E-04	4.16E-06
Chromium	1.01E-02	5.00E-03	2.03E+00	4.36E-03	5.00E-03	8.71E-01
4,4' DDT	1.85E-10	5.00E-04	3.69E-07	8.18E-11	5.00E-04	1.64E-07
1,1 Dichloroethane	8.86E-03	1.20E-01	7.38E-02	3.16E-03	1.20E-01	2.63E-02
1,1 Dichloroethylene	1.66E-03	9.00E-03	1.84E-01	6.18E-04	9.00E-03	6.87E-02
Trans-1,2 Dichloroethylene	1.29E-02	2.00E-02	6.43E-01	3.53E-03	2.00E-02	1.76E-01
Lead	1.29E-04	NA	0.00E+00	6.43E-05	NA	0.00E+00
Mercury	0.00E+00	2.00E-03	0.00E+00	0.00E+00	2.00E-03	0.00E+00
Tetrachloroethylene	2.86E-02	1.00E-02	2.86E+00	1.16E-02	1.00E-02	1.16E+00
1,1,1 Trichloroethane	8.86E-02	3.00E-01	2.95E-01	3.09E-02	3.00E-01	1.03E-01
Trichloroethylene	2.26E-02	1.30E-02	1.74E+00	2.54E-03	1.30E-02	1.95E-01
Vinyl Chloride	2.60E-04	NA	0.00E+00	1.42E-04	NA	0.00E+00

- a. CDI = Chronic Daily Intake
 b. AIC = Acceptable Chronic Intake
 c. NA = Data not available.

TABLE P-54

CHRONIC HAZARD INDEX
 ONSITE CHILD RESIDENTS AT SITE 3
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Barium	1.07E-02	5.10E-02	2.10E-01	6.78E-03	5.10E-02	1.33E-01
Benzene	7.71E-04	NA	0.00E+00	2.18E-04	NA	0.00E+00
Cadmium	0.00E+00	2.90E-04	0.00E+00	0.00E+00	2.90E-04	0.00E+00
Chromium	7.61E-03	5.00E-03	1.52E+00	3.27E-03	5.00E-03	6.54E-01
4,4' DDT	0.00E+00	5.00E-04	0.00E+00	0.00E+00	5.00E-04	0.00E+00
1,1 Dichloroethane	6.64E-03	1.20E-01	5.54E-02	2.37E-03	1.20E-01	1.97E-02
1,1 Dichloroethylene	1.24E-03	9.00E-03	1.38E-01	4.64E-04	9.00E-03	5.15E-02
Trans-1,2 Dichloroethylene	9.64E-03	2.00E-02	4.82E-01	2.65E-03	2.00E-02	1.32E-01
Lead	2.57E-04	NA	0.00E+00	1.29E-04	NA	0.00E+00
Mercury	0.00E+00	2.00E-03	0.00E+00	0.00E+00	2.00E-03	0.00E+00
Tetrachloroethylene	2.14E-02	1.00E-02	2.14E+00	8.71E-03	1.00E-02	8.71E-01
1,1,1 Trichloroethane	6.64E-02	3.00E-01	2.21E-01	2.32E-02	3.00E-01	7.73E-02
Trichloroethylene	1.69E-02	1.30E-02	1.30E+00	1.90E-03	1.30E-02	1.46E-01
Vinyl Chloride	1.95E-04	NA	0.00E+00	1.07E-04	NA	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-55

CHRONIC HAZARD INDEX FOR WORKERS ON SITE 3
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation			Ingestion		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Barium	0.00E+00	1.40E-04	0.00E+00	1.01E-07	5.10E-02	1.99E-06
Benzene	0.00E+00	NA	0.00E+00	1.51E-09	NA	0.00E+00
Cadmium	0.00E+00	NA	0.00E+00	2.60E-09	2.90E-04	8.98E-06
Chromium	0.00E+00	NA	0.00E+00	3.72E-08	5.00E-03	7.43E-06
4,4' DDT	0.00E+00	NA	0.00E+00	8.39E-10	5.00E-04	1.68E-06
1,1 Dichloroethane	1.51E-11	1.38E-01	1.09E-10	3.69E-11	1.20E-01	3.08E-10
1,1 Dichloroethylene	1.44E-11	NA	0.00E+00	6.21E-11	9.00E-03	6.90E-09
Trans-1,2 Dichloroethylene	3.38E-11	NA	0.00E+00	2.35E-11	2.00E-02	1.17E-09
Lead	0.00E+00	NA	0.00E+00	7.62E-09	NA	0.00E+00
Mercury	0.00E+00	5.10E-05	0.00E+00	3.29E-11	2.00E-03	1.64E-08
Tetrachloroethylene	3.15E-12	NA	0.00E+00	5.03E-09	1.00E-02	5.03E-07
1,1,1 Trichloroethane	4.93E-10	6.30E+00	7.82E-11	3.52E-10	3.00E-01	1.17E-09
Trichloroethylene	2.62E-10	NA	0.00E+00	1.58E-09	1.30E-02	1.21E-07
Vinyl Chloride	3.07E-12	NA	0.00E+00	0.00E+00	NA	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-56

CHRONIC HAZARD INDEX FOR WORKERS ON SITE 3
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation			Ingestion		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Barium	0.00E+00	1.40E-04	0.00E+00	5.85E-08	5.10E-02	1.15E-06
Benzene	0.00E+00	NA	0.00E+00	7.55E-10	NA	0.00E+00
Cadmium	0.00E+00	NA	0.00E+00	1.40E-09	2.90E-04	4.82E-06
Chromium	0.00E+00	NA	0.00E+00	2.67E-08	5.00E-03	5.34E-06
4,4' DDT	0.00E+00	NA	0.00E+00	1.50E-10	5.00E-04	3.00E-07
1,1 Dichloroethane	8.32E-12	1.38E-01	6.03E-11	2.26E-11	1.20E-01	1.89E-10
1,1 Dichloroethylene	6.93E-12	NA	0.00E+00	3.27E-11	9.00E-03	3.63E-09
Trans-1,2 Dichloroethylene	2.23E-11	NA	0.00E+00	1.68E-11	2.00E-02	8.39E-10
Lead	0.00E+00	NA	0.00E+00	2.44E-09	NA	0.00E+00
Mercury	0.00E+00	5.10E-05	0.00E+00	1.64E-11	2.00E-03	8.22E-09
Tetrachloroethylene	2.30E-12	NA	0.00E+00	1.38E-10	1.00E-02	1.38E-08
1,1,1 Trichloroethane	2.11E-10	6.30E+00	3.36E-11	8.21E-11	3.00E-01	2.74E-10
Trichloroethylene	1.26E-10	NA	0.00E+00	3.24E-10	1.30E-02	2.49E-08
Vinyl Chloride	2.35E-12	NA	0.00E+00	0.00E+00	NA	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-57

CHRONIC HAZARD INDEX FOR ADULTS NEAR SITE 3
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (ng/kg/day)	AIC (b) (ng/kg/day)	CDI:AIC	CDI (ng/kg/day)	AIC (ng/kg/day)	CDI:AIC
Arsenic	7.27E-07	NA (c)	0.00E+00	3.63E-07	NA	0.00E+00
Barium	1.09E-05	5.10E-02	2.14E-04	6.36E-06	5.10E-02	1.25E-04
Benzene	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Cadmium	4.07E-07	2.90E-04	1.40E-03	2.91E-07	2.90E-04	1.00E-03
Chromium	3.63E-06	5.00E-03	7.27E-04	1.82E-06	5.00E-03	3.63E-04
4,4' DDT	0.00E+00	5.00E-04	0.00E+00	0.00E+00	5.00E-04	0.00E+00
1,1 Dichloroethane	1.34E-06	1.20E-01	1.12E-05	7.41E-07	1.20E-01	6.18E-06
1,1 Dichloroethylene	1.27E-06	9.00E-03	1.41E-04	6.11E-07	9.00E-03	6.79E-05
Trans-1,2 Dichloroethylene	2.98E-06	2.00E-02	1.49E-04	1.97E-06	2.00E-02	9.83E-05
Lead	4.14E-06	NA	0.00E+00	1.71E-06	NA	0.00E+00
Mercury	0.00E+00	2.00E-03	0.00E+00	0.00E+00	2.00E-03	0.00E+00
Tetrachloroethylene	3.63E-07	1.00E-02	3.63E-05	2.65E-07	1.00E-02	2.65E-05
1,1,1 Trichloroethane	5.09E-05	3.00E-01	1.70E-04	2.18E-05	3.00E-01	7.28E-05
Trichloroethylene	2.69E-05	1.30E-02	2.07E-03	1.29E-05	1.30E-02	9.95E-04
Vinyl Chloride	2.18E-07	NA	0.00E+00	1.67E-07	NA	0.00E+00

- a. CDI = Chronic Daily Intake
b. AIC = Acceptable Chronic Intake
c. NA = Data not available.

TABLE F-58

CHRONIC HAZARD INDEX FOR CHILDREN NEAR SITE 3
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Arsenic	3.82E-06	NA (c)	0.00E+00	1.91E-06	NA	0.00E+00
Barium	5.72E-05	5.10E-02	1.12E-03	3.34E-05	5.10E-02	6.55E-04
Benzene	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Cadmium	2.14E-06	2.90E-04	7.37E-03	1.53E-06	2.90E-04	5.26E-03
Chromium	1.91E-05	5.00E-03	3.82E-03	9.54E-06	5.00E-03	1.91E-03
4,4' DDT	0.00E+00	5.00E-04	0.00E+00	0.00E+00	5.00E-04	0.00E+00
1,1 Dichloroethane	7.06E-06	1.20E-01	5.88E-05	3.89E-06	1.20E-01	3.24E-05
1,1 Dichloroethylene	6.68E-06	9.00E-03	7.42E-04	3.21E-06	9.00E-03	3.56E-04
Trans-1,2 Dichloroethylene	1.56E-05	2.00E-02	7.82E-04	1.03E-05	2.00E-02	5.16E-04
Lead	5.80E-05	NA	0.00E+00	2.39E-05	NA	0.00E+00
Mercury	0.00E+00	2.00E-03	0.00E+00	0.00E+00	2.00E-03	0.00E+00
Tetrachloroethylene	1.91E-06	1.00E-02	1.91E-04	1.39E-06	1.00E-02	1.39E-04
1,1,1 Trichloroethane	2.67E-04	3.00E-01	8.90E-04	1.15E-04	3.00E-01	3.82E-04
Trichloroethylene	1.41E-04	1.30E-02	1.09E-02	6.79E-05	1.30E-02	5.23E-03
Vinyl Chloride	1.14E-05	NA	0.00E+00	8.78E-07	NA	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-59

RISK FROM POTENTIAL CARCINOGENS
 ONSITE ADULT RESIDENTS OR WORKERS AT SITE 3
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	0.00E+00	1.50E+01	0.00E+00	0.00E+00	1.50E+01	0.00E+00
Barium	1.43E-02	- (b)	0.00E+00	9.04E-03	-	0.00E+00
Benzene	1.03E-03	2.90E-02	2.98E-05	2.90E-04	2.90E-02	8.42E-06
Cadmium	1.48E-09	NA	0.00E+00	1.21E-09	NA (c)	0.00E+00
Chromium	1.01E-02	NA	0.00E+00	4.36E-03	NA	0.00E+00
4,4' DDT	1.85E-10	3.40E-01	6.27E-11	8.18E-11	3.40E-01	2.78E-11
1,1 Dichloroethane	8.86E-03	-	0.00E+00	3.16E-03	-	0.00E+00
1,1 Dichloroethylene	1.66E-03	6.00E-01	9.94E-04	6.13E-04	6.00E-01	3.71E-04
Trans-1,2 Dichloroethylene	1.29E-02	-	0.00E+00	3.53E-03	-	0.00E+00
Lead	1.29E-04	NA	0.00E+00	6.43E-05	NA	0.00E+00
Mercury	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Tetrachloroethylene	2.86E-02	-	0.00E+00	1.16E-02	-	0.00E+00
1,1,1 Trichloroethane	8.86E-02	-	0.00E+00	3.09E-02	-	0.00E+00
Trichloroethylene	2.26E-02	1.10E-02	2.48E-04	2.54E-03	1.10E-02	2.79E-05
Vinyl Chloride	2.60E-04	2.30E+00	5.98E-04	1.42E-04	2.30E+00	3.27E-04

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-60

RISK FROM POTENTIAL CARCINOGENS
ONSITE CHILD RESIDENTS AT SITE 3
FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	0.00E+00	1.50E+01	0.00E+00	0.00E+00	1.50E+01	0.00E+00
Barium	1.07E-02	- (b)	0.00E+00	6.78E-03	-	0.00E+00
Benzene	7.71E-04	2.90E-02	2.24E-05	2.18E-04	2.90E-02	6.31E-05
Cadmium	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Chromium	7.61E-03	NA	0.00E+00	3.27E-03	NA	0.00E+00
4,4' DDT	0.00E+00	3.40E-01	0.00E+00	0.00E+00	3.40E-01	0.00E+00
1,1 Dichloroethane	6.64E-03	-	0.00E+00	2.37E-03	-	0.00E+00
1,1 Dichloroethylene	1.24E-03	6.00E-01	7.46E-04	4.64E-04	6.00E-01	2.78E-04
Trans-1,2 Dichloroethylene	9.64E-03	-	0.00E+00	2.65E-03	-	0.00E+00
Lead	2.57E-04	NA	0.00E+00	1.29E-04	NA	0.00E+00
Mercury	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Tetrachloroethylene	2.14E-02	-	0.00E+00	8.71E-03	-	0.00E+00
1,1,1 Trichloroethane	6.64E-02	-	0.00E+00	2.32E-02	-	0.00E+00
Trichloroethylene	1.69E-02	1.10E-02	1.86E-04	1.90E-03	1.10E-02	2.09E-05
Vinyl Chloride	1.95E-04	2.30E+00	4.49E-04	1.07E-04	2.30E+00	2.45E-04

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-61

RISK FROM POTENTIAL CARCINOGENS FOR WORKERS ON SITE 3
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation			Ingestion		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	0.00E+00	5.00E+01	0.00E+00	0.00E+00	1.50E+01	0.00E+00
Barium	0.00E+00	- (b)	0.00E+00	1.01E-07	-	0.00E+00
Benzene	0.00E+00	2.90E-02	0.00E+00	1.51E-09	2.90E-02	4.38E-11
Cadmium	0.00E+00	6.10E+00	0.00E+00	2.60E-09	NA (c)	0.00E+00
Chromium	0.00E+00	4.10E+01	0.00E+00	3.72E-08	NA	0.00E+00
4,4' DDT	0.00E+00	3.40E-01	0.00E+00	8.39E-10	3.40E-01	2.85E-10
1,1 Dichloroethane	1.51E-11	-	0.00E+00	3.69E-11	-	0.00E+00
1,1 Dichloroethylene	1.44E-11	1.16E+00	1.67E-11	6.21E-11	6.00E-01	3.72E-11
Trans-1,2 Dichloroethylene	3.38E-11	-	0.00E+00	2.35E-11	-	0.00E+00
Lead	0.00E+00	NA	0.00E+00	7.62E-09	NA	0.00E+00
Mercury	0.00E+00	-	0.00E+00	3.29E-11	-	0.00E+00
Tetrachloroethylene	3.15E-12	-	0.00E+00	5.03E-09	-	0.00E+00
1,1,1 Trichloroethane	4.93E-10	-	0.00E+00	3.52E-10	-	0.00E+00
Trichloroethylene	2.62E-10	NA	0.00E+00	1.58E-09	1.10E-02	1.73E-11
Vinyl Chloride	3.07E-12	2.50E-02	7.67E-14	0.00E+00	2.30E+00	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-62

RISK FROM POTENTIAL CARCINOGENS FOR WORKERS ON SITE 3
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation			Ingestion		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	0.00E+00	5.00E+01	0.00E+00	0.00E+00	1.50E+01	0.00E+00
Barium	0.00E+00	- (b)	0.00E+00	5.85E-08	-	0.00E+00
Benzene	0.00E+00	2.90E-02	0.00E+00	7.55E-10	2.90E-02	2.19E-11
Cadmium	0.00E+00	6.10E+00	0.00E+00	1.40E-09	NA (c)	0.00E+00
Chromium	0.00E+00	4.10E+01	0.00E+00	2.67E-08	NA	0.00E+00
4,4' DDT	0.00E+00	3.40E-01	0.00E+00	1.50E-10	3.40E-01	5.10E-11
1,1 Dichloroethane	8.32E-12	-	0.00E+00	2.26E-11	-	0.00E+00
1,1 Dichloroethylene	6.93E-12	1.16E+00	8.04E-12	3.27E-11	6.00E-01	1.96E-11
Trans-1,2 Dichloroethylene	2.23E-11	-	0.00E+00	1.68E-11	-	0.00E+00
Lead	0.00E+00	NA	0.00E+00	2.44E-09	NA	0.00E+00
Mercury	0.00E+00	-	0.00E+00	1.64E-11	-	0.00E+00
Tetrachloroethylene	2.30E-12	-	0.00E+00	1.38E-10	-	0.00E+00
1,1,1 Trichloroethane	2.11E-10	-	0.00E+00	8.21E-11	-	0.00E+00
Trichloroethylene	1.26E-10	NA	0.00E+00	3.24E-10	1.10E-02	3.56E-12
Vinyl Chloride	2.35E-12	2.50E-02	5.88E-14	0.00E+00	2.30E+00	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-63

RISK FROM POTENTIAL CARCINOGENS FOR ADULTS NEAR SITE 3
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	7.27E-07	1.50E+01	1.09E-05	3.63E-07	1.50E+01	5.45E-06
Barium	1.09E-05	- (b)	0.00E+00	6.36E-06	-	0.00E+00
Benzene	0.00E+00	2.90E-02	0.00E+00	0.00E+00	2.90E-02	0.00E+00
Cadmium	4.07E-07	NA (c)	0.00E+00	2.91E-07	NA	0.00E+00
Chromium	3.63E-06	NA	0.00E+00	1.82E-06	NA	0.00E+00
4,4' DDT	0.00E+00	3.40E-01	0.00E+00	0.00E+00	3.40E-01	0.00E+00
1,1 Dichloroethane	1.34E-06	-	0.00E+00	7.41E-07	-	0.00E+00
1,1 Dichloroethylene	1.27E-06	6.00E-01	7.63E-07	6.11E-07	6.00E-01	3.67E-07
Trans-1,2 Dichloroethylene	2.98E-06	-	0.00E+00	1.97E-06	-	0.00E+00
Lead	4.14E-06	NA	0.00E+00	1.71E-06	NA	0.00E+00
Mercury	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Tetrachloroethylene	3.63E-07	-	0.00E+00	2.65E-07	-	0.00E+00
1,1,1 Trichloroethane	5.09E-05	-	0.00E+00	2.18E-05	-	0.00E+00
Trichloroethylene	2.69E-05	1.10E-02	2.96E-07	1.29E-05	1.10E-02	1.42E-07
Vinyl Chloride	2.18E-07	2.30E+00	5.02E-07	1.67E-07	2.30E+00	3.85E-07

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-64

RISK FROM POTENTIAL CARCINOGENS FOR CHILDREN NEAR SITE 3
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Arsenic	3.82E-06	1.50E+01	5.72E-05	1.91E-06	1.50E+01	2.86E-05
Barium	5.72E-05	- (b)	0.00E+00	3.34E-05	-	0.00E+00
Benzene	0.00E+00	2.90E-02	0.00E+00	0.00E+00	2.90E-02	0.00E+00
Cadmium	2.14E-06	NA (c)	0.00E+00	1.53E-06	NA	0.00E+00
Chromium	1.91E-05	NA	0.00E+00	9.54E-06	NA	0.00E+00
4,4' DDT	0.00E+00	3.40E-01	0.00E+00	0.00E+00	3.40E-01	0.00E+00
1,1 Dichloroethane	7.06E-06	-	0.00E+00	3.89E-06	-	0.00E+00
1,1 Dichloroethylene	6.68E-06	6.00E-01	4.01E-06	3.21E-06	6.00E-01	1.93E-06
Trans-1,2 Dichloroethylene	1.56E-05	-	0.00E+00	1.03E-05	-	0.00E+00
Lead	5.80E-05	NA	0.00E+00	2.39E-05	NA	0.00E+00
Mercury	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Tetrachloroethylene	1.91E-06	-	0.00E+00	1.39E-06	-	0.00E+00
1,1,1 Trichloroethane	2.67E-04	-	0.00E+00	1.15E-04	-	0.00E+00
Trichloroethylene	1.41E-04	1.10E-02	1.55E-06	6.79E-05	1.10E-02	7.47E-07
Vinyl Chloride	1.14E-06	2.30E+00	2.63E-06	8.79E-07	2.30E+00	2.02E-06

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

SECTION P.4
SITE 4 RISK ASSESSMENT TABLES

This page intentionally left blank.

SECTION P.4

SITE 4 RISK ASSESSMENT TABLES

This section contains the risk assessment worksheets for Site 4.

P.4.1 Site 4 Indicator Chemical Selection

Data used in the selection of indicator chemicals were compiled from both the Remedial Investigation performed at the Base by ES in 1988 and the 1986 Phase II Stage 2 study (Dames & Moore, 1987). These data are summarized in Table P-65, while Tables P-66 through P-69 step through the USEPA selection process.

P.4.2 Site 4 Estimation of Chemical Intake for Each Pathway

Tables P-70 through P-78 summarize the upper bound and best estimate chronic daily intakes from each potential pathway for each population at risk, as calculated from the maximum and average indicator chemical concentrations, respectively.

P.4.3 Site 4 Estimation of Total Chemical Intake for Each Exposure Route

Chronic daily intakes for pathways categorized as oral, dermal or inhalation routes were summed to yield total chronic daily intake via a particular route for a target population. Tables P-79 through P-83 present the total chemical intake for each exposure route.

P.4.4 Site 4 Characterization of Risk From Noncarcinogens

Tables P-84 through P-89 present the chronic hazard index values for each target population.

P.4.5 Site 4 Characterization of Risk From Potential Carcinogens

Tables P-90 through P-95 present the risk from potential carcinogens for each target population.

This page intentionally left blank.

9

TABLE P-65
MAXIMUM AND REPRESENTATIVE CHEMICAL CONCENTRATIONS AT SITE 4

Parameter	CAS Number	Ground Water (mg/L)			Surface Water (mg/L)			Sediment (mg/kg)			Soils at 0 to 2 Feet (mg/kg)			Soils Below 2 Feet (mg/kg)		
		Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed	Maximum Value	Representative Value	# Detected/ # Analyzed
Barium	7440-39-3	1.70E-01	1.30E-01	7/13	ND (b)	ND	0/7	8.37E-02	5.51E-02	7/7	9.17E-02	6.24E-02	6/6	8.56E-02	5.20E-02	9/9
Benzene	71-43-2	2.20E-02	1.26E-02	2/17	9.30E-01	2.23E-01	8/11	1.60E+01	4.64E+00	4/11	ND	ND	0/6	6.20E+00	2.09E+00	3/27
Cadmium	7784-42-9	3.70E-03	2.80E-03	2/13	ND	ND	0/7	1.30E-03	6.50E-04	1/7	1.57E-02	7.70E-03	6/6	8.56E-02	5.20E-02	9/9
Chlorobenzene	108-90-7	ND	ND	0/21	2.20E-03	1.89E-03	4/15	ND	ND	0/7	ND	ND	0/6	ND	ND	0/9
Chromium	7440-47-3	3.90E-03	2.74E-03	7/13	ND	ND	0/7	2.34E-02	1.53E-02	7/7	4.97E-02	2.90E-02	6/6	4.93E-02	3.21E-02	9/9
Trans-1,2 Dichloroethylene	540-59-0	5.80E-03	2.60E-03	1/17	5.30E-03	3.56E-03	5/11	ND	ND	0/11	ND	ND	0/6	ND	ND	0/27
Ethyl Benzene	100-41-4	ND	ND	0/13	1.50E-01	5.91E-02	4/7	4.00E+02	1.00E+02	5/11	ND	ND	0/6	1.20E+01	6.00E+00	1/27
Lead	7439-92-1	ND	ND	0/13	ND	ND	0/7	2.31E-02	1.37E-02	7/7	2.16E-02	8.00E-03	6/6	7.30E-03	4.09E-03	9/9
Toluene	108-88-3	ND	ND	0/17	2.30E-02	9.77E-03	3/11	5.40E+01	1.78E+01	8/11	3.30E-01	1.23E-01	4/6	2.50E+01	2.72E+00	13/27
1,1,1 Trichloroethane	71-55-6	ND	ND	0/17	1.90E-02	1.45E-02	2/11	ND	ND	0/11	ND	ND	0/6	ND	ND	0/27
Trichloroethylene	79-01-6	ND	ND	0/17	2.20E-02	8.23E-03	6/11	ND	ND	0/11	ND	ND	0/6	ND	ND	0/27
Xylenes	1330-20-7	2.70E-03	1.35E-03	1/17	1.02E+00	4.31E-01	5/11	6.90E+02	1.27E+02	8/11	ND	ND	0/6	3.15E+02	7.71E+01	5/27

a. CAS = Chemical Abstracts Service
b. ND = Not Detected

Source: Engineering-Science, Inc. and Dames & Moore (1987)

TABLE P-66

TOXICITY DATA FOR COMPOUNDS DETECTED AT SITE 4

Parameter	CAS (a) Number	Toxicologic Class	Severity Rating (RfV) (b)				Carcinogen Assessment Group (CAG) (c)		Toxicity Constants (d)			
			Oral Route		Inhalation Route		Oral Route	Inhalation Route	Noncarcinogens		Potential Carcinogens	
									Water ($\mu\text{g/l}$) (e)	Soil ($\mu\text{g/kg}$) (f)	Water ($\mu\text{g/l}$) (g)	Soil ($\mu\text{g/kg}$) (h)
Barium	7440-39-3	NC (g)	10		10		D	D	4.08E+00	2.04E-04	- (h)	-
Benzene	71-43-2	NC, PC (i)	5		10		A	A	1.17E-01	5.85E-06	7.71E-03	3.36E-07
Cadmium	7740-43-9	NC, PC	-		8		NA (j)	B1	NA	NA	NA	NA
Chlorobenzene	108-90-7	NC	4		1		D	D	1.43E-01	7.14E-06	-	-
Chromium	7440-47-3	NC, FC	NA		NA		NA	A	NA	NA	NA	NA
Trans-1,2 Dichloroethylene	540-59-0	NC	5		5		D	D	5.29E-02	2.65E-06	-	-
Ethyl Benzene	100-41-4	NC	4		4		D	D	1.10E-02	5.52E-07	-	-
Lead	7439-92-1	NC, PC	10		10		B2	B2	8.93E-01	4.46E-05	-	-
Toluene	108-88-3	NC	7		10		D	D	5.20E-03	2.60E-07	-	-
1,1,1 Trichloroethane	71-55-6	NC	2		2		D	D	7.33E-04	3.67E-08	-	-
Trichloroethylene	79-01-6	NC, PC	5		4		B2	B2	1.05E+00	5.26E-05	4.29E-03	2.14E-07
Xylenes	1330-20-7	NC	8		8		D	D	1.07E-01	5.33E-06	-	-

a. CAS = Chemical Abstracts Service

b. Rating Value = RfV = USEPA health effect rating value for noncarcinogens

c. Carcinogen Assessment Group = CAG = USEPA classification of carcinogenicity

d. Toxicity Constant = USEPA potency factor based on either carcinogenic or noncarcinogenic endpoints for a given medium

e. $\mu\text{g/l}$ = Water toxicity constantf. $\mu\text{g/kg}$ = Soil toxicity constant

g. NC = Noncarcinogenic effects

h. Not applicable to Parameter

i. PC = Potential Carcinogen

j. ND = No data available

Source: U.S. Environmental Protection Agency (1986a)

TABLE P-67
CT VALUES FOR NONCARCINOGENIC COMPOUNDS DETECTED AT SITE 4

Parameter	CAS (a) Number	Ground Water CT Value (b)		Surface Water CT Value		Sediment CT Value		CT Values for Soils			
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	0 to 2 Feet		Below 2 Feet	
								Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value
Barium	7440-39-3	6.94E-01	5.30E-01	0.00E+00	0.00E+00	1.71E-05	1.13E-05	1.87E-05	1.27E-05	1.75E-05	1.06E-05
Benzene	71-43-2	2.57E-03	1.47E-03	1.09E-01	2.61E-02	9.36E-05	2.71E-05	0.00E+00	0.00E+00	3.63E-05	1.22E-05
Cadmium	7740-43-9	-	-	-	-	-	-	-	-	-	-
Chlorobenzene	108-90-7	0.00E+00	0.00E+00	3.15E-04	2.71E-04	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Chromium	7440-47-3	-	-	-	-	-	-	-	-	-	-
Trans-1,2 Dichloroethylene	540-59-0	3.07E-04	1.38E-04	2.80E-04	1.88E-04	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	100-41-4	0.00E+00	0.00E+00	1.65E-03	6.50E-04	2.21E-04	5.52E-05	0.00E+00	0.00E+00	6.62E-06	3.31E-06
Lead	7439-92-1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.03E-06	6.13E-07	9.63E-07	3.57E-07	3.26E-07	1.82E-07
Toluene	108-88-3	0.00E+00	0.00E+00	1.20E-04	5.08E-05	1.40E-05	4.63E-06	8.58E-08	3.19E-08	6.50E-06	7.08E-07
1,1,1 Trichloroethane	71-55-6	0.00E+00	0.00E+00	1.39E-05	1.06E-05	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trichloroethylene	79-01-6	0.00E+00	0.00E+00	2.31E-02	8.64E-03	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	1330-20-7	2.89E-04	1.44E-04	1.09E-01	4.62E-02	3.68E-03	6.77E-04	0.00E+00	0.00E+00	1.69E-03	4.11E-04

a. CAS = Chemical Abstracts Service
b. CT Value = Concentration x Toxicity. CT values equaling zero are the result of nondetected compounds.
c. No toxicity data available.

TABLE P-68
CT VALUES FOR POTENTIALLY CARCINOGENIC COMPOUNDS DETECTED AT SITE 4

Parameter	CAS (a) Number	Ground Water CT Value (b)		Surface Water CT Value		Sediment CT Value		CT Values for Soils					
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	0 to 2 Feet		Below 2 Feet		Maximum Value	Represent- ative Value
								Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value		
Barium	7440-39-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Benzene	71-43-2	1.70E-04	9.71E-05	7.17E-03	1.72E-03	6.18E-06	1.79E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	2.39E-06	8.07E-07
Cadmium	7740-43-9	-	-	-	-	-	-	-	-	-	-	-	-
Chlorobenzene	108-90-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Chromium	7440-47-3	-	-	-	-	-	-	-	-	-	-	-	-
Trans-1,2 Dichloroethylene	540-59-0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	100-41-4	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Lead	7439-92-1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Toluene	108-88-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
1,1,1 Trichloroethane	71-55-6	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trichloroethylene	79-01-6	0.00E+00	0.00E+00	9.44E-05	3.53E-05	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	1330-20-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00

a. CAS = Chemical Abstracts Service
b. CT Value = Concentration x Toxicity. CT values equaling zero are the result of nondetected compounds.
c. No toxicity data available.

TABLE P-69
INDICATOR SCORES AND TENTATIVE RANKING FOR COMPOUNDS DETECTED AT SITE 4

Parameter	CAS (a) Number	Indicator Score for Noncarcinogenic Effects		Tentative Rank for Noncarcinogenic Effects		Indicator Score for Potential Carcinogens		Tentative Rank for Potential Carcinogens	
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value
Barium	7440-39-3	7.47E-01	5.65E-01	1	1				
Benzene	71-43-2	1.09E-01	2.62E-02	3	3	7.18E-03	1.72E-03	1	1
Cadmium	7740-43-9								
Chlorobenzene	108-90-7	3.15E-04	2.71E-04	7	7				
Chromium	7440-47-3								
Trans-1,2 Dichloroethylene	540-59-0	3.07E-04	1.88E-04	8	8				
Ethyl Benzene	100-41-4	1.88E-03	7.09E-04	6	6				
Lead	7439-92-1	2.32E-03	1.15E-03	5	5				
Toluene	108-88-3	1.40E-04	5.61E-05	9	9				
1,1,1 Trichloroethane	71-55-6	1.39E-05	1.06E-05	10	10				
Trichloroethylene	79-01-6	2.31E-02	8.64E-03	4	4	9.44E-05	3.53E-05	2	2
Xylenes	1330-20-7	1.14E-01	4.72E-02	2	2				

TABLE P-70

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF GROUND WATER AS DRINKING WATER
FOR ADULT ONSITE RESIDENTS OR WORKERS AT SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	1.70E-01	1.30E-01	5.00E-01	1.43E-02	2.43E-03	1.86E-03
Benzene	2.20E-02	1.26E-02	1.00E+00	2.86E-02	6.29E-04	3.60E-04
Cadmium	3.10E-03	2.80E-03	8.00E-02	2.29E-03	7.09E-06	6.40E-06
Chlorobenzene	ND (a)	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Chromium	3.90E-03	2.74E-03	5.00E-01	1.43E-02	5.57E-05	3.92E-05
Trans-1,2 Dichloroethylene	5.80E-03	2.60E-03	1.00E+00	2.86E-02	1.66E-04	7.43E-05
Ethyl Benzene	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Lead	ND	ND	4.00E-01	1.14E-02	0.00E+00	0.00E+00
Toluene	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
1,1,1 Trichloroethane	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Trichloroethylene	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Xylenes	2.70E-03	1.35E-03	1.00E+00	2.86E-02	7.71E-05	3.86E-05

a. ND = Not Detected

TABLE P-71

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF GROUND WATER AS DRINKING WATER
FOR ONSITE CHILD RESIDENTS AT SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	1.70E-01	1.30E-01	5.00E-01	1.07E-02	1.82E-03	1.39E-03
Benzene	2.20E-02	1.26E-02	1.00E+00	2.14E-02	4.71E-04	2.70E-04
Cadmium	3.10E-03	2.80E-03	8.00E-02	1.71E-03	5.31E-06	4.80E-06
Chlorobenzene	ND (a)	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Chromium	3.90E-03	2.74E-03	5.00E-01	1.07E-02	4.18E-05	2.94E-05
Trans-1,2 Dichloroethylene	5.80E-03	2.60E-03	1.00E+00	2.14E-02	1.24E-04	5.57E-05
Ethyl Benzene	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Lead	ND	ND	4.00E-01	8.57E-03	0.00E+00	0.00E+00
Toluene	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
1,1,1 Trichloroethane	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Trichloroethylene	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Xylenes	2.70E-03	1.35E-03	1.00E+00	2.14E-02	5.79E-05	2.89E-05

a. ND = Not Detected

TABLE P-72

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF SOIL AT DEPTH
FOR WORKERS AT SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	8.56E+01	5.20E+01	5.00E-01	8.39E-10	7.18E-08	4.36E-08
Benzene	6.20E+00	2.09E+00	1.00E+00	1.68E-09	1.04E-08	3.51E-09
Cadmium	1.15E+01	1.01E+01	8.00E-02	1.34E-10	1.54E-09	1.36E-09
Chlorobenzene	ND (a)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Chromium	4.93E+01	3.21E+01	5.00E-01	8.39E-10	4.13E-08	2.70E-08
Trans-1,2 Dichloroethylene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Ethyl Benzene	1.20E+01	6.00E+00	1.00E+00	1.68E-09	2.01E-08	1.01E-08
Lead	7.30E+00	4.09E+00	1.50E-01	2.52E-10	1.84E-09	1.03E-09
Toluene	2.50E+01	2.72E+00	1.00E+00	1.68E-09	4.19E-08	4.57E-09
1,1,1 Trichloroethane	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Trichloroethylene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Xylenes	3.15E+02	7.71E+01	1.00E+00	1.68E-09	5.28E-07	1.29E-07

a. ND = Not Detected

TABLE P-73

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE SOILS
FOR WORKERS AT SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	9.17E+01	6.24E+01	5.00E-01	8.39E-10	7.69E-08	5.23E-08
Benzene	ND (a)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Cadmium	1.57E+01	7.70E+00	8.00E-02	1.34E-10	2.11E-09	1.03E-09
Chlorobenzene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Chromium	4.97E+01	2.99E+01	5.00E-01	8.39E-10	4.17E-08	2.51E-08
Trans-1,2 Dichloroethylene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Ethyl Benzene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Lead	2.16E+01	8.00E+00	1.50E-01	2.52E-10	5.43E-09	2.01E-09
Toluene	3.30E-01	1.23E-01	1.00E+00	1.68E-09	5.54E-10	2.06E-10
1,1,1 Trichloroethane	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Trichloroethylene	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Xylenes	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-74
CURRENT EXPOSURE POINT INTAKE VIA VOLATILIZATION OF SURFACE WATER
FOR WORKERS AT SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Emission Rate From Water Surface (mg/hr)		Exposure Point Concentration (mg/m3)		Human Intake Factor (m3/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative	Upper Bound	Best Estimate	Upper Bound	Best Estimate		Upper Bound	Best Estimate
Barium	ND (a)	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Benzene	9.30E-01	2.23E-01	1.41E+00	3.38E-01	2.46E-07	5.91E-08	1.94E-03	4.79E-10	1.15E-10
Cadmium	ND	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Chlorobenzene	2.20E-03	1.89E-03	2.77E-03	2.39E-03	4.84E-10	4.17E-10	1.94E-03	9.41E-13	8.10E-13
Chromium	ND	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	5.30E-03	3.56E-03	7.21E-03	4.84E-03	1.26E-09	8.45E-10	1.94E-03	2.45E-12	1.64E-12
Ethyl Benzene	1.50E-01	5.91E-02	1.95E-01	7.69E-02	3.41E-08	1.34E-08	1.94E-03	6.62E-11	2.61E-11
Lead	ND	ND	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.94E-03	0.00E+00	0.00E+00
Toluene	2.30E-02	9.77E-03	3.21E-02	1.36E-02	5.61E-09	2.38E-09	1.94E-03	1.09E-11	4.63E-12
1,1,1 Trichloroethane	1.90E-02	1.45E-02	2.21E-02	1.68E-02	3.85E-09	2.94E-09	1.94E-03	7.49E-12	5.71E-12
Trichloroethylene	2.20E-02	8.23E-03	2.57E-02	9.63E-03	4.50E-09	1.68E-09	1.94E-03	8.74E-12	3.27E-12
Xylenes	1.02E+00	4.31E-01	1.33E+00	5.61E-01	2.32E-07	9.80E-08	1.94E-03	4.50E-10	1.90E-10

a. ND = Not Detected

TABLE P-75

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE WATER DURING RECREATION
FOR ADULTS NEAR SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	ND (a)	ND	5.00E-01	1.82E-05	0.00E+00	0.00E+00
Benzene	9.30E-01	2.23E-01	1.00E+00	3.63E-05	3.38E-05	8.11E-06
Cadmium	ND	ND	8.00E-02	2.91E-06	0.00E+00	0.00E+00
Chlorobenzene	2.20E-03	1.89E-03	1.00E+00	3.63E-05	8.00E-08	6.89E-08
Chromium	ND	ND	5.00E-01	1.82E-05	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	5.30E-03	3.56E-03	1.00E+00	3.63E-05	1.93E-07	1.29E-07
Ethyl Benzene	1.50E-01	5.91E-02	1.00E+00	3.63E-05	5.45E-06	2.15E-06
Lead	ND	ND	4.00E-01	1.45E-05	0.00E+00	0.00E+00
Toluene	2.30E-02	9.77E-03	1.00E+00	3.63E-05	8.36E-07	3.55E-07
1,1,1 Trichloroethane	1.90E-02	1.45E-02	1.00E+00	3.63E-05	6.91E-07	5.27E-07
Trichloroethylene	2.20E-02	8.23E-03	1.00E+00	3.63E-05	8.00E-07	2.99E-07
Xylenes	1.02E+00	4.31E-01	1.00E+00	3.63E-05	3.71E-05	1.57E-05

a. ND = Not Detected

TABLE P-76

CURRENT EXPOSURE POINT INTAKE VIA DERMAL CONTACT WITH SURFACE WATER DURING RECREATION
FOR ADULTS NEAR SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Permeability Constant (cm/hr)	Exposed Skin Area (cm ²)	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative				Upper Bound	Best Estimate
Barium	ND (a)	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Benzene	9.30E-01	2.23E-01	4.10E-01	1.82E+04	5.41E-03	5.03E-03	1.21E-03
Cadmium	ND	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Chlorobenzene	2.20E-03	1.89E-03	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Chromium	ND	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	5.30E-03	3.56E-03	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	1.50E-01	5.91E-02	1.00E-03	1.82E+04	1.32E-05	1.98E-06	7.80E-07
Lead	ND	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Toluene	2.30E-02	9.77E-03	9.00E-04	1.82E+04	1.19E-05	2.73E-07	1.16E-07
1,1,1 Trichloroethane	1.90E-02	1.45E-02	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Trichloroethylene	2.20E-02	8.23E-03	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Xylenes	1.02E+00	4.31E-01	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-77

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE WATER DURING RECREATION
FOR CHILDREN NEAR SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	ND (a)	ND	5.00E-01	9.54E-05	0.00E+00	0.00E+00
Benzene	9.30E-01	2.23E-01	1.00E+00	1.91E-04	1.77E-04	4.26E-05
Cadmium	ND	ND	8.00E-02	1.53E-05	0.00E+00	0.00E+00
Chlorobenzene	2.20E-03	1.89E-03	1.00E+00	1.91E-04	4.20E-07	3.62E-07
Chromium	ND	ND	5.00E-01	9.54E-05	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	5.30E-03	3.56E-03	1.00E+00	1.91E-04	1.01E-06	6.79E-07
Ethyl Benzene	1.50E-01	5.91E-02	1.00E+00	1.91E-04	2.86E-05	1.13E-05
Lead	ND	ND	4.00E-01	7.63E-05	0.00E+00	0.00E+00
Toluene	2.30E-02	9.77E-03	1.00E+00	1.91E-04	4.39E-06	1.86E-06
1,1,1 Trichloroethane	1.90E-02	1.45E-02	1.00E+00	1.91E-04	3.63E-06	2.77E-06
Trichloroethylene	2.20E-02	8.23E-03	1.00E+00	1.91E-04	4.20E-06	1.57E-06
Xylenes	1.02E+00	4.31E-01	1.00E+00	1.91E-04	1.95E-04	8.23E-05

a. ND = Not Detected

TABLE P-78

CURRENT EXPOSURE POINT INTAKE VIA DERMAL CONTACT WITH SURFACE WATER DURING RECREATION
FOR CHILDREN NEAR SITE 4

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Permeability Constant (cm/hr)	Exposed Skin Area (cm ²)	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative				Upper Bound	Best Estimate
Barium	ND (a)	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Benzene	9.30E-01	2.23E-01	4.10E-01	9.40E+03	1.47E-02	1.37E-02	3.28E-03
Cadmium	ND	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Chlorobenzene	2.20E-03	1.89E-03	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Chromium	ND	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	5.30E-03	3.56E-03	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Ethyl Benzene	1.50E-01	5.91E-02	1.00E-03	9.40E+03	3.59E-05	5.38E-06	2.12E-06
Lead	ND	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Toluene	2.30	9.77E-03	9.00E-04	9.40E+03	3.23E-05	7.43E-07	3.15E-07
1,1,1 Trichloroethane	1.90E-01	1.45E-02	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Trichloroethylene	2.20E-02	9.23E-03	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Xylenes	1.02E+00	9.23E-01	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00

a. ND = No Detected

TABLE P-79

FUTURE TOTAL CHRONIC INTAKE
ONSITE ADULT RESIDENTS OR WORKERS AT SITE 4

Indicator Chemical	Ingestion of Soil at Depth (mg/kg/day)		Ingestion of Ground Water (mg/kg/day)		Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Barium	7.18E-08	4.36E-08	2.43E-03	1.86E-03	2.43E-03	1.86E-03
Benzene	1.04E-08	3.51E-09	6.29E-04	3.60E-04	6.29E-04	3.60E-04
Cadmium	1.54E-09	1.36E-09	7.09E-06	6.40E-06	7.09E-06	6.40E-06
Chlorobenzene	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Chromium	4.13E-08	2.70E-08	5.57E-05	3.92E-05	5.58E-05	3.92E-05
Trans-1,2 Dichloroethylene	0.00E+00	0.00E+00	1.66E-04	7.43E-05	1.66E-04	7.43E-05
Ethyl Benzene	2.01E-08	1.01E-08	0.00E+00	0.00E+00	2.01E-08	1.01E-08
Lead	1.84E-09	1.03E-09	0.00E+00	0.00E+00	1.84E-09	1.03E-09
Toluene	4.19E-08	4.57E-09	0.00E+00	0.00E+00	4.19E-08	4.57E-09
1,1,1 Trichloroethane	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trichloroethylene	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Xylenes	5.28E-07	1.29E-07	7.71E-05	3.86E-05	7.77E-05	3.87E-05

TABLE P-80

FUTURE TOTAL CHRONIC INTAKE
ONSITE CHILD RESIDENTS AT SITE 4

Indicator Chemical	Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate
Barium	1.82E-03	1.39E-03
Benzene	4.71E-04	2.76E-04
Cadmium	5.31E-06	4.80E-06
Chlorobenzene	0.00E+00	0.00E+00
Chromium	4.18E-05	2.94E-05
Trans-1,2 Dichloroethylene	1.24E-04	5.57E-05
Ethyl Benzene	0.00E+00	0.00E+00
Lead	0.00E+00	0.00E+00
Toluene	0.00E+00	0.00E+00
1,1,1 Trichloroethane	0.00E+00	0.00E+00
Trichloroethylene	0.00E+00	0.00E+00
Xylenes	5.79E-05	2.89E-05

TABLE P-81

TOTAL CHRONIC INTAKE FOR WORKERS AT SITE 4
CURRENT

Indicator Chemical	Total Chronic Daily Intakes Oral Route (mg/kg/day)		Total Chronic Daily Intakes Inhalation Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Barium	7.69E-08	5.23E-08	0.00E+00	0.00E+00
Benzene	0.00E+00	0.00E+00	4.79E-10	1.15E-10
Cadmium	2.11E-09	1.03E-09	0.00E+00	0.00E+00
Chlorobenzene	0.00E+00	0.00E+00	9.41E-13	8.10E-13
Chromium	4.17E-08	2.51E-08	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	0.00E+00	0.00E+00	2.45E-12	1.64E-12
Ethyl Benzene	0.00E+00	0.00E+00	6.62E-11	2.61E-11
Lead	5.43E-09	2.01E-09	0.00E+00	0.00E+00
Toluene	5.54E-10	2.06E-10	1.09E-11	4.63E-12
1,1,1 Trichloroethane	0.00E+00	0.00E+00	7.49E-12	5.71E-12
Trichloroethylene	0.00E+00	0.00E+00	8.74E-12	3.27E-12
Xylenes	0.00E+00	0.00E+00	4.50E-10	1.90E-10

TABLE P-82

TOTAL CHRONIC INTAKE FOR ADULTS NEAR SITE 4
CURRENT

Indicator Chemical	Total Chronic Daily Intake Oral Route (mg/kg/day)		Total Chronic Daily Intake Dermal Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Barium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Benzene	3.38E-05	8.11E-06	5.03E-03	1.21E-03
Cadmium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Chlorobenzene	8.00E-08	6.89E-08	0.00E+00	0.00E+00
Chromium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	1.93E-07	1.29E-07	0.00E+00	0.00E+00
Ethyl Benzene	5.45E-06	2.15E-06	1.98E-06	7.80E-07
Lead	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Toluene	8.36E-07	3.55E-07	2.73E-07	1.16E-07
1,1,1 Trichloroethane	6.91E-07	5.27E-07	0.00E+00	0.00E+00
Trichloroethylene	8.00E-07	2.99E-07	0.00E+00	0.00E+00
Xylenes	3.71E-05	1.57E-05	0.00E+00	0.00E+00

TABLE P-83

TOTAL CHRONIC INTAKE FOR CHILDREN NEAR SITE 4
CURRENT

Indicator Chemical	Total Chronic Daily Intake Oral Route (mg/kg/day)		Total Chronic Daily Intake Dermal Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Barium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Benzene	1.77E-04	4.26E-05	1.37E-02	3.28E-03
Cadmium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Chlorobenzene	4.20E-07	3.62E-07	0.00E+00	0.00E+00
Chromium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Trans-1,2 Dichloroethylene	1.01E-06	6.79E-07	0.00E+00	0.00E+00
Ethyl Benzene	2.86E-05	1.13E-05	5.38E-06	2.12E-06
Lead	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Toluene	4.39E-06	1.86E-06	7.43E-07	3.15E-07
1,1,1 Trichloroethane	3.63E-06	2.77E-06	0.00E+00	0.00E+00
Trichloroethylene	4.20E-06	1.57E-06	0.00E+00	0.00E+00
Xylenes	1.95E-04	8.23E-05	0.00E+00	0.00E+00

TABLE P-84

CHRONIC HAZARD INDEX
 ONSITE ADULT RESIDENTS OR WORKERS AT SITE 4
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	2.43E-03	5.10E-02	4.76E-02	1.86E-03	5.10E-02	3.64E-02
Benzene	6.29E-04	NA	0.00E+00	3.60E-04	NA	0.00E+00
Cadmium	7.09E-06	2.90E-04	2.44E-02	6.40E-06	2.90E-04	2.21E-02
Chlorobenzene	0.00E+00	2.70E-02	0.00E+00	0.00E+00	2.70E-02	0.00E+00
Chromium	5.58E-05	5.00E-03	1.12E-02	3.92E-05	5.00E-03	7.84E-03
Trans-1,2 Dichloroethylene	1.66E-04	2.00E-02	8.29E-03	7.43E-05	2.00E-02	3.71E-03
Ethyl Benzene	2.01E-08	1.00E-01	2.01E-07	1.01E-08	1.00E-01	1.01E-07
Lead	1.84E-09	NA	0.00E+00	1.03E-09	NA	0.00E+00
Toluene	4.19E-08	3.00E-01	1.40E-07	4.57E-09	3.00E-01	1.52E-08
1,1,1 Trichloroethane	0.00E+00	9.00E-02	0.00E+00	0.00E+00	9.00E-02	0.00E+00
Trichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	7.77E-05	1.00E-02	7.77E-03	3.87E-05	1.00E-02	3.87E-03

TABLE P-85

CHRONIC HAZARD INDEX
 ONSITE CHILD RESIDENTS AT SITE 4
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	1.82E-03	5.10E-02	3.57E-02	1.39E-03	5.10E-02	2.73E-02
Benzene	4.71E-04	NA (c)	0.00E+00	2.70E-04	NA	0.00E+00
Cadmium	5.31E-06	2.90E-04	1.83E-02	4.80E-06	2.90E-04	1.66E-02
Chlorobenzene	0.00E+00	2.70E-02	0.00E+00	0.00E+00	2.70E-02	0.00E+00
Chromium	4.18E-05	5.00E-03	8.36E-03	2.94E-05	5.00E-03	5.88E-03
Trans-1,2 Dichloroethylene	1.24E-04	2.00E-02	6.21E-03	5.57E-05	2.00E-02	2.79E-03
Ethyl Benzene	0.00E+00	1.00E-01	0.00E+00	0.00E+00	1.00E-01	0.00E+00
Lead	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Toluene	0.00E+00	3.00E-01	0.00E+00	0.00E+00	3.00E-01	0.00E+00
1,1,1 Trichloroethane	0.00E+00	9.00E-02	0.00E+00	0.00E+00	9.00E-02	0.00E+00
Trichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	5.79E-05	1.00E-02	5.79E-03	2.89E-05	1.00E-02	2.89E-03

- a. CDI = Chronic Daily Intake
 b. AIC = Acceptable Chronic Intake
 c. NA = Data not available.

TABLE P-86

CHRONIC HAZARD INDEX FOR WORKERS ON SITE 4
CURRENT - UPPER BOUND

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	0.00E+00	1.40E-04	0.00E+00	7.69E-08	5.10E-02	1.51E-06
Benzene	4.79E-10	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Calcium	0.00E+00	NA	0.00E+00	2.11E-09	2.90E-04	7.26E-06
Chlorobenzene	9.41E-13	5.70E-03	1.65E-10	0.00E+00	2.70E-02	0.00E+00
Chromium	0.00E+00	NA	0.00E+00	4.17E-08	5.00E-03	8.34E-06
Trans-1,2 Dichloroethylene	2.45E-12	NA	0.00E+00	0.00E+00	2.00E-02	0.00E+00
Ethyl Benzene	6.62E-11	NA	0.00E+00	0.00E+00	1.00E-01	0.00E+00
Lead	0.00E+00	NA	0.00E+00	5.43E-09	NA	0.00E+00
Toluene	1.09E-11	1.50E+00	7.27E-12	5.54E-10	3.00E-01	1.85E-09
1,1,1 Trichloroethane	7.49E-12	6.30E+00	1.19E-12	0.00E+00	9.00E-02	0.00E+00
Trichloroethylene	8.74E-12	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	4.50E-10	4.00E-01	1.13E-09	0.00E+00	1.00E-02	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-87

CHRONIC HAZARD INDEX FOR WORKERS ON SITE 4
CURRENT - BEST ESTIMATE

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	0.00E+00	1.40E-04	0.00E+00	5.23E-08	5.10E-02	1.03E-06
Benzene	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Cadmium	1.15E-10	NA	0.00E+00	1.03E-09	2.90E-04	3.56E-06
Chlorobenzene	0.00E+00	5.70E-03	0.00E+00	0.00E+00	2.70E-02	0.00E+00
Chromium	8.10E-13	NA	0.00E+00	2.51E-08	5.00E-03	5.02E-06
Trans-1,2 Dichloroethylene	0.00E+00	NA	0.00E+00	0.00E+00	2.00E-02	0.00E+00
Ethyl Benzene	1.64E-12	NA	0.00E+00	0.00E+00	1.00E-01	0.00E+00
Lead	2.61E-11	NA	0.00E+00	2.01E-09	NA	0.00E+00
Toluene	0.00E+00	1.50E+00	0.00E+00	2.06E-10	3.00E-01	6.85E-10
1,1,1 Trichloroethane	4.53E-12	6.30E+00	7.35E-13	0.00E+00	9.00E-02	0.00E+00
Trichloroethylene	5.71E-12	NA	0.00E+00	0.00E+00	NA	0.00E+00
Xylenes	3.27E-12	4.00E-01	8.17E-12	0.00E+00	1.00E-02	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-88

CHRONIC HAZARD INDEX FOR ADULTS NEAR SITE 4
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	0.00E+00	5.10E-02	0.00E+00	0.00E+00	5.10E-02	0.00E+00
Benzene	3.38E-05	NA (c)	0.00E+00	8.11E-06	NA	0.00E+00
Cadmium	0.00E+00	2.90E-04	0.00E+00	0.00E+00	2.90E-04	0.00E+00
Chlorobenzene	8.00E-08	2.70E-02	2.96E-06	6.89E-08	2.70E-02	2.55E-06
Chromium	0.00E+00	5.00E-03	0.00E+00	0.00E+00	5.00E-03	0.00E+00
Trans-1,2 Dichloroethylene	1.93E-07	2.00E-02	9.63E-06	1.29E-07	2.00E-02	6.47E-06
Ethyl Benzene	5.45E-06	1.00E-01	5.45E-05	2.15E-06	1.00E-01	2.15E-05
Lead	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Toluene	8.36E-07	3.00E-01	2.79E-06	3.55E-07	3.00E-01	1.18E-06
1,1,1 Trichloroethane	6.91E-07	9.00E-02	7.67E-06	5.27E-07	9.00E-02	5.86E-06
Trichloroethylene	8.00E-07	NA	0.00E+00	2.99E-07	NA	0.00E+00
Xylenes	3.71E-05	1.00E-02	3.71E-03	1.57E-05	1.00E-02	1.57E-03

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-89

CHRONIC HAZARD INDEX FOR CHILDREN NEAR SITE 4
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	0.00E+00	5.10E-02	0.00E+00	0.00E+00	5.10E-02	0.00E+00
Benzene	1.77E-04	NA (c)	0.00E+00	4.26E-05	NA	0.00E+00
Cadmium	0.00E+00	2.90E-04	0.00E+00	0.00E+00	2.90E-04	0.00E+00
Chlorobenzene	4.20E-07	2.70E-02	1.55E-05	3.62E-07	2.70E-02	1.34E-05
Chromium	0.00E+00	5.00E-03	0.00E+00	0.00E+00	5.00E-03	0.00E+00
Trans-1,2 Dichloroethylene	1.01E-06	2.00E-02	5.06E-05	6.79E-07	2.00E-02	3.40E-05
Ethyl Benzene	2.86E-05	1.00E-01	2.86E-04	1.13E-05	1.00E-01	1.13E-04
Lead	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Toluene	4.39E-06	3.00E-01	1.46E-05	1.86E-06	3.00E-01	6.21E-06
1,1,1 Trichloroethane	3.63E-06	9.00E-02	4.03E-05	2.77E-06	9.00E-02	3.07E-05
Trichloroethylene	4.20E-06	NA	0.00E+00	1.57E-06	NA	0.00E+00
Xylenes	1.95E-04	1.00E-02	1.95E-02	8.23E-05	1.00E-02	8.23E-03

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. NA = Data not available.

TABLE P-90

RISK FROM POTENTIAL CARCINOGENS
 ONSITE ADULT RESIDENTS OR WORKERS AT SITE 4
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	2.43E-03	- (b)	0.00E+00	1.86E-03	-	0.00E+00
Benzene	6.29E-04	2.90E-02	1.82E-05	3.60E-04	2.90E-02	1.04E-05
Cadmium	7.09E-06	NA (c)	0.00E+00	6.40E-06	NA	0.00E+00
Chlorobenzene	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Chromium	5.58E-05	NA	0.00E+00	3.92E-05	NA	0.00E+00
Trans-1,2 Dichloroethylene	1.66E-04	-	0.00E+00	7.43E-05	-	0.00E+00
Ethyl Benzene	2.01E-08	-	0.00E+00	1.01E-08	-	0.00E+00
Lead	1.84E-09	NA	0.00E+00	1.03E-09	NA	0.00E+00
Toluene	4.19E-08	-	0.00E+00	4.57E-09	-	0.00E+00
1,1,1 Trichloroethane	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Trichloroethylene	0.00E+00	1.10E-02	0.00E+00	0.00E+00	1.10E-02	0.00E+00
Xylenes	7.77E-05	-	0.00E+00	3.87E-05	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-91

RISK FROM POTENTIAL CARCINOGENS
 ONSITE CHILD RESIDENTS AT SITE 4
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	1.82E-03	- (b)	0.00E+00	1.39E-03	-	0.00E+00
Benzene	4.71E-04	2.90E-02	.05	2.70E-04	2.90E-02	7.83E-06
Cadmium	5.31E-06	NA (c)	0.00E+00	4.80E-06	NA	0.00E+00
Chlorobenzene	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Chromium	4.18E-05	NA	0.00E+00	2.94E-05	NA	0.00E+00
Trans-1,2 Dichloroethylene	1.24E-04	-	0.00E+00	5.57E-05	-	0.00E+00
Ethyl Benzene	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Toluene	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
1,1,1 Trichloroethane	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Trichloroethylene	0.00E+00	1.10E-02	0.00E+00	0.00E+00	1.10E-02	0.00E+00
Xylenes	5.79E-05	-	0.00E+00	2.89E-05	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-92

RISK FROM POTENTIAL CARCINOGENS FOR WORKERS ON SITE 4
UPPER BOUND

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	0.00E+00	- (b)	0.00E+00	7.69E-08	-	0.00E+00
Benzene	4.79E-10	2.90E-02	1.39E-11	0.00E+00	2.90E-02	0.00E+00
Cadmium	0.00E+00	6.10E+00	0.00E+00	2.11E-09	NA (c)	0.00E+00
Chlorobenzene	9.41E-13	-	0.00E+00	0.00E+00	-	0.00E+00
Chromium	0.00E+00	4.10E+01	0.00E+00	4.17E-08	NA	0.00E+00
Trans-1,2 Dichloroethylene	2.45E-12	-	0.00E+00	0.00E+00	-	0.00E+00
Ethyl Benzene	6.62E-11	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	0.00E+00	NA	0.00E+00	5.43E-09	NA	0.00E+00
Toluene	1.09E-11	-	0.00E+00	5.54E-10	-	0.00E+00
1,1,1 Trichloroethane	7.49E-12	-	0.00E+00	0.00E+00	-	0.00E+00
Trichloroethylene	3.74E-12	1.30E-02	1.14E-13	0.00E+00	1.10E-02	0.00E+00
Xylenes	4.50E-10	-	0.00E+00	0.00E+00	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-93

RISK FROM POTENTIAL CARCINOGENS FOR WORKERS ON SITE 4
BEST ESTIMATE

Indicator Chemical	Inhalation-Adult			Oral-Adult		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	0.00E+00	- (b)	0.00E+00	5.23E-08	-	0.00E+00
Benzene	1.15E-10	2.90E-02	3.33E-12	0.00E+00	2.90E-02	0.00E+00
Cadmium	0.00E+00	6.10E+00	0.00E+00	1.03E-09	NA (c)	0.00E+00
Chlorobenzene	8.10E-13	-	0.00E+00	0.00E+00	-	0.00E+00
Chromium	0.00E+00	4.10E+01	0.00E+00	2.51E-08	NA	0.00E+00
Trans-1,2 Dichloroethylene	1.64E-12	-	0.00E+00	0.00E+00	-	0.00E+00
Ethyl Benzene	2.61E-11	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	0.00E+00	NA	0.00E+00	2.01E-09	NA	0.00E+00
Toluene	4.63E-12	-	0.00E+00	2.06E-10	-	0.00E+00
1,1,1 Trichloroethane	5.71E-12	-	0.00E+00	0.00E+00	-	0.00E+00
Trichloroethylene	3.27E-12	1.30E-02	4.25E-14	0.00E+00	1.10E-02	0.00E+00
Xylenes	1.90E-10	-	0.00E+00	0.00E+00	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-94

RISK FROM POTENTIAL CARCINOGENS FOR ADULTS NEAR SITE 4
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	0.00E+00	- (b)	0.00E+00	0.00E+00	-	0.00E+00
Benzene	3.38E-05	2.90E-02	9.80E-07	8.11E-06	2.90E-02	2.35E-07
Cadmium	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Chlorobenzene	8.00E-08	-	0.00E+00	6.89E-08	-	0.00E+00
Chromium	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Trans-1,2 Dichloroethylene	1.93E-07	-	0.00E+00	1.29E-07	-	0.00E+00
Ethyl Benzene	5.45E-06	-	0.00E+00	2.15E-06	-	0.00E+00
Lead	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Toluene	8.36E-07	-	0.00E+00	3.55E-07	-	0.00E+00
1,1,1 Trichloroethane	6.91E-07	-	0.00E+00	5.27E-07	-	0.00E+00
Trichloroethylene	8.00E-07	1.10E-02	8.80E-09	2.99E-07	1.10E-02	3.29E-09
Xylenes	3.71E-05	-	0.00E+00	1.57E-05	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound.

c. NA = Data not available.

TABLE P-95
RISK FROM POTENTIAL CARCINOGENS FOR CHILDREN NEAR SITE 4
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	0.00E+00	- (b)	0.00E+00	0.00E+00	-	0.00E+00
Benzene	1.77E-04	2.90E-02	5.15E-06	4.26E-05	2.90E-02	1.24E-06
Cadmium	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Chlorobenzene	4.20E-07	-	0.00E+00	3.62E-07	-	0.00E+00
Chromium	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Trans-1,2 Dichloroethylene	1.01E-06	-	0.00E+00	6.79E-07	-	0.00E+00
Ethyl Benzene	2.86E-05	-	0.00E+00	1.13E-05	-	0.00E+00
Lead	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Toluene	4.39E-06	-	0.00E+00	1.86E-06	-	0.00E+00
1,1,1 Trichloroethane	3.63E-06	-	0.00E+00	2.77E-06	-	0.00E+00
Trichloroethylene	4.20E-06	1.10E-02	4.62E-08	1.57E-06	1.10E-02	1.73E-08
Xylenes	1.95E-04	-	0.00E+00	8.23E-05	-	0.00E+00

a. CDI = Chronic Daily Intake
b. Not applicable to this compound.
c. NA = Data not available.

This page intentionally left blank.

SECTION P.5
SITE 8 RISK ASSESSMENT TABLES

This page intentionally left blank.

SECTION P.5

SITE 8 RISK ASSESSMENT TABLES

This section contains the risk assessment worksheets for Site 8.

P.5.1 Site 8 Indicator Chemical Selection

Data used in the selection of indicator chemicals were compiled from both the Remedial Investigation performed at the Base by ES in 1988 and the 1986 study (Dames & Moore, 1987). These data are summarized in Table P-96, while Tables P-97 through P-100 step through the USEPA selection process.

P.5.2 Site 8 Estimation of Chemical Intake for Each Pathway

Tables P-101 through P-108 summarize the upper bound and best estimate chronic daily intakes from each potential pathway for each population at risk, as calculated from the maximum and average chemical concentrations, respectively.

P.5.3 Site 8 Estimation of Total Chemical Intake for Each Exposure Route

Chronic daily intakes for pathways categorized as oral, dermal or inhalation routes are summed to yield total chronic daily intake via a particular route for a target population. Tables P-109 through P-113 present the total chemical intake for each exposure route.

P.5.4 Site 8 Characterization of Risk from Noncarcinogens

Tables P-114 through P-118 present the chronic hazard values for each target population.

P.5.5 Site 8 Characterization of Risk From Potential Carcinogens

Tables P-119 through P-123 present the risk from potential carcinogens for each target population.

This page intentionally left blank.

TABLE P-96
MAXIMUM AND REPRESENTATIVE CHEMICAL CONCENTRATIONS AT SITE 8

Parameter	CAS (a) Number	Ground Water (mg/L)			Surface Water (mg/L)			Sediment (mg/kg)			Soils at 0 to 2 Feet (mg/kg)			Soils Below 2 Feet (mg/kg)		
		Maximum Value	Represent- ative Value	No. Detected/ No. Analyzed	Maximum Value	Represent- ative Value	No. Detected/ No. Analyzed	Maximum Value	Represent- ative Value	No. Detected/ No. Analyzed	Maximum Value	Represent- ative Value	No. Detected/ No. Analyzed	Maximum Value	Represent- ative Value	No. Detected/ No. Analyzed
Bariem	7440-39-3	1.00E+00	2.88E-01	5/11	ND (b)	ND	0/3	1.00E+00	7.65E-02	6/6	2.00E-01	7.70E-02	8/8	8.50E-02	4.73E-02	19/19
Cadmium	7740-43-9	ND	ND	0/11	ND	ND	0/3	ND	ND	0/6	1.01E-02	8.43E-03	6/8	1.44E-02	1.06E-02	12/19
Chromium	7440-47-3	5.20E-01	1.16E-01	8/11	ND	ND	0/3	4.8E-02	2.40E-02	6/6	4.00E-02	2.82E-02	8/8	4.34E-02	2.88E-02	19/19
4,4' DDO	72-54-8	ND	ND	0/11	9.00E-03	6.00E-03	2/5	ND	ND	0/6	1.80E-01	4.88E-02	6/36	ND	ND	0/20
4,4' DDE	72-55-9	ND	ND	0/11	ND	ND	0/5	ND	ND	0/6	1.30E-01	4.32E-02	5/36	ND	ND	0/20
4,4' DDT	50-29-3	ND	ND	0/11	1.00E-02	5.00E-03	1/5	ND	ND	0/6	1.50E+00	2.46E-01	8/36	ND	ND	0/20
Delta BHC	319-86-8	ND	ND	0/8	ND	ND	0/3	ND	ND	1/6	ND	ND	0/34	ND	ND	0/13
Dieldrin	60-57-1	ND	ND	0/8	ND	ND	0/3	ND	ND	0/6	1.00E-03	5.00E-04	1/34	ND	ND	0/13
Endosulfan I	115-29-7	ND	ND	0/8	ND	ND	0/3	4.00E-02	4.00E-02	1/6	ND	ND	0/36	ND	ND	0/13
Lead	7439-92-1	ND	ND	0/11	4.00E-02	3.50E-02	2/3	1.90E-01	4.66E-02	5/6	1.80E-02	1.02E-02	7/8	1.14E-02	6.16E-03	12/19
PCB's	1336-36-3	ND	ND	0/8	ND	ND	0/3	2.30E+00	2.30E+00	1/6	3.30E-01	3.30E-01	1/36	ND	ND	0/20
Toluene	108-88-3	ND	ND	0/11	6.50E-03	3.25E-03	1/5	4.10E-01	4.10E-01	1/6	1.40E+00	2.85E-01	7/9	7.20E-01	1.10E-01	12/20
Xylenes	1330-20-7	ND	ND	0/11	ND	ND	0/5	ND	ND	0/6	ND	ND	0/9	5.60E-03	2.30E-03	1/20

a. CAS = Chemical Abstracts Service

b. ND = Not Detected

Source: Engineering-Science, Inc. (1988) and Dames & Moore (1987)

TABLE P-97

TOXICITY DATA FOR COMPOUNDS DETECTED AT SITE 8

Parameter	CAS (a) Number	Toxicologic Class	Severity Rating (RVE) (b)		Carcinogen Assessment Group (CAG) (c)		Toxicity Constants (d)			
							Noncarcinogens		Potential Carcinogens	
			Oral Route	Inhalation Route	Oral Route	Inhalation Route	Water (WT) (e) (L/mg)	Soil (ST) (f) (kg/mg)	Water (WT) (L/mg)	Soil (ST) (kg/mg)
Barium	7440-39-3	NC (g)	10	10	D	D	4.08E+00	2.04E-04	- (h)	-
Cadmium	7740-43-9	NC, PC (i)	10	8	-	B1	4.45E+00	2.23E-04	-	-
Chromium	7440-47-3	NC, PC	-	8	-	A	NA (j)	NA	-	-
4,4' DDD	72-54-8	NC, PC	-	-	B2	B2	NA	NA	3.71E-02	1.86E-06
4,4' DDE	72-55-9	NC, PC	-	-	B2	B2	NA	NA	1.13E-01	5.64E-06
4,4' DDT	50-29-3	NC, PC	-	-	B2	B2	NA	NA	1.59E-01	7.97E-06
Delta BHC	319-86-8	NC	-	-	D	D	NA	NA	-	-
Dieldrin	60-57-1	NC, PC	-	-	B2	B2	NA	NA	3.66E+00	1.83E-04
Endosulfan I	115-29-7	NC	-	-	D	D	NA	NA	-	-
Lead	7439-92-1	NC, PC	10	10	B2	B2	8.93E-01	4.44E-05	NA	NA
PCB's	1336-36-3	NC, PC	-	-	B2	B2	NA	NA	5.71E-01	2.86E-05
Toluene	108-88-3	NC	7	10	-	-	5.20E-03	2.60E-07	-	-
Xylenes	1330-20-7	NC	8	8	-	-	1.07E-01	5.33E-06	-	-

a. CAS = Chemical Abstracts Service

b. Rating Value = RVE = USEPA health effect rating value for noncarcinogens

c. Carcinogen Assessment Group = CAG = USEPA classification of carcinogenicity

d. Toxicity Constant = USEPA potency factor based on either carcinogenic or noncarcinogenic endpoints for a given medium

e. WT = Water toxicity constant

f. ST = Soil toxicity constant

g. NC = Noncarcinogenic effects

h. Not applicable to parameter

i. PC = Potential Carcinogen

j. NA = No data available

Source: U.S. Environmental Protection Agency (1986a)

TABLE P-98

CT VALUES FOR NONCARCINOGENIC COMPOUNDS DETECTED AT SITE 8

Parameter	CAS (a) Number	Ground Water CT Value (b)		Surface Water CT Value		Sediment CT Value		CT Values for Soils			
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	0 to 2 Feet Represent- ative Value	Maximum Value	Below 2 Feet Represent- ative Value
Barium	7440-39-3	4.08E+00	1.18E+00	0.00E+00	0.00E+00	2.04E-04	1.56E-05	4.08E-05	1.57E-05	1.73E-05	9.65E-06
Cadmium	7740-43-9	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	2.25E-06	1.88E-06	3.21E-06	2.36E-06
Chromium	7440-47-3	-	-	-	-	-	-	-	-	-	-
4,4' DDD	72-54-8	-	-	-	-	-	-	-	-	-	-
4,4' DDE	72-55-9	-	-	-	-	-	-	-	-	-	-
4,4' DDT	50-29-3	-	-	-	-	-	-	-	-	-	-
Delta BHC	319-86-8	-	-	-	-	-	-	-	-	-	-
Dieldrin	60-57-1	-	-	-	-	-	-	-	-	-	-
Endosulfan I	115-29-7	-	-	-	-	-	-	-	-	-	-
Lead	7439-92-1	0.00E+00	0.00E+00	3.57E-02	3.13E-02	8.47E-06	2.08E-06	6.03E-07	4.56E-07	5.08E-07	2.75E-07
PCB's	1336-36-3	-	-	-	-	-	-	-	-	-	-
Toluene	108-88-3	0.00E+00	0.00E+00	3.38E-05	1.69E-05	1.07E-05	1.07E-05	3.64E-07	7.41E-08	1.87E-07	2.86E-08
Xylenes	1330-20-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	2.98E-08	1.49E-08

a. CAS = Chemical Abstracts Service

b. CT Value = Concentration x Toxicity. CT values equaling zero are the result of nondetected compounds.

c. No toxicity data available.

TABLE P-99

CT VALUES FOR POTENTIALLY CARCINOGENIC COMPOUNDS DETECTED AT SITE 8

Parameter	CAS (a) Number	CT Values for Soils									
		Ground Water CT Value (b)		Surface Water CT Value		Sediment CT Value		0 to 2 Feet		Below 2 Feet	
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value
Barium	7440-39-3	-	-	-	-	-	-	-	-	-	-
Cadmium	7740-43-9	-	-	-	-	-	-	-	-	-	-
Chromium	7440-47-3	-	-	-	-	-	-	-	-	-	-
4,4' DDD	72-54-8	0.00E+00	0.00E+00	3.34E-04	2.23E-04	0.00E+00	0.00E+00	3.35E-07	9.08E-08	0.00E+00	0.00E+00
4,4' DDE	72-55-9	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	7.33E-07	2.44E-07	0.00E+00	0.00E+00
4,4' DDT	50-29-3	0.00E+00	0.00E+00	1.59E-03	7.95E-04	0.00E+00	0.00E+00	1.20E-05	1.96E-06	0.00E+00	0.00E+00
Delta BHC	319-86-8	-	-	-	-	-	-	-	-	-	-
Dieldrin	60-57-1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.83E-07	9.15E-08	0.00E+00	0.00E+00
Endosulfan I	115-29-7	-	-	-	-	-	-	-	-	-	-
Lead	7439-92-1	-	-	-	-	-	-	-	-	-	-
PCB's	1336-36-3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	6.58E-05	6.58E-05	9.44E-06	9.44E-06	0.00E+00	0.00E+00
Toluene	108-88-3	-	-	-	-	-	-	-	-	-	-
Xylenes	1330-20-7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00

a. CAS = Chemical Abstracts Service

b. CT Value = Concentration x Toxicity. CT values equaling zero are the result of nondetected compounds.

c. No toxicity data available.

TABLE P-100

INDICATOR SCORES AND TENTATIVE RANKING FOR COMPOUNDS DETECTED AT SITE 8

Parameter	CAS (a) Number	Indicator Score for Noncarcinogenic Effects		Tentative Rank for Noncarcinogenic Effects		Indicator Score for Potential Carcinogens		Tentative Rank for Potential Carcinogens	
		Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value	Maximum Value	Represent- ative Value
Barium	7440-39-3	4.34E+00	1.22E+00	1	1				
Cadmium	7740-43-9	5.46E-03	4.24E-03	3	3				
Chromium	7440-47-3								
4,4' DDD	72-54-8					3.34E-04	2.23E-04	2	2
4,4' DDE	72-55-9					7.33E-07	2.44E-07	4	4
4,4' DDT	50-29-3					1.60E-03	7.97E-04	1	1
Delta BHC	319-86-8								
Dieldrin	60-57-1								
Endosulfan I	115-29-7					1.83E-07	9.15E-08	5	5
Lead	7439-92-1	4.51E-02	3.41E-02	2	2				
PCB's	1336-36-3								
Toluene	108-88-3	4.50E-05	2.77E-05	4	4	7.52E-05	7.52E-05	3	3
Xylenes	1330-20-7	2.98E-08	1.49E-08	5	5				

a. CAS = Chemical Abstracts Service

TABLE P-101

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF SOIL AT DEPTH
FOR WORKERS AT SITE 8

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	8.50E+01	4.73E+01	5.00E-01	8.39E-10	7.13E-08	3.97E-08
Cadmium	1.44E+01	1.06E+01	8.00E-02	1.34E-10	1.93E-09	1.42E-09
Chromium	4.34E-02	2.88E-02	5.00E-01	8.39E-10	3.64E-11	2.42E-11
4,4' DDT	ND (b)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Dieldrin	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Endosulfan I	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Lead	2.75E+00	6.16E+00	1.50E-01	2.52E-10	6.92E-10	1.55E-09
Toluene	7.20E-01	1.10E-01	1.00E+00	1.68E-09	1.21E-09	1.85E-10
Xylenes	5.60E-03	2.80E-03	1.00E+00	1.68E-09	9.39E-12	4.70E-12

a. ND = Not Detected

TABLE P-102

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF GROUND WATER AS DRINKING WATER
FOR ADULT ONSITE RESIDENTS OR WORKERS AT SITE 8

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	1.00E+00	2.88E-01	5.00E-01	1.43E-02	1.43E-02	4.11E-03
Cadmium	ND (a)	ND	8.00E-02	2.29E-03	0.00E+00	0.00E+00
Chromium	5.20E-01	1.16E-01	5.00E-01	1.43E-02	7.43E-03	1.66E-03
4,4' DDT	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Dieldrin	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Endosulfan I	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Lead	ND	ND	1.50E-01	4.29E-03	0.00E+00	0.00E+00
Toluene	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00
Xylenes	ND	ND	1.00E+00	2.86E-02	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-103

FUTURE EXPOSURE POINT INTAKE VIA INGESTION OF GROUND WATER AS DRINKING WATER
FOR CHILD RESIDENTS AT SITE 8

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	1.00E+00	2.88E-01	5.00E-01	1.07E-02	1.07E-02	3.09E-03
Cadmium	ND (a)	ND	8.00E-02	1.71E-03	0.00E+00	0.00E+00
Chromium	5.20E-01	1.16E-01	5.00E-01	1.07E-02	5.57E-03	1.24E-03
4,4' DDT	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Dieldrin	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Endosulfan I	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Lead	ND	ND	4.00E-01	8.57E-03	0.00E+00	0.00E+00
Toluene	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00
Xylenes	ND	ND	1.00E+00	2.14E-02	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-104

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE SOILS
FOR WORKERS AT SITE 8

Indicator Chemical	Indicator Chemical Concentration (mg/kg)		Fraction Absorbed Into Body	Human Intake Factor (kg/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	2.00E+02	7.70E+01	5.00E-01	8.39E-10	1.68E-07	6.45E-08
Cadmium	1.01E+01	8.43E+00	8.00E-02	1.34E-10	1.36E-09	1.13E-09
Chromium	4.00E-02	2.80E-02	5.00E-01	8.39E-10	3.35E-11	2.35E-11
4,4' DDT	1.50E+00	2.46E-01	1.00E+00	1.68E-09	2.52E-09	4.13E-10
Dieldrin	1.00E-03	5.00E-04	1.00E+00	1.68E-09	1.68E-12	8.39E-13
Endosulfan I	ND (a)	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00
Lead	1.80E+01	1.02E+01	1.50E-01	2.52E-10	4.53E-09	2.57E-09
Toluene	1.40E+00	2.85E-01	1.00E+00	1.68E-09	2.35E-09	4.78E-10
Xylenes	ND	ND	1.00E+00	1.68E-09	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-105

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE WATER DURING RECREATION
FOR ADULTS NEAR SITE 8

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	ND (a)	ND	5.00E-01	1.82E-05	0.00E+00	0.00E+00
Cadmium	ND	ND	8.00E-02	2.91E-06	0.00E+00	0.00E+00
Chromium	ND	ND	5.00E-01	1.82E-05	0.00E+00	0.00E+00
4,4' DDT	1.00E-02	5.00E-03	1.00E+00	3.63E-05	3.63E-07	1.82E-07
Dieldrin	ND	ND	1.00E+00	3.63E-05	0.00E+00	0.00E+00
Endosulfan I	ND	ND	1.00E+00	3.63E-05	0.00E+00	0.00E+00
Lead	4.00E-02	3.50E-02	1.50E-01	5.45E-06	2.18E-07	1.91E-07
Toluene	6.50E-03	3.25E-03	1.00E+00	3.63E-05	2.36E-07	1.18E-07
Xylenes	ND	ND	1.00E+00	3.63E-05	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-106

CURRENT EXPOSURE POINT INTAKE VIA DERMAL CONTACT WITH SURFACE WATER DURING RECREATION
FOR ADULTS NEAR SITE 8

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Permeability Constant (cm/hr)	Exposed Skin Area (cm ²)	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative				Upper Bound	Best Estimate
Barium	ND (a)	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Cadmium	ND	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Chromium	ND	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
4,4' DDT	1.00E-02	5.00E-03	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Dieldrin	ND	ND	5.10E-04	1.82E+04	6.73E-06	0.00E+00	0.00E+00
Endosulfan I	ND	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Lead	4.00E-02	3.50E-02	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00
Toluene	6.50E-03	3.25E-03	9.00E-04	1.82E+04	1.19E-05	7.72E-08	3.86E-08
Xylenes	ND	ND	NA	1.82E+04	0.00E+00	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-107

CURRENT EXPOSURE POINT INTAKE VIA INGESTION OF SURFACE WATER DURING RECREATION
FOR CHILDREN NEAR SITE 8

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Fraction Absorbed	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative			Upper Bound	Best Estimate
Barium	ND (a)	ND	5.00E-01	9.54E-05	0.00E+00	0.00E+00
Cadmium	ND	ND	8.00E-02	1.53E-05	0.00E+00	0.00E+00
Chromium	ND	ND	5.00E-01	9.54E-05	0.00E+00	0.00E+00
4,4' DDT	1.00E-02	5.00E-03	1.00E+00	1.91E-04	1.91E-06	9.54E-07
Dieldrin	ND	ND	1.00E+00	1.91E-04	0.00E+00	0.00E+00
Endosulfan I	ND	ND	1.00E+00	1.91E-04	0.00E+00	0.00E+00
Lead	4.00E-02	3.50E-02	4.00E-01	7.63E-05	3.05E-06	2.67E-06
Toluene	6.50E-03	3.25E-03	1.00E+00	1.91E-04	1.24E-06	6.20E-07
Xylenes	ND	ND	1.00E+00	1.91E-04	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-108

CURRENT EXPOSURE POINT INTAKE VIA DERMAL CONTACT WITH SURFACE WATER DURING RECREATION
FOR CHILDREN NEAR SITE 8

Indicator Chemical	Indicator Chemical Concentration (mg/L)		Permeability Constant (cm/hr)	Exposed Skin Area (cm ²)	Human Intake Factor (L/day/kg)	Chronic Daily Intake (mg/kg/day)	
	Maximum	Representative				Upper Bound	Best Estimate
Barium	ND (a)	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Cadmium	ND	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Chromium	ND	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
4,4' DDT	1.00E-02	5.00E-03	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Dieldrin	ND	ND	5.10E-04	9.40E+03	1.83E-05	0.00E+00	0.00E+00
Endosulfan I	ND	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Lead	4.00E-02	3.50E-02	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00
Toluene	6.50E-03	3.25E-03	9.00E-04	9.40E+03	3.23E-05	2.10E-07	1.05E-07
Xylenes	ND	ND	NA	9.40E+03	0.00E+00	0.00E+00	0.00E+00

a. ND = Not Detected

TABLE P-109

FUTURE TOTAL CHRONIC INTAKE
ONSITE ADULT RESIDENTS OR WORKERS AT SITE 8

Indicator Chemical	Ingestion of Soil at Depth (mg/kg/day)		Ingestion of Ground Water (mg/kg/day)		Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Barium	7.13E-08	3.97E-08	1.43E-02	4.11E-03	1.43E-02	4.11E-03
Cadmium	1.93E-09	1.42E-09	0.00E+00	0.00E+00	1.93E-09	1.42E-09
Chromium	3.64E-11	2.42E-11	7.43E-03	1.66E-03	7.43E-03	1.66E-03
4,4' DDT	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Dieldrin	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Endosulfan I	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Lead	6.92E-10	1.55E-09	0.00E+00	0.00E+00	6.92E-10	1.55E-09
Toluene	1.21E-09	1.85E-10	0.00E+00	0.00E+00	1.21E-09	1.85E-10
Xylenes	9.39E-12	4.70E-12	0.00E+00	0.00E+00	9.39E-12	4.70E-12

TABLE P-110

FUTURE TOTAL CHRONIC INTAKE
ONSITE CHILD RESIDENTS AT SITE 8

Indicator Chemical	Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate
Barium	1.07E-02	3.09E-03
Cadmium	0.00E+00	0.00E+00
Chromium	5.57E-03	1.24E-03
4,4' DDT	0.00E+00	0.00E+00
Dieldrin	0.00E+00	0.00E+00
Endosulfan I	0.00E+00	0.00E+00
Lead	0.00E+00	0.00E+00
Toluene	0.00E+00	0.00E+00
Xylenes	0.00E+00	0.00E+00

TABLE P-111

TOTAL CHRONIC INTAKE FOR WORKERS AT SITE 8
CURRENT

Indicator Chemical	Total Chronic Daily Intakes Ingestion Route (mg/kg/day)	
	Upper Bound	Best Estimate
Barium	1.68E-07	6.45E-08
Cadmium	1.36E-09	1.13E-09
Chromium	3.35E-11	2.35E-11
4,4' DDT	2.52E-09	4.13E-10
Dieldrin	1.68E-12	8.39E-13
Endosulfan I	0.00E+00	0.00E+00
Lead	4.53E-09	2.57E-09
Toluene	2.35E-09	4.78E-10
Xylenes	0.00E+00	0.00E+00

TABLE P-112

TOTAL CHRONIC INTAKE FOR ADULTS NEAR SITE 8
CURRENT

Indicator Chemical	Total Chronic Daily Intake Oral Route (mg/kg/day)		Total Chronic Daily Intake Dermal Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Barium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Cadmium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Chromium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
4,4' DDT	3.63E-07	1.82E-07	0.00E+00	0.00E+00
Dieldrin	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Endosulfan I	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Lead	2.18E-07	1.91E-07	0.00E+00	0.00E+00
Toluene	2.36E-07	1.18E-07	7.72E-08	3.86E-08
Xylenes	0.00E+00	0.00E+00	0.00E+00	0.00E+00

TABLE P-113

TOTAL CHRONIC INTAKE FOR CHILDREN NEAR SITE 8
CURRENT

Indicator Chemical	Total Chronic Daily Intake Oral Route (mg/kg/day)		Total Chronic Daily Intake Dermal Route (mg/kg/day)	
	Upper Bound	Best Estimate	Upper Bound	Best Estimate
Barium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Cadmium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Chromium	0.00E+00	0.00E+00	0.00E+00	0.00E+00
4,4' DDT	1.91E-06	9.54E-07	0.00E+00	0.00E+00
Dieldrin	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Endosulfan I	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Lead	3.05E-06	2.67E-06	0.00E+00	0.00E+00
Toluene	1.24E-06	6.20E-07	2.10E-07	1.05E-07
Xylenes	0.00E+00	0.00E+00	0.00E+00	0.00E+00

TABLE P-114

CHRONIC HAZARD INDEX
 ONSITE ADULT RESIDENTS OR WORKERS AT SITE 8
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	1.43E-02	5.10E-02	2.80E-01	4.11E-03	5.10E-02	8.07E-02
Cadmium	1.93E-09	2.90E-04	6.66E-06	1.42E-09	2.90E-04	4.90E-06
Chromium	7.43E-03	5.00E-03	1.49E+00	1.66E-03	5.00E-03	3.31E-01
4,4' DDT	0.00E+00	5.00E-04	0.00E+00	0.00E+00	5.00E-04	0.00E+00
Dieldrin	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Endosulfan I	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Lead	6.92E-10	NA (c)	0.00E+00	1.55E-09	NA	0.00E+00
Toluene	1.21E-09	3.00E-01	4.03E-09	1.85E-10	3.00E-01	6.15E-10
Xylenes	9.39E-12	1.00E-02	9.39E-10	4.70E-12	1.00E-02	4.70E-10

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. Data not available

TABLE P-115

CHRONIC HAZARD INDEX
ONSITE CHILD RESIDENTS AT SITE 8
FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	1.07E-02	5.10E-02	2.10E-01	3.09E-03	5.10E-02	6.05E-02
Cadmium	0.00E+00	2.90E-04	0.00E+00	0.00E+00	2.90E-04	0.00E+00
Chromium	5.57E-03	5.00E-03	1.11E+00	1.24E-03	5.00E-03	2.49E-01
4,4' DDT	0.00E+00	5.00E-04	0.00E+00	0.00E+00	5.00E-04	0.00E+00
Dieldrin	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Endosulfan I	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Lead	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Toluene	0.00E+00	3.00E-01	0.00E+00	0.00E+00	3.00E-01	0.00E+00
Xylenes	0.00E+00	1.00E-02	0.00E+00	0.00E+00	1.00E-02	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. Data not available

TABLE P-116

CHRONIC HAZARD INDEX FOR WORKERS ON SITE 8
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	1.68E-07	5.10E-02	3.29E-06	6.45E-08	5.10E-02	1.27E-06
Cadmium	1.36E-09	2.90E-04	4.67E-06	1.13E-09	2.90E-04	3.90E-06
Chromium	3.35E-11	5.00E-03	6.71E-09	2.35E-11	5.00E-03	4.70E-09
4,4' DDT	2.52E-09	5.00E-04	5.03E-06	4.13E-10	5.00E-04	8.25E-07
Dieldrin	1.68E-12	5.00E-05	3.35E-08	8.39E-13	5.00E-05	1.68E-08
Endosulfan I	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Lead	4.53E-09	NA (c)	0.00E+00	2.57E-09	NA	0.00E+00
Toluene	2.35E-09	3.00E-01	7.83E-09	4.78E-10	3.00E-01	1.59E-09
Xylenes	0.00E+00	1.00E-02	0.00E+00	0.00E+00	1.00E-02	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. Data not available

TABLE P-117

CHRONIC HAZARD INDEX FOR ADULTS NEAR SITE 8
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	0.00E+00	5.10E-02	0.00E+00	0.00E+00	5.10E-02	0.00E+00
Cadmium	0.00E+00	2.90E-04	0.00E+00	0.00E+00	2.90E-04	0.00E+00
Chromium	0.00E+00	5.00E-03	0.00E+00	0.00E+00	5.00E-03	0.00E+00
4,4' DDT	3.63E-07	5.00E-04	7.27E-04	1.82E-07	5.00E-04	3.63E-04
Dieldrin	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Endosulfan I	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Lead	2.18E-07	NA (c)	0.00E+00	1.91E-07	NA	0.00E+00
Toluene	2.36E-07	3.00E-01	7.87E-07	1.18E-07	3.00E-01	3.94E-07
Xylenes	0.00E+00	1.00E-02	0.00E+00	0.00E+00	1.00E-02	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. Data not available

TABLE P-118

CHRONIC HAZARD INDEX FOR CHILDREN NEAR SITE 8
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	AIC (b) (mg/kg/day)	CDI:AIC	CDI (mg/kg/day)	AIC (mg/kg/day)	CDI:AIC
Barium	0.00E+00	5.10E-02	0.00E+00	0.00E+00	5.10E-02	0.00E+00
Cadmium	0.00E+00	2.90E-04	0.00E+00	0.00E+00	2.90E-04	0.00E+00
Chromium	0.00E+00	5.00E-03	0.00E+00	0.00E+00	5.00E-03	0.00E+00
4,4' DDT	1.91E-06	5.00E-04	3.82E-03	9.54E-07	5.00E-04	1.91E-03
Dieldrin	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Endosulfan I	0.00E+00	5.00E-05	0.00E+00	0.00E+00	5.00E-05	0.00E+00
Lead	3.05E-06	NA (c)	0.00E+00	2.67E-06	NA	0.00E+00
Toluene	1.24E-06	3.00E-01	4.13E-06	6.20E-07	3.00E-01	2.07E-06
Xylenes	0.00E+00	1.00E-02	0.00E+00	0.00E+00	1.00E-02	0.00E+00

a. CDI = Chronic Daily Intake

b. AIC = Acceptable Chronic Intake

c. Data not available

TABLE P-119

RISK FROM POTENTIAL CARCINOGENS
 ONSITE ADULT RESIDENTS OR WORKERS AT SITE 8
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	1.43E-02	- (b)	0.00E+00	4.11E-03	- (b)	0.00E+00
Cadmium	1.93E-09	NA (c)	0.00E+00	1.42E-09	NA (c)	0.00E+00
Chromium	7.43E-03	NA	0.00E+00	1.66E-03	NA	0.00E+00
4,4' DDT	0.00E+00	3.40E-01	0.00E+00	0.00E+00	3.40E-01	0.00E+00
Dieldrin	0.00E+00	1.60E+01	0.00E+00	0.00E+00	1.60E+01	0.00E+00
Endosulfan I	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	6.92E-10	NA	0.00E+00	1.55E-09	NA	0.00E+00
Toluene	1.21E-09	-	0.00E+00	1.85E-10	-	0.00E+00
Xylenes	9.39E-12	-	0.00E+00	4.70E-12	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound

c. Data not available

TABLE P-120

RISK FROM POTENTIAL CARCINOGENS
 ONSITE CHILD RESIDENTS AT SITE 8
 FUTURE

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	1.07E-02	- (b)	0.00E+00	3.09E-03	-	0.00E+00
Cadmium	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA	0.00E+00
Chromium	5.57E-03	NA	0.00E+00	1.24E-03	NA	0.00E+00
4,4' DDT	0.00E+00	3.40E-01	0.00E+00	0.00E+00	3.40E-01	0.00E+00
Dieldrin	0.00E+00	1.60E+01	0.00E+00	0.00E+00	1.60E+01	0.00E+00
Endosulfan I	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
Toluene	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Xylenes	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound

c. Data not available

TABLE P-121

RISK FROM POTENTIAL CARCINOGENS FOR WORKERS ON SITE 8
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	1.68E-07	- (b)	0.00E+00	6.45E-08	- (b)	0.00E+00
Cadmium	1.36E-09	NA (c)	0.00E+00	1.13E-09	NA (c)	0.00E+00
Chromium	3.35E-11	NA	0.00E+00	2.35E-11	NA	0.00E+00
4,4' DDT	2.52E-09	3.40E-01	7.40E-09	4.13E-10	3.40E-01	1.21E-09
Dieldrin	1.68E-12	1.60E+01	1.05E-13	8.39E-13	1.60E+01	5.24E-14
Endosulfan I	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	4.53E-09	NA	0.00E+00	2.57E-09	NA	0.00E+00
Toluene	2.35E-09	-	0.00E+00	4.78E-10	-	0.00E+00
Xylenes	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00

a. CDI - Chronic Daily Intake

b. Not applicable to this compound

c. Data not available

TABLE P-122

RISK FROM POTENTIAL CARCINOGENS FOR ADULTS NEAR SITE 8
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	0.00E+00	- (b)	0.00E+00	0.00E+00	- (b)	0.00E+00
Cadmium	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA (c)	0.00E+00
Chromium	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
4,4' DDT	3.63E-07	3.40E-01	1.07E-06	1.82E-07	3.40E-01	5.34E-07
Dieldrin	0.00E+00	1.60E+01	0.00E+00	0.00E+00	1.60E+01	0.00E+00
Endosulfan I	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	2.18E-07	NA	0.00E+00	1.91E-07	NA	0.00E+00
Toluene	2.36E-07	-	0.00E+00	1.18E-07	-	0.00E+00
Xylenes	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound

c. Data not available

TABLE P-123

RISK FROM POTENTIAL CARCINOGENS FOR CHILDREN NEAR SITE 8
CURRENT

Indicator Chemical	Upper Bound			Best Estimate		
	CDI (a) (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk	CDI (mg/kg/day)	Potency Factor (1/mg/kg/day)	Route-Specific Risk
Barium	0.00E+00	- (b)	0.00E+00	0.00E+00	- (b)	0.00E+00
Cadmium	0.00E+00	NA (c)	0.00E+00	0.00E+00	NA (c)	0.00E+00
Chromium	0.00E+00	NA	0.00E+00	0.00E+00	NA	0.00E+00
4,4' DDT	1.91E-06	3.40E-01	5.61E-06	9.54E-07	3.40E-01	2.81E-06
Dieldrin	0.00E+00	1.60E+01	0.00E+00	0.00E+00	1.60E+01	0.00E+00
Endosulfan I	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00
Lead	3.05E-06	NA	0.00E+00	2.67E-06	NA	0.00E+00
Toluene	1.24E-06	-	0.00E+00	6.20E-07	-	0.00E+00
Xylenes	0.00E+00	-	0.00E+00	0.00E+00	-	0.00E+00

a. CDI = Chronic Daily Intake

b. Not applicable to this compound

c. Data not available

APPENDIX Q
TABLE OF CONTENTS

	Page
Q.1 INTRODUCTION	Q-3
Q.2 FIELD NOTES	Q-5
Q.2.1 Notebook 1, Field Team Leader Notebook No. 1	Q-6
Q.2.2 Notebook 2, Rig No. 1	Q-71
Q.2.3 Notebook 3, Assistant Field Team Leader	Q-130
Q.2.4 Notebook 4, Field Technician	Q-174
Q.2.5 Notebook 5, Sample Collection Log	Q-202
Q.2.6 Notebook 6, Sampling Purge Records	Q-255
Q.2.7 Notebook 7, Slug Test Notes	Q-322
Q.2.8 Field Drilling Record	Q-331
Q.2.9 Notebook 8, Field Team Leader Notebook No. 2	Q-403

This page intentionally left blank.

APPENDIX Q
FIELD NOTES

This page intentionally left blank

SECTION Q.1

INTRODUCTION

This page intentionally left blank.

SECTION Q.1 INTRODUCTION

The contents of the field notebooks are included here as required by the statement of work.

There are eight notebooks.

The field notes for the lithologic logs were kept on separate sheets of paper and these are included as Section Q.2.8. They are grouped by site, and within each site, in the sequence: boreholes drilled for monitoring wells and boreholes drilled for well points.

A brief summary of the contents of each notebook is given at the beginning of each section before the copies of the field notes themselves.

This page intentionally left blank.

SECTION Q.2
FIELD NOTES

This page intentionally left blank.

SECTION Q.2
FIELD NOTES

Q.2.1 Notebook 1, Field Team Leader Notebook No. 1

This notebook contains notes of the Field Team Leader for field work done during the summer of 1988. The notes consist of overall field strategy, personnel and the work progress.

All 122 pages in this notebook were used. The first entry is 6 July 1988 and the last is 8 September 1988. The pages are signed by John D. Hardeman.

This page intentionally left blank.



"Life in the Rain"

WEATHERPROOF

FIELD BOOK

No. 350

DUNN AND

Project No. 0001


Book No. 1

Field Notebook

FTL John D. Hardeman

DISTANCES FROM SIDE STAKES FOR CROSS-SECTIONING

Railway of any Width. Side Slopes 1 1/2 to 1.
In the figure below opposite 7 under "Cut or Fill" and under .3 read 11.0, the distance out from the side stake at left. Also, opposite 11 under "Cut or Fill" and under .7 read 16.7 the distance out from the side stake at right.



Cut or Fill	Distance out from Side or Shoulder Stake									
	0	.1	.2	.3	.4	.5	.6	.7	.8	.9
0	0.0	0.2	0.3	0.5	0.6	0.8	0.9	1.1	1.2	1.4
1	1.6	1.7	1.8	2.0	2.1	2.3	2.4	2.6	2.7	2.9
2	3.0	3.2	3.3	3.5	3.6	3.8	3.9	4.1	4.2	4.4
3	4.5	4.7	4.8	5.0	5.1	5.3	5.4	5.6	5.7	5.9
4	6.0	6.2	6.3	6.5	6.6	6.8	6.9	7.1	7.2	7.4
5	7.5	7.7	7.8	8.0	8.1	8.3	8.4	8.6	8.7	8.9
6	9.0	9.2	9.3	9.5	9.6	9.8	9.9	10.1	10.2	10.4
7	10.5	10.7	10.8	11.0	11.1	11.3	11.4	11.6	11.7	11.9
8	12.0	12.2	12.3	12.5	12.6	12.8	12.9	13.1	13.2	13.4
9	13.5	13.7	13.8	14.0	14.1	14.3	14.4	14.6	14.7	14.9
10	15.0	15.2	15.3	15.5	15.6	15.8	15.9	16.1	16.2	16.4
11	16.5	16.7	16.8	17.0	17.1	17.3	17.4	17.6	17.7	17.9
12	18.0	18.2	18.3	18.5	18.6	18.8	18.9	19.1	19.2	19.4
13	19.5	19.7	19.8	20.0	20.1	20.3	20.4	20.6	20.7	20.9
14	21.0	21.2	21.3	21.5	21.6	21.8	21.9	22.1	22.2	22.4
15	22.5	22.7	22.8	23.0	23.1	23.3	23.4	23.6	23.7	23.9
16	24.0	24.2	24.3	24.5	24.6	24.8	24.9	25.1	25.2	25.4
17	25.5	25.7	25.8	26.0	26.1	26.3	26.4	26.6	26.7	26.9
18	27.0	27.2	27.3	27.5	27.6	27.8	27.9	28.1	28.2	28.4
19	28.5	28.7	28.8	29.0	29.1	29.3	29.4	29.6	29.7	29.9
20	30.0	30.2	30.3	30.5	30.6	30.8	30.9	31.1	31.2	31.4
21	31.5	31.7	31.8	32.0	32.1	32.3	32.4	32.6	32.7	32.9
22	33.0	33.2	33.3	33.5	33.6	33.8	33.9	34.1	34.2	34.4
23	34.5	34.7	34.8	35.0	35.1	35.3	35.4	35.6	35.7	35.9
24	36.0	36.2	36.3	36.5	36.6	36.8	36.9	37.1	37.2	37.4
25	37.5	37.7	37.8	38.0	38.1	38.3	38.4	38.6	38.7	38.9
26	39.0	39.2	39.3	39.5	39.6	39.8	39.9	40.1	40.2	40.4
27	40.5	40.7	40.8	41.0	41.1	41.3	41.4	41.6	41.7	41.9
28	42.0	42.2	42.3	42.5	42.6	42.8	42.9	43.1	43.2	43.4
29	43.5	43.7	43.8	44.0	44.1	44.3	44.4	44.6	44.7	44.9
30	45.0	45.2	45.3	45.5	45.6	45.8	45.9	46.1	46.2	46.4
31	46.5	46.7	46.8	47.0	47.1	47.3	47.4	47.6	47.7	47.9
32	48.0	48.2	48.3	48.5	48.6	48.8	48.9	49.1	49.2	49.4
33	49.5	49.7	49.8	50.0	50.1	50.3	50.4	50.6	50.7	50.9
34	51.0	51.2	51.3	51.5	51.6	51.8	51.9	52.1	52.2	52.4
35	52.5	52.7	52.8	53.0	53.1	53.3	53.4	53.6	53.7	53.9
36	54.0	54.2	54.3	54.5	54.6	54.8	54.9	55.1	55.2	55.4
37	55.5	55.7	55.8	56.0	56.1	56.3	56.4	56.6	56.7	56.9
38	57.0	57.2	57.3	57.5	57.6	57.8	57.9	58.1	58.2	58.4
39	58.5	58.7	58.8	59.0	59.1	59.3	59.4	59.6	59.7	59.9
40	60.0	60.2	60.3	60.5	60.6	60.8	60.9	61.1	61.2	61.4

RETURN TO: ROBERT S. McLEOD
Engineering Science
710 S. Illinois Ave.
Suite F-103
Oak Ridge, TN.
37830
(615) 481-3920

FED EX # 1196-4207-8

"Rite in the Rain"
WEATHERPROOF

a product of
J. L. DARLING CORPORATION
TACOMA, WASHINGTON 98421 U.S.A.

CONTACTS

NAME			
MAJ. JOEL D. MANN	Duluth ANG	218-723-7290	
COL DON SOLWOLD	Hq Mn ANG	612-296-4673	
Sgt Jim Norton	Duluth ANG (CE)		
(utilities) work control		X 292	
Sgt John Wheeland	Facility Mgr. (CE)	X 408	
Sgt Harold Stevens	supply	X 293	
Bill Heyden	ES-Deputy PM GR	615-481-3720	
LARRY ANDERSON	Hazwep	615-576-1967	
TOM STURDIVANT	Hazwep	615-482-6601	
Enrique Geatzsch	MPCA site response	612-296-7823	
Elizabeth Gowers	MPCA site response	612-296-7821	
ED Greenwood	H's Mgr. ES	404-325-0770	
TOM CATHOLOT	North Star Drilling	612-622-6552	
Melanie Baltz	Beckler Lab	612-632-3306	
Kathleen Field	Berkley Lab	615-841-7353	
Bruce Bucke	(Utilities Giv)	615-937-5368	
GAWES (DANNY) Drilling shop		615-937-5368	
old shop		615-937-5368	
USGS Belton Missouri		615-937-5368	
Map Archive		615-937-5368	
Johnson a/c O Screen		612-636-7900	
Secty		442 X 282	
Fire Dept		X 434	
Bldg 103		218-723-7470	

EMERGENCY CONTACTS

Base Main Gate Security		723-7280
Fire Department		723-7233
Police Control		1-800-332-3073
Medical Emergency		
Hospital	St. Lukes Hospital of Duluth	
Airport	915 East 1st St. Duluth, Mn	
Phone	(218) 726-5555	
Base PIC	Maj. Joel Mann	
CE	Mn. ANG	
W. (218) 723-7290		
H. (218) 728-2633		
ES		
PM	ES. McLeod	
	ES. D.R. Tm. (615) 481-3920	
Art. 615-483-4613	Mn (404) 953-9623	
H's	Ed Greenwood	
	ES. ATL. Gm. (404) 325-0770	
FAA C.A. K. b. GATE		727-2260
		2151

3

Sampling Equipment Utilized

ITEM	Eqpt.	Asset #	Serial No.
1	HNU RT 101 Field PID	566791	701235
	Probe & Pump	500018	M1144
2	HNU RT 101 Field PID	164716	601288
	Probe & Pump	501288	707031
3	GASTECH Explosimeter		CX4994
	Three way gas Alham		
	Gx 82		
4	Biosensor II		C-611-1182
	Explosimeter		
5	Foxboro OVA 128 60	500452	50654

4

DATE: 7-6-88	
E.S. Personnel on Sit.	
FTL: John D. HADDEMAN E.S. NTL	
Tech: Kim DAVIS E.S. OR	
Geol: Peter Riemersma E.S. OR	
Tech Sal Gns: Dennis Muckhead E.S. OR	
Tech " " Dan Brookshire E.S. OR	
Weather: Hot - Sunny light wind - west	
0800 Arrived CE & met Maj. Manns.	
Received keys to hangar 103	
Sgt. Stevens escorted JDA, KD	
& PR. to supply storage to	
move eqpt. to E.S. Field	
office	
0900 STARTED transfer of supplies	
to F.O. unloaded all eqpt.	
& supplies & inspected contents	
to insure that shipments	
were complete to Sigcom Calb. Ept.	
1200 Lunch break	
1300 Refueled from lunch &	
continued unpacking and	

C. L. Hadden 7-6-88

5

7-6-88 Cont'd

Setting up office. Soil gas crew continued calibration of equip. for primary target compounds. Reviewed Site 3 and established soil gas grid on map w/ refer. to site facilities. Site 3 closed @ \approx 1530 hrs + access could not be obtained. Established reference data for M.W. Sites @ FTAs 1 & 2. Also established SS. sites & references on map for Site 8. Checked operation of site mobil. equipment. HMU's & explosimeter. Reviewed operation of equipment using manuals.

1900 Departed site for day.

7-6-88
J. L. Anderson 7-6-88

6

7-7-88 Thursday

EO Personnel on Site
FTL JD Harrison
Greel A. Riemersma
Tech K. Davis
Tech soil gas D. Michael Dev
Tech D. Brookshire Dev
Weather - Sunny - Hot No wind
0730 Arrived Site
0745 H's Review w/ soil gas personnel. Dennis Michael E.S. Denver is responsible for insuring compliance w/ H's Plan. H's Plan acceptance forms signed.
0800 Secured additional exp't for field work.
0830 Went to office supply store. Eng'r Supply & Army supply store for exp't.
1030 Returned to office.
1051 Start Flapping Site 3
1230 Break for lunch

J. L. Anderson 7/7/88

7

7/2/88 cont'd

1330 Return from lunch

1345 Enrique Gentsch from NPLC

Arrived @ office, Peter &

Kim go to Central supply to

pick up packages

1405 Kim & Peter return - NPLC

water did not arrive. Kim

called Fisher Scientific &

they informed her that they

had failed to finalize order.

T. (John) called B. McLeod

to inform him that we did

not have water & ask him

to locate some & ship to us.

1426 Arrived Site 3 to restart

staking & start soil gas

work

1742 Returned to office. Completed locat.

21 of the 49 soil gas points.

Will complete remaining locations

on Friday. E. Gentsch DEPARTED

Site while we were still staking

@ Site 3 to 1200 hrs. Soil gas

Crews completed one location and

C. V. Hudson 7/2/88

8

7/2/88 cont'd

were preparing to depart site

at 1730 hrs.

1800 hrs. DEPARTED field office

C. V. Hudson 7/2/88

9

7-8-88

FRIDAY

E.S. Personnel on Site.

FTL J.D. Hopperman

Cowl P. Riemersma

Tech L. Davis

Tech S.G. D. Mickend

Tech S.G. D. Brookshire

Weather Warm - 51. overcast 51 breeze from west.

07:15 Arrived Site & prepared to complete setting S.G. locations @ Site 3.

0730 Notified Sgt. J. Norton of Co. that S.G. points were set in front of Demo yard & requested with clearance on those Site

0800 Moved to Site 3. Notified personnel at Demo we would need access to yard on Saturday & Sunday and that we would need access to field beyond their security fence. They will contact C.E. and security to arrange access for us over the weekend.

C. J. Spade - 7/8/88

7/4/88 noted

0830 Start Soil gas location

0900 C.E. Arrived to CK utility locations. All points were approved or relocated to accommodate utilities

1130 Lunch break

1230 Left office to go to

A & E office supplies for supplies. Also went to Target & picked up misc cleaning mat's

12:30

Returned to base & went by CE to Calhoun access to POL - Site 8 & Site 3 over walked.

Maj. Manns informed Security that we would be on base working during entire weekend. Also picked up Key for POL Site access & Flight 114 access.

1500 Returned to office & called Kathleen Kidd

C. J. Spade - 7/5/88

11

7/8/88 Conf

@ Berkeley Lab. to inform her of sample shipment times & schedule & also discuss analysis to be run. Lab was concerned about holding time on volatile for soils. She confirmed Lab's ability to run multiple samples. She does not anticipate problem w/ holding times.

1530 Called North Star drilling to discuss drill procedures, specifics & anticipated time-table for Duluth Field Activities

1630 Returned to Site 3. Flagged S.G.

Sites along roadway.

1800 Departed Site for day.

7-8-88

12

7-9-88 Saturday

E.S. Personnel

JD Hardeman

P. Rickerson

K. Davis

Dennis M. McLeod

Dan Brookshire

Weather: Clear, Sunny, Warm
wind: Calm

0745 Arrived Site. Checked Keys to Demo Gak. Key did not fit. Also checked mag. Keys to POL Site. These did fit but could not gain access to Demo from this site.

0810 Arrived office & called CE Fire Dept. to open gak for Soil gas Crew

0830 Began Flagging Site 3

1030 Completed Site 3

Began Flagging Site 8

1115 Completed Site 8 and

quit flagging - 8/7/88

13

7/9/88 cont'd

Began gathering mats & data to set monitoring wells.

1145 Lunch

1245 Returned from lunch.

1300 Proceeded to FTA's 1+2 to

stake monitoring well

locations. Completed

locations for WP 1,2,3.

1800 DEPARTED SITE

J. L. Hardman 7-9-88

14

7-10-88 Sunday

F.S. Personnel

JD Hardman

R. Riemersma

K. Davis

D. Michard

D. Brookshire

Weather: Clear Sunny S. breeze from EAST.

0900

Arrived Site - contacted CE Fire Dept. to open front gate to DEMO. Consulted w/ soil gas crew as to days proposed activities. Have completed 20 soil gas points at this time.

The remaining crew will complete locations for monitoring wells at Sites 1,2,3,4 & 8 today.

T.S. time permits we will

collect some soils at Site 8.

DEPARTED for FTA's 1+2.

1040 Completed locations for FTA's 1+2

5. INCREased Flushing Site 3, 4 & 8.

J. L. Hardman 7/10/88

15

7/10/88 Cont'd

12415 Completed Flagging Sites 3, 4 & 8
Break for lunch

1330 Began Decan soil sampling sypt,
Bowls, spoons, Augers etc Decan
Consisted of ligunway wash,
Potable H₂O Rinse, Methanol
Rinse, HPLC grade water Rinse
each item was wrapped in
Aluminum foil & stored for use.

1445 Proceeded to Site 8 to
Collect Soil Samples.

1700 Colled Sample DANG 8-83

Meth consist of gl fill, sand
silt & clays w/ 2-4" pebbles
up to 2' in diameter. Auger
bucket distorted, rods will
not take abuse. At 15' hit
a sandy, silty clay w/ few
pebbles, clump.

1720 Decan'd hand Auger.

1726 DANG 8-A3. Soil very hard w/
large pebbles - Cobbles struck
3 holes could not penetrate
even 6". Will discontinue &

Chapman 7/10/88

16

7/10/88 Cont'd

Attempt to find a new method.
1800hr. Disrupted Site.

Chapman
7-10-88

17

7-11-88 Monday

F.S. Persevel

JD Haden

K. Davis

D. Ackersma

D. Mickleed

D. Brookshire

Weather - overcast - cool wind from

west ~ 10 k.

0730 Arrived Site - went to Know
Lumber & board Post hole
clippers & wrecking bar. Will
attempt one hole in area before
sampling.

0815 Arrived Site & attempted to
use post hole clippers to
sample. Cannot penetrate
mat'l. Will rent power
auger w/ two pieces of
head.

0930 Rented Power Auger, sand blasted
pieces to remove rust, paint
and other residue.

Phil Handman 7/11/88

7-11-88 (Cont'd)

0945 - Kim set up Decon area at
Site 3 Decon Power Auger
Decon consists of pressure
to remove gross dirt, Alcon
wash w/ heavy brush Decon
Potable water Rinse. McDaniel
Rinse and final Rinse w/ HMC
grade water.
1000 started 1st hole. Power auger
work well in soils. Will
Auger All holes to 1.5'
below the major contamination
soil. Will then return w/
55 hand augers & back to
2' & pull sample below
area of penetration of power
auger. Drilled hole Aug 8-C3
Power Auger Drilling
Time begins
1000 DMHG 8-C3 Auger Bore
1010 8-d 43 17431
1020 8-15E 3144
1040 8-15E 3144
7/11/88
Phil Handman 7/11/88

19

7-11-88 (cont'd)

Power Auger holes	Full size Auger
Time	beginning
1045	8-10-88 F21 July
1054	8-10-88 E22 July
1105	8-10-88 D23 July
1110	8-10-88 C24 July
1115	8-10-88 B25 July
1120	8-10-88 A26 July
1125	8-10-88 B27 July
1130	8-10-88 A28 July
1135	Break for lunch & to replace Decan center. Also took fast hole diggers & working bar to Mac's tent & had each 1-1/2 sand blasted & enamel painted
1330	Returned to site began Augering
1340	8-10-88 B29 July
1345	8-10-88 B30 July
1405	8-10-88 C31 July
1430	8-10-88 D32 July
	Recall Spacing broke at Auger motor
	Full size Auger 7/11/88

20

7-11-88 cont'd

	Returned to tented Co. to fix spacing
	Pipes & kin as 11 Chem. bottles
	for sampling
1535	22660 Fused - returned to site
	& to complete bearings. Clouds
	Gathering rain possible 1/2 a.m. 11
	Collect samples on bearings
	open
1606	SAMPLED DANG-8-55-A-3 July
1620	SAMPLED DANG-8-55-C3 July
1630	Decan sampling to 1/3
1647	SAMPLED DANG-8-55-D3 July
1651	SAMPLED DANG-8-55-E3 July
	Soil sampling - sampling packages
	and Decan being completed
	concurrently
	Samples collected by JDH
	Samples bottled by PK
	Decan completed by KB
Sample time	Location TJD
1700	DANG-8-55-F3 July
1705	DANG-8-55-A2 JDH
1714	DANG-8-55-A2 JDH
1725	DANG-8-55-C2 JDH

Full size Auger 7/11/88

21 7/14/88 Cont'd

Sample time Location ID Dean Clapp

1733 DANC-8-55-D2 JDI

1733 DANC-8-55-G2 JDI

Duplicate of 8-D2

Sampling Complete for the day Samples
Refined

1830 Called Beckley Lab

10 boxes M. Baltimore sent

5 samples wanted be shipped

7/12/88 for water samples

shipment confirmed & will

not cause lab to be JDI after

miss holding time

1845 DEPARTED office

7/12/88

Dean Clapp

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

JDI

22

7-12-88 Tuesday

ES Personnel

JDI Maclean

P. K. Maclean

K. Davis

D. McLeod

D. Brooks

Weather - Clear, Sun, warm and

± 5K from EAST

0800 Arrived office - B. McLeod Called

Discussed progress of JG crew

& sampling @ site 8. JG will

be complete today. All hand

prints should be completed by

7-12-88. will include packets

A. P. Property with side of

field. Prepared deck notes

to sample @ site 8

Moved to site 8 to begin

Sampling

Location ID Dean Clapp

0930 DANC-8-55 F3

0940 DANC-8-51 F2

J. J. Henderson 7/12/88

23

7-12-58 Cont'd.

Time	Location & IO	Initials	Exp.
0955	DHUC-8-SS-F21	Jul	Exp.
1005	DHUC-8-SS-F21	Jul	Exp.
1021	DANG-8-SS-E1	Peter Rimmer	
1049	DANG-8-SS-D11	Peter Rimmer	
1104	DANG-8-SS-C1	Peter Rimmer	
1116	DANG-8-SS-B11	Peter Rimmer	
1131	DANG-8-SS-A1	Peter Rimmer	
1200	Lunch		
1232	Returned from lunch & completed		
	vacations w/ Peter Auger		
1230	Dang 8-SS-A0	Jul	
1242	Dang 8-SS-B0	Jul	
1248	Dang 8-SS-C0	Jul	
1305	Dang 8-SS-D0	Jul	
1315	Dang 8-SS-E0	Jul	
@	1315 Both Gravity arrived @		
	Sail sampling site. Explained procedure		
	being used and justification @ =		
	1325 she departed site & for lunch		
1330	DANG 8-SS-F0		
	Sail Augering complete & started		
	Sail sampling @ each Auger locat.		
	Jul Rimmer 7/12/58		

24

7/17/58 Cont'd.

Time	Location & IO	Initials	Exp.
1335	DANG-8-SS-B0	Peter Rimmer	
1335	DANG-8-SS-C0 (DANG)		
1345	DANG-8-SS-B0	JDH	
1355	DANG-8-SS-C0	JDH	
1356	DANG-8-SS-D0	JDH	
1359	DANG-8-SS-E0	JDH	
1405	DANG-8-SS-F0	JDH	
	Shipping Complete Start		
	Final Decan on Sampling Tanks		
	7 Sept.		
1435	Completed Decan. P. Rimmer		
	Auger one load of equipment back to		
	office. K. Davis stayed on-site		
	with remaining equipment - KLI		
	1's, John Henderson went to make		
	copies of claims for custody @ 1450 - KLI		
1450	Peter returned. Took rest of equipment		
	to mine KLI. Packaged and prepared		
	samples for shipment to the		
	Beckley Lab. Samples were sealed		
	w/ elect. tape - Custody seals placed		
	on all bottles, labels checked, wrapped		
	Jul Rimmer 7/17/58		

25

2/12/88 Cat-D

in bubble pack and packed in
disposable coolers. Ice was placed
in cooler in dual zip lock bags.
Coolers were sealed w/ a sturdy seal
and placed in cardboard shipping
containers. Chain of custody for
each cooler was placed in a
zip lock bag & taped to the
inside of the cooler lid.
Soil gas crew and Beth Greenlys
(IMPCA) arrived @ office. We reviewed
soil gas data of selected
for additional soil gas samples.
Crew returned to Site 3 to collect
additional samples.

1730 Departed office to take samples to Fed E

1800	Left Field's office & departed site for the day
------	---

W. Hudson 7/12/88

23

7-13-88 Wed 11/10/88

ES Personnel

SP Had. O. in Pen.

Aliments

① Davis

Michael

D. Brookside

weather - overcast
high humidity, rain
nightly w/ to Calm.

1800 Arrived office 5:15/900

Crew preparing to conduct
Soil gas probe in flight lane

Sgt. Dennis of CE will
 11/10/48
 escort Gen. P.R. and

KD will and J.G. crew

w/ additional probe in an attempt to complete 5k3

J.D.H. will prepare maps for
C.E. to approve Soil Binding

27

try to complete site by 1400.
 1420 Soil for Cows returned to office.
 Brett C. (MPCA) w/ crew all
 additional. Site complete. D. Gahup
 completed completion of site & stated
 that sufficient data had been
 collected to adequately describe
 site. When asked if he would
 like to see and addit. site
 sampled she commented that she
 knew of no other locations that
 she thought she wanted sampled. She departed site
 1445
 1445 went to CE to get animal
 photos to take to D. McLeod &
 J. Duncan.
 1400 returned to Bldg 103. SG crew
 has departed site for Denver
 office.
 1430 R.P. Reimerson & K. Davis left
 site to return generator & return
 Co. for S.G. crew.
 1730 DEPARTED SITE.

J. R. Jordan 7/13/88

28

7-14-88

DEPARTED SITE 7-14-88 for
 Atlanta. Will return to site and
 mobilize for drilling activities
 on 7-25-88

J. R. Jordan
 7-14-88

29

7-25-88

1030 Arrived Duluth A.P. w.
 Ed Gerndwald, H&S office
 from Atlanta Ga. Went
 directly to CE to notify them
 that field activities would
 begin w/ mobilization today
 & drilling would begin 7-26
 or 7-27-88 After initial
 clean & setup. Also picked up
 supplies from CE that had
 arrived during our absence.
 1100 J.D.H. & E.G. went to meet
 bldg mtl's to pick up elect.
 cable for power at decan
 pad. & returned to bldg
 103 to await arrival of
 Alan H. Stark Drilling.
 1230 Lunch P.R. & K.D. arrived from Knoxville
 1315 Returned - Graves Drilling Rig
 parked at west gate of bldg 103.
 1410 Telephone Co Representative
 came by office. Took telephone
 Rep. around to sites 3, 4 & 8
 & showed him all planned

7/25/88

30

Notes Clean up will be
 ready by 7/26/88.
 1530 Danny Graves arrived w/
 last load of supplies from
 his office. Jan Daugherty
 called & said all his supplies
 had not arrived. He planned
 to get supplies in of around
 Duluth date in 7-25-88.
 Will meet at site morning
 of 7-26-88.

1630 Departed Site

7/25/88

Jul Anderson

31

7-26-88

Tuesday

E.S. Personnel on Site

JD Hardeman

FTL

ED Grundwald H.S. office

P. Kuwarska

Geol.

K. Davis

weather clear cool slight breeze
from Southwest.

0730 Arrived Hanger 103 & began

Reviewing project Matk.

Ed prepared to give health
& safety briefing. Kim &

Peter degrammeting clean
supplies. ^{supplies} ~~clean~~ S.S. Sprayers & buckets

0800 Sgt Dennis arrived & requested
that we establish new location

@ Site 2 between taxiway
& Runway. While away Tom
Dortlandt from North Star
Drilling & Guss Arrived.

North Star Drilling crew

1) Tom Dortlandt owner

2) Bill Erickson H.S. Supervisor

3) John Anderson Driller

Bill Anderson 7/26/88

32

7/26/88 cont'd

0830 North Star Drilling crew began
unpacking cases and began
and preparing to set up
for drilling. Graves drilling
crew due to arrive site
in 1100 hrs. H.S. drilling
crew Graves drilling crew arrived
Denny Graves due by 1100.

1100 Started H.S. briefing

conducted by ED Grundwald

H.S. from Atlanta Ga.

Personnel present

Engineering Science

1) JD HARDMAN

2) P. Kuwarska

3) K. Davis

North Star Drilling

1) T. Dortlandt owner

2) B. Erickson H.S.C.

3) J. Anderson Driller

Graves Drilling

1) D. Graves owner

2) Jeff Island Driller

3) Mike Edwards Driller

Bill Anderson 7/26/88

33

7/24/88 Canceled

4) Phil Kulpala Helport
Hd & Bickins complete

1200

Lunch
Returned to Airport to

Pick up Jo Ann. Tom
stordrums did not arrive

To Co to pick up Fades

packages & returned to

office @ 1350

Returned to Airport &

picked up 1. Spoonman

E. Greenwood Rd. left site

on flight @ 1415. Drillers

started entry decontamination

on drill Rig.

Returned to Bldg 103

decontaminative from Culligan

was completing installation

on Millipore System

Went to CE to get Keys to

existing monitor wells for

water level measurement

Jo Mares & Gt Dennis not

available. If location would

Phil Hardin 7/24/88

34

7/24/88 Canceled

try to locate Keys & have
them mail to Co. tomorrow.

1615 Returned to Bldg 103. Relieved

Jo Ann & Kimberly for the

day. Peter & I will remain

up Decan from until Rig

complete. Drill rig in

extremely dirty & decan

will be lengthy. Detailed

decan notes are lagged in

log book Rig 1.

1830 Water pressure dropping

& water Ambient. Pressure

has low to supply steam

clean. Hope pressure loss is

due to peak usage by

surrounding civilian population.

Decided to discontinue decan

until 7/12/88. Jo Ann & I remain

is still the low w/decana

w/ CE to find alternate

Source

1900 Departed Site

Phil Hardin 7/24/88

35

7-27-88

Wednesday

Ed. Personnel on Site
 J.D. Harwood FTL
 P. Kiewit Geol.
 L. Sherwin Geol.
 R. Davis Eng
 Martin Marotta Representative
 Dennis Forsberg U.M. Worker
 Tam Stoddman U.M. Hydrogeologist
 Subcontract Personnel on Site
 North Star Drilling
 Lee Rothardt owner
 Bill Erickson HSO
 John Anderson Driller
 Ernest Drilling
 Timmy Graves owner
 Jeff Osland Driller
 Mike Edwards Deco
 Paul Kilpatrick helper

Weather clear with slight breeze from west.

Davis Activities will consist of decant of drilling equipment & supply water. Recovery will be taken and recorded.

Pik Hardman 7/27/88

36

7/27/88 Cont'd

on existing monitoring well.
 If decan procedure are complete we will begin collecting soil samples @ Site 2.
 0710 J.D. H. arrived Site w/ Nailless North Star on Site for Deco.
 0730 Peter, Kim & Jo Ann arrived Site.
 0745 T. Stoddman & Dennis I arrived Site Prepared R.D. H.S. to collect water levels. Tam Stoddman & Dennis Forsberg reviewed Decan of Rig Recommended that Rubber connection on Williams Systems Decantation completed by Peter Kiewit.
 0830 J.D.H., T.S. & D.F. went to CE of well w/ Capt. Dennis for web meeting also picked up key for existing monitor well. If key for P.O.C.

Pik Hardman 7/27/88

37

7/27/88 Caled

Sgt Dennis injured about above ground construction of well next to taxiway. It's concerned about planes hitting above ground construction.

Potential for damage to structures if plane if hit by plane. Sgt Dennis also expressed concern about

FAA Dennis w/ contact of FAA & discuss above ground construction.

0945 Returned to Hangar 103 &

Calibrated HNO. K.D. & L.S.

will start water levels after

Calibration. Head space on

each well will be measured

open openings.

1045 finished Site 2 located &

dumps - Hydraulic & cleaners.

1054 Sgt Dennis arrived Site 2

& informed us that FAA requires

that well pts will be

min of 75' from edge

J. L. Hardman 7/27/88

38

if taxiway. Based on max. aircraft wing span landing.

② Facility which is 747.

148' & wingspan - 376' for

& taxiway min distance

approved by FAA will be 75'

Additionally any permanent structure

will have to have construction

permitted. Also any above ground

structure w/in 500' has to have

breakdown complies.

1115 began AIT for K Davis &

J. Scherwin for wake level

Did measurements on

July 27, 1988. E & G W 2 D.

1155 Complete AIT & back for

Lunch @ 1230 after checks

CE for Mail.

1400 returned from lunch checked

Aspers after sandblasting.

Guest left in Hespero. Return

to Sandblasting for completion

K. Davis decontaminating

water level indicator

J. L. Hardman 7/27/88

39

7/27/88 Cont'd

on per work plan specs.

1500 Metw/54t Dennis @ C.E.

about permitting by FAA.

Details unclear about what

is required. Will meet w/Dennis

Co. at 8:15 7-28-88 at talk w/

FAA to get details

1530 Left Dennis office & went to

Site 2 to check on K.D. &

J.S. progress w/ water benches.

Identification of wells as different

locations incorrect. ID'd J.S.

Relocated & identified wells prior

to w.t. measurement. J.S. & K.D. will

spend the rest of the afternoon

accurately locating well.

1730 Left Site 2 to return to

Bldg 103. Dec 88, developed

hydraulic leaks around rear

jack cylinder. The stopcock of

Mantle Houston suggested we

use 2 55 gallon drums w/

1/4" 1/2" water jacks to catch

if a small flow of hydrocarbons

40

7/27/88 Cont'd

Dennis Forebush also agreed

big will need additional

Dolan beyond the rear

moat.

1745 Tom Stewart & Dennis

Forebush depart Site.

1830 IDH & Peter R. depart

Site. Drill crew still

dewatering big.

J. J. Hardeman 7/27/88

43.

7/28/88 Cont'd

May Dennis placed buffer on
base plat for each runway.
Both buffers 500' and 750'.
All were south of Site 2. Talk
with 750' buffer & three fold
with 500' buffer. May Dennis
will take plat to FAA of checker.
Return to Bldg 103. Reviewed fld.
Procedures w/ Dennis F & Tom
Steward. Dennis departed
Site ~ 1015 to catch flight
home.

7115 Talked w/ Sgt Dennis. Will meet
personnel from FAA who are
familiar w/ FTA's Site 2
lunch

1120 Returned from lunch to unit
on Sgt Dennis.

1230 Sgt Dennis arrived & JCS of JDAH
left to meet FAA personnel.
Met w/ Jim Ragan & Dan
Campbell of FAA. FTA 1 was
uncovered during construction
work ~ 1980. Site is located

7/28/88 Cont'd

44

clasee to Runway 1330E. When
originally thought. Walbeel
site of found area thought to
be old FTA. Some stress vegetation
that may be due to old burn
area. Pit is thought to be
~ 20' below ground surface.
Prior to doing soil borings in
this area we will uncover
w/ backhoe to locate. Also
thought by Mr. Ragan that some
aerial photos may still exist
that were taken by the Wayne
Catholic for war Command of
ANG @ Duluth. Also Ken
Winberg of FTA for City photo
Airport Authority City of Duluth
May have some photos. Also
aerial photos on wall of
Old Terminal @ FAA.
1330 Stopped by FAA to check
aerial photos. Photo does not
show old FTA. Talked to
Current FAA Director about

John A. Hansen 7/28/88

45

7/25/88 Contd

permitted w/ all 2 along
 highway at Site 4 & 5.
 Told us that plans &
 written description would
 have to be forwarded to
 FAA for permits in approx.
 permit time 90 days. Also
 stated that all bare ground
 areas were required to have
 shrub away bases. no known
 exceptions. Site 2 may be
 excepted due to 500' width
 from nearest Runway & that
 area sets upon hill. will
 discuss results of conv. w/
 Bob McLeod.

1425 Called B. McLeod & relayed
 conversation w/ FAA.

1520 May Manns called & said that
 Kenny Weinberg of City had no
 problems w/ sites @ site 2
 outside 500' buffer boundary.
 Manns believes that FAA approval
 is still needed. Agreed to meet

Jul Hardin 7/28/88

96

7/28/88 Contd

w/ May Manns, Mr. Weinberg
 & FAA official at office @
 1114g 103 00830 on 7/28/88
 to discuss Site 2.
 1600 Began preparing eqpt
 & sampling mat'l for drilling
 tomorrow. Rig cleaned &
 hoses & hoses from Springfield
 Hydraulics in key engine
 panel water fixed by
 Miller. Will begin drilling
 7/29/88.

1800 Checked w/ Miller on time
 for start up 7/29/88. will
 meet @ 2000 & start @ site
 2. Will do 2 soil borings
 & possibly w.P.s.

1830 John & Kim return from
 taking water levels. Indication
 of work existing. probably
 battery dead. will complete
 levels on 7/29/88.

1840 Departed site

Jul Hardin 7/28/88

47

7/29/88 FRIDAY

F.S. Personnel at Site

D. HARDEN

J. Shearman

P. Riemersma

K. Davis

North Star Drilling

John Anderson

Bill Erickson

Graves Drilling

Mike Edwards

Jeff Island

0640 Arrived Site. P. Riemersma
 @ Office began loading van
 w/ Sampling Supplies & Eqp't.
 Will send J. Shearman to
 Complete H/O funds alone
 & left K. Davis work with
 J. P. Riemersma on Reg. while
 I attend meeting w/ May
 Mann & FAA.

0730 J. Shearman depart Bldg 103
 for Site &

John Anderson 7/29/88

7/29/88 Cont'd

48

0800 Checked w/ Drilling
 anticipated time of depart.

No rope for 140 ft haul.

As soon as a rope is

found they can depart

for Site 2. While waiting

the A-TV Engineer Site

& crew is doing cleaning.

0830 May. Manns arrive

0850 Kenny Winberg from

Both Airport Authority

arrive & May Manns depart.

Mc Winberg continues drilling

@ Site 2 outside 500'

buffer. No other authorization

needed. @ site 4 along

following MC Winberg arrival.

FAA approval before well

are constructed however he feels

that 800 buffer is adequate

is that correct?

0905 Mc Winberg depart to get

manual slawes standard

construction site. Back to Dr.

John Anderson 7/29/88

49

FAA will return ~ 0930
 1100 FAA has not show up must
 get to drill site 2 & start
 work will try to contact
 FAA later.

1130 Arrive Site 2. No water truck
 will wait for remaining egg
 1245 still no H₂O truck will

go to CE to see Maj. Manns.
 1300 At CE TALKED to Sgt. Dennis.
 FAA has sent map thru CE.
 Must maintain 750' setback
 on ~~not~~ runways NE Runway &
 1050 on E-W Runway &
 300' on NW-SE Runway.
 This eliminates all proposed
 drilling south of roadway @
 site 1.

1315 AT Site 2. START Drilling.
 All remaining notes in log
 book for Rig 1.

1430 Kim Davis left to take
 J. Shannon to contact flight.
 home

Phil Hardin 2/29/85

50

1500 K. Davis Returns & helps
 on Rig 1.

1715 Thunderstorm start.
 Suspended drilling until
 7/30/85. Prepare samples
 for FedEx shipment to
 CA. lab.

1745 AT Bldg 103 helps P.
 Remersma clean down
 egg for tomorrow's
 work.

1800 Depart Site for Dine.

Phil Hardin 2/29/85

51

7/30/88 Interview
Personnel on Site

B.S.

J. D. GARDNER

P. R. GARDNER

K. DAVIS

Drillers

Bill Erickson

John Anderson

Mike Edwards

L. A. Osland

Frank Kipfer

D. GARDNER

Weather Sunny Clear Wind E 15 Kts
cast

0630 Arrived office w/ P. R. & K.D.
loaded van to go to well
site

0705 Arrived Site 2 set up Decon
area. Drillers preparing to
drill.

0745 Started Drilling. acceleration
of Bdl

0810 Cleared a big brake well spirit
casing drilling.

Bill Gardner 7/30/88

7/30/88 cont'd

52

0920	Harmer repaired Cultivator
	Drill Rig
1122	B.T. @ 16' River Refused will back for back of the breakdown. Saw. Rig.
1300	When from back set up
0940-1000	on S.H. 2
	will discontinue drilling
	@ 20' until ready Rig
	setting a wooden pavement
	get siding 2.5000 down
	hole. Will try to remove
	Boulder Monday, Aug.
1030	K.D. Takes sample to Fed
	Ex. 10 H & K. taken to
	Office. Unlabeled trucks of
	preparation to clean on Monday.
1720	Depart 103

Bill Gardner 7/30/88

53

5/1/88 Monday

E. S. Personnel

J. D. Thompson

F. R. Lawrence

R. Davis

(C. Green)

Darryl Glaser

Jeff Asland

Mike Edwards

Weather overcast windy, 8-15 K from west - some showers.

0600 Arrive office prepare paperwork for Daniel Field Egg.

0710 Arrive Site 2 Driller prepares to start drilling. Well log to leave boulder.

0750 Complete BH2 Site 2, Auger Refused @ 21.1

0830 Setup well point next Site 2. J.D.H. to Bldg 103 to check ATU Rig.

0850 Sgt. Schwartz from OSHK & from Woodward Clyde

John Haden 5/1/88

8/1/88 Cont'd

54

arrive office Woodward Clyde brought sampling next 1/2 supplies & gear stored there.

1000 Returned to Site 2 Drilling on BH2 Bored 1st hole to

10' and standard hole bit boulder @ 10' Handed in

in 7' to west of drilled hole started sampling 2nd

hole @ 10' Handed rig to J.D.H. @ WPC.

Break on lunch before continue boring

1130 Bored 1st hole.

1230 Returned for lunch.

Continued WPC Hill H20 @ 10.5. Completed boring

to 21' - 17'

1500 Cannot get well log

Remain Driller left Site to get training gyro.

J.D.H. left Site to go to C.E.

1515 Tacked to Mt. Mans

John Haden 8/1/88

50 Gulikander 8/1/88 cont

about FAA permits will try to set up spot w/ Kenny Winberg for Tuesday AM. Went to Airport to see K. Winberg. Out of office. Also talked to Ray Manna about woodland Clyde sharing our office space. He will try to relocate their sampling team.

1700 Returned to Site 2. 5 foot shoring shooting in our general direction. broke down site because of unsafe area. Moved to FTA to grant bare holes.

1800 Started granting bare holes. IDH Departed Site to go with R. McLeod at airport. P. Riemann & Jo Ann S. will remain w/ Driller.

Gulikander 8/1/88

8/2/88 Tuesday
Packed in Site

ES.
R. McLeod
J. Heppner
P. Riemann
K. Davis
J. S.
Driller
Darryl Graves
Jeff Ireland
Mike Edwards
John Anderson
Bill Erickson

Weather: Cool, overcast, windy from west.
will complete well Point 6 Site 2.
Grant bareholes & confirm well points

0645 R. McLeod & IDH arrived office. KD, P.R. S.J.S.
at office preparing to go to Field. LT scheduled 7:30

Gulikander 8/2/88

57

8/2/88 Cont'd

woodenware. Chyle personnel
on Site.
0730 Kim Fisher & Ann went to
Site. 2. Kim & Ann will
survey in all areas of old
Site. EDH & PHU went to S. Mans
office to discuss meeting w/
Airport Board & F.A.A.
0800 Arrived Site 2. Driller not
on Site. Returned to Bldg
103 to check on North Side.
Met Willie Conig out.
0900 Driller still not started. Danny
& Bill left Site to pick up
glove box. Prepped to set
well. Pulled auger ~ 2' off
bottom to set sand base. Mud
in Auger. Tied unsuccessful
to bit. Knocked plug out of
base and gravel flowed in to
well base. Reamed well, auger
casing too crooked. Decided
to drill new well.
1035 11' are ATU Pig to new hole

John Anderson 8/2/88

58

8/2/88 Cont'd

ATU Kevin Pig not heavy enough
to penetrate or move boulders in
material. Will run Kofasane
Pig on Site & drill w/it.
1130 Lunch
1230 Ret.
1300 at Site 2 waiting on Kofasane
Pig. Driller from Canada to
arrive ~ 1300 @ Airport
1500 go to BH 1 & 2 & complete
grouting of BH 2. Excise
Gravel from MPFA. Arrive
on Site.
1530 Complete grouting. Still waiting
on Driller.
1645 Heavy thunderstorm with
lightning for day. Depart Site

John Anderson 8/2/88

61

8/3/88 cont'd

1515 completely sand pack to 9' bgs. setting up to pump back into slurry.

1600 Encasing Bentonite Seal Set

1730 Depart Site well set up on deep well @ G-20 on 8-4-88.

Ch. Graham 8/3/88

62

8/4/88 Thursday

Perkins Co. Silo

R. McLeod

J. Harpwood

M. R. Emerson

J. Sherman

K. Davis

Dallas

Bill Erickson

J. Anderson

Jim HARTISON

D. Crane

M. Edwards

Jeff Hestland

with Rainier wind gusting ~ 30k from west

0650 arrive office w/ R.M. help getting get ready to go to G-20.

0715 Met J. Anderson & Jim H.

@ Silo 2. Having lunch, Jim will take to fire a trap for Roon of Reg. will take to drill in 1000

Ch. Graham 8/4/88

63

8/4/88 Cont'd


J. Henderson & Co. to C.E.
 Develop Corroded pipe and
 construction. ^{below 100'} Franchises for
 Major Hayes to take to
 Henry Winberg.
 0930 Return to 614, 105. adjacent boring
 location @ 5-20 3 & 4.
 1030 Return to Site 2. Began digging
 test pits w/ backhoe for FTA-1.
 Began in area where FAA employee
 said that Cartton w/ encountered
 during grading. No cartton
 found w/ backhoe
 1245 Complete backhoe work leave
 for work @ 1300
 1425 Return from work
 1445 Began drilling Dmg 2 - MW 12.
 1500 R. McKee left site to catch
 plane home.
 1621 B.T. @ MW 12 TD 213' Adjacent
 wall MW 12E is presently
 screened @ backhoe. This
 wall will be abandoned.
 Boring will be grouted to surface.

J. K. Henderson 8/4/88

64

8/4/88 Cont'd

Completed Sieve Analysis Sample.
 Sieve tag. 5 samples taken
 in channel through
 total agreed thickness.
 1700 Departed site for office.
 1800 Arrive office
 1800 Departed site for dinner



J. K. Henderson 8/4/88

65

8/5/88 Friday

0635 Arrive office
Fireman on site

J. Henderson

P. Richardson

J. Shepherd

K. Davis

D. Miller

D. Gardner

J. Anderson

J. HARTVISHIN

J. Aslund

M. Edwards

P. Kilpatrick

Weather overcast - raining windy from
west.

0700 Depart office for Site 2.

0710 Arrive Site 2. Setup on Site 2

NW 13 adjacent to GORCA.

J. Shepherd will complete top-

site for FTA

J. L. Gardner 8/6/88.

66

8/5/88 Contd

0900 Complete NW 13 BT @

Adj. as per the well NW 2A

Succeeded to bedrock.

NW 13 will be abandoned.

1000 Reverse drill & return to

Decm. Area. Will down

log & move to Site 8.

1200 Decm. Complete -

Lunch

1300 Return from lunch set

up @ Site 8 NW 18

adjacent to NW 8C

1445 NW 18 complete. Bedrock

encountered @ base of

section @ NW 8C. The

boring will be abandoned

1500 J.D.H. left Site for

Airport will depart

@ 1600

67

8/3/88 Monday

Dist 1410

1115 Arrived Duluth Airport of
west to Site. weather sunny
clear. slight breeze from west
Drill set up @ Site & over
Mud 15.

Personnel Site

ADH

R. Krenner

R. Davis

J. Sherrin

Duelin

Bill Erickson

J. Anderson

J. Bursbach

1240 Drilling complete well hole
back & complete over 11 PM.

1400 Preparing SS casing 2' Johnson-
Schubert 5 type 304

Ref casing in well & prepared
to sand pack, Battery on
drill rig dead. Spent 2 hrs
trying to crank rig. will

68

have to take battery out
& have them recharged.
will continue boring
& setting well in AM.
1415 Departed Site & for office
1430 Departed office

Phil Gardner 8/18/88

63

8/9/88 Tuesday

Personnel on Site

J. D. Anderson

P. Riemann

R. D. Davis

J. Sherman

Drillers

T. Oothout

B. Erickson

L. Anderson

J. D. Davis

D. Geaves

Weather Sunny Clear wind =

10-20 K from west.

0630 Moved office. Prepared to go to Site 3. W.S. & R.D. will locate all backhoe test pits at Site 2.

0700 at Site 2. Prepared to set

sand pack, turbine pipe too

large for basis Diameter

ver. 0.0 chance to set up w/

3/4" turbine.

J. D. Anderson 8/9/88

8/9/88 Cont'd

70

750 Continue sand pack from 44' to 26.0

1115 Complete sand pack of place

ben to it. Sleepy Seal

1215 Complete ben to it. Turbine

& begin mixing grout. Mixer

brake down

1245 Start grouting

1300 Complete grouting & set

Protective casing

grade. ft. below

1330-1430 Decom. Drill pipe

1455 Start Drilling 8" x 15"

1556 Drilling Comp. TD 20'

STARTED Setting MW 15'

Construction

2 1/2" stick pipe

1' bit & 2' sample

2' top of S.P.

5'

15'

TD 20'


8/9/88 Cont'd J. D. Anderson

71. 8-9-58 Contd

1850 Construction now 15' complete

more drill to 8' was 19.

1815 Paper 27 Set



J. R. Anderson 5/19/58

72

8/10/58 Wednesday

Reamed in situ

J. R. Anderson

P. R. Anderson

K. D. Davis

J. R. Anderson

Drill bit

1 on Dorthardt

J. R. Anderson

Bill J. Anderson

Watch Jerry Chen Brown

10-15 K for South.

0640

Apex site

0715

Drill pick up Drill rods

0801

Start drilling 8-11/19

0845

TD 13.5' - Ad. 12' - 13' at

Drill Rod and Set 13' at

bedrock contact well

Plug 8-11/19

0920

Set up 8-11/19 & start

Drilling

1130

3' into bedrock

Completed

Casing into bedrock

73 8/10/88 Contd.

1200 Lunch
 1300 began Constructing Casings & Screen & Sand Packing
 Screen 10'
 Casings 21' Top of Ground
 2.5" stick pup
 Bentonite Seal 1-2'
 Sand Pack 14'
 Grout 15'
 1534 Complete BMU 16. Mass Reg for BMU 17
 1600 start Drilling BMU 17.
 1645 TD 15' BMU 17 well set
 Screen bore @ 12' - 150 x 6' BLS.
 1700 Began setting well.
 Screen 10'
 Blank 4.5'
 Bore set @ 12'
 Sandpack from base to L.S.
 1815 well constr. Complete
 1830 Depart Site.

J. L. Gardner 8/10/88

8/11/88 Thursday

74

Resonator Site
 D. Harpender
 P. K. Reinartz
 J. Shewen
 K. Davis
 Michael Raddy
 J. Bellan
 F. Othardt
 J. Anderson
 B. Erickson
 Weather S! overcast occasional breeze
 ± 5 K. from west.
 0630 Arrive Site prep
 29 at for drill act.
 well casing drilling site
 8 1 2
 0720 TD CE to see Bore @
 0.1 litie for approval
 Bore 5' 4' 6' both sites
 Cleared P.O.B. 15.
 0830 L.S. + U.P. move to Site 2.
 to locate FTA / w/ B.H.
 0900 Move Dig to 8 hrs 54 6 p.

75

8/11/88 Cont'd

Set up.

Cable station
OP 9090

0930 Start Drilling @ 8 hrs 57.5

Also set w/ T. Othard & to

discuss usage of conductor

pipe on the well & 2" well

1100 Returned to Sperry. Completed

Drilling @ 8 hrs 90 @ 130.5

1305 lunch

1336 Return from lunch & started

Completing WP90 - Great Pump

break down - repaired pump

1700 Completed WP90

TD 54'

Screen 5'

Base of Screen @ 50'

Sand pack from 54' to 40'

Gravel @ 38' surface

Bentonite seal 2'

1875 started drilling WP93

1904 TD 21' Completed well

Screen 10-15'

Sand back to 5'

Bentonite seal 3-5'

Gravel to surface

1950 Draped Seals

C. D. Shaden 8/12/88

76

8/12/88 Furlon

0800 Arrive Site

Furnish Site

FS

J. D. Hardin

P. Laine

K. Davis

Mr. Laddy

J. Sherman

Drillers

T. Othard & A

B. Erickson

J. Anderson

Shirland

death. Overcast. Rains and

low west-southwest

Drillers Dean says to move to

Site 2 will set up adjacent.

great truck to help site

0930 met w/ T. Othard & to complete

this study

1100 lunch

1300 Site to office nearby on Keller

C. D. Shaden 8/12/88

77 8/12/88 Contd

to complete exp't again
1513 Started Dilling 2 min 38
TD @ 20' sand set well
@ this location 195 banded
a base will now = 10'
ahead & well

1530 In Steno: Dept Site for
Name

1656 Left Site 2. Thousands tops
cannot complete well.

1720 Departed office.

G. L. Anderson 8/12/88

8/13/88 Saturday

78

0700 Finished Site
Fossil

19 banded

19 banded

K. Davis

M. Ladd

Dilling

J. Anderson

B. Erickson

J. Anderson

Weather Clouds low wind SW
W: SW ~ 20-30 K.

0720 Started Dilling 2 min 38
24 banded TD @ 21'

0755 Stopped Dilling because
lighting.

0910 Finished Dilling

0940 Complete Dilling Start setting
mills. Contrails will not
set well. J.D. H. desert site
to find 55 banded Dilling
mills. 5 min

G. L. Anderson 8/13/88

79

8/13/88 Conf'd

1040 Retired Site Thunderstorm

Leave. Depart Site @ 1200

1200 Ret to office to set up report

for meeting - work on carpenter

for Squaw Lake.

1330 Depart Site.

J. Anderson 8/13/88

Sci

8/15/88 Monday

Diamond Lake Site

J. Anderson

P. Peterson

K. Davis

M. Buckley

Dulle

J. Anderson

B. Buckley

J. Anderson

Weather: Sunny - clear with thin wet

2 5 K.

0730 Start setting well. No. 53

clays. J. Buckley & J.D.H.

go to fault down for clays.

0930 Return to Site 2 complete sets

well 2/mv 38

1100 Complete work

TD 20'

Breakfast 15'-8'

Sand 20' to 2'

Breakfast 5' long 0-2'

Casing 7 1/2"

1115 more 2' 2 mvs 37 Dulle

take 1100 track & split

8/15/88 J. Anderson

82

8/16/88 Tuesday

Personnel on site	
JD Andeman	
P. Klemens	
K Davis	
J. S. Herwin	
M. Bloddy	
T. Miller	
J. Anderson	
B. Etickson	
M. Edwards	
J. Ashtand	
D. Grooms	
- Weather Survey, warm breeze west.	
- P. Klemens & K. Davis w/ 11	
Cont. wait drilling @ site 2.	
J. Herwin & M. Bloddy w/ 11	
begin soil sampling @ site 2	
0635 Arrive site prepare for work	
0715 Driller arrive & complete loading	
Packing of Drill steel for site 2	
0835 Talked w/ Tom Stordvick of	
Harvard. end of construction	

8/16/88 J. Ashtand

8/15/88 Cont'd

1212 start Drilling MW37	
1355 Complete MW37 TD 18.5'	
Installation of	
TD 18.5'	
screen 5-15'	
sand pack 18.5-2'	
Bentonite 0-2'	
Move to MW39	
1617 start Drilling MW39	
1849 Complete MW39	
TD 22.5'	
Screened 4-14'	
SANDPACK 2-22.5'	
Bentonite 0-2'	
1900 Complete well casing & Decan	
All SS centrifuges & pumps	
1915 Depart Site	

8/15/88 J. Ashtand

83

8/16/88 Cont'd

if 8:12 hrs concerning granting of
 permits & mass will grant complete
 plan with Benfante slurry to

grand surface as per MCA Regs.
 If Benfante slurry into Amherst

will complete w/ Benfante

Grand grant. also talked to

B McLeod 208 to discuss

possibility of demolishing if

insurance does not continue funding

project. Approx. target of

Demolish is Saturday 8/20/88. B.

McLeod asked me to talk to T.

Dorlandt & advise that Demolish

may be required.

Talked to T. Dorlandt &

informed him that demolish may

occur & to prepare for possibility

moved to Site 2. & setup an

24 hr

0930 Start Drilling new 20 ft diameter

1030 Drilling Complete TD 20' 17"

will prepare ss casing

12:00 Start 1. and 2. w/ 40

8/16/88 J. L. Gaudin

84

8/16/88 Cont'd

TD 17'

Screen 2-17'

SAND PACK 0-17'

1330 Move to 2 up 7+70

1402 Start Drilling 2 up 70

1553 TD 2 up 70 @ 29'

Begin Construction

Screen back @ 27'

SAND PACK 29-15'

Benfante Slurry 0-15'

Casing 15' to 25' AG

1900 Construction 2 up 70 Complete

Depart Site

8/16/88 J. L. Gaudin

85

8/17/88 windward day

Personnel

J.D. Haidich

P. Kieniewicz

R. Davis

L. Shewell

M. Roddy

Drillers

I. Othman

J. Anderson

B. Eickes

M. Edwards

Weather Cloudy very windy from East

- 20 K. Raining possible.

0640 Arrived site began prep work for Day. P. Kieniewicz &

K. Davis will complete Soil

Sampling @ site 3 & 1 Shewell

& M. Roddy will work

with Drill Rig

Move to site 2 to complete

2 WP 7's. Started Drilling

0900 Completed Drilling 2 WP 7's TD

15' Start WP. Caser

J.D. Haidich 8/17/88

86

8-17-88 Cont'd

TD 15'

Suf WP 8-13'

SANDPACK 15'-3'

Blasthole Shown 0-3'

0940 Construction Complete

Move to Site 2 new 4's

1045 Set Tor Extent in 2 WP 8

to grade and f'd w/ back

hoe

1115 Started Drilling 2 new 4's

1210 TD 20.0'

H.O. est @ 7'

1240 Begin completion of well

Screen 2'-12'

SAND 0-20'

stick up 2.5'

well set 3' lines 15' 2 attempts Screen

& casing, rose 2' 1' cleaned well &

Reset both lines

1505 Complete 2 new 4's turned to 2 WP 8

1605 started drilling

1727 TD @ 28.18'

1735 Begin construction

J.D. Haidich

8-17-88

J.D. Haidich

87. 8-17-88 cont'd

TD 18'

WP Base 17'

Grand Pack 18-8'

Bentley's Slurry 8-8'

1807 Caster 2 WP 8 complete.

1820 Depart Site 2

J. L. Gardner 8/17/88

8/18/88 Thursday 88

Arrived

W.D. Hatcher

R. R. Jensen

M. Kelly

K. Davis

L. Skerwin

D. Allen

W.D. Hatcher

R. V. Oshland

B. Erickson

M. Edwards

J. Ashland

Sunny, clear windy E. 20-25 K
from S.

0645 Arrived office

0700 To CE to contact J. Denney
went to Background Site west
Side of field - Drilling @ Site
supervised

0815 Arrived Hanger 103 Puller

we need ATV to Access Site

Took K. M. Edwards to Site 2 to

get ATV

J. L. Gardner 8/18/88

82	8/18/88	Cont'd
0900	Sgt.	from station arrived to escort drillers to site
0930		Depart Deck area for site.
0950		Start drilling
1040		Stopped drilling @ 12' went into a concrete structure ~ 2'.
		Stopped drilling & got utility to check on str. will move to new str. moved ~ 20' south.
1114		Started Redrilling BG now 42
1120		Hit Concrete str @ 4' stopped Drilling & move location
1230		Stopped drilling 2 1/2' into bedrock
		Met U.O. Hand TD 18 1/2' hit bedrock @ 19 3/4' Move to new location closer to highway
1300		Started Redrilling
1330		Complete Hdy TD 15.5' start saturation
1445		will complete TD 15.5'
		sand 15.5'-0
		Screen 12'-2'
		Core 4.5'
		W. J. Jordan 8/18/88

8/18/88 Cont'd 90

1500	Move to BG MW-13 & set up.
1540	Begin drilling
1650	Complete drilling
1800	will complete TD 24'
	Base of gravel 20'
	SAND 24'-7'
	Bedrock 0-7'
	stick up 2.5'
1802	Back to Bldg 103
1830	Depart site

W. J. Jordan

91

8/19/88 FRIDAY

Personal

JD Anderson

A. R. Eversman

J. Skewin

Mr. Roddy

Peters

J. Anderson

A. Eversman

McEversman

J. Husland

T. Oetlowdt

Weather Sunny Clear Breeze from

East to SK

06:15 Arrived Office

04:50 Calculated HNO₃

Trust # 500791

07:30 Talk over w/ Bob McKeel discuss:

Standardized procedure of art.

Application of to for drilling.

08:00 Drilling to Set to start Drilling

09:30 To Set 3 w/ Mike Roddy to

take HNO₃ readings on hole

J. Anderson 8/19/88

92

8/19/88 Cont'd

While Sail Suppls taken at offsite.

HNO₃ presented readings during

Sampling. New hole on old and

hole w/ be surveyed at this

time

Boring

No

Time

HNO₃ Readings

58

9:40

0 ppm

54

9:43

0 ppm

A1

9:45

0 ppm

A0

9:47

0 ppm

A2

9:49

0 ppm

A3

9:51

0 ppm

A4

9:53

0 ppm

A5

9:55

0 ppm

B4

9:59

0 ppm

55

10:01

4 ppm

B3

10:04

0 ppm

B2

10:06

0 ppm

B1

10:25

0 ppm

49

10:30

25 ppm

C3

10:35

21 ppm

C2

10:37

0 ppm

J. Anderson 8/19/88

93

2/19/88

Boring	Time	HNU
NO	Reading	
C1	10:42	0 ppm
C0	10:44	0 ppm
D0	10:47	0 ppm
D1	10:49	0 ppm
D2	10:51	0 ppm
E2	10:52	0 ppm
E1	10:53	0 ppm
E0	10:55	0 ppm
Q4	10:59	0 ppm
D3	11:02	0 ppm
C5	11:04	0 ppm
S7	11:09	0 ppm
S6	11:11	0 ppm

11:15 Back to site 4 WPC 410 chiller waiting on clamps for Centalgen.
J.D. & M.R. pick up truck for E.S. Chen

12:00 Back to site 4.

12:20 WPC 410 complete will move to WPC 410 near the D.D.C. of Kogen chiller.

John Hudson 2/19/88

94

2/19/88

1335	Begin Construct WPC 410	End 15:05
1354	WPC 410 Complete	2:34
1405	Begin Installation of WPC 410	
1505	Installation Complete	
1457	Complete drilling WPC 410	TD 38'10"
1521	Construction of WPC 410 complete	
	TD 33'10"	
	Swam 22'6" to 32'6"	
	Sandpack 18'6" to 33'10"	
	Bentrite Surface to 18'6"	
2030	Depart Site	

John Hudson 2/19/88

95

8/20/84

SANDHILL

SANDHILL

0645 Hiram's office

Hiram's office

J.D. Hardin

P. R. Hardin

M. R. Hardin

J. S. Hardin

D. Hardin

John Hardin

Tom Othardt

Bill Erickson

M. R. Erickson

Weather Clear - Warm Breezy - Sun

Sight - 10-15 K

0750 Start Dredging M. 22 Site 4

P.R., M.R. & J.S. Hardin - with complete

of water & water, J.D. at water level

on Dredge log sheet & total

0330 P.R. Hardin to office - Dredging complete

with water, with data of

Self well

TD 35'

Sieve 33-25

Sand Pit 35 to 19

S. Hardin 0-19'

8/20/84 J.D. Hardin

96

8/20/84 Can. L.H.

1121 1st Station Complete

1131 1221 1221 1221

1231 1231 1231

1341 1st Station Dredging 1221

1451 TD 22.5' 1221 1221

1501 1st Station in 1221

1501 1st Station in 1221

1611 1st Station Complete

TD 22.5' BR @ 19'

Sieve 12-20' 1221 1221

Sieve 12-20' 1221 1221

Sieve 12-20' 1221 1221

1631 1st Station Complete & Home 1221

J.D. Hardin 8/20/84

97

5/22/88

Mauldin

0640 Arrived office

P. H. H. H.

J. D. H. H.

P. H. H. H.

M. H. H. H.

L. H. H. H.

D. H. H. H.

J. H. H. H.

B. H. H. H.

M. H. H. H.

12051 left office 8:30 to CE to

request escort for wife along

highway

0715 Back to office

0754 Drilling ready to start - still

waiting in escort from Harris

0815 Escort Arrives

0815 Start Drilling, WP11D

0922 TD 25' Fuel 3' to be drilled in

bedrock casing + 1/2" casing

1030 Drilling complete @ 35'

Begin well construction

TD 25'

Sump 27-32' Denton 0-21.5'

J. H. H. H. 8/22/88

98

5/22/88 Cont'd

1130-1230 Lunch

1230 Start Drilling WP13S

1310 stop drilling WP13S TD 230'

1415 Start Construction

1415 Complete WP12S

Sump 9'10" - 14'10"

Sand Pack 20'-4'

Denton 0-6'

1435 Start drilling WP13D

1520 stop drilling TD 25'

Start Construction

1617 WP13D Complete & Start

Drilling WP13S

1635 TD WP13S 0-11'

Construction

Sump 5-10' 2 1/2" casing

Sump 2-11'

Denton 0-2'

1720 Construction Complete

1740 Depart Site

100

5/23/88 Cont'd

1045	5. top WP 145	
1050	Drilling Complete TD 12'	
	4. start Construct	
	TD 12'	
	Screen 5-10'	
	SAND 2-12'	
	Bank 0-2'	
1124	Complete Construct WP 145	
	Lunch	
1230	Return for lunch set up to	
	4 WP 150	
1242	start Drilling 4 WP 150	
1400	TD @ 31.6"	
	Stand well Construct	
	Screen 25.6" to 30.6"	
	SAND 24.6" to 31.6"	
	Gravel 0-22.6"	
1518	Complete Construct 4 WP 150	
1540	start Drilling 4 WP 155	
1610	Drilling Complete TD 17'	
1615	Begin Construct	
	Screen 10-15'	
	SAND PACK 6-17'	
	Bank 0-6'	

Oil Harder 8/23/88

99 5/23/88 Tuesday

	Completed	
	1. D. Harmon	
	2. M. Cleach	
	P. R. Harmon	
	M. Peckley	
	L. Skamion	
	Driller	
	L. Adams	
	B. Erickson	
	M. Pinnick	
	J. Harland	
	weather clear cool w/ breeze --	
	10k for South to west	
0650	Harmon Site waiting Escort for	
	Driller	
0825	Escort Arrived Bldg 103	
0835	start Drilling WP 140	
0955	Drilling Complete TD 27.5'	
1000	Begin Construct	
	Screen 20-25'	
	SAND 16.5-27.5	
	Bank 0-16.5	
1032	Complete Construct WP 140	

Oil Harder 5/23/88

101 8/22/85

1642	Consolid. Complete	2/10/155
------	--------------------	----------

16-53 Allgemeine Kasse in Paris

1755 .. 24th, SkatAgc Edward Hall

② This has been the meaning:-

1800 Depart Site

Q. Jordon 8/23/88

122

8/21/88 Wednesday

Richard

W.D. Hardin

K. McLeod

W. Kestel

1. Secum

دیکھو

1. Cid theodot	1	1
----------------	---	---

20	1	Handwritten
----	---	-------------

Dr. C. C. C. C.

[illegible]

more at 1600 w/ Shasta Bros.

0745 T. Oathardt ~~from~~ ^{to} ~~the~~ ^{the} Talk

w/ a mixed of LDH. Duller

UDH 5/24/44
Action "Dinner Complicity Claims"

of the line Capt.

Служба безопасности

0930 Boats Complete TD 37!

10/10	Began with copy letter		
-------	------------------------	--	--

	10	37'		Square 25-35
	-	L.	'	

3000	21-31	
6	14	21

[illegible]

130 water capress

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

for Garden 8/24/88

10:3

8/24/88 Contd

12-1300 lunch

1340 Set up @ 3mw25 area low -

Drill & H₂O track stuck, will
relocate hole around existing
utility & drill @ later date

1524 set up @ 3mw27 & start drilling

1605 Drilling complete TD 15'

1638 stuck well complete

TD 15'

Seven 2-12'

SANDPACK 0-15'

1811 3mw27 complete

1840 depart Site

J. L. Hardin 8/24/88

8/25/88 Thursday

104

Personnel on Site

J. D. Hardin

R. McLeod

M. Reddy

J. L. Shaw

Drilling

J. Anderson

B. Erickson

M. Rasmussen

Craig Othard

T. Othard

Weather Clear & Cool, breeze ≈ 10 K for 5

0700 Arrive Base

0800 Set up @ 3mw35

0930 Drilling complete TD @ 25'

Hole incomplete hit boulder

@ 7.5' moved hole $\approx 10'$

300 ft

0953 Started Redwell

1025 Drilling 14' break in drilling for fuel

1045 Restart drilling

1145 Drilling complete TD 17'

1150-1250 Lunch

J. L. Hardin 8/25/88

105

5/25/88 Cont'd.

1250 Begin well construction 3 MW25

TD 17'

Screen 2-12'

SAND 0-17'

Well damaged during construction

Screen \approx 6" below grade. well

Reset well.

1405 Begin reconstruction.

1600 Construction Complete.

1635 Fence replaced along backside

1657 Depart Site

D. L. Hardin 8/25/88

106

5/26/88 Friday

Pinned.

L. D. Hardin

M. Roddy

L. Shuman

Duller

L. Anderson

B. Erickson

C. Oathardt

weather clear to P.C. Cool &

breezy

0700 Appx. Office M.R. L.D.H.

well drill new @ Site 3

L.S. will stay w/ C. Oathardt

on development area

0750 Sit up on 3 MW25.

0902 Duller Complete TD 18'

0909 Start construction 3 MW25

0945 Construct Capplate

TD 18'

Screen 6-16'

SAND 3-18'

Perforate 0-3'

D. L. Hardin 8/26/88

109

8/27/88

1225 Begin Casita
TD 15'

Screw 2-12'

SAND 6-15'

1257 Casita Complete

1330-1415 lunch

1425 start Drilling Borewell 33

1452 Begin Drilling

1600 Drilling Compl TD 24'

1619 J.D.H. Departs Site to

End 84

1700 J.D.H. Returns

1725 well Casita Complete

TD 24.5'

Screw 12'-22'

SAND 9-21.5'

Sherry 8-9'

Departs Site

1736

D. J. Hardin 8/27/88

110

8/28/88

Sunday

1200 Meet with Catharine &

Site to discuss well

Completion & drilling

1300 Departs Site

D. J. Hardin 8/28/88

111

5/22/58 Monday

W. C. C. C.

W. D. H. H.

M. K. K.

J. S. S.

D. L. L.

C. O. O.

J. A. A.

B. E. E.

Went to C. C. to P. C. Cool Calm Bay

0640 Arrive Site & begin prep
for day. Diller will begin
3 new 34" when they arrive

1040 C. O. will demolish
wells.

0730 Called ATL. Talked to
S. Skulte if residential needed
hand pump on site to help
w/ development. Diller still
not on site.

0745 Diller arrive on site &

more to Site 3, still open

0805 4.1 (cannot count the li

at. H. H. 5/23/58

112

5/23/58 Monday

W. C. C. C.

W. D. H. H.

M. K. K.

J. S. S.

D. L. L.

C. O. O.

J. A. A.

B. E. E.

Went to C. C. to P. C. Cool Calm Bay

1348 Consta. new 34" complete
1430 Set up 8" new 32"
1450 Start Drilling new 32"
1558 TD 22.5' Begin Consta.

TD 22.5'
Sun 17-7'
SAND 4' 22.5'

Buttild 0-4'
BLANK 6.5'

1753 Pass to Canal
1800 Depress site

1800 Depress site

1800 Depress site

1800 Depress site

at. H. H. 5/29/58

8/30/88 Tuesday

Personnel

J. Anderson B. Kleck

M. Ruddy P. Brown

A. Sherman

Drillers

C. Oathardt M. Resnick

J. Anderson

B. Erickson

Weather Cool, P.C., S. breeze

0645 Arrive @ office Set up

Crew for day M. Ruddy &

S. it will continue drilling

J. Sherman w/ work w/ Gary

Oathardt. Developing well.

0745 Set up 2nd 2nd 2nd 2nd 2nd 2nd

had to stop for 1st 2nd 2nd

drilled to 7' & stopped hole

not straight very off boulder

hole started & stopped 3 times

0800 Contacted director of DPMO @

Savannah in Indiana & advised

situation & requested to move

hole to east of drive was explained.

8/30/88

Jul. Sanchez

8/30/88 Tuesday

0920 Set up operations down

stand drilling

1000 T.D. 3 in 2.7 (2.6)

1 Begin small cavity.

Screen 2-12'

Sand 0-16'

Blank 4.5'

1040 Casing Sample to

1102 Set up new 30' stand

drilling.

~~1115~~ T.D. 15' of comp. casing.

T.D. 15'

Screen 2-12'

Sand 0-15'

Blank 4.5'

Casing was completed @ previous

hole. This was Redwell &

Resample - Dig samples

Broken

Set up inside DPMO to collect

samples @ Soil Gen. location

1144 - 1151 S.E.D. 3 - 3' depth

1158 - 1200 S.E.D. 3 - 3' depth

1200 - 1220 Collected & bottled samples

Jul. Sanchez 8/30/88

1:15 8/30/88 Tuesday

12:20 lunch
13:00 Return from lunch will
Decon Rig & move to
Site 2 to Redwell 2BH1 &
2BH2.
14:50 Decon Complete & move @
Site 2. stopped @ FED EX
on way to site.
15:05 Set up 2BH2 start drilling
15:58 BT TD 27' @ Bedrock
16:02 Set up 2BH1 start drilling
16:29 BT TD 24.5'
Samples collected from 2BH1
& 2BH2 Replace Sample
Presumably collected @ this
site lab extended holding
times.
16:30 Preparing & Packaging Samples
for shipment
17:55 To Fed EX.
18:55 Complete cleaning in office &
Depart site

C. D. Anderson 8/30/88

8/31/88 Wednesday

Personnel
J. D. Anderson R. Brown
M. Ruddy
J. Sherman
Driller
J. Anderson
B. Erickson
G. Oathead
M. Razuski
J. in
Weather Cloudy, cool & breezy
will complete Drilling &
Begin well completions
M. Ruddy will complete drilling,
clean site, JS will continue
development
0758 Start Redrilling MW14.
0820 TD 25'
after completion of drilling
I met w/ T Oathead &
discussed completion work
to be finished this week!

8/31/88 J. D. Anderson

9-1-88 Thursday 118

Personnel
 J. D. Hardin
 M. Roddy
 J. Skene
 Miller
 J. Anderson
 A. Erickson
 G. Oothardt
 M. Kozuski
 T. T. T.
 Weatherclady Coal, Brazy
 0700 Arrive office & meet w/
 DeWitt & discuss day activities
 M. Roddy with Spudger w/
 Miller & J. Skene
 in well development
 J. D. H. will continue checking
 well and out sheet
 0830 Leave office & visit Mine
 check locations to check
 completion progress

J. D. Hardin 9/1/88

117

Anticipate completion of all
 work of development by
 Saturday Sept 10 in morning
 Sept 10. All work would be
 complete except for locks
 which have been ordered. They
 should be in during week of
 9-16-88.
 T. Oothardt departed Site ~
 Noon
 J. D. H. spent remainder of
 afternoon inspecting muck
 & sites for completion.
 1830 Depart Site

J. D. Hardin 8/31/88

119 9/1/88 Contd

1130 Lunch break

1230 Return from lunch will

continue checking wells sites

1600 Catch place to A.T.C. after

giving sign off sheet to

P. Piciniano. Will check

well capl on Wellers last

day



9/1/88

120

9-7-88 Wednesday

J.D. Haden

J. Schultz

J. Schen

M. Kaddy

K. Davis

J. Baker

J. O'Brien

10300 Arrived site weather

clear. All personnel on

site. Will help show

Schultz setup & complete

sampling.

1300 went to pick up equipment

for sampling crew. Battery to

operate pump cables, & pump

for sampling crew.

1330 Returned to site lunch.

1400 Returned to work. Returned to

office for supplies & continued

helping sampling crew

about to purchase Universal

1740 Returned to office too

late to pull chemicals to

9/7/88

12-1 9/7/88 Cont'd

in Sample Cores

1800 Pumped bottles + math's for
next day sampling. Made
labels.

1930 Departed Site. Picked K. McLeod.

Del Hardin

9/8/88

Personal

J. Hardin P. McLeod

S. Schultze J. Beerlin

P. Krenner M. Roddy

K. Davis J. Oliver

Kobath - Cool & Clean, Druggery

0700 Arrived at office. Sampling
Cores w/ Chertini w/ purged
wells. P. Krenner & M. Roddy

4:00 Chertini purging wells.

S. Oliver & J. Davis will purify

5 kg tests on Sediment wells.

Will purify 5 kg in 5 kg

out tests on all wells.


where tests are performed.

Note: will be kept in

5 kg test vials.

Del Hardin 9/8/88

TRIGONOMETRIC FORMULÆ



Solution of Right Triangles

For Angle A.	$\sin A = \frac{a}{c}$	For Angle B.	$\sin B = \frac{b}{c}$
Given	a, b	Given	A, B, c
Required	A, B, c	Required	a, b, c
a, c	$\tan A = \frac{a}{b}$	A, a	$\tan A = \frac{a}{b}$
A, a	$\sin A = \frac{a}{c}$	A, b	$\sin A = \frac{a}{c}$
A, b	$\cos A = \frac{b}{c}$	A, c	$\cos A = \frac{b}{c}$
A, c	$\sec A = \frac{c}{b}$		

Solution of Oblique Triangles

Given	A, B, a	Required	a, b, c
A, a, b	$\sin B = \frac{b \sin A}{a}$	A, B, c	$\sin A = \frac{a \sin B}{c}$
A, B, c	$\sin C = \frac{c \sin A}{a}$	A, a, c	$\sin B = \frac{b \sin A}{a}$
A, a, c	$\sin C = \frac{c \sin A}{a}$	A, b, c	$\sin B = \frac{b \sin A}{a}$
A, b, c	$\sin B = \frac{b \sin A}{a}$		
A, c	$\sin C = \frac{c \sin A}{a}$		

REDUCTION TO HORIZONTAL

Horizontal distance = Slope distance multiplied by the cosine of the vertical angle. Thus: slope distance = 319.4 ft. Vert. angle = 5° 10'. From Table, Page IX, $\cos 5^\circ 10' = .9869$. Horizontal distance = $319.4 \times .9869 = 315.09$ ft. Horizontal distance also = Slope distance minus slope distance times (1 - cosine of vertical angle). With the same figures as in the preceding example, the following result is obtained. $\cos 5^\circ 10' = .9869$. $1 - .9869 = .0131$. $319.4 \times .0131 = 4.18$ ft. When the rise is known, the horizontal distance is approximately the slope distance less the square of the rise divided by twice the slope distance. Thus: rise = 14 ft. slope distance = 302.6 ft. Horizontal distance = $302.6 - \frac{14 \times 14}{2 \times 302.6} = 302.6 - 0.32 = 302.28$ ft.

MADE IN U. S. A.

46' 7"
7' 1 1/2"
34 5 1/2"
20
19' 5 1/2"

28' 1 1/2"
4' 1 1/2"
= 19 -

Table 5' 2" a TOS
Total Depth 31' Bottom Casings
50' to top of table

36.8'
- 14' SANDPACK
22.8' from top of table

6.3" table
35' 10' 5000
41.3" table top
575' Camp & screen

41' 3" from table top
- 14' 273' Top of Sand Pack

Q.2.2 Notebook 2, Rig No. 1

This notebook contains notes of the drill rig geologist.

Entries were made by Peter Riemersma, Jo-Ann Sherwin and Mike Roddy. One hundred and seven pages were used; several pages in the back were used as scratch sheets. The first entry was 26 July 1988 and the last is 2 September 1988. The pages are signed by Peter E. Riemersma, Mike Roddy and Jo-Ann Sherwin.

This page intentionally left blank.




DULUTH RNCB
Project No. 00001
Book No. 2
RIG NO. 1

GEOLOGIST PETER
REHERSMA

DISTANCES FROM SIDE STAKES FOR CROSS-SECTIONING

Roadway of any Width. Side Slopes 1 1/2 to 1.
 In the figure below opposite 7 under "Cut or Fill" and under 3 read 11.0, the distance out from the side stake at left. Also, opposite 11 under "Cut or Fill" and under 1 read 16.7, the distance out from the side stake at right.



Cut or Fill	Distance out from Side or Shoulder Stake										Cut or Fill									
	0	.1	.2	.3	.4	.5	.6	.7	.8	.9	0	1	2	3	4	5	6	7	8	9
0	0.0	0.2	0.3	0.5	0.6	0.8	0.9	1.1	1.2	1.4	0	1	2	3	4	5	6	7	8	9
1	1.5	1.7	1.8	2.0	2.1	2.3	2.4	2.6	2.7	2.9	1	2	3	4	5	6	7	8	9	10
2	3.0	3.2	3.3	3.5	3.6	3.8	3.9	4.1	4.2	4.4	2	3	4	5	6	7	8	9	10	11
3	4.5	4.7	4.8	5.0	5.1	5.3	5.4	5.6	5.7	5.9	3	4	5	6	7	8	9	10	11	12
4	6.0	6.2	6.3	6.5	6.6	6.8	6.9	7.1	7.2	7.4	4	5	6	7	8	9	10	11	12	13
5	7.5	7.7	7.8	8.0	8.1	8.3	8.4	8.6	8.7	8.9	5	6	7	8	9	10	11	12	13	14
6	9.0	9.2	9.3	9.5	9.6	9.8	9.9	10.1	10.2	10.4	6	7	8	9	10	11	12	13	14	15
7	10.5	10.7	10.8	11.0	11.1	11.3	11.4	11.6	11.7	11.9	7	8	9	10	11	12	13	14	15	16
8	12.0	12.2	12.3	12.5	12.6	12.8	12.9	13.1	13.2	13.4	8	9	10	11	12	13	14	15	16	17
9	13.5	13.7	13.8	14.0	14.1	14.3	14.4	14.6	14.7	14.9	9	10	11	12	13	14	15	16	17	18
10	15.0	15.2	15.3	15.5	15.6	15.8	15.9	16.1	16.2	16.4	10	11	12	13	14	15	16	17	18	19
11	16.5	16.7	16.8	17.0	17.1	17.3	17.4	17.6	17.7	17.9	11	12	13	14	15	16	17	18	19	20
12	18.0	18.2	18.3	18.5	18.6	18.8	18.9	19.1	19.2	19.4	12	13	14	15	16	17	18	19	20	21
13	19.5	19.7	19.8	20.0	20.1	20.3	20.4	20.6	20.7	20.9	13	14	15	16	17	18	19	20	21	22
14	21.0	21.2	21.3	21.5	21.6	21.8	21.9	22.1	22.2	22.4	14	15	16	17	18	19	20	21	22	23
15	22.5	22.7	22.8	23.0	23.1	23.3	23.4	23.6	23.7	23.9	15	16	17	18	19	20	21	22	23	24
16	24.0	24.2	24.3	24.5	24.6	24.8	24.9	25.1	25.2	25.4	16	17	18	19	20	21	22	23	24	25
17	25.5	25.7	25.8	26.0	26.1	26.3	26.4	26.6	26.7	26.9	17	18	19	20	21	22	23	24	25	26
18	27.0	27.2	27.3	27.5	27.6	27.8	27.9	28.1	28.2	28.4	18	19	20	21	22	23	24	25	26	27
19	28.5	28.7	28.8	29.0	29.1	29.3	29.4	29.6	29.7	29.9	19	20	21	22	23	24	25	26	27	28
20	30.0	30.2	30.3	30.5	30.6	30.8	30.9	31.1	31.2	31.4	20	21	22	23	24	25	26	27	28	29
21	31.5	31.7	31.8	32.0	32.1	32.3	32.4	32.6	32.7	32.9	21	22	23	24	25	26	27	28	29	30
22	33.0	33.2	33.3	33.5	33.6	33.8	33.9	34.1	34.2	34.4	22	23	24	25	26	27	28	29	30	31
23	34.5	34.7	34.8	35.0	35.1	35.3	35.4	35.6	35.7	35.9	23	24	25	26	27	28	29	30	31	32
24	36.0	36.2	36.3	36.5	36.6	36.8	36.9	37.1	37.2	37.4	24	25	26	27	28	29	30	31	32	33
25	37.5	37.7	37.8	38.0	38.1	38.3	38.4	38.6	38.7	38.9	25	26	27	28	29	30	31	32	33	34
26	39.0	39.2	39.3	39.5	39.6	39.8	39.9	40.1	40.2	40.4	26	27	28	29	30	31	32	33	34	35
27	40.5	40.7	40.8	41.0	41.1	41.3	41.4	41.6	41.7	41.9	27	28	29	30	31	32	33	34	35	36
28	42.0	42.2	42.3	42.5	42.6	42.8	42.9	43.1	43.2	43.4	28	29	30	31	32	33	34	35	36	37
29	43.5	43.7	43.8	44.0	44.1	44.3	44.4	44.6	44.7	44.9	29	30	31	32	33	34	35	36	37	38
30	45.0	45.2	45.3	45.5	45.6	45.8	45.9	46.1	46.2	46.4	30	31	32	33	34	35	36	37	38	39
31	46.5	46.7	46.8	47.0	47.1	47.3	47.4	47.6	47.7	47.9	31	32	33	34	35	36	37	38	39	40
32	48.0	48.2	48.3	48.5	48.6	48.8	48.9	49.1	49.2	49.4	32	33	34	35	36	37	38	39	40	
33	49.5	49.7	49.8	50.0	50.1	50.3	50.4	50.6	50.7	50.9	33	34	35	36	37	38	39	40		
34	51.0	51.2	51.3	51.5	51.6	51.8	51.9	52.1	52.2	52.4	34	35	36	37	38	39	40			
35	52.5	52.7	52.8	53.0	53.1	53.3	53.4	53.6	53.7	53.9	35	36	37	38	39	40				
36	54.0	54.2	54.3	54.5	54.6	54.8	54.9	55.1	55.2	55.4	36	37	38	39	40					
37	55.5	55.7	55.8	56.0	56.1	56.3	56.4	56.6	56.7	56.9	37	38	39	40						
38	57.0	57.2	57.3	57.5	57.6	57.8	57.9	58.1	58.2	58.4	38	39	40							
39	58.5	58.7	58.8	59.0	59.1	59.3	59.4	59.6	59.7	59.9	39	40								
40	60.0	60.2	60.3	60.5	60.6	60.8	60.9	61.1	61.2	61.4	40									

For Curve Tables see end of book.

KEUFFEL & ESSER CO.

Return TO, Robert S. McLeod
 Engineering - Science
 710 S. Illinois Ave.
 Suite F-103
 Oak Ridge, TN 37830
 (615) 481-3920



The paper in this book is
 made of 50% high grade rag stock with
 a WATER RESISTING surface sizing.

KEUFFEL & ESSER CO.

3

Sampling Equipment Utilized

Item	Egpt.	Asset #	Serial No.
1	HNU PI 101 Field PID	566791	

4

DATE 7-26-88

E.S. Personnel on Site

F.T.L. John D. HARDEMAN

Geol: Peter Riemersma

Geol: Jo Ann Sherwin

Eng. Kim DAVIS

North Star Drilling

Tom Cothoudt owner

Bill Erickson HSC

John Anderson Driller

1400-

Rig Decontamination, steam cleaning,
soap wash with Liguinox

1535

Used Quic-Kut by Geraco for wash for 5 minutes

Personnel Decanning

Mike Edwards

Bill Erickson

Jeff Ausland

Dan Graves

1547

Working on getting soap to flow, try
putting it up above valve, switch back to

At Liguinox

1600

run Liguinox through steam cleaner
drain for decon. area is backed up

1803

put diesel fuel in steam cleaner for heater
pump runs on electricity

1830

water problems → pressure loss

7-26-88


Peter E. Riemersma

5

trying to switch hose at fire hydrant, may be
high water usage, time


1855

Leave the field, drill crew in process of leaving
due to water loss



7-26-88 Peter Rumsdorn

6



7 Date 7-27-88

ES. Personnel

John Harelemann
Peter Riemersma
Kim DAVIS
Jo Ann Sierwin

7:30 arrive on site

PLAN Jim D. and John S. will go measure water levels at site 2.
John H and Peter R. will observe decon of equipment

7:56 Rig decontamination continues. Mike Edwards, Bill Erickson and John Edwards per Anderson decontam. Mike E. says they started at 7:00 AM. Steam cleaner water temp 230.
Tom Sturdivant and Dennis Forsberg arrive. They examined Colligan water purification system

8:22-9:04 John H arrives at DeCon Rig. Peter R. goes to decon 4 pieces of tubing from Colligan Supply (cylinder). Decontamination Procedure involves
1) Lignox wash with brush
2) thorough rinse with potable water
3) thorough HPLC water wash and rinse

Methanol rinse was omitted due to concerns of ES (John H) and Dennis F. of reaction with plastic.

Decon complete / Peter E Riemersma

9:10 observe decontamination of rig

7-27-88 Peter E Riemersma

7-27-88

AS 142

8

10:20 John H. comes to pre-inspect cleaning of rig.

11:22 We are turning soap off for final.

RINSE (Bill Erickson, Mike E and Peter R.)

11:45 Final Rig Decontamination completed

Accepted by Peter Riemersma

total steam clean hours for rig 14.25 hrs

12:00-2:00 LUNCH

2:00 PM John H. steam cleaning North Star Flatbed

Peter R. and Bill E. work on deionized water backup

2:28 PM Truck with barrels arrive

3:29 PM Start to clean white schedule 40 PVC

Procedure Steam clean with ALQUINOX (outside)

(use snake for inside). Steam clean water (outside and inside)

Methanol rinse (car and in)

DI organic free rinse (out and in)

Start of cleaning of PVC positioned, need more diesel fuel for steam heater

4:11 Truck returns with diesel fuel, Mike continues cleaning truck with cold water

4:30 Start cleaning white PVC (procedure above)

4:45 want to attach snake for PVC internal wash

4:58 Tom S. + Dennis F. and John H. arrive

We notice a small cylinder leak? valve from

Jack - John A took care of problem per suggestion

7-27-88 Peter E Riemersma

by Tom S. of HAZWAP - put a bucket with an absorbent below the
jack to hold leaking fluid.

5:34 Several areas on rig appear dirty when tower

is raised. John A. is cleaning it.

6:15 John A. and Peter R. leave site.

7-27-88 Peter E. Remersma

7-28-1988

10

ES Personnel @ Site

Peter Remersma

John Hardeman

Kim Davis

Jo Ann Sharwin

HAZWAP Personnel

Tom Sturdivant

Dennis Forsberg

7:55 Peter R. arrives on site, delays due to

dead battery on Van. Kim D and Jo Ann S.

work on water levels. John A. discusses

rig fluid leaks with John H. Suggests that if

rig is leaking this much without any pressure it

might leak more under pressure. Tentative decision

is reached to bring in another rig. Mike E. sprays

off rig

Well point PVC casing has been steam cleaned

and rinsed and put all together under plastic by

Mike E. and Bill E.

8:47 John A. starts down procedure per work plan

(Steam clean with foam, steam rise, methanol and di-organic

free water). Cleaning 16 drill pipe 3 1/2 inch outer

diameter 1.5, 1 3/4 inch 20' (2 1/2 pipes together)

9:28 Bill E. and Mike E. are breaking pipe 20 foot

sections in preparation for cleaning

7-29-88 Peter E. Remersma

11

7-28-88

10:10 AM Bill E. is wrapping up in plastic total of

6 3 1/2 inch drill pipes and 2 smaller pipes

each tool is being wrapped individually in case of need. Decontamination complete Peter E. Remmer

John is working on 1 7/8 inch pipe we will

use of them in drilling.

10:40 John A and Mike E. work on rig. Bill E. finish wrapping pipes described above.

11:20 Met Sgt. Dennis. no message. Meet with FRA at

12:30 - message for John H.

11:27 Break for Federal Express punch

1:35 PM Danny Graves replaced seals on controls and said he put seals on. Mike E. steam cleaning rig. They said augers were not done yet

1:55 Tom S. and John H. came to take a look at new seals and plugs.

3:28 Wrapping in plastic 10 1 7/8 drill pipe plus 4 other tools Decon procedure as follows 1st Steam clean with Alginox (outside) 2nd Steam clean water rinse (outside and inside).

3rd methanol rinse

4th DI Rinse

Drill pipe will be used with split spoon sampler. Decontaminated same as above two split spoon samplers with attachments.

7-28-88

Peter E. Remmer

12

Decontamination of 10 1 7/8" drill pipes

2 split spoon samplers & misc tools (6) complete per work plan.

Peter E. Remmer 7-28-88

3:39 11 10 6 5/8 ID diameter hollow stem augers

12 4 1/4 ID diameter hollow stem augers have come back from the sand blasters and are being unloaded

4:20 New bit for hollow stem auger is being put on. Hollow stems steam washed with soap

4:45 Jack Ausland cleaning up sludge and putting in drum

5:41 Decontamination of 13 hollow stem augers clean per work plan.

Confirmation by Peter E. Remmer 7-28-88 wrapped together in plastic and put in labeled trailer

6:00 Left Decon area with site

Peter E. Remmer

7-28-88

13

7-29-88

6:30 AM arrive at office on site, clean up
Van and prepare for day. Partly cloudy
with very light sprinkles.

To Ann will go down to measure water levels

6:30-7:45 Loading van up with supplies

8:05 John A. washing wheel buggy ring

9:30 Went to drop Kim off to help Jo Ann

Dan Graves arrives with shur, final preparations
for going to Site 2

Show drillers Site 2 Fire training area number 2

They are in the process of moving their
equipment over here, Told them about J568A.
Stopping and looking for airplanes when driving
on the dirt road near the runway approach.

Waiting for rest of drill equipment to come.

D. Graves is setting his rig up near center
of FRT No. 2

11:00 Augers and other drill pipe arrive

11:55 Phil E. goes to get water truck

in procedure for Mason jar samples

2-BH-1 SS-1, Fstage

HNU Procedure

(HA) 1) take reaching when cap of auger is taken off

(HB) 2) take reading of breathing space

1:11 PM Drillers prepare for drilling

7-29-88 Peter C. Rimmerman

7-29-88

14

1:20 Work on getting Sample 2-BH-1 SS-1 0-2.
requires two split spoons due to poor
recovery. 2 jars sent - 1 liter and 40Z

2:12 taking SS-2 at Site 2 BH-1 40Z bottle
SS-2 1 liter co. from 2-6' actually

HNU reading at top of split spoon is 150 ppm

2:40 Took HNU reading in bottle - maximum of

7 ppm - Oppen in breathing zone

2:55 PM poor recovery of 4-6" not enough

sample to send to lab, do get HNU reading

of split spoon top of 175 ppm

3:49 Drillers back from getting 5' drill pipe

4:08 Took 40Z sample 65-4. HNU reading

at split spoon tip upon opening was 225 ppm

4:340 collected SS-5 sample to go to lab

because of HNU reading of 175 ppm

in split spoon

5:20 leave Site 2 for day, storm approaching

Kim D. and John H. go to Fed X

5:00-5:45 Peter R. decons 5 stainless

steel buckets

7-29-88 Peter Rimmerman

15

7-30-1988

6:35 AM arrive at office, calibrate HNU working
no page 5-501 ASSET 164746 Pick + SORZEE spin setting
inamer 0.5. clear

7:10 arrive at site. Jeff A. and Bill E. already
at site

7:40 start drilling - piling upper down BH1

ES Personnel John H

Peter

Kim D

North Star Mike E

Dan G.

Bill E.

Jeff A.

John A.

7:52 45 ppm down hole at top of upper fly, it
measuring zone less than 1 ppm

8:04 Hammer on rig breaks down

9:22 Hammer is ready and was welded

ready to start pounding split spoon in

9:39 Took analytical sample at 10-12 SS-b

at water table split spoon headspace
5 ppm

10:14 Sample SS-7 taken, slight petroleum smell

5 ppm split spoon headspace,

10:45 SS-7, clay, no color, puffy, mass for
sample taken

7-30-88 Peter E Rimmerman

7-30-1988

16

11:22 pull out of hole at 16' due to major
refusal, lost 4 feet Probable
boulder.

13:06 Back from Lunch (11:30-13:00)

Move rig to BH-2

13:28 Start hammering in SS-1 in BH2 0-2'

13:37 Take sample SS-1 BH2 SS Head = 90 ppm
(SS Head = split spoon headspace)

13:50 SS-2 sample down hole + put in mason jar

14:05 SS-3 sample taken in mason jar

14:23 SS-4 sample, high SS head reading, sending
sample to the lab. Need to take another
sample in same interval for lab samples.

15:00 SS-6 taken, sent to lab, estimated location
of the water table

15:10 SS-7 taken, very moist to wet, at or
below water table

15:30 SS-8 taken, very wet, various sandy silt
zone

Only 18" of split spoon hammered
before refusal

15:50 SS-9 cobb. wet and clay on clay depending
on proportion of sand and clay apparently

16:13 Attempt taking sample 18-20 but
boulder in the way

7-30-88 Peter E Rimmerman

17

16:36 Clean up site

17:20 Leave office

7-30-88 Peter E Riemann

18

8-1-88

Weather cloudy, occasional sprinkles,
possible heavy rain6:00 AM Arrive at office, start packing and
decon bucket

6:16 Calibration of HNU Asset to 164716 and

H.7 ex Asset no. 501288 to 94.7 MM

Isobutyl standard

6:15-6:50 Decon 5 stainless steel buckets Acrodine

McQuibb Wash w/ brush

potable water rinse

methanol

D. 1 ionized 8-1-88 Peter E Riemann

7:16 Arrived at Site 2, Schramm Rig (Covers)

7:43 55-10 only 4" recovery! before refusal

7:51 Auger refusal, bedrock at 2.1, pulling
augers out of borehole

8:31 Start Setup at Well point 6 name of well

DANG 2 - WP 6 - shallow Schramm Rig (Gravel)

9:41 Pang and Jeff Aus arrive. Start work WP-6

Drill Crew Mike E

Jeff A

Dan C.

ES Peter R.

Kim D.

9:49 57 55-1 taken

10:17 55-2 taken

10:40 No split spoon sample taken at 10-12

8-1-88 Peter E Riemann

19

8-1-88

due to auger refusal, try to auger past obstacle

11:00-12:00 Lunch

12:24 Move WP-6 location 7' west to a new location to attempt to drill below 10' obstruction at earlier borehole.

12:52 Borehole 10' - 14" split spoon 10-12 at new location

13:03 SS 3 WP 6-2 (second, adjacent hole)

13:47 No split spoon taken at 15-17 due to racks and probable refusal, will try to auger past obstruction then split spoon

14:15 Still trying to auger past obstruction

14:40 stop at 17', wait for John H. to come back

Scattered flume debris nearby. Wait for additional grouting equipment to come

17:25 Grouting material arrived, mix more to B4-1 to to grout the holes. UP, work on getting fittings put on

Grout CALS 2 lbs bent 100 lbs cement

Paul 6 gallons of water per 100 lbs

8" borehole 2 gallons to the fast

RETIAL mixture

14:41 Lehigh Portland Cement Type 1A 94 lbs net

add ~ 10 lbs bentonite 1/5 bag

ill

pump fan belt broke

8-1-88 Peter E. Kiemenner

8-1-88

20

19:11 bore giant area Site 2

8-1-88 Peter E. Kiemenner

21

8-2-88

6:00 Arrive at office. Very cloudy and raining.
 6:52 Calculated 1744 ASST NO. 164716 and broke.
 501288 to 44290 1500 ft line mixture
 span set at 8
 7:40 Jeff A and Mike E go to fill water truck w/o
 Peter K., Bob McKeep and John H look for
 NW-3. Kim D and John S go to transport
 FIH NO. 2 wells
 8:56 Help John S and Kim D, pressure in wells
 9:19 NW-6 Construction
 1 1/4" Closures PVC Sch 40 PVC 1120
 to glue fittings use OATLEY medium clear
 cement PVC
 12 1/2 feet casing
 5' screen .10 size screen
 Prepare to put casing
 in
 10:35 move to new location to drill a straight hole
 for NW-6 using water "buggy" drill rig. Begins
 drilling. Encountered rocks at new hole. Abandon hole
 11:30-12:30 Lunch
 12:00 AT NW-6 site. Rotasonic drill rig on site, will soon
 begin to drill when Canadian arrives.
 13:14 Go to site 4 to help Kim and John

8-2-88 Peter Kerevnen

8-2-88

22

13:14-14:22 IN office
 14:22 AT site of NW-6, crew Jeff A's. Mike E,
 John A. Bill E. are working on cement
 pump, Canadian Rotasonic rig has still not arrived.
 15:01 8H-7, finishing up grouting of
 hole
 16:26 Continuing to wait upon Canadian driller to help
 with Rotasonic
 17:01 leave site
 17:10 leave office for day

8-2-88 Peter Kerevnen

23 8-3-82

6:30 Arrive at office, weather is cool, very foggy.

ES persons Ben McLeod

Peter Reinman
Kumawara

John Thurin
John Hardman

7:20 Arrive at WP-6 location, start on 4th WP-6 hole

with Rotations, Dicks Paul K.
Jeff A.
John A.
Bill E.

Hold Calibration Asset No. 50071 Probe 50018

Calibrated to 94.7% porosity per instructions

Span Setting 22

7:57 Real Time Teflon Paste Thread Sealant manufactured by Hercules contains fine ground Teflon particles

Stock No. 15-630

HRM reading of Teflon Paste 0.1 ppm

John Hatcher - Canadian Midwest Driller

8-8:53 need air pump, so John Brewster is back for one

9:15-10:00 Went to Knox Hardware and bought

4 yellow hardhats

10:13 Tom Shindland, Larry Jensen from HAZWOP

onsite WP-6 Enrique (MRA) also on site.

Drillers have drilled down to 25', will put

well screen 10-15' and sand pack beneath it.

3'10 1/2 base of well to split table

8-3-82 Peter E Kumawara

8-3-82 rotation 96 rpm

Release time 45 sec per minute

6'6" ground to split table



11:30-1:00 Go back to area, drop off laundry,

Eat lunch

1:00-2:00 John talks to Larry J, Tom S.

WP-6 Well Construction - Sand pack cemented by Cummins Corp. 6/20/82 02018

25.4 IPD



1445 Continue to construct well point

1525 Prepare to put 11-12' perforated steel in WP-6

WP-6

1705 Look for way to get to WP-in swamp at site 2

Wait to get WP-6 tomorrow

1730 Leave site to go home

8-3-82 Peter E Kumawara

25 8-4-88

220 G

6:15 Arrive at office. weather is raining with cloudy skies, appears it's going to last much of the day.

Calibrates INM H5541 N9. 500 ± 91 cm

11:7 ev. Photo 500018 pen instrument

manuel SPAN setting 32

7:10 AT SITE MNV 111 ETH NO. 2 John F. and

MIKE E. Go to get rammer and sheeting

Peter R gets van stuck and pulled out

by JEFF D's truck

7:30-10:30 : Deen & scene 20' steel pipe casing per workshop procedure

filled up springs

10:50 Re-King. move off trailer

11:07 START DIGGING with Buckles. Drillers work on bury

12:42 STOP digging with machine

13:00-14:25 Lunch

14:57 P.W. - 12 took duplicate of Page 2 - MNV 12

SS1, C-2' mixed SS4 C-2'

(duplicate)

15:08 SS2 taken 2-5'

15:40 SS3 Analytical sample

SS4 SS5 5-20' Serial sample to the lab

16:21 SS1 5-15-20' take grain size and soil samples to the lab

13: TD for MNV 12 (Page 2)

will abandon hole as adjacent well is at similar depth

8-4-88 Peter E. Remmers

8-4-88

26

16:21-16:40 Work on getting 5 grain size samples

16:33 took 4 photos of cores

17:16 Sent 9 samples to lab / duplicate of SS1 (labeled SS4)

17:50 Arrive at office to drop off equipment

18:00 leave office

8-4-88

27 8-5-88

6:00 PM Clear, level, sunny, windy
 6:30 PM
 7:30 Set up on level MW-13 adjacent to GW2A
 7:49 Took sample for 1st at MW-13 Site 2 0-2' no HW' reading
 HW' calibration K. Davis fieldbook
 8:17 collected SS 2' 5-15' Arlat
 8:31 SS-3 taken at 9-10' estimate well
 water little firm adjacent well
 8:47 SS4 sample taken 14-5' sent to lab coarse-grained pebbly sand, coarse, no cement
 8:53 Grout hole up since adjacent well screened off at about the same interval
 Top of bedrock was fractured per Diller from drilling noise
 9:27 Dillers working on grouting up borehole MW-13
 10:03 Go to Recon area of base to see and check about where cement is and document decision
 10:46 Recon of Potomac pipe per Work Plan
 Potomac Recon 8-5-88
 11-12:00 Grout up MW-13, stop by
 Civil Eng. to try to pick

8-5-88

Peter E. Kremenova

8-5-88

28

up drilling permission forms for Site 8, not there.
 Talked to Bill Hayden on the phone

1:38 start drilling at MW-18 Site 8

well is adjacent to MW GW8-C

1:48 SS1 sent to lab, collected sample

water little in adjacent well no 8' below land surface and TD=16' according to own

water level indicator measurements

1:43:2 SS2 taken, sent to lab, water bearing, graded

well silt zone, broken for sample taken

SS3 to 14-15'

1:53 Start drilling MW20 at Site 8

adjacent well water table at 6.5' (GW8-B)

total depth 19'

1:45 SS1 taken 0-2' -clay

1:05 SS2 taken 6-8' for lab

SS4 taken for lab base of borehole

Grain size analysis below water table

GSA1 6-7

GSA2 7-8

GSA3 8-9.5'

GSA4 9.5-10.3

GSA5 10.5-11.5

8-5-88 Peter E. Kremenova

29

8-5-88

At

1600-1800 Sample preparation and Fed Xing

6:30 Back at Hotel

8-5-88 Peter E. Remane

8-6-88

30

6:10 Arrive at office, prepare for work - decan
buckets and bowls. Weather: sunny, clear blue sky7:30 John H and Jim (Canadian) discuss
drill rods

Personal

E.S. Kim D., Peter K., Jo Ann S.

NorthStar John Anderson

Midwest Jim H.

7:51 Start drilling WP-10 Site 8

0-5 and 5-10 done by 8:08

8:28 10-15' sample taken very wet

organic rich zone 10-14 may be part
of peat soil zone

9:11 Drilling from 22.5' down

9:30 got sample from 22.5-32

Going through quite a few layers

slightly moist clay and silt layers
with probably poor sand production

Kim D. is taking photos of core samples

10:00 Take a break for John H and Jim

10:18 End of break

10:30 Sampled 32-35

11:30 break for lunch

12:30 waiting for Drillers to come back so

we can begin WP 10.D construction

8-6-88 Peter E. Remane

31

8-6-88

Point 10 D Construction

TP of borehole 47.5 btm of casing at 40'

bedrock at 45

PLAN - 2' of sand pack below bottom of well point

3' of sand pack above screen interval

ground to hble = 6.5' shot for 5'

btm of hole is 45.5' bnd 43.8'

42.5 + 6.5 = 50.20' hq of a 38.8' screen

btm sand pack in to 43'

4.0' out of 5 gallon pail of sand fills 67.2 - 64.4

-20

44.4

6.5

37.9

we want to

want sand pack up to 35.9

to (35 + 20 + 6.5) = 61.5

61.9

6.5 btm of sand pack below well point 43

20 well point 43 - 38

14 sand above well point to 34.4

then pull casing measured sand at 35.9

need to put 1 more foot of sand in

34.4 measured sand above casing at 34'

ground

62.4

12.4

42.4

6.5

35.9

3

31.1

42.4

6.5

35.9

34


Peter Carnevali

8-6-88

8-6-88

32

WP 10 (deep) sketch with actual dimensions



13.30 J.A. Ann and Kim arrive from Grand

2.27 (1422) start to put bentonite seal in

14.40 Finish putting bentonite seal in

We are going to start MW 10 (shallow)

after the casing is pulled up from MW 10.0

14.57 START drilling MW 10 shallow

approx 6' east of MW 10 Deep

15.13 55.2 measured

15.30 55.3 recovered

15.51 Pump for Well Point 10.5 Shallow

33

8-6-88

Construction

PLAN ID ~ 20'

want well point to bracket gravel lens
which is approx. 13-14' so put well point
screen at 17', probably missing 15-16.5'
on in next core so screen that
interval also

cored to 20'
holes 15
44
20.1
24.6
6.5
17.5

fill up casing 3' feet after putting
approx 3' of sand on it
sand until
put in at 11' → put out 5' of

Casing

put sand pack in to 8' with
casing lifted to 5'

45.5 34.5
25.5 44.5
6.5 6.5
19 8
-1.5 16.5
-17.5
44.5 36.1
16.9 16.5
6.5 6.5
12.5 4.3
-7.1
19.1 16.5
6.5 4.3


8-6-88 Peter E Remersma

34

8-6-88

WP ATT 10 Shallow sketch

16.5-5
11.5
8.5



16.44 finished putting sand pack in to 8' below
ground surface
17.01 finish bentonite seal - 2 gallons
17.30 leave office
18.00 Arrive at hotel

8-6-88 Peter E Remersma

35

8-8-88

6:15 Arrive at office, ^{some} weather partly cloudy but sunny, wind, down 2 buckets
 Kim P. in lab, 14
 7:05 Prepare to move equipment to NW 1/4
 deep, fort heat to the north
 7:53 Setting up winter truck
 Personnel on Site
 E.S. Peter Riemann on
 To Ann Sherwin
 Kim Davis
 North Star John Anderson
 Jeff Ausland
 8:25 SS1 taken 0-1' sent to lab
 8:32 SS2 taken wet or
 8:58 SS3 sent to lab from 10-12' gravel zone
 cpl duplicate
 9:11-9:59 Break, get diesel fuel for rig
 10:19 Poor recovery on sample SS4 15-25'
 once core was very wet and went through drill but upon removal
 10:52 Drilling SS6
 11:25 SS7 full core
 Rock fragments are often granitic and gneiss
 12:07 SS8 taken Lab sample from 39-39 1/2'

8-8-88 Peter E Riemann

36

8-8-88

Going to set casing at 40'
 12:40-2:00 Lunch and errand break
 2:00 Prepare stainless steel casing 2" Johnson
 sand pack TD to 40'
 3:30 3:45 rig battery needs recharging
 4:00 rig needs to be recharged, leave site for the day
 at office, organize stuff, call Oldham
 chemical
 4:54 Leave office
 MWH
 continued on page 38
 Bedrock
 40'
 sand pack
 40'

8-8-88 Peter E Riemann

37: 8-9-88

625

Arrive at office, Partly cloudy, sunny

Calibrate HNU ASSET NO. 164716

Pipe No. 501288

Span setting 90

ES AT MW14 Sta

Peter Riemann

John Hardemann

North Star

Bill E

John A.

Jeff A.

7:00-7:30 Determine we need centralizers and $\frac{3}{4}$ "

PVC tremie pipe for MW14

7:30 MW10 D depth to top of bentonite ~~335-20~~ ³³⁵⁻²⁰ (125)

MW10 S depth to top of bentonite ~~8~~

Came back with tremie pipe and reached

bentonite at MW10 S and max. 25' in MW10 D

since that's all the tremie we have

7:30-9:00 Drillers go to get $\frac{3}{4}$ " tremie, prepare

equipment for grouting MW14

9:20 John H. goes to Knox to buy PVC couplings

9:28-9:50 Put Methuene Lot no. 882613 in skinner steel

sprayer, Decon 50' of $\frac{3}{4}$ " tremie pipe

9:50-11:19 Put sand pack in up to 26' by tremie pipe

8-9-88 Peter E Riemann

51.7 54.1 8-9-88 52.2 54.6 38.

31.7 34.1

6 MW 14

27.8

25.4

MW 14

52.5

32.5

6.5

26.0

24.5 - top of bentonite

26.0 2x3 gallons of bentonite

sand pack

30

30.0

sand pack

40

40

sand pack

44

TD

Bedrock

11:43

Put 3 gallons of bentonite plus some bentonite pellets at the top of the bentonite

Good

12:17 Trouble with cement mixer engine

Now on site Tom C., Dan Groves for North Star

12:45 Start mixing cement

Lunch 12:45-13:00

When I came back protective casing

had been installed while John H.

was there.

8-9-88 Peter E Riemann

8-9-88

Summary

MW 14 Construction Total depth 44' back at 40'
 10' screen from 30-40
 total casing 31.3" (14" short)

MW 15 Drilling

20' Total depth drilled

MW 15 Construction

screen from 5-15

sand pack to 2'

total casing 7 1/2'

8-10-88

42

6:30 AM Arrive at office, Sunny, blue
 skies, slight breeze.

GW8-A, adjacent to MW 19

approx depth to water table 6.5

total depth ~ 13.0'

Auger refusal from boring log at 13'

7:52 John back with drill rods

8:01 Start Drilling MW 19

8:10 Sample SS1 0-5 (sampled at 0-2') to

Laboratory

8:25 Sample SS2 6.5-7.5 to Laboratory

8:37 Sample SS3 9-10" to Laboratory

8:48 Took picture of 0-13.5' Photo

boring terminated at 13.5' and abandoned

since adjacent well GW8-A is

TD at 13'

9:21 Setting up at MW 16 Site 8

8-10-88

9:24 Start Drilling MW 16 Site 8

9:34 Water table very shallow at 2' in wet ^{6.5'} clay

9:34 SS-1 taken at 0-1, clay peat, Laboratory sample

9:44 SS-2 taken at 4-5, ^{most} peat, Laboratory sample

Decide to take sample SS-2 material at

10:04 clay interval 6.5-7.5 to send to Laboratory

as this interval made appropriately

represents top of the water table (done at 10:04)

8-10-88 Peter E Rimmerma

8-9-88 Peter E Rimmerma

43

26.8 - 28.10' bould
28.10 - 29.11" Sand
29.11 - 33.2" Rock

Casing at 30.2"

8-10-88

1101 Took SSC sample of coarse sand
and core of boulders

1124 SSC taken for laboratory 29-30', gravel between
bedrock and boulder
summary from driller

26.8" - 28.8"

26.66 - 28.85 boulder

28.85 - 29.95 sand

29.95 - 33.66 bedrock

11.40-12.40 Lunch

MW16 GSA 1 14-15 sand

GSA 2 16-17 clay, little silt

GSA 3 20-21 silt


GSA 4 24-25 sand and silt

GSA 5 29-30' gravel

13.11 Finished collecting grain size samples

Peter R. Start to assist John H. in construction of MW16

MW16



8-10-88

44

1439 Finished putting bentonite in, start
mixing concrete


15:02 Finish putting grout into MW16 from 16' →
still to put protective casing in

16:00 Start drilling MW17

16:38 Finish drilling MW17

MW17 Construction

Total length of screen 10'
Casing length



17:57 Have finished putting sand pack up to
land surface

18:21 leave office

8-10-88 Peter E Riemann

8-10-88

Summary

Sire 8 MW 19 TD @ 13' v adjacent to CWB-A

abandoned since adjacent well was to back

Total Depth 13'

MW 16

hit bedrock at 29' 11"

Deep

Total depth 33' 8"

Screen from 21'-31'

total casing 23 1/2'

sand pack to 17'

MW 17

Total Depth @ 15'

Screen from 2'-12'

sand pack in land surface

total casing 5 1/2' 4 1/2'

8-10-88

Peter E. Remersma

77 357

72 52

8-11-88

46

51' 2 1/2' soft
51 1/2' 53 1/2' rockWeather, clear blue sky, warm, breezy
6.40 Arrive at office, clean materials, load the

Van.

7-8:23 Work on preparing and reversing driller

sheets Kim, Mike R, and Jo Ann S

are going to backhoe up at Site 2.

9.19 Start Drilling MW 9 D

10.07 Finish describing 11-18' Kim D. assisting in

map for collection and photography

Drillers: John A. and Bill E.

11.10 Kim took picture of core picture 20m from
back, 36-38' picture of poorly sorted
injected fill

11.43 Finish describing 41-46'

12.08 Went through 2" of gneiss boulder

before and 2 1/2 feet of coarse sand

and gravel. Finish Drilling at 1.05

12.36 51. Quick break for lunch (12:57-1:36)

1.3.6 Bottom at well 9D final TD 54'

Want screen at 45-50. Start construction
6.5' total incl. casing sand up to 89' 40' to cover sand

Zone at 41'-41 1/2'.

50' in hole

15' 2"

50' 10"

57' 2' want 52.5'


-55.2'

4.7'

2.0'

45' 2" to the top

47:16.5 90' of casing 60 gallons of grout 8-11-88
 5' WP 9 D



Have 339 Put ~ 50 gallons of grout in well put more, John H. left at 3:00, back at 3:44. We're encountering difficulties with cement blobs plugging up the pump → drillers suggest installing a screen at the base of the fifty gallon mixing drum

3:50 John H. leaves to call time in.
 4:47 Application of grout per foot for 6 inch hole
 5:13 PM Leave site to go to office

5:13 PM Start putting remainder of grout in WP 9 D

6:11 Have moved to WP 9 S, which is approx 8' north of WP 9 D

6:15 Start drilling WP 9 S

8-11-88 Peter E Remmersma

8-11-88 98

Construction of WP 9 S

7:04 PM Finish drilling WP 9 S, TDE 21'

Well screen 10-15

Sand pack TD to 5'

bentonite seal 3 1/2-5

7:53 leave office

Summary for the Day

TOTAL

M WP 9 D WP 9 S

Total Depth 59' 21' 75'

Casing Ft 44' 45' 10' 53'

Screen Ft 5' 5' 10'

Base of Screen 50' 5' 10'

Stickup 2 1/2' 2 1/2' 5'

Sand pack 40-54' 21-5' 30'

bentonite seal 2-3' 1 1/2-2' 3 1/2-5'

Grout 38' -

8-11-88 Peter E Remmersma

49

8-12-88

7:30 - Arrive at office, Weather is raining,
9:30 drillers arrive to decom rig on site.

8 is finished and we are preparing
to move to site 2. Kim D. is running
decon. Peter R. went to check out
batters shops.

9:30 Weather is clearing up abit, blue sky.

9:30-11:00 Prepare drilling summary for John

Harlem on summarizing depth of well,
amt of casing etc. Go to supply at
MIGS and picked up packages.

11-1:20

work on organizing well logs, eat lunch,

2:30

Arrive at site MW-38

Go to get core holder and drill pipe
at decon area

3:13

Start drilling MW-38

3:20

Took 551 0-1 1/2' clay

but something hard at 13.5

ES Personnel

John H.

Mike Roddy

Kim D.

Peter R.

8-12-88

Peter E Rimensma

8-12-88

50

North Star Drilling
Bill E.

John A.

4:10 PM

Working on drilling past possible boulder
from 17' down, clearly drilled past
boulder from 13.5' to 16'

4:56

Left borehole, boulder or bedrock from
16.5 - 25', no water saturated zones

recorded, may be screened off by boulder

5:20

Left office for the day

8-12-88

Peter E Rimensma

51

8-13-88

6:25 AM Arrive at office. Calibrate HARE
Asset NO. 164716 11" Probe 501288

Span setting 12

6:50 Kim D., John H., and Mike R. arrive
at office MW 38

7:16 Arrive at site, Drillers have not arrived yet

7:42 Start Drilling 10' NE of previous borehole

7:55 Stop because of lightning

8:29 Resume drilling

9:10 SS1 0-2'

9:10 SS2 9-10 1/2'

9:40 SS4 17-19'

Set Screen middle str. 10' - 5-15'

9:50 Drillers go to water screen and casing: Done

with drilling MW 38

Leave site due to continued rain and
lightening

12:00-13:00 Stop in office, to unload van, cover
for the day

8-13-88

Peter E Remersma

8-15-88


52

6:30 AM Arrive at office, pack up van
Asset NO. 500791
Calibrate HNW Probe NO 500018

7:25 AM Arrive at MW 38, drillers raise tower

8:30 Waiting to get centrifuges for well

MW 38



ES Personnel

Kim D., John H., Mike R., Peter R.

North Star John H., Bill E., Jeff A.

10:19 As casing was pulled out, well rose 1 foot
probably because centrifuges (2) were
too tight in the hole. We pumped
water down the casing and as it came
out of the hole it forced the sand out,
enabling us to pull the well casing
out of the hole, check the condition
of the screen and stabilizer. The

8-15-88 Peter E Remersma

53

8-15-88

Screen and strainer were fine and we
are re-sand packing it.

11.00 Finished MW 38; 7' x 8.0', screen 8-15
sand pack to 2'

12.18 Start drilling MW 37

12.55 551, Laboratory sample 0-1', clay, some silt

13.28 552 Laboratory 5-6'

13.26 553 Laboratory 16-17' sand,


13.22 554 Laboratory 17.5-18.0

13.35 Finish drilling MW 37

14.13 Waiting for welder to weld cap on top of
casing before installation

outer casing down to 18.5

MW 37



15.30 Finish installing MW 37

15.17 Start drilling MW 39

16.24 551 Laboratory sample 0-1'

8-15-88 Peter E. Rimmerman

8-15-88

54


Estimate water table at approx. 5', other wells
measure water at 6-7', first test wet sample
at 5-6'

16.42 552 Laboratory 5-6'

17.05 553 Laboratory 21-22'

17.15 Kim leaves to bring samples to Fed Express

18.49 Complete construction of MW 39



19.8 Left site after decon contingency

Summary - Construction MW 39
Drill + Construct MW 37

Total depth MW 38 20' MW 39 22.5' Drill + Construct MW 39

Casing Fe 7 1/2' 7 1/2' 6.65'

Screen 10' 10' 10'

Base of screen 15' 15' 14'

Stickup 2.5' 2.5' 2.5'

Sand pack 3-20' 2-18.5' 2-22.5'

benlonite seal 0-2' 0-2' 0-2'

Grout

8-15-88 Peter E. Rimmerman

55

8-16-88

175

27-

- Clear blue sky.

6:30 AM Arrive at office, Calverton

HMV Asset No. 500791, Photo No. 500018

SPAN 86

7-8:15 Drilling down civil pipes per work plan
Prepar and pick Van for startcheck Civil Eng for any packages that
have arrived.

9:30 Start drilling MW 40

9:40 SS1 Laboratory 0-1' clay

10:30 Finish drilling MW 40

10:45 SS2 Laboratory 7-8' clay w/ estimate

10:53 SS3 Laboratory 15.5-16.5

MW 40 TD @ 17

Plan to screen 2-12'

10:53-11:30 wait for welder, lightening in the distance

11:30-11:58 Lunch

12:39 Finish construction of MW 40

14:02 Start drilling WP 7D

Location is in swampy region south west of
fishing range.

Have pulled to 25'

15:06 Finish drilling WP 7D Going to screen from
21-26' TD @ 29'

16:24 Begin construction of WP 7D

17:14 Have to take out screen and casing since the well
came up when other casing was removed


8-16-88 Peter E Remensma

8-16-88 Peter E Remensma


8-16-88 MW

56

MW 40 Construction



17:14
Casing to 25'
C 15-15 1/2
GW 13-14 1/2
27' 30"



57

8-16-88

1900 Leave site of WP 7D for the day

Summary

total depth

Casing ft

screen

base of screen

stickup

sand pack

bentonite

grout

8-17-88 Wes

58

6:30 Arrive at office, Foggy, rainy day,
leave thunderstorm warnings until 11 AM
North Star Personnel

7:45 Calibrate HNU

HNU Asset No. 500791, Probe No. 500018

Span 18

7:50 Start Drilling Well Point 75 (WP 7)

8:25 Bentonite slurry & coil wire 4-10 ft

ES personnel Mike Raddy, John 5

John H

North Star John Anderson, Mike X, Tom O

0900 Drilling Complete TD 15'

will start well construction

Table at 58'

from
tablefrom
ground

Table

5' 8"

ground

16' 4"

2 1/2' pipe above ground

3' Bentonite

8' 8"

13' 8"

stop of screen

sand

18' 8"

base of screen

sand

22'

16' 4" TD

8/17


J. Ann Sherwin 8/17/88

59

8/17/88 cont.
completed well at 9:4010:40 start setup at site 2MW41
11:05 start drillingDuplications taken, Sample
Station ID is 2MP41

TD at 12:10 p. 20.0'

Water Table 5'-7"

Start constructing monitoring
well at 12:40 p

Go-Land Sherrin 8/17/88

8/17/88

60

In pulling up the casing, the
well point came up 3'.
Proceeded to flush hole to 15'
after pulling the well and
the casing. After flushing to
15', added sand to 1' and
started to reconstruct well.

2:40 well constructed, pulled casing,
well popped up again.
Washed out, reset well.

3:05 Finished

3:10 Pulling off site

Move to 2MP8

4:05 Started Drilling


Water table at 13'

7:27 TD at 18'

17:35 Start construction of monitoring well
point

Fike Roddy 8/17/88

61 WP 8



DAUER

leave 2 WP 8 at 18:15

Mike Roddy 8/17/88

8/17/88

8/18/88

62

6:40 Arrive at office, work on expenses
clean equipment, load up van

Weather: blue sky, some clouds

strong winds blowing scatterly

ES Personnel

Kim R who is leaving for home at 4:00

Mike Roddy } going to work on Site

Jo Ann Sharwin } shallow soil samples

Peter Riemersma } going to work on

John Hirdman } background monitoring well

Drillers

John Anderson

Tom O

Mike

10:00-8:48 We are awaiting clearance to background well site

10:11 Start drilling MW42

10:17 SS-1 Laboratory - 0-1 clay MW42A background

10:30 AT 11" we recover white material interpreted to be concrete, we stop and ask boss, personnel what it might be

Peter Riemersma 8/18/88

88-1-80-1-2

11:07	Move ~ 20' South to new location, remove entire backhole MW43A
11:14	Hit concrete at 3'-5', going to move again
11:43	Start drilling 25' south of previous hole at 110.7

11.50	SS-1 Lake's story 0-1', to replace SS-1 from west
	previous attempt at 10:17
12.24	Abandon well at approx 10', cored 2' of granite boulder, then was the third drilling attempt

2.50 Stasi drilling 4th attempt on HW42 - down the road along the side with a pond nearby. SSI, Laboratory, 0-1', HW42, pebbles even sample taken at 11:50 whose bottle was


319 SS2, Laboratory, 7-8' HW42'
325 SS3, Laboratory, 4.5-15.5', HW42
330 Stop drilling MW42 John H. suggests
that well abandoned at 12:24 when was
probably hitting bedrock. TD of Background
Monitored 42 is 15.5'. Plan to screen from

2-12'	Water Table at 2'	
33	Finish Completion of MW42	Background
14	Set up at MW43 Background Site	
	Start Drilling	
	3-18-88	Peter E. Kiernersm

50

00-130-0000

Background: HW 421



3:34 PM in 1541 SS1, Laboratory 1-2" HW43
3:45 PM HW malfunctioning, will be returned to
US Analytical Instruments
3:53 PM SS2, Laboratory 14-15' water hole
4:14 PM SS3, Laboratory, 23-24" TID
4:25 PM Finish drilling
4:30-5:30 Work on processing samples
for Fed X
5:30 6:30 Unload van, go to airport to
see about car rental payment

8-18-88 Letter Pienezza


65

8-18-88

Summary

total depth	15.5	background MW42	NW43
casing ft w/ stickup	4.5		24'
screen	10		12.5
base of screen	12'		10
stickup	2.5		30'
sand pack	15.5 - surface		2.5
bentonite	-		7-24'
grout	-		7-0

Background MW43



8/18/88 Peter E Remersma

8-19-88

66

6:25	Cool day, blue skies, breeze to the SW
	Callibrate H.W. ASET NO. 164716 Probe
	NO. 501288 spin setting 56 (3)
	per instruction manual
7:15 AM	ES Personnel
	Peter Remersma
	Mike Roddy
	Jo Ann Sherwin
	John Hardeman
	PLAN - Peter R. and Jo Ann S. are going to work the rig. Mike R. is going to follow A. Jeff A. on well completion.
	John H. is going to review drillers completion sheets.
7:15-8:00	Peter R. and Jo Ann S. go to buy aluminum foil
8:24	Start drilling DANGB-4 - ^{UP} 11D
	Narcis Star Drillers
	John Anderson
	Mike Rosinski
9:32	Have drilled to 23.5'
9:57	Stop drilling casing to 23.6 TD 24.3'
	sand to 15'
10:25 (10:35)	screen from 15'-10'
	sand to 5'

8/19/88 Peter E Remersma

69

8-19-88

SUN


10'6" to 2"

MW23 Site 4

24' 8" to 32' 8"

54' 8"

55' 4"



7.21 Well Completed

Summary

Total depth	NP 11D	WP 16D
Casing ft w/ stick	24.3	24.4
screen	12.5	17.5
base of screen	5	5
stickup	15	20
sand pack	2.5	2.5
bentonite	6-24.3	10'7" - 24.4
grout	0-6	0-10'7"
	-	-

8-20-88

70

6.30 Arrive at office, Newton is clean,

Slight Bunge

ES Personnel

Peter Riemersma

Mike Roddy

JoAnn Shewen

North Star

Mike Rasinski, drill helper

John Anderson

Bill Erickson

7.50 Start drilling MW 22 Site 4

8.15 SS-1 Laboratory 0-1 peat

8.30 Record 150 ft from borehole, adjacent well

log notes fuel odor, adjacent well GWD

water table is at 4'

8.30 Water table est at between 5-9 feet,

clay is very moist, pending of water above

clay and below peat very likely

8.35 SS-2 Laboratory 5-6 7 clay, moist

9.00 SS-3 Laboratory 30-31' sand

9.35 Stop Drilling TD at 35' Bedrock at 32'

PLAN screen 33-33.5 to 23-23.5

sand pack 35 to 19-20'

9.50 Start Construction Peter R.

over seeing construction

8-20-88 Peter & Riemersma

8-20-88
MW22


33.5"
5'10"

23'6"
5'10"
29'4"

67.3"
37.3"
5'10"
31'3"

26'5'10"

2.9"
3'9" → mark
on connector



37.3"
5'10"
31'5"

336"
226"

26'6"
casing
needed

Outer casing

31.5'
-5'
26.5'
36.5'
26.5'
-4'
32.5'

11.27 Finish Completion of MW22

11.30-13.0 Move to new location and take lunch

8-20-88

Peter E Rimmerman

8-20-88 3' to 11 inch 72

1 23'6" + 5'10" = 29'4" top of screen

PLAN

Base of screen 336" + 5'10" = 39'4"

Top of screen 236" + 5'10" = 29'4"

Top of sand pack 20' + 5'10" = 25'10"

Length of casing at table

10' + 26' + 3'4" of connector =

5'10" 3'4" = 2'6"

21'5"

1340 Start drilling MW21

1345 SS Laboratory 0-1' clay and silt

1420 SS2 Laboratory 5-7' clay unit

Duplicate MP21 3:20 same as SS2

1455 SS3 Laboratory 18-19'

1456 Stop drilling TO 22.5' below 19'

15:15 Start construction

16:10 Stop construction

base of screen set at 20'

Top of screen set at 10'

Bill E. put soil auger from MW22

into barrel since we recorded an

elevated HW reading from the borehole.

16:39 Leave Site


8-20-88

Peter E Rimmerman

73

MW21

8-20-88



Summary

	MW22	MW21	Total
Total Depth	35	22.5	
Casing Fe w/stock	26	12.5	
Screen	10'	10	
base of screen	33.5	20'	
stickup	2.5	2.5	
sand pack	35-20'	22.5-7	
bentonite	0-20'	0-7	
grout	—	—	

8-20-88

Peter E. Ramersma

8-22-88

74

6:30 AM Arrive at office, pack up van,
decon. bowls, spoons and buckets
with help of Mike Roddy

Weather: Cloudy, foggy, hazy, rained last
night, small breeze

Calibrated HNU Asset NO. 500791

Probe NO. 500018

with SPAN(S) 34

8:25 Start drilling ~~with~~ WP 122, near runway
taxiway

9:22 Have drilled to 25' and hit bedrock of

North Star

John Anderson driller

Mike Rasinski driller helper

Bill Erickson Health & Safety

ES

John Henderson

Peter Ramersma on the rig

Jo Ann Sherwin taking water level
measurements

Mike Roddy

PLAN

Screen 32-27

Sand pack top to 24

top of

blm of screen 32 to 27

75


8-22-88

10:30 Encountering difficulty in retrieving core

WP 12 D (Deep)

10:40 Complete drilling WP 12 D TD at 35'

Start Construction WP 12 D



11:27 Complete Construction WP 12 D

12:26 Back from lunch, prepare to drill adjacent shallow well 12 S, raining - sprinkle

12:35 Start drilling WP 12 S

1:10 PM Stop drilling WP 12 S TD at 20'

Start Construction

14:15 Finish Construction WP 12 S

Screen at 9'10" - 14'00"


Sand pack up to 6'

8-22-88 Peter E. Rumsen

76

8-22-88

WP 13 S



14:35 Start drilling WP 13 D (Deep)

15:20 Stop drilling TD at 22'

Start Construction

PLAN bring over 22'

top of sand 10.5'

16:19 Finish

Begin drilling WP 13 S

16:35 Finish drilling WP 13 S

Begin construction

17:20 Finish Construction

SUMMARY WP 13 D WP 12 S WP 13 D WP 13 S

TOTAL Depth


Casing FEW feet

base of screen

77

10-22-88

WP 13 S



8-22-88

8/23/88

78

6:30 a. Arrive at office, pack up room
windy weather bright and clear -

Severe shortly before 6:30

7:30 Wait for escort to drill site

8:25 Escorted to drill location

Geologists: Peter Kernerma,

J. Lem-Oberwin, Mike Roddy

8:34 Start drilling WP 14D

9:55


Finish drilling

PLAN 25+6.2" = 31.2"

Scum 25-20

sand pack up 16 (16H 62' 22")

10:00 Start construction of WP 14D



10:32 Finish construction of WP 14D

8-23-88 Peter Kernerma

71


8-23-88

10:45 Move to WP 145, approx. 6' west of 14D. Plan to drill to 12' down.

5-10'

10:56 Finish drilling, Start Construction

WP 145



11:24 Complete Construction of WP 145

Lunch

12:30 Move to 4WP 15D

12:42 Start Drilling, 4WP 15D

1:00 Solid overcast gray clay

2:00 TD at 31'6"


Start well construction

8-23-88

WP 15D

5'10" drilled Table ground

bottom to screen



Complete construction of 4WP 5D 15:18

Start Drilling 4WP 15D 15:40


Drilling Completed 16:10

Start construction of 4WP 5S 16:15

Archie Batty

8/23/88

4W P155



16:42 Complete construction of 4W P155
 16:53 Arrive at 4W P155
 17:55 Decide not to do 4W P241 - need to decontaminate bit

8-23-88 Mike Roddy

8/24/88

82

6:30 Arrive at Office. Weather is partly cloudy & cool with slight breeze
 6:45 Load Van

6:59 Calibrate HNU ASSET NO. SUB 791

Probe No. 500018 with span set at 18. Calibrated with 94.7 ppm
 150 butylene supplied by Liger Carbonic
 batch # 9488-061589. Lot # 12

7:58 Start Drilling 4W P155

SS1 8:10 Depth 0-

SS2 8:20 Depth 3-4

North Star Personnel

John Anderson

Mike Raskinski (Driver helper)

ES Personnel

Mike Roddy

Jo Ann Sherman

John Henderson


SS3 9:30 Depth 33' to 40' 32"

9:45 Finish Drilling 4W P155

8-24-88

83

8-24-88



1136 Well Completed

8-24-88 Mike Cook

84


8-24-88

11:40	Drill off well
12:02	Lunch
13:04	Break for lunch
13:40	Weather partly cloudy. Cool & breezy. Arrive at 3pm 25
15:00	Drill bit and water truck both get stuck. Pedals not to drill. This hole at this time
15:24	Start drilling 3pm 27
15:38	0-1'
16:05	Finish drilling TD 15'
16:10	5-6'
16:32	14-15'
16:38	Start construction
	Set screen 12'-2'

8-24-88 Mike Cook

8/24/88

3MW27



17:05 well casing pulled up
start over again

redo same as above

18:11 final construction, well 3mw27

18:20 Attempt to seal up 3mw27

18:40 Give up - decide to wait till

Tomorrow morning

8/24/88

Mike Roddy

8-25-88

6:40 arriving on base

Weather clear & cool start breeze 15-20

7:18 Calibrate HNU asset # 500711

probe # 500018 1/16 spin set at 0

Calibration with 94.7 ppm 150.5 ft/sec

Supplied by light Carbon-13 Carbonyl

located at 9488-06588 Lot #111

8:00 start setting up at 3mw35

8:38 start drilling SS 18-50 SS 18-50 2-3'

9:30 TD at 75' Decide to make hole

9:53 start drilling

10:25 stop drilling TD 14' go set gas

10:15 SS 3A 10-11.5

10:25 SS 3 Baploga

10:45 recess drilling

11:45 stop drilling 17'

11:50 lunch break

12:48 drive from base

ES Personnel at Rig North Star

Mike Roddy John Anderson

John Anderson Bill

Bill McLeod

8-25-88

Mike Roddy

85

8/26/88

06:40 Arrive on site
Weather: mainly cloudy cool and breezy

7:06 Calibrate H/VU asset # S00791
probe #1 S0018 with span set at 0
Calibrated with 94.7 ppm isobutylene
supplied by Liquefied Carbonic bath
9488-061588 Lot #12

7:50 Start drilling 3" CW 25"
8:16 SS1 0-1"
8:20 SS2 2-3"
8:53 SS3 14-15"
9:02 Stop drilling TD 18"


9:09 Start construction SHW 25"

North Star Personnel at Rig
at John Anderson
Mike Kelly
John Hardman

8/26/88

8/25/88

12:50 Start construction of 3" CW 35"



note: 110 ft screen damaged during 1st construction

13:46 Finish construction of 3" CW 35"

14:05 Re-measure - find screen only 6" below the surface - decide to reset well screen

16:00 finish setting well device off - see above

16:35 finish stringing fence


16:57 only decide not to do another hole

8/25/88

Mike Kelly

8/26/88

3mw25



9:48 Finish construction

10:10 Start Drilling 3mw26

11:04 Finish Drilling T.D. 145 ft

11:20 Start well construction of 3mw26

1:50 go get water

16:00 back from getting water

12:08 Drive to go to lunch

13:10 back from lunch


8/26/88

Mike Riedel

8/26/88

90

3mw26



3:50 Finish well construction

Note: Construction had to be done twice

110 ft screen damaged

14:30 pull off well & get water truck

out from being stuck - go to decon

drilling equipment

15:00 back from decon

15:24 set up on 3mw30

15:35 reset up on 3mw30

15:57 Start Drilling

16:52 Finish Drilling


17:00 Start construction

8/26/88

Mike Riedel

8/26/88

3mw30



18:10 finish construction pull off well

18:15 Check out next location

8/26/88 Mike Bobb

8/27/88

0640 Arrive on site

Weather partly cloudy, cool, and breezy

722 calibrate HNU asset NO 500791

probe 500018 with geoset at 0

Calibrate with 947 ppm 100 butylene

supplied by Iniquid Carbonic hotel

9488-081588 Lot # 12

748 Start Drilling 3mw31

8:25 SS1 0-10'

8:41 SS2 9-10'

Note: SS3 not recovered by idries

8:55 Finish Drilling TD 18'

9:05 Driller go to decontaminate equipment

9:35 back for decon - begin well construction

9:45 10' PVC casing pipe down hole


10:00 retrieve pipe

Resume well construction

8/27/88

Mike Bobb

8/27/88



Finish well construction 10:32

10:46 going to set water

11:18 set up on 3mw28

11:20 Start Drilling 3mw28

11:30 SS 1 0-1'

11:50 SS 2 2-3'

12:05 SS 3 14-15'

12:02 finish Drilling TO 15'


12:23 Start well construction

8/27/88

Finish Roddy

8/27/88

3mw28



12:59 finish well construction on 3mw28

13:05 rig stuck

13:23 Get rig out

Lunch 13:30 - 14:15

14:35 Start Drilling 3mw33

14:52 SS 1 0-1'

15:25 SS 2 11-12'

15:55 SS 3 20-21'


16:00 finish Drilling TO 24'

16:25 begin well construction

8/27/88

Finish Roddy

8/27/88



Finish construction 17:25
Drillers Drive off well location 17:38

8/27/88 Mike Roddy

8/29/88

06:40 arrive on site
Weather partly cloudy + cool slight breeze

7:11 Calibrate HNU Asset NO 500791
probe # 50018 with spec set at 90
Calibrator with a 4.7 ppm ISO butylene
Supplied by Liquid Carbonic bottle
94588 - 061588 Lot #12

9:45 go to set up on 3NW 34
9:55 batteries on fire dead - drillers take them
to be recharged

10:00 - 11:00 break for lunch

11:00 Start Drilling 3NW 34
12:32 stop Drilling T.O. 15'


13:06 Start construction of 3NW 34

8/29/88 Mike Roddy

97

8/24/88

3mw34



13:48 finish construction of 3mw34
 13:55 water truck stuck
 14:05 get water truck out
 14:10 Driller goes to get water
 14:30 Set up on 3mw32

17:42 Start Drilling 3mw32
 14:50 SS 1 2-3
 15:40 SS 2 11 12
 16:01 SS 3 20 21 19:20
 15:58 finish Drilling 3mw32

16:35 Begin Construction


8/24/88

Mike Kelly

98

8/24/88

3mw32



17:32 finish construction
 17:53 Driller move rig from well site
 8:00 Driller operational objective with Driller

8/29/88

Mike Kelly

8/30/88

8/30/88

0640

arrive on site
Weather Cool, partly cloudy, with slight breeze
0711 Calibrate MWU as set # S-0791
probe H 500018 with spec set at 65
Calibrate with 94.7 pp-1 isobutylene
Supplied by Imperial Carbonic Water H
9484-061588 lot #112

0745 Set up on 3mw 29

0757 Start Drilling

0810 have to stop Drilling at 7'-4" in
hole was clogged on twist

0815 Start Drilling

0818 Stop Drilling 2" in b

0830 Start Drilling

0837 Stop Drilling 5' hole becomes off

0920 Set up on new location for 3mw 29

0925 Start Drilling

0940 SS1 0-1'

0955 SS2 3-4'


1000 SS3 14-15'

1007 SS3A Asphalte 14-15'

9:54 stop Drilling 10' 16'

8/30/88 Mike Roddy

10:05 Begin Well Construction
3mw 29



1040 Finish Construction

11:02 Start Drilling MW 30A

11:10 SS7 0-1'

11:12 SS/A 0-1'

11:24 SS2 4-11'

11:29 Finish Drilling TO 15'

11:30 SS3 14-15'

8/30/88

Mike Roddy

101

8/30/88

Start
11:43.8 03 3 ft
11:51 finish
11:55 Start SG 03 2' SS1 HNU of sample 21 ppm
11:58 SS1A Duplicate
11:58 Start E3
12:00 Finish Drilling
12:00 SG E3 2' SS1, SS1A duplicate
HNU of sample 21 ppm
12:20 Lunch
13:10 back for lunch - decontaminate press
14:50 arrive at site 2 wait with Whalen
For JH to show up
15:05 Set up on 2BH2
15:12 Start Drilling 0-1
15:20 2BH2 SS1 HNU - 300 ppm
15:30 2BH2 SS2 5-6' 400 ppm
15:40 2BH2 SS3 10-12' 350 ppm
15:45 2BH2 SS4 14-5' 150 ppm
15:50 2BH2 SS5 26' 40 ppm
15:55 2BH2 SS6 25' 0 ppm
15:58 stop drilling TD 27'

8/30/88

Mike Bolder

8/30/88

102

16:02 start Drilling 2BH1
16:15 2BH1 SS1 0-2 HNU of sample 400
HNU recorded 300 ppm 5-8' 350 ppm 10-12' 40-150
16:20 2BH1 SS2 2-4'
16:30 2BH1 SS3 6-8'
16:30 2BH1 SS4 8-10'
16:40 2BH1 SS5 10-12'
16:40 2BH1 SS6 15-17'
16:45 2BH1 SS7 23-24' - HNU 290 ppm
16:50 stop Drilling 2BH1 TD 24.5
16:55 18:30 prepare sample for shipping
16:55 add take samples to field
18:55 leave office

8/30/88

Mike Bolder

153

8/31/88

0645	arrive on site.	
	Weather cloudy and slightly breezy	
0711	Calibrate HNU asset # 50079	
	probe # 50018 with sp. set # 35	
	Calibrated with 94.7 ppm isobutylene	
	Supplied by Liquid Carbonic Vitech	
	# 9488-061595 Lot # 112	
0758	Start Drilling MW14	
0800	Finish Drilling TD 23'	
0820	SS3 10-12' HNU clipping	
0820	SS9 10-12" HNU upper Dup	
0835	Drill down 3'	
0838	Stop Drilling TD 3'	
0845	8mw20 SS1 0-2'	
0845	8mw20 SS5 0-2' Duplicate	
8:55	9:40 pink samples	
10:05	4mw27 SS1 0-2'	
	4mw24 SS19 0-2' Duplicate	
10:45	B6 MW32 SS1 0-1'	
10:45	B6 MW32 SS4 0-1' Duplicate	
11:20	SGE4 SS1 0-2'	
11:20	SGE4 SS2 0-2' Duplicate	
	8/31/88 Mike Rodde	

8/31/88

154

11:40	SGC4 SS1 0-2'	
11:45	SGC4 SS2 0-2' Duplicate	
11:55	6 inch bore	
12:45	back from lunch begin packing samples	
1500	Take water sample from 10-12"	
1540	Continue packing ^{water} samples for shipment	
1700	Take samples to Fed X for shipment	
17:45	Go to airport to pick up Airline tickets	

8/31/88

Mike Rodde

105

9/11/88

06:45 Arrive at Office

Weather cloudy, cool, slight breeze, misty
 07:05-7:40 Discuss what needs to be done with drillers

8:00-9:00 Fill out chart

9:20-10:00 Check out Site 2 with Bill & Greg

10:10-10:35 Clean yard and office

10:35-10:55 Clean up Van

11:20-12:00 Observe operating procedures at drillers regarding the fabrication of well Cas protective well casing and placement of well caps

12:00-3:05 Lunch break

13:10-14:05 Wash bowls, spoons, buckets

14:10-14:50 Check Progress of Driller;

Assist in procurement of much needed supplies for Driller

14:55-15:15 Remove surficial deposits

around office area for visual enhancement of office area

15:20-15:30 Meet with Driller to review

operational objectives

15:30-16:00 Proceed to Base Supply to secure

Several packages reserved to place

16:04-16:15 Discuss well maintenance with Driller. Numbering system resolved

9/11/88

Pinto Ridge

9/11/88

106

16:15-16:29 Unload packages for Van

16:30- Proceed to Site 2 to observe installation of

16:45 - Protective casing at (WOP) & (WOP)

17:20 Protective Casing for Hydrocarbon Wells

and Well Pumps dropped off at Site 2

17:45 Leave Office

9/11/88 Pinto Ridge

107

9/2/88

200 Arrive on site

Weather: partly cloudy, cool, no strong breeze
rain clouds on the horizon

7:30 Discuss operational objectives with

Bill and John - load cement to fill buckets

8:08 Leave for site 2

8:20-8:50 problems with gravel truck

9:12 2B H1 and 2B H2 filled with cement

9:15-10:40 problem protective casing in and

do well casing measurements for site 2

ground to top of casing

10:40 Drive over to discuss area meet

with Drillers - go back over to site 2

11:20 final re-cutting protective casing follow 37

11:30 final re-cutting and putting in place

the protective casing for BGM 2mw 39

12:05 Install protective casing for BGM 43

12:15 lunch break

13:10 back from lunch

13:18-14:55 Drive around putting locks

on protective well casing and do top of

casing to ground measurements

15:30 leave for airport

9/2/88

Bobo Rods

Total Depth	31' bottom of casing
	5.8' to top of table
	36.8"
	-14' sand pack
	22.8" from top of table
Things to do	
check WP for QA/QC samples needed for this	
Analysis for Background Soils	
SW 8010	Volatiles Org
SW 8020	Volatiles
SW 8270	Semi-Volatiles
SW 7060 As	Metals
SW 6010 Ba	"
SW 7131 Cd	"
SW 7191 Cr	"
SW 7421 Pb	"
SW 7471 Hg	"
SW 8080	Organic Chlorine Pesticides
	PCB's
EPA 418.1	

CURVE TABLES

Published by KEUFFEL & ESSER CO.

HOW TO USE CURVE TABLES

Table I. contains Tangents and External to a 1° curve. Tan. and Ext. to any other radius may be found nearly enough, by dividing the Tan. or Ext. opposite the given Central Angle by the given degree of curve. To find Deg. of Curve, having the Central Angle and Tangent: Divide Tan. opposite the given Central Angle by the given Tangent. To find Deg. of Curve, having the Central Angle and External: Divide Ext. opposite the given Central Angle by the given External. To find Nat. Tan. and Nat. Ex. Sec. for any angle by Table I.: Tan. or Ext. of twice the given angle divided by the radius of a 1° curve will be the Nat. Tan. or Nat. Ex. Sec.

EXAMPLE

Wanted a Curve with an Ext. of about 12 ft. Angle of Intersection or I. P. = 23° 20' to the R. at Station 542+72.

Ext. in Tab. I opposite 23° 20' = 120.87
120.87 ÷ 12 = 10.07. Say a 10° Curve.

Tan. in Tab. I opp. 23° 20' = 1183.1
1183.1 ÷ 10 = 118.31.

Correction for A. 23° 20' for a 10° Cur. = 0.16
118.31 + 0.16 = 118.47 = corrected Tangent.

(If corrected Ext. is required find in same way)

Ang. 23° 20' = 23.33° ÷ 10 = 2.3333 = L. C.


2° 19½' = def. for sta.	542	I. P. = sta.	542+72
4° 49½' = " " "	+50	Tan. =	1.18.47
7° 19½' = " " "	543	B. C. = sta.	541+53.53
9° 49½' = " " "	+50	L. C. =	2.33.33
11° 40' = " " "	543+	E. C. = Sta.	543+86.86

100 - 53.53 = 46.47 × 3' (def. for 1 ft. of 10° Cur.) = 139.41' =

2° 19½' = def. for sta. 542.

Def. for 50 ft. = 2° 30' for a 10° Curve.

Def. for 36.86 ft. = 1° 50½' for a 10° Curve.




$46 \frac{1}{2}''$ $16 \frac{1}{2}''$ $18 \frac{1}{2}''$
 $37 \frac{3}{4}''$
 $48 \div 27 = 1.77$
 $4' 11''$
 $10' 3 \frac{1}{2}''$
 $5' 8''$
 putting buttons in 7 1/2"
 $37 \frac{3}{4}''$
 $32 \frac{1}{2}''$
 $4' 7 \frac{1}{2}''$
 then put sand in
 then pump into well until water comes out
 then pump into well until water comes out
 then pump into well until water comes out
 then pump into well until water comes out

69.7
 49.7
 6.5
 43.2
 7.25
 2.6
 2.2
 46.2
 47.8
 7
 33.2
 $46 \frac{1}{2}''$ to top of plate $5' 8''$
 $39' 6 \frac{1}{2}''$
 $3 \frac{1}{2}''$
 34
 35.46
 5.8
 27
 $32.8''$

1) put btm sand pack in
 2) put screen casing in
 put screen top down inside of hole
 its total length
 3) mark where top of land surface
 should be on pipe - dip it at that
 level
 4) put sand in, some coming up
 check on verticalness of hole
 $47' 10''$

TRIGONOMETRIC FORMULAE



For Angle A, $\sin A = \frac{a}{c}$, $\cos A = \frac{b}{c}$, $\tan A = \frac{a}{b}$, $\cot A = \frac{b}{a}$, $\sec A = \frac{c}{b}$, $\csc A = \frac{c}{a}$
 $\tan A = \frac{a}{b}$, $\cot A = \frac{b}{a}$, $\sec A = \frac{c}{b}$, $\csc A = \frac{c}{a}$
 $\sin A = \frac{a}{c}$, $\cos A = \frac{b}{c}$, $\tan A = \frac{a}{b}$, $\cot A = \frac{b}{a}$, $\sec A = \frac{c}{b}$, $\csc A = \frac{c}{a}$
 $B = 90^\circ - A$, $a = b \tan A$, $c = \frac{b}{\cos A}$
 $B = 90^\circ - A$, $a = c \sin A$, $b = c \cos A$

Solution of Oblique Triangles
 Given A, B, C: $a = \frac{b \sin A}{\sin B}$, $c = \frac{b \sin C}{\sin B}$
 Given A, a, b: $B = 180^\circ - A - C$, $c = \frac{a \sin C}{\sin A}$
 Given A, a, c: $B = 180^\circ - A - C$, $b = \frac{a \sin B}{\sin A}$
 Given B, b, c: $A = 180^\circ - B - C$, $a = \frac{b \sin A}{\sin B}$
 Given B, b, a: $A = 180^\circ - B - C$, $c = \frac{a \sin C}{\sin A}$
 Given C, c, a: $B = 180^\circ - C - A$, $b = \frac{a \sin B}{\sin A}$
 Given C, c, b: $A = 180^\circ - C - B$, $a = \frac{b \sin A}{\sin B}$
 Given A, a, c: $B = 180^\circ - A - C$, $b = \frac{a \sin B}{\sin A}$
 Given A, a, b: $C = 180^\circ - A - B$, $c = \frac{a \sin C}{\sin A}$
 Given B, b, c: $A = 180^\circ - B - C$, $a = \frac{b \sin A}{\sin B}$
 Given B, b, a: $C = 180^\circ - B - A$, $c = \frac{a \sin C}{\sin A}$
 Given C, c, a: $B = 180^\circ - C - A$, $b = \frac{a \sin B}{\sin A}$
 Given C, c, b: $A = 180^\circ - C - B$, $a = \frac{b \sin A}{\sin B}$

REDUCTION TO HORIZONTAL
 Horizontal distance = Slope distance multiplied by the cosine of the vertical angle. Thus: slope distance = 318.4 ft. Vert. angle = $5^\circ 10'$. From Table, Page 1X, $\cos 5^\circ 10' = .9959$. Horizontal distance = $318.4 \times .9959 = 318.09$ ft.
 Horizontal distance also = Slope distance minus slope distance times (1 - cosine of vertical angle). With the same figures as in the preceding example, the following result is obtained. $\cos 5^\circ 10' = .9959$. $1 - .9959 = .0041$. $318.4 \times .0041 = 1.31$. $318.4 - 1.31 = 318.09$ ft.
 When the rise is known, the horizontal distance is approximately: — the slope distance less the square of the rise divided by twice the slope distance. Thus: rise = 14 ft., slope distance = 302.6 ft. Horizontal distance = $302.6 - \frac{14 \times 14}{2 \times 302.6} = 302.28$ ft.

XII

Natural Trigonometrical Functions

Angle, Sin, Tan, Sec, Cos, Cotg, Cosec.	Angle, Sin, Tan, Sec, Cos, Cotg, Cosec.	Angle, Sin, Tan, Sec, Cos, Cotg, Cosec.	Angle, Sin, Tan, Sec, Cos, Cotg, Cosec.
32 3299 .6249 1.1792 1.587 1.600 84805 58	33 3466 .6494 1.1024 1.836 1.540 83867 57	34 3643 .6763 1.0231 2.183 1.483 82904 56	35 3831 .7061 1.2203 2.743 1.429 81915 55
10 3324 .6289 1.1313 1.878 1.500 84650 50	10 3471 .6536 1.1946 1.823 1.530 83708 50	10 3648 .6830 1.1101 2.173 1.464 82577 50	10 3840 .7163 1.2101 2.731 1.404 81580 50
20 3348 .6330 1.1833 1.870 1.580 84405 40	20 3495 .6577 1.1969 1.820 1.520 83519 40	20 3674 .6873 1.1134 2.176 1.455 82413 40	20 3864 .7183 1.2134 2.736 1.401 81482 40
30 3373 .6371 1.1857 1.861 1.570 84339 30	30 3519 .6619 1.1972 1.812 1.511 83359 30	30 3698 .6910 1.1158 2.181 1.446 82248 30	30 3888 .7203 1.2158 2.741 1.396 81371 30
40 3398 .6412 1.1879 1.853 1.560 84182 20	40 3544 .6661 1.2015 1.804 1.501 83228 20	40 3723 .6959 1.1183 2.186 1.441 82132 20	40 3913 .7236 1.2183 2.746 1.391 81244 20
50 3422 .6453 1.1901 1.844 1.550 84025 10	50 3569 .6702 1.2058 1.796 1.492 83066 10	50 3748 .7000 1.1213 2.191 1.436 82016 10	50 3938 .7279 1.2213 2.751 1.386 81116 10
33 3446 .6494 1.1024 1.836 1.540 83867 57	34 3643 .6763 1.0231 2.183 1.483 82904 56	35 3831 .7061 1.2203 2.743 1.429 81915 55	36 4024 .7386 1.2440 3.401 1.381 80038 54
10 3471 .6536 1.1946 1.823 1.530 83708 50	10 3648 .6830 1.1101 2.173 1.464 82577 50	10 3840 .7163 1.2101 2.731 1.404 81580 50	10 4041 .7511 1.2651 4.081 1.343 79050 53
20 3495 .6577 1.1969 1.820 1.520 83519 40	20 3674 .6873 1.1134 2.176 1.455 82413 40	20 3864 .7183 1.2134 2.736 1.401 81482 40	10 4065 .7535 1.2675 4.101 1.341 79050 50
30 3519 .6619 1.1972 1.812 1.511 83359 30	30 3698 .6910 1.1158 2.181 1.446 82248 30	30 3888 .7203 1.2158 2.741 1.396 81371 30	20 4089 .7559 1.2699 4.121 1.339 79050 40
40 3544 .6661 1.2015 1.804 1.501 83228 20	40 3723 .6959 1.1183 2.186 1.441 82132 20	40 3913 .7236 1.2183 2.746 1.391 81244 20	30 4113 .7583 1.2723 4.141 1.337 79050 30
50 3569 .6702 1.2058 1.796 1.492 83066 10	50 3748 .7000 1.1213 2.191 1.436 82016 10	50 3938 .7279 1.2213 2.751 1.386 81116 10	40 4137 .7607 1.2747 4.161 1.335 79050 20
34 3643 .6763 1.0231 2.183 1.483 82904 56	35 3831 .7061 1.2203 2.743 1.429 81915 55	36 4024 .7386 1.2440 3.401 1.381 80038 54	50 4161 .7631 1.2771 4.181 1.333 79050 10
10 3648 .6830 1.1101 2.173 1.464 82577 50	10 3840 .7163 1.2101 2.731 1.404 81580 50	10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4185 .7655 1.2795 4.201 1.331 79050 50
20 3674 .6873 1.1134 2.176 1.455 82413 40	20 3864 .7183 1.2134 2.736 1.401 81482 40	20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4209 .7679 1.2839 4.221 1.329 79050 40
30 3698 .6910 1.1158 2.181 1.446 82248 30	30 3888 .7203 1.2158 2.741 1.396 81371 30	30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4233 .7703 1.2863 4.241 1.327 79050 30
40 3723 .6959 1.1183 2.186 1.441 82132 20	40 3913 .7236 1.2183 2.746 1.391 81244 20	40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4257 .7727 1.2887 4.261 1.325 79050 20
50 3748 .7000 1.1213 2.191 1.436 82016 10	50 3938 .7279 1.2213 2.751 1.386 81116 10	50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4281 .7751 1.2911 4.281 1.323 79050 10
35 3831 .7061 1.2203 2.743 1.429 81915 55	36 4024 .7386 1.2440 3.401 1.381 80038 54	37 4013 .7536 1.2521 4.051 1.327 79050 53	10 4305 .7775 1.2935 4.301 1.321 79050 50
10 3840 .7163 1.2101 2.731 1.404 81580 50	10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4065 .7559 1.2699 4.121 1.339 79050 50	20 4329 .7800 1.2959 4.321 1.319 79050 40
20 3864 .7183 1.2134 2.736 1.401 81482 40	20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4089 .7583 1.2723 4.141 1.337 79050 40	30 4353 .7824 1.2983 4.341 1.317 79050 30
30 3888 .7203 1.2158 2.741 1.396 81371 30	30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4113 .7583 1.2723 4.141 1.337 79050 30	40 4377 .7848 1.3007 4.361 1.315 79050 20
40 3913 .7236 1.2183 2.746 1.391 81244 20	40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4137 .7607 1.2747 4.161 1.335 79050 20	50 4401 .7872 1.3031 4.381 1.313 79050 10
50 3938 .7279 1.2213 2.751 1.386 81116 10	50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4161 .7631 1.2771 4.181 1.333 79050 10	10 4425 .7896 1.3055 4.401 1.311 79050 50
36 4024 .7386 1.2440 3.401 1.381 80038 54	37 4013 .7536 1.2521 4.051 1.327 79050 53	38 4105 .7625 1.2610 4.041 1.320 78901 52	20 4449 .7920 1.3079 4.421 1.309 79050 40
10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4065 .7559 1.2699 4.121 1.339 79050 50	10 4089 .7583 1.2723 4.141 1.337 79050 40	30 4473 .7944 1.3103 4.441 1.307 79050 30
20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4089 .7583 1.2723 4.141 1.337 79050 40	20 4113 .7583 1.2723 4.141 1.337 79050 30	40 4497 .7968 1.3127 4.461 1.305 79050 20
30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4113 .7583 1.2723 4.141 1.337 79050 30	30 4137 .7607 1.2747 4.161 1.335 79050 20	50 4521 .7992 1.3151 4.481 1.303 79050 10
40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4137 .7607 1.2747 4.161 1.335 79050 20	40 4161 .7631 1.2771 4.181 1.333 79050 10	10 4545 .8016 1.3175 4.501 1.301 79050 50
50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4161 .7631 1.2771 4.181 1.333 79050 10	50 4185 .7655 1.2795 4.201 1.331 79050 50	20 4569 .8040 1.3199 4.521 1.299 79050 40
37 4013 .7536 1.2521 4.051 1.327 79050 53	38 4105 .7625 1.2610 4.041 1.320 78901 52	39 4197 .7714 1.2700 4.031 1.319 78901 51	30 4593 .8064 1.3223 4.541 1.297 79050 30
10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4065 .7559 1.2699 4.121 1.339 79050 50	10 4089 .7583 1.2723 4.141 1.337 79050 40	40 4617 .8088 1.3247 4.561 1.295 79050 20
20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4089 .7583 1.2723 4.141 1.337 79050 40	20 4113 .7583 1.2723 4.141 1.337 79050 30	50 4641 .8112 1.3271 4.581 1.293 79050 10
30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4113 .7583 1.2723 4.141 1.337 79050 30	30 4137 .7607 1.2747 4.161 1.335 79050 20	10 4665 .8136 1.3295 4.601 1.291 79050 50
40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4137 .7607 1.2747 4.161 1.335 79050 20	40 4161 .7631 1.2771 4.181 1.333 79050 10	20 4689 .8160 1.3319 4.621 1.289 79050 40
50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4161 .7631 1.2771 4.181 1.333 79050 10	50 4185 .7655 1.2795 4.201 1.331 79050 50	30 4713 .8184 1.3343 4.641 1.287 79050 30
38 4105 .7625 1.2610 4.041 1.320 78901 52	39 4197 .7714 1.2700 4.031 1.319 78901 51	40 4281 .7751 1.2811 4.281 1.323 79050 10	40 4737 .8208 1.3367 4.661 1.285 79050 20
10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4065 .7559 1.2699 4.121 1.339 79050 50	10 4089 .7583 1.2723 4.141 1.337 79050 40	50 4761 .8232 1.3391 4.681 1.283 79050 10
20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4089 .7583 1.2723 4.141 1.337 79050 40	20 4113 .7583 1.2723 4.141 1.337 79050 30	10 4785 .8256 1.3415 4.701 1.281 79050 50
30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4113 .7583 1.2723 4.141 1.337 79050 30	30 4137 .7607 1.2747 4.161 1.335 79050 20	20 4809 .8280 1.3439 4.721 1.279 79050 40
40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4137 .7607 1.2747 4.161 1.335 79050 20	40 4161 .7631 1.2771 4.181 1.333 79050 10	30 4833 .8304 1.3463 4.741 1.277 79050 30
50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4161 .7631 1.2771 4.181 1.333 79050 10	50 4185 .7655 1.2795 4.201 1.331 79050 50	40 4857 .8328 1.3487 4.761 1.275 79050 20
39 4197 .7714 1.2700 4.031 1.319 78901 51	40 4281 .7751 1.2811 4.281 1.323 79050 10	41 4373 .7840 1.2900 4.271 1.318 78901 50	50 4881 .8352 1.3511 4.781 1.273 79050 10
10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4065 .7559 1.2699 4.121 1.339 79050 50	10 4089 .7583 1.2723 4.141 1.337 79050 40	10 4905 .8376 1.3535 4.801 1.271 79050 50
20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4089 .7583 1.2723 4.141 1.337 79050 40	20 4113 .7583 1.2723 4.141 1.337 79050 30	20 4929 .8400 1.3559 4.821 1.269 79050 40
30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4113 .7583 1.2723 4.141 1.337 79050 30	30 4137 .7607 1.2747 4.161 1.335 79050 20	30 4953 .8424 1.3583 4.841 1.267 79050 30
40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4137 .7607 1.2747 4.161 1.335 79050 20	40 4161 .7631 1.2771 4.181 1.333 79050 10	40 4977 .8448 1.3607 4.861 1.265 79050 20
50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4161 .7631 1.2771 4.181 1.333 79050 10	50 4185 .7655 1.2795 4.201 1.331 79050 50	50 5001 .8472 1.3631 4.881 1.263 79050 10
40 4281 .7751 1.2811 4.281 1.323 79050 10	41 4373 .7840 1.2900 4.271 1.318 78901 50	42 4461 .7929 1.2989 4.261 1.313 78901 49	10 5025 .8496 1.3655 4.901 1.261 79050 50
10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4065 .7559 1.2699 4.121 1.339 79050 50	10 4089 .7583 1.2723 4.141 1.337 79050 40	20 5049 .8520 1.3679 4.921 1.259 79050 40
20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4089 .7583 1.2723 4.141 1.337 79050 40	20 4113 .7583 1.2723 4.141 1.337 79050 30	30 5073 .8544 1.3703 4.941 1.257 79050 30
30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4113 .7583 1.2723 4.141 1.337 79050 30	30 4137 .7607 1.2747 4.161 1.335 79050 20	40 5097 .8568 1.3727 4.961 1.255 79050 20
40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4137 .7607 1.2747 4.161 1.335 79050 20	40 4161 .7631 1.2771 4.181 1.333 79050 10	50 5121 .8592 1.3751 4.981 1.253 79050 10
50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4161 .7631 1.2771 4.181 1.333 79050 10	50 4185 .7655 1.2795 4.201 1.331 79050 50	10 5145 .8616 1.3775 5.001 1.251 79050 50
40 4281 .7751 1.2811 4.281 1.323 79050 10	41 4373 .7840 1.2900 4.271 1.318 78901 50	42 4461 .7929 1.2989 4.261 1.313 78901 49	20 5169 .8640 1.3799 5.021 1.249 79050 40
10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4065 .7559 1.2699 4.121 1.339 79050 50	10 4089 .7583 1.2723 4.141 1.337 79050 40	30 5193 .8664 1.3823 5.041 1.247 79050 30
20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4089 .7583 1.2723 4.141 1.337 79050 40	20 4113 .7583 1.2723 4.141 1.337 79050 30	40 5217 .8688 1.3847 5.061 1.245 79050 20
30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4113 .7583 1.2723 4.141 1.337 79050 30	30 4137 .7607 1.2747 4.161 1.335 79050 20	50 5241 .8712 1.3871 5.081 1.243 79050 10
40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4137 .7607 1.2747 4.161 1.335 79050 20	40 4161 .7631 1.2771 4.181 1.333 79050 10	10 5265 .8736 1.3895 5.101 1.241 79050 50
50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4161 .7631 1.2771 4.181 1.333 79050 10	50 4185 .7655 1.2795 4.201 1.331 79050 50	20 5289 .8760 1.3919 5.121 1.239 79050 40
40 4281 .7751 1.2811 4.281 1.323 79050 10	41 4373 .7840 1.2900 4.271 1.318 78901 50	42 4461 .7929 1.2989 4.261 1.313 78901 49	30 5313 .8784 1.3943 5.141 1.237 79050 30
10 4041 .7511 1.2651 4.081 1.343 79050 53	10 4065 .7559 1.2699 4.121 1.339 79050 50	10 4089 .7583 1.2723 4.141 1.337 79050 40	40 5337 .8808 1.3967 5.161 1.235 79050 20
20 4065 .7535 1.2675 4.101 1.341 79050 50	20 4089 .7583 1.2723 4.141 1.337 79050 40	20 4113 .7583 1.2723 4.141 1.337 79050 30	50 5361 .8832 1.3991 5.181 1.233 79050 10
30 4089 .7559 1.2699 4.121 1.339 79050 40	30 4113 .7583 1.2723 4.141 1.337 79050 30	30 4137 .7607 1.2747 4.161 1.335 79050 20	10 5385 .8856 1.4015 5.201 1.231 79050 50
40 4113 .7583 1.2723 4.141 1.337 79050 30	40 4137 .7607 1.2747 4.161 1.335 79050 20	40 4161 .7631 1.2771 4.181 1.333 79050 10	20 5409 .8880 1.4039 5.221 1.229 79050 40
50 4137 .7607 1.2747 4.161 1.335 79050 20	50 4161 .7631 1.2771 4.181 1.333 790		

Q.2.3 Notebook 3, Assistant Field Team Leader

This notebook contains Site 2 pace and compass measurements on existing well locations, and the locations of the trench FTA-1; rounds 1 and 2 of water level measurements; well development records; shallow soil sampling at Site 3 and records of HNU readings for Site 8 shallow soil boreholes.

Eighty two pages of this notebook were used. The first entry is July 26 1988 and the last is September 2, 1988. This notebook is signed by Jo-Ann Sherwin.

This page intentionally left blank.

Life in the

WEATHERPROOF

FIELD BOOK

No. 350

Duluth ANGB

Project No. 00001

Book No. 1

FTLA Notebook

FTLA Jo-Ana Sherwin

RETURN TO: ROBERT S. McLEOD
ENGINEERING SCIENCE
710 S. ILLINOIS AVE
SUITE F-103
OAK RIDGE, TN 37830
(615) 481-3920

"Rite in the Rain"
WEATHERPROOF

a product of
J. L. DARLING CORPORATION
TACOMA, WASHINGTON 98421 U.S.A.

DISTANCES FROM SIDE STAKES FOR CROSS-SECTIONING
Roadway of any Width. Side Slopes 1 1/2 to 1.

In the figure below opposite 7 under "Cut or Fill" and under 11.0, the distance out from the side stake at left. Also, opposite 11 under "Cut or Fill" and under 10.7 the distance out from the side stake at right.

Cut or Fill (ft.)	Distance out from Side or Shoulder Stake										Cut or Fill (ft.)
	0	.1	.2	.3	.4	.5	.6	.7	.8	.9	
0	0.0	0.2	0.3	0.5	0.6	0.8	0.9	1.1	1.2	1.4	0
1	1.5	1.7	1.8	2.0	2.1	2.3	2.4	2.6	2.7	2.9	1
2	3.0	3.2	3.3	3.5	3.6	3.8	3.9	4.1	4.2	4.4	2
3	4.5	4.7	4.8	5.0	5.1	5.3	5.4	5.6	5.7	5.9	3
4	6.0	6.2	6.3	6.5	6.6	6.8	6.9	7.1	7.2	7.4	4
5	7.5	7.7	7.8	8.0	8.1	8.3	8.4	8.6	8.7	8.9	5
6	9.0	9.2	9.3	9.5	9.6	9.8	9.9	10.1	10.2	10.4	6
7	10.5	10.7	10.8	11.0	11.1	11.3	11.4	11.6	11.7	11.9	7
8	12.0	12.2	12.3	12.5	12.6	12.8	12.9	13.1	13.2	13.4	8
9	13.5	13.7	13.8	14.0	14.1	14.3	14.4	14.6	14.7	14.9	9
10	15.0	15.2	15.3	15.5	15.6	15.8	15.9	16.1	16.2	16.4	10
11	16.5	16.7	16.8	17.0	17.1	17.3	17.4	17.6	17.7	17.9	11
12	18.0	18.2	18.3	18.5	18.6	18.8	18.9	19.1	19.2	19.4	12
13	19.5	19.7	19.8	20.0	20.1	20.3	20.4	20.6	20.7	20.9	13
14	21.0	21.2	21.3	21.5	21.6	21.8	21.9	22.1	22.2	22.4	14
15	22.5	22.7	22.8	23.0	23.1	23.3	23.4	23.6	23.7	23.9	15
16	24.0	24.2	24.3	24.5	24.6	24.8	24.9	25.1	25.2	25.4	16
17	25.5	25.7	25.8	26.0	26.1	26.3	26.4	26.6	26.7	26.9	17
18	27.0	27.2	27.3	27.5	27.6	27.8	27.9	28.1	28.2	28.4	18
19	28.5	28.7	28.8	29.0	29.1	29.3	29.4	29.6	29.7	29.9	19
20	30.0	30.2	30.3	30.5	30.6	30.8	30.9	31.1	31.2	31.4	20
21	31.5	31.7	31.8	32.0	32.1	32.3	32.4	32.6	32.7	32.9	21
22	33.0	33.2	33.3	33.5	33.6	33.8	33.9	34.1	34.2	34.4	22
23	34.5	34.7	34.8	35.0	35.1	35.3	35.4	35.6	35.7	35.9	23
24	36.0	36.2	36.3	36.5	36.6	36.8	36.9	37.1	37.2	37.4	24
25	37.5	37.7	37.8	38.0	38.1	38.3	38.4	38.6	38.7	38.9	25
26	39.0	39.2	39.3	39.5	39.6	39.8	39.9	40.1	40.2	40.4	26
27	40.5	40.7	40.8	41.0	41.1	41.3	41.4	41.6	41.7	41.9	27
28	42.0	42.2	42.3	42.5	42.6	42.8	42.9	43.1	43.2	43.4	28
29	43.5	43.7	43.8	44.0	44.1	44.3	44.4	44.6	44.7	44.9	29
30	45.0	45.2	45.3	45.5	45.6	45.8	45.9	46.1	46.2	46.4	30
31	46.5	46.7	46.8	47.0	47.1	47.3	47.4	47.6	47.7	47.9	31
32	48.0	48.2	48.3	48.5	48.6	48.8	48.9	49.1	49.2	49.4	32
33	49.5	49.7	49.8	50.0	50.1	50.3	50.4	50.6	50.7	50.9	33
34	51.0	51.2	51.3	51.5	51.6	51.8	51.9	52.1	52.2	52.4	34
35	52.5	52.7	52.8	53.0	53.1	53.3	53.4	53.6	53.7	53.9	35
36	54.0	54.2	54.3	54.5	54.6	54.8	54.9	55.1	55.2	55.4	36
37	55.5	55.7	55.8	56.0	56.1	56.3	56.4	56.6	56.7	56.9	37
38	57.0	57.2	57.3	57.5	57.6	57.8	57.9	58.1	58.2	58.4	38
39	58.5	58.7	58.8	59.0	59.1	59.3	59.4	59.6	59.7	59.9	39
40	60.0	60.2	60.3	60.5	60.6	60.8	60.9	61.1	61.2	61.4	40

Page 1

CONTACTS

Maj. Joe L. D. Manns Duluth ANG 218-723-7220
 Col. Don. Sawicki Ha. Mo. ANG 612-296-4673
 Sgt. Jim Norton Duluth ANG (CE)
 (Utilities) work control x 292
 Sgt. John Wedlund Facility Mgr (CE) x 408
 Sgt. Harold Stevens Supply x 293
 Bill Hayden ES-Deputy PM O.R. 615-481-3920
 Larry Janssen Hazwopar 615-576-1967
 Tom Sturdivant Hazwopar 615-482-6601
 Enrique Gentsch Meca
 Site Response 612-296-7803
 Elizabeth Gagnys MCA Site Response 612-296-7821
 Ed Grunwald HES Mgr ES 404-325-0770
 Tom Othowdt - North Star Delg O. 612-632-6552
 H. 612-632-2326
 Melanie Baltimore, Berkeley Lab 0.415-841-7353
 H. 415-937-5348
 Kathleen Kidd Berkeley Lab H. 415-937-9475
 Bruce Bucke (Utilities C.V. EL) 218-723-7294
 Graves (Danny) Drilling Shop 877-2076
 old shop 624-4344

Page 2

EMERGENCY CONTACTS

Base Main Gate Security 723-7280
 Fire Dept 723-7233
 Base Control 1-800-337-3073
 Medical Emergency
 Hospital St. Lukes Hospital of Duluth
 Adm 915 East 1st St. Duluth, MN
 Repair (218) 726-5555
 Base POC Maj. Joel Manns
 CE MN ANG
 W (218) 723-7270
 H (218) 728-2633
 ES
 P.M. R.S. McLeod
 ES OR RV (615) 481-3920
 Apt. 615-483-4613
 Home (404) 953-9603
 HSO Ed Grunwald
 ES AL GA (404) 325-0770

SAMPLING EQUIPMENT USED

Item	Egpt	Asset #	Serial No
1	HNU RT 101 Field ID	566791	761235
	Probe & Pump	500018	M1144
2	HNU PI 101 Field ID	164716	601288
	Probe & Pump	501288	707031
3	Gastech Explosimeter		CY4994
	THREE way gas alarm		
	Q x 82		
4	Biosensor II		C-611-1182
	Explosimeter		
5	Foxboro OVA 128-60	500452	50654

July 26, 1988

Arrived on site at 12:35 p.
 Met Ed Grunwald, John Hasdemann, Kim Davis, Peter Riemersma in airport restaurant for lunch
 1:00 p. arrived at hangar Met Martin Phietta representative Tom Stuchand who works for Automated Sciences.
 3:00 p. Observed decontamination initiation of drill rig about 4:30 p. there were problems with water pressure. Plain steam insufficient for cleaning. Alconox added.
 8:00 p. Dinner is all above people plus Dennis Forsberg, AT person from W.M. Discussion of application of RQA 1 to all DOE projects. Discussed construction of wells & the advisability of piling in (cementing) and to well casing (baker of frost heave against post causing destruction of integrity of shallow wells, in particular separation of

Jo. Lynn Stuchand 7/26/88

5. The screen from the well ~~is~~ itself. Perhaps a new design where the pad was separated from the well by a buffer of bentonite would protect the integrity of the well. If the design were changed this would have to be approved in writing by the properly authorized parties. At present there is no clearly understood field change procedure.

John Sherwin 7/20/88

July 27, 1988

6.

7:30. Met at hangar w/ J. Hardeman, K. Davis, P. Clemensma, T. Sturchmann, D. Forsberg also present.

Prepared for taking water level readings w/ K. Davis.

Obtained key for wks.

Prepared personal field equipment

Calibration of HNU meter # 500791 procedure observed by D. Forsberg.

T. Sturchmann, K. Davis. procedure done by J. Hardeman. using procedure described in Instruction Manual # 601213.

provided by US Analytical Instruments for Model # P1 101

Span set on 5, for 11.72V
Battery O.K.

Pump is operating reading ~150

John Sherwin 7/26/88

7. New Spain's
Et. 12-3.32

Calibration gas into
bp from liquid Carbonic
Dore: June 15, 1988

Content 94.7 ppm Isobutylene
Bal air

Batch # 9488-061588

Lot # 12

Certified by SL
#

Weather info

Skewed and cloudy in 70's. By
mid-day bright, clear sky, a
slight breeze.

#

Jo Ann Sherwin 7/26/88

8°

FAA Standards as

brought to our atten. By Sgt
Denney

← 75' →

← 37½' →

118' - 37' = 81' * 75' →

total wingspan largest aircraft

747 236'

1/2 of this is 118'

any permanent construction needs
to the outside of 500' of runway
or else it has to have breakaway
couplings.

=

Jo Ann Sherwin 7/27/88

9.

Well #

Time 11:17

Oppm Hdr. Reading
Signal indicator set on 5

Well # Time Reading TDC TOSC total depth

GW 2E 11:12 Oppm 13.22 13.22 14.03

~~GW 2D 11:23~~ 13.54 13.54 23.48

GW 2D 11:23 Oppm 13.54 13.54 23.48 (below TDC)

GW 2E 11:40 13.15 13.98 20.25

Break for lunch. Equipment decontaminated by Kim Davis before return to field according to procedures described in work plan

OJT is water level measurement given to J. Sherman & Kim Davis by J. Hardeman

Used electronic water indicator calibrated by manufacturer to 1 foot intervals. Obtained additional information by using an engineers scale accurate to 100ths of an inch. This is different from the work plan as described on pg. 2-9 See 2.2.6 which says "An electronic water level indicator accurate to 0.01 feet will be used to measure the depth to water."

Decontamination procedures differ from those in the work plan and are described in Kim Davis field notes

J. Sherman 7/27/88

10.

Remarks.

John Hardeman took readings and protection worn, decontamination done.

Undocked well casing cap well above casing. Was this original construction or did it float loose? It did read 100 ft.

2nd Reading Kim Davis operator

Equipment decontaminated by Kim Davis before return to field according to procedures described in work plan

given to J. Sherman & Kim Davis by J. Hardeman

Used electronic water indicator calibrated by manufacturer to 1 foot intervals. Obtained additional information by using an engineers scale accurate to 100ths of an inch. This is different from the work plan as described on pg. 2-9 See 2.2.6 which says "An electronic water level indicator accurate to 0.01 feet will be used to measure the depth to water."

Decontamination procedures differ from those in the work plan and are described in Kim Davis field notes

J. Sherman 7/27/88

Remarks

Well Time HNU TOS TOSC T.D.

difficulty locating existing wells on site #2
provided to use tape & compass to relocate wells
data on following pages

J. J. Sherwin 7/27/88

J. J. Sherwin 7/25/88

13

Remapping Data

GNW2-C to MW-4 S ~~N~~ 33° ~~E~~ E
122.2 + 121.2' N 28° W (BS)

GNW2-C to B2-9 S 10° W
237.5 - 236.5

MW-4 to B2-9 N 37° E
161.3 + 60.3 S 37° W (BS)

B2-9 to MW-5 S 27° E
151.9 + 50.9 N 23° W (BS)

MW-5 to GNW2-B N 40° E
217.7 + 60.7 S 39° W (BS)

MW5 to MW6 S 78° W
144.0 + 133.0 N 82° E (BS)

MW6 to GNW2A S 82° W
198.0 + 97.0 N 83° E (BS)

MW5 to GNW2A S 83° W
N 84° E (BS)

Q. Shown in 12/1/88

14

GNW2A to MW7 N 27° E
110.6 + 99.6 S 28° W (BS)

Finished at 6:15 p.m.

Scattered clouds

Temperature around 75°F
Pleasant.

Field Assistant Jim Davis

Shut HNU Meter off & left at
hangar.

Closed & locked warehouse at
hangar.

Data Reduction using map scale
& 40 ruler scale.

400' = $\frac{x'}{x}$ = map
452' = $\frac{x'}{x}$ = index
82 x = 2' + 1.13

GNW2-C to MW-4 137' x 121' S 30° E

GNW2-C to B2-9 267' x 236' S 10° W

MW-4 to B2-9 181' x 160' N 35° E

B2-9 to MW-5 171' x 151' S 25° E

MW-5 to GNW2-B 245' x 217' N 45° E

Golden Shown 7/27/88

15

		X	Y	
MW-5	to	MW-6	162	143
MW-6	to	GW2A	223	197
MW-9	to	GW2A	—	—
GW2A	to	MW-7	124	110
				N27E

July 22, 1988

16

Procedure used to obtain water level readings at Start of Day

① Calibrate HNU wrap probe in plastic

② Decontaminate water level indicator & wrap in aluminum foil

③ Obtain key for wells of fenced areas

④ Take maps, rubber gloves, plastic, trash bag, small HPLC & methanol bottles, tape measure calibrated to 100 ft.

⑤ Take large dominating water jug, large refill HPLC, methanol, bottles, machete, measuring tape, compass, ruler & personal field gear & P.F.

J. Sherrin

7/28/88

J. Sherrin 7/28/88

17.

At each well

- ① Unhook cap
- ② Take +HND reading as inner cap is lifted
- ③ ~~At each~~ set indicator on 0-200
- ④ Stand ^{upward} to the side. ^{stand by put plastic back} Put on protective gloves ^{on probe}
- ⑤ Set water level indicator at 5.
- ⑥ Lower tool in hole until sound is heard, adjust until spot where sound just begins is determined. Take foot reading, use tape measure to read Sounding's Read from where fingers mark to nearest pole of foot marker on tool. This measurement is TDC
- ⑦ Repeat for TOSC (outer protective casing)
- ⑧ Lower tool to bottom of hole until line goes slack. Adjust spot where weight of tool is barely perceptible. Record reading as above, and note where this reading is from TDC or TOSC

Q. Sherrin 7/28/88

18.

- ⑧ decontaminate ~~tool~~ line, then probe by washing down with methanol & rinsing with HPLC water. Place on plastic do not permit probe to touch ground.
- ⑨ Dispose of gloves in plastic bag.
- ⑩ Repeat TDC
- ⑩ Take additional measurements such as TOSC to ground or TOSC to top of pad
- ⑪ Note general condition of well
- ⑫ Lock TOSC

Q. Sherrin 7/28/88

7/19.

The weather is bright & clear, no clouds - it is in the 70's at 8:30 a.m. and supposed to get quite hot. It is quite breezy.

Recalibrated HNU (K. Duns) after Lurschi and before taking readings at sites 3, 4 & 8.

All readings at Site # 2 were 0 ppm the first time the well was opened. ~~the~~ water level readings were taken at two wells (GW2-E & GW2-D) on two successive days. On the 2nd day the readings were 20 ppm.

Jo Ann Sherman 7/20/88

20.

Jo Ann Sherman 7/20/88

Well	Time	HND	SITE #2	TOC	TOSC	T.D	Remarks
SW-2	9:30a	50 ppm	13.57 (+11)	13.46	23.43 (TOC)	1.66	Distance between ground & bottom of pad varies between 13-15. Thickness of pad approximately 0.45'
SW-2E	10:12a	75 ppm	12.93 (+10)	13.69	20.18 (TOC)	0.59	Grind & bottom of pad 15'
						0.63	Grind to top of pad -
							Thickness of pad approx 0.45'
MW-1	10:31	0 ppm	15.32 (+10)	15.33	26.19 (TOC)	1.79	TOC to grind surf -
							Pad has disintegrated & is now a heap of weathered cement
MW-2	10:55	0 ppm	12.56 (+14)	12.60	26.29 (TOC)	1.79	This hole is moist located on the map TO SC to gym sand
							Pad has disintegrated. Small rubble pile. There is no back on this well.

J. Sherwin 7/28/88

83.

Well	Time	HAUV	TOC	TDSS	ID
GW2-C	11:17	Oppm	13.99	(-11) 13.88	23.98
MW-4	11:30	Oppm	12.97	12.97	22.98
MW-5	11:45	Oppm	20.14	(+02) 20.16	22.29
GW2-B	11:58	Oppm	18.62	(-11) 18.51	14.10
MW-6	12:09	Oppm	13.02	(+03) 13.05	16.14
GW2-A	12:21	Oppm	11.41	(-22) 11.29	12.39
MW-7	12:30	Oppm	11.00	(+03) 11.03	22.06

Finished at 12:42 Lunch break

24.

Remarks	Top of Pad	Pad to Top of Ground
Bottom of pad to ground about .04' small separate inner cap cracked & open	2.28	1.50
No pad, small dirt mound	2.14	→
Cement pad weathered away from ground	2.43	75
Appears as an inverted cone, casing can be shaken from side to side		
Gloves decontaminated & stored in separate plastic bag. Will be reused for all following		
Off ground about 12'	2.51	0.56
No pad small weathered pad	2.93	→
Pad sitting directly on ground	2.49	46
Concrete pad sitting in ground at ground level	2.34	→

2. Sherwin 7/20/88

25.

Well	Time	HNU	Site # 3	TOC	TOC	ID
GW3-C	3:55	4 ppm	9.28	9.28	21.39	
GW3-B	4:10	1 ppm	11.40	11.54	22.00	
GW3-D	4:23	0.5 ppm	8.21	8.93	19.13	
GW3-A	4:35	0.5 ppm	13.60	13.67	18.14	
Finished site # 3 at 4:43 p.						

J. Sherwin 7/29/88

26.

Top of Pad	Top of Pad	Remarks
1.99	.41	Cap broken into 3 parts - one part missing. Pad off ground about .08"
2.45	.45	Cap crack in half. Separated ~ 1/8" Correction there is a 1/8" saw cut in top of cap. Pad is completely on ground.
2.07	.52	.07 off the ground
2.68	.42	1/8 inch saw cut in cap. Pad off ground by about .05"

J. Sherwin 7/29/88

29

Located all other wells at Site 4.

Water level indicator may need new batteries. Takes 3 AA.

Stop at Target to get batteries, screwdrivers, pliers & adjustable wrench.

July 29, 1988

30

Start work 7:00 a.m.
Weather partly overcast.
Occasional drizzle.

Put batteries in water level indicator and it tests out o.k.

Kim Davis calibrated HNU.

Will take rest of water level measurements by myself this morning. All previous measurements taken this book done by Kim Davis & J. Sherrin (includes remapping Site 2 north of road).

9:00 a. Bought pocket watch. Delay in start of drilling ~~at~~ ^{by} Kim Davis.

Ride Site #4. Beginnings ~~at~~ ^{of} Not as. Since today's readings for MW-8 were within 100 yds. yesterday's readings, Decided to not ~~redo~~ redo MW-9, GW-4 & GW-5. ^{9:45 a.m. 7/29/88}

Go. Kim Sherrin 7/28/88

[illegible]

TDSC to top of pad	Top of pad to ground	Remarks
2.98	→	see previous page & day No Luck. No pad is spout visible, ground flat. Looks like well might have been hit by equipment or vehicle. It is no longer vertical. A reflector is now wired to the protective casing. Pipe is now at 80° to the ground. 1.86 → The well was disturbed yesterday, as readings were attempted but water level indicator was not working. Bottom sediments were stirred up. Pipe goes into ground. No pad or spout seen. 2.48 417 Vertical cap (0.27) back now at pad - 0.15 = .37, no chicken wire pad 0.1 distance to ground. J. S. Durwin 7/29/48

33

Well	Time	HNU	TOC	TDSC	TD
GW4-B	10:19	1.00	8.06	8.38	23.28

END OF SITE #11

START OF SITE #8

GW8-B	10:38	1.00	8.25	9.53	21.86
-------	-------	------	------	------	-------

GW8-A	10:49	1.00	8.90	9.29	15.11
-------	-------	------	------	------	-------

GW8-C	11:00	1.00	10.85	10.94	19.48
-------	-------	------	-------	-------	-------

END OF SITE 4

Finished taking readings at 11:07a

4 Sherwin 7/29/88

34

Top of pad	Top of pad	Top of pad
2.76	5.9	5.9
2.65	.5	.5
2.17	.53	.53
2.63	.57	.57

4 Sherwin 7/29/88

Aug 2, 1988

Start work 6 a.m. cloudy with

barraging in all other holes

to finish Davey & Peter Remington

8:00 a.m.

Working on holes 5, 6, 7, 8, 9

North of road.

Established new base point

from MW-4 & GW2-B.

from ~~MW-4~~

MW-4 to base point 60 S56W

300' 201.0 N47E (BS)

GW2-B to base point S 44W 17

201.4' 202.9 S 44W N47E (BS)

MW-2 to base point S 33E

220' 7 (N47E) (BS)

Tower (BS) were since MW-2 surrounded by iron

1' needs to be added to all

previous linear measurements

since J.S. did not hold 0' at

start point. She held -0.0' at

points. She ruled all previous

start points. DONE @ 10:55a J. Sherrin 8/2/88.

MW-2 to	MW-1	N 27 E
	153'	(S 55 W) BS
	we BS because of	
	cultural iron lying around	
MW-2		
MW-2 to	GW2-E	67 N 43 E
	182.7'	S 60 W (E)
GW2-E to	GW2-E to	S 55 E
	139.1'	50
	Possible soil boring 7.4' from	
	GW2-E. It consists of stick with	
	red flagging around in	
	ground. No numbers	
	visible on stick	
	GW2-D to possible boring	547 E
	4.4'	41
SB2-C to	GW2-D	70 N 67 E
	142.6'	S 63 W
	Finished data 2 at 10:10 a.	
	Tried to locate MW-3 MW-3 and	
	could not	
	Also tried to locate S-2A, S-2C	
	and S-2B as shown on Fig. 4.1	

J. Sherrin 8/2/88

and could not find them.
The termed area on map does not correspond to relationship between termed area and location of wells as observed in the field.

The FTA south of the road had a fire smell this morning and old sheep and kid bleats were observed in some of the standing puddles which formed as a result of recent rains and excess water from pouring of two holes in the center of the area.

Site #3

EW3-D to corner of shed 58°E
137°

EW3-D to Marker in parking lot 58°W
19.8
N38°E (BS)
44

J. Shorman 8/2/88

Marker to GW3-B
41.6
90 S87°W
N85°E (BS)

Marker to GW3-C
76.8
56 S48°W
N81°E (BS)

GW3-C to GW3-B
41.3
25 N19°E

Marker to GW3-A
138.0
4 S44°E
N82°W (BS)

(BS) is better measured in situ
Finish Site 3 at 11:40 a

Site 8
NE corner of Quonset hut to GW8-B
58
552°W
N58°E

GW8-B to GW8-A
302.1
S86°E
80°N55°E

GW8-A to GW8-C
252.8
N85°E
N82°E

Marker to GW8-C
239.8
N5 S8°E
N5W

Finished 12:25 p

(BS) = Back-sight
IS = J. Shorman

KD = Kim Davis

J. Shorman 8/2/88

39

Site #4

MW 8 to SE Shed corner

N 9 E
N 3 E

MW-9 to NE Shed corner

N 3 E N 12 E
S 5 W (BS)

MW-9 to fence corner

N 2 W KD
N 3 W JS

Fence corner to GW4-D

N 65 W JS

302.3

MW-9 to GW4-D

N 52 W
H 52 W

No distance recorded

S 53 E

All readings on Thursday prior to this reading need to be made

consistent w readings previous day. Following "marker" set opposite previous readings. Thus day JS Brunton was used. Previous day JH Brunton was used.

GW4-D to GW4-C

N 77 E KD
N 75 E JS

217.2

GW4-C

to MW-11

S 35 W KD
S 34 W JS

105.4

GW4-C

to GW4-B

S 16 W KD
S 15 W JS

177.2

~~GW4-C~~

J. Sherwin 8/2/88

40

MW-11 to GW4-B

S 8 E

85.5

MW-10 to Shed @ SW corner

N 81 E JS

172.6

N 80 E KD

MW-8 to GW4-A

S 60 W JS

200.0

N 63 E JS

8

Corrections made. 1° Added to NXF readings. 6° Subtracted from NW readings

Spunished oil
5:00 p.

J. Sherwin 8/2/88

41

August 3, 1988

6:30 a Start work

Plot holes on aerial photos
marked - 45 plots drawn on
plain white paper. KD trans-
cribes them to aerial photos
using pin method.

Chat w Eugene -
the Monarcha population
control person.

finish 2:30 p

G. Shewin 8/3/88

42

August 5, 1988

Start work 6:30 a Rain chilly
Search for barn lanes & FIAZ-1.
Literature search in prepara-
tion for using backhoe.


Wester report. MW-5, MW-6, MW-7.
These holes are isolated on
their maps. Actual distances
between holes is $\frac{1}{2}$ to $\frac{3}{4}$ the
distance shown. The only hole
which is rough analysis
shows anything but ~~very~~
very minor contamination
is MW-5 or Table 4-1 (pg 4-7)

Wester report shows:

MW-4	0.42	15.9	5.6
MW-5	0.75	28.0	44.6
MW-6	0.33	15.4	24.6
MW-7	0.38	126.3	17.0
	organic	TOX	TDC
	mg/l	ug/l	mg/l


G. Shewin 8/5/88

43



Edwin Shorwin 9/2/88

44



Edwin Shorwin 9/2/88

45

2:30 p Searching FIH-2-1 wells

Backhoe

4:00 p Finished

Nothing found

J. Sherman 8/5/88

46

August 6, 1988

Start work at 1:30

Three sunny days, increase

about 6:15 a light breeze

ES personnel of Sherman

Robert Bremersma and Jim

Edwards

Drillers: Jim & John

* Midway North Star.

Levin equipment and

rigs from yesterday.

Start drilling W.P. 10 at 8:00

Reached 35' at 1:00 p.m.

An airport authority person came up and explained that all fence gates must be kept locked. Flagrant violator would receive a \$1000 fine. It is O.K. to leave open a gate that is within one's constant view as we had done with the gate to the site. The problems turned out.

J. Sherman 8/6/88

47

the gate area by the desert area that the drillers had left open. Our view of it is blocked by the fuel tank hut. I said we would take care of it right away. He said he was going back by that area and would check it. We 3 FS people do not have a key to that gate. Will tell the drillers at the first opportunity that all gates should be kept shut & locked.

11:30a Bedrock at 45.0' drilled to 47.5'

Lunch

Set well point.

Drilled shallow well to 70'

Helped log core, discussed well with Peter. Finished at 4:10p

Then Davis & I went back to Site 7 to measure the distance between MW-1 & QW2-D with a tape

J. Shorwin 8/6/88

48

@ 586E

MW-1 to QW2-D @ E-W 452.4' 16.0' + 12.8' = 272.8' S82E

Paul & K. Davis doing measurements & measure of my previous theory. ~~for~~ Measurements are not completely accurate since a term obstructs visibility between the two wells, and a small shed close to MW-1 may also intrude on a small way on the line of sight.

Left Duluth IAP at 5:00p.

J. Shorwin 8/6/88

49

8/8/88

Start work at 6:30a.

Pilot Riverina

J. Sherwin

Kim Davis

Started drilling at 8:00a.

8/9/88

Measuring in trenches at

Site #1 FTA 2-1

From	To	Distance	azimuth	Notes
MW-5	5	167.9	S39E	
MW-5	6	183.0	S50E	
6	3	59.5	S12E	#4 missing -
6	1	111.2	S16E	the number -
6	32	142.0	S24E	not the hole -
6	13	134.3	S41E	No hole given
6	12	131.2	S60E	the number
6	14	171.3	S43E	
6	2	97.3	S27E	
6	7	35.4	S53E	
6	8	35.1	N79E	
6	9	79.2	N89E	

J. Sherwin 8/10/88

50

From	To	Distance	azimuth	Notes
6	10	93.0	N87E	
6	16	126.9	N89E	
6	11	102.9	S81E	
6	15	150.5	S84E	
6	17	144.6	N61E	
6	18	173.2	N68E	
6	31	144.2	N24E	
6	30	87.4	N11W	
6	29	104.0	N26W	
6	28	156.6	N18W	
28	MW5	96.8	S71W	
28	26	144.3	N55W	
28	25	96.0	N2W	
28	24	178.9	N12E	
6W2-B	25	66.5	S48W	
6W2-B	24	35.5	N16W	
6W2-B	23	61.2	N26E	
6W2-B	23	159.1	N78E	
6W2-B	34	147.7	S38E	S73E the hole
28	27	86.1	S89W	Chuck measurement
MW-5	27	157.9	N146W	Use this for #27
21	22	121.4	S61W	
21	20	49.1	S26W	
22	33	87.3	S54E	No hole #19

J. Sherwin 8/10/88

J. Sherwin 8/10/88

mismarked

1 ✓ 2 ✓ 3 ✓ 4 ✓ 5 ✓ 6 ✓
 7 ✓ 8 ✓ 9 ✓ 10 ✓ 11 ✓ 12 ✓
 13 ✓ 14 ✓ 15 ✓ 16 ✓ 17 ✓ 18 ✓
 (19) 20 ✓ 21 ✓ 22 ✓ 23 ✓ 24 ✓
 25 ✓ 26 ✓ 27 ✓ 28 ✓ 29 ✓ 30 ✓
 31 ✓ 32 ✓ 33 ✓ 34 ✓

No holes numbered 4, 19

~~These~~ Misnumbered & these numbers were stripped.

done by J. Sherwin, assisted at 11:50

J. Sherwin 8/10/88

8/11/88

Cloudy, overcast. 70's.
 7:40 Starting backhoe work
 8 locate FIA2-1
 Didn't find anything
 12:10 Lunch

HMM readings on Site 8

Hole #	Reading	Comments
A0	0 ppm	2.4' deep
A1	0 ppm	2' deep
A2	0 ppm	went down 2'
A3	0 ppm	3' 1000' holes - depth 8.5' - water to (4" diam), 1.6" diameter 1' deep
B0	0 ppm	1.7'
B1	0 ppm	1.8" deep (1.7' deep)
B2	0 ppm	1.8' deep
B3	0 ppm	1.6' deep
C0	0 ppm	1.7' deep
C1	0 ppm	1.5' deep
C2	0 ppm	1.4' deep
C3	0 ppm	2.0' deep
D0	0 ppm	1.6' deep
D1	0 ppm	1.4' deep

J. Sherwin 8/11/88

53

Hole #	Time	Reading	Comments
D2	Oppm	1.4'	deep
D3	Oppm	1.7'	deep
E0	Oppm	1.3'	deep
E1	Oppm	1.4'	deep - perhaps 14' mud
E2	Oppm	2 holes, 1.1', 1.2'	deep
E3	Oppm	2.1'	deep
F0	Oppm	1.9'	deep
F1	Oppm	1.2'	additional (total 1.6')
F2	Oppm	1.3'	mud & water in bottom .4'
F3	Oppm	1.4'	deep

J. Sherrin 8/11/88

54

8/16/88

Start 6:30
 Start soil borings - hand augering
 at Site 3 at 8:30a
 Clear, sunny light breeze
 J. Sherrin & Mike Rowdy
 doing the sampling. Start
 Samples at only the
 following points will be
 attempted

Number	Time	Depth	Remarks
B1	8:45	1.2	950 10.00 #100 sample
A1			
A0	1:45	1.9	150 1.55 (1.9-1.9) sample
A1	1:15	2.3	135 1.40 easy digging
A2	12:15p	1.9	120 1.25 easy digging
A3	2:00p	1.8	210 2:15 easy digging
A4			
A5			
B2			
B2.1	12:40p	1.8	150 1.55 easy digging
B3	2:50	1.7	300 3:00 sample 1.5-1.67
B3.5	3:30	2.0	210 2:15 sample 1.8-2.0

55

55	Number	Time	Depth	Vol	Soil	Remarks
	*B 4	3:15	1.7	3.20	3.25	3.25 samples
	*C 0	11:15	1.3	11:25	11:30	1.5-1.7
						by 5 holes to 7 inches
	*C 0	10:50	2.0	10:55	11:00	no gravel, all soil
	*C 2	8:45	1.2	9:00	10:10	4" brs, 1 channel samples
	*C 3	10:15	1.8	10:25	10:35	easy sample
	C 5	10:15		10:25	11:00	no gravel, all soil

D1
D2
~~D3~~
D4
D5
~~E1~~
E2

prefix 3SS used on all samples.

~~F-3~~

H/E 3 Volatile

Samples with an asterisk (*) beside them are labeled 8/15/88 which is incorrect. It should be 8/16/88 sampling finished at 4:00 p.m.
Arrived at hotel at 7:30 p.m. H.E.S.

55

Core #	Time	Depth	Remarks
1	8:35	0	10' to 12' to 14'
2	8:43	0	15' to 17'
3	8:50	0	12' to 14'
4	8:56	0	13' to 15'
5	9:08	0	10' to 12' to 14'
6	9:15	0	15' to 17'
7	9:31	0	12' to 14'
8	9:35	0	10' to 12' to 14'
9	9:43	0	13' to 15'
10	9:51	0	15' to 17'
11	9:56	0	12' to 14'
12	10:04	0	13' to 15'
13	10:12	0	15' to 17'
14	10:20	0	12' to 14'
15	10:28	0	13' to 15'
16	10:36	0	15' to 17'
17	10:44	0	12' to 14'
18	10:52	0	13' to 15'
19	11:00	0	15' to 17'
20	11:08	0	12' to 14'
21	11:16	0	13' to 15'
22	11:24	0	15' to 17'
23	11:32	0	12' to 14'
24	11:40	0	13' to 15'
25	11:48	0	15' to 17'
26	11:56	0	12' to 14'
27	12:04	0	13' to 15'
28	12:12	0	15' to 17'
29	12:20	0	12' to 14'
30	12:28	0	13' to 15'
31	12:36	0	15' to 17'
32	12:44	0	12' to 14'
33	12:52	0	13' to 15'
34	13:00	0	15' to 17'
35	13:08	0	12' to 14'
36	13:16	0	13' to 15'
37	13:24	0	15' to 17'
38	13:32	0	12' to 14'
39	13:40	0	13' to 15'
40	13:48	0	15' to 17'
41	13:56	0	12' to 14'
42	14:04	0	13' to 15'
43	14:12	0	15' to 17'
44	14:20	0	12' to 14'
45	14:28	0	13' to 15'
46	14:36	0	15' to 17'
47	14:44	0	12' to 14'
48	14:52	0	13' to 15'
49	15:00	0	15' to 17'
50	15:08	0	12' to 14'
51	15:16	0	13' to 15'
52	15:24	0	15' to 17'
53	15:32	0	12' to 14'
54	15:40	0	13' to 15'
55	15:48	0	15' to 17'
56	15:56	0	12' to 14'
57	16:04	0	13' to 15'
58	16:12	0	15' to 17'
59	16:20	0	12' to 14'
60	16:28	0	13' to 15'
61	16:36	0	15' to 17'
62	16:44	0	12' to 14'
63	16:52	0	13' to 15'
64	17:00	0	15' to 17'
65	17:08	0	12' to 14'
66	17:16	0	13' to 15'
67	17:24	0	15' to 17'
68	17:32	0	12' to 14'
69	17:40	0	13' to 15'
70	17:48	0	15' to 17'
71	17:56	0	12' to 14'
72	18:04	0	13' to 15'
73	18:12	0	15' to 17'
74	18:20	0	12' to 14'
75	18:28	0	13' to 15'
76	18:36	0	15' to 17'
77	18:44	0	12' to 14'
78	18:52	0	13' to 15'
79	19:00	0	15' to 17'
80	19:08	0	12' to 14'
81	19:16	0	13' to 15'
82	19:24	0	15' to 17'
83	19:32	0	12' to 14'
84	19:40	0	13' to 15'
85	19:48	0	15' to 17'
86	19:56	0	12' to 14'
87	20:04	0	13' to 15'
88	20:12	0	15' to 17'

57

well #	Time	WT	TOC to ground	Remarks
MW 1	10:01	C	7.15	
MW 5	10:05	D	8.27	
GW 13 B	10:08	D	8.44	
3MW 23	10:12	D	7.99	2.53 TOC to ground
3MW 27	10:17	D	4.75	1.46 TOC to ground
3MW 29	10:24	D	9.72	2.61 TOC to ground
2MW 40	10:35	D	8.60	2.55 TOC to ground
3MW 48	10:53	D	5.73	2.17 TOC to ground
Unlocked		Site	2 at 10:51	
Start		Site	2 at 12:45	
8MW 14	12:50	D	8.24	2.06 TOC to ground
8MW 15	12:47	D	10.14	2.24 TOC to ground
8WP 9	1:07	rain	7.59	2.58 TOC to ground
8WP 10	1:10	rain	8.11	0.99 TOC to ground
4WP 11 D	1:20	rain	10.02	2.48 TOC to ground
8WP 16	1:27	rain	7.61	2.71 TOC to ground
8WP 17	1:31	rain	8.25	2.47 TOC to ground
GW 8-C	1:41	rain	6.91	
GW 8-A	1:52	rain	6.56	Well unlocked
GW 8-B	1:59	rain	6.63	
8WP 10 D	2:08	rain	7.11	2.27 TOC to ground
8WP 10	2:11	rain	5.80	2.18 TOC to ground
				2.71 TOC to ground
				Unlocked

Unlocked 8/22/08

58

well #	Time	WT	TOC to ground	Remarks
MW 10	3:17	rain	5.61	no lock
				order is in
				opened
MW 8	2:21	rain	6.78	
MW 9	2:27	rain	6.49	no more gas
4MW 21	2:32	rain	7.30	2.79 TOC to ground
8MW 42	2:42	rain	6.26	2.79 TOC to ground
GW 4 D	2:48	rain	10.59	2.79 TOC to ground
4MW 22	2:51	rain	9.49	2.58 TOC to ground
GW 10	2:54	rain	10.95	
4MW 23	2:59	rain	7.72	1.69 TOC to ground
MW 11	3:03	rain	7.83	
GW 3 A	3:33	rain	11.98	
GW 3 B	3:26	rain	9.82	
GW 3 C	3:30	rain	9.95	
GW 3 D	3:22	rain	6.40	
GW 4 B	3:39	rain	5.70	
GW 4 A	3:47	rain	5.00	
8MW 43	4:04	rain	13.13	8.45 TOC to ground

Unlocked 8/22/08

59

74th
8/25/88

3:10 Watching well development
on MW14 1 MW15 - 17 at least
and 1800 ft long 1800 ft
diameter. Also along scattered
climbs. They have been working
on these for awhile

8/25/88

7:00 Clear blue sky, wind 15-25
3:00 Observed pumping of MW16
T. Cochran & Greg Davidson. They
started pumping this well at
7:00 a

8:15 a. B. McLeod came by and decided
we should try flushing wells
MW14, MW16 & MW17 with potable
water to see if that speeded
up the process of development
Delayed pumping MW16

9:15 Initiated pumping MW16

10:15 a. Started pumping MW14 & MW16, MW17

11:20 a. Started pumping MW14

D. Cochran, McLeod 8/25/88

60

11:25 a. Watching well development
pumping Continue
11:30 MW17 Start development
11:50 Lunch
12:45 Cochran to well pump
not working. Out of gas
12:50 Start pumping
1:10 MW14 clear OK Bar
development
1:15 a. Not entirely clear, but the
MW17 well makes a little
water that it is unlikely
that it will put very
much water. Hand pump
water on this well
12:17 a. D. Cochran - go to next
pits
2:40 Start development of MW21
Not re - forget to get for
water
2:50 Start well development
3:10 Start well development of MW24
with hand pump

D. Cochran, McLeod 8/25/88

61

8/26/88

8:00 Start work on large water
clean battery in rain

Start development of 4MW22 at
10:00

Start development of 4MW23 oil
10:30a. Electric pump lot 3:20

Calibrated pH meter (Hardenman
did): Ohaus Research model
SA 230 SN#2617 used fresh
quantities of

pH 4.01 Lot No 8 23.47
expiration date Apr 1989
Cole Parmer

pH 10.00 Lot No 8 26.92
exp date Aug 1989
Cole Parmer

pH 7.00 Lot No 8 26.01
exp date Jul 1989
Cole Parmer

John H. also calibrated the
Go Ann Sherwin 8/25/88

62

Working well development is Aug

Conductivity Meter

Model 1484-10 Cole Parmer

SN 7092003

93 Well# Time Temp °C pH Conductivity

4MW23 2:00 27.8 7.88 950

4:30 26.0 7.87 900

3MW27 Start development at 5:30p
(pumping)

Shut down, its not producing
5:35p

6:00p Attempt to flush well
points along primary of
site 8. Did not have all the
fittings needed will do 1st
thing in morning
get at 6:40p

John Sherwin 8/26/88

63

8/27/88

Clear, sunny, windy and chilly -
in the 50's.

7:00^{am} Calibrate the conductivity &
pH meters with the same standards
as used yesterday.

10:00^{am} Flush 3MW25 & 3MW26
start pumping.

3MW26 flushed back up
through sand pack.

3MW25 pieces of the black
plastic flush pipe seen
in washings.

Need to get straight pipe,
looks like the inside of
the screen is cut through
on the curved portion of
the black pipe.

Get straight flush pipe

To Ann Sherman 8/29/88

Temp Correction JS 9/1/88 64

and constructed yet.

11:35 Flush 3MW25
11:40 ~~Flush~~ 3MW25 ~~flush~~ to
Pumps

Well #	Time	Temp ^o	pH	Conduc
4MW25	12:05	24.5	8.02	750
	12:35	26.7	8.06	813
	1:45	20.1	8.30	144
	3:40	Shut off pump		

4MW26	12:10	27.3	8.00	475
	12:40	26.7	7.85	550
	1:50	no sample available		
	2:15	Shut off pump		

Will develop wells by hand pump &
flushing

4MW27	3:40	17.3	8.11	225
"	4:55	13.4	6.97	250
"	5:30	14.5	7.31	300

To Ann Sherman 8/29/88

65

8/29/88

7:00 Start work, calibrate inst.
overcast, on the cool side

8:00 Start development of MW27
Greg O

Well	Time	pH	condue	Temp	TOC to 9m
MW27	8:30	6.31	275		2.83'
"	8:45	6.74	260		
"	8:55	7.04	325		

9:00 Stop work on MW27. It's done
Water a little milky but

hardly any sediment at all

9:10 Move to MW26 & put in
hand pump

9:15 Start development of MW26

These readings taken is a pH
meter that may be acting up,
need to take 1 or 2 more readings

9:20 Leave to get water truck

10:15 returns - stake one sample
Mike (from Graves on the lot)

Recalibrated pH meter. One
appears to malfunction

Go Jim Sherman 8/29/88

66
pump's temp connections 28 9/1/88

	Well #	Time	pH	Condue	Temp
1	3 MW25	10:20	6.89	400	14.5
2	3 MW25	10:35	6.92	380	14.5
3	3 MW25	11:00	7.02	410	15.6
11	3 MW25	11:15	8.30	170	17.3 mud resample Capten flush
4	3 MW26	11:25	7.50	310	13.4
2	3 MW25	11:35	8.18	225	13.4 mud
5	3 MW26	11:55	7.62	300	13.4
3	3 MW25	12:00	8.36	325	13.4
6	3 MW26	12:15	7.30	340	14.5
7	3 MW26	1:25	7.02	340	15.6
4	3 MW25	1:30	8.18	400	17.3
5	3 MW25	2:35	8.03	400	17.3
6	3 MW25	2:50	8.11	200	15.6
7	3 MW25	2:55	8.02	425	14.5
8	3 MW25	3:25	8.8	250	15.6
9	3 MW25	3:40	8.14	300	15.6*
	3 MW27	3:50	7.83	375	15.4*
1	3 MW31	5:25	7.57	475	11.2
11	3 MW30	5:35	7.80	135	11.2
2	3 MW30	6:20	7.93	210	10.1

* means done, finished for Jim Sherman 8/19/88

67

10:30 left to get fitting Mike
 & water truck left behind
 10:40 flushed MW25 1 whole barrel
 a lot of whitish - grayish particles
 floating about

10:55 hand pump now assembled,
 and pumping MW25

11:15 flushed MW26 used just
 enough water to saturate
 sand pack

12:20 flushed MW25
 MW26 looks clear
 wait for pH

1:35 3MW26 is done

2:00 Flush MW25

2:45 Flush MW25 after Reading # [5]
 TOC MW25 is 1.94' ^{Sealering} Total is 2.0'

3:45 Finished development 3MW25

MW25 TOC = 2.78 TOC = 3.0'

MW25 = Barrels 5

MW26 = Barrels 2

3:45 Sample MW27

MW27 TOC = Barrels 1

4:20 Set up for wells MW30 & MW31
 Jo Ann Sherwin 8/29/88

68

Jo Ann Sherwin 8/29/88

69

Handpumps on both wells - good stream coming flush 30 at 4:45. Hand pump clogged, need to clear it.

Flushed 31 at 5:05

Pumping good w hand pump. Stopped pumping at 5:30

Section 9 more hand pump to 30. Put electric pump in 31

6:10 started pumping w electric pump in 31

6:15 Stopped pumping in 31 - something wrong w pump

6:30 Picked up NW30. Used hand pump until 7:45. Just for day

Jo Ann Sherrin. 8/29/88

8/30/88

70

Developing wells.

D. Orlhout. Loves people. Mike Start foggy, and blue sky high clouds

7:30 Set pump in NW30 & start pumping

Calibrated pH & Conductivity meters 10:40 Finished with NW30

10:45 Set hand pump in NW31

10:55 1st sample NW31

TDC NW30 is 2' 70' Barrels = 1 $\frac{1}{2}$

TDC NW31 is 2' 30' Barrels = 1

11:40 Finished with NW31

11:55 Put hand pump into NW33 & start pumping

12:25 Put pump in NW34 & start hand pumping

1:45 Flushed NW34 - not producing any water

2:25 Short flush of NW34

4:10 Flushed BHT (next to NW30)

4:20 Finished NW34

5:00 Finished NW33

4:55 Start hand pump in NW32

J. Sherrin 8/30/88

71

Well #	Time	Temp	Conduc	pH	Remarks
① MW30	9:30	10.8	300	7.99	
② MW30	10:10	10.1	350	7.90	cleaning up
③ MW30	10:40	10.1	350	7.78	DONE
④ MW31	10:55	8.9	600	7.55	
⑤ MW31	11:10	9.10	675	7.42	
⑥ MW31	11:25	9.10	750	7.18	
⑦ MW31	11:35	8.9	725	7.31	DONE
⑧ MW33	1:25	10.1	500	7.95	
⑨ MW33	1:50	8.9	1025	7.97	
⑩ MW34	1:55	12.3	135	9.15	1st after flushing
⑪ MW33	2:15	8.9	525	8.16	
⑫ MW34	2:20	11.2	260	8.41	
⑬ MW34	2:45	12.4	225	8.31	
⑭ MW33	2:50	8.9	1025	7.89	getting clear
⑮ MW34	3:15	12.3	400	8.03	
⑯ MW33	3:20	8.9	775	7.81	
⑰ MW34	3:45	11.2	525	7.92	getting clear
⑱ MW33	3:50	8.9	1275	7.80	cleaning up
⑲ MW34	4:15	11.2	525	7.88	DONE
⑳ MW33	4:20	9.10	1200	7.77	
㉑ MW33	4:55	8.9	1275	8.01	DONE
㉒ MW32	5:05	10.1	1375	7.78	very 1st muddy sample
㉓ MW32	5:30	9.10	1500	7.52	
㉔ MW28	5:35	10.1	180	8.50	muddy 1st sample

J. Sherrin 8/30/88

Temp corrections 8/9/1/88

72

5:30	Start handpump in MW28				
5:30	Thrued & pumping MW29				
	USED curved black pipe - bound to have black plastic cuttings in the well (electric pump)				
6:40	Stopped pumping MW32 & MW28				
6:45	Stopped electric pump in MW29				
	Quit for day				
/					
Well #	Time	Temp	Conduc	pH	Remarks
① MW32	5:55	8.9	1550	7.61	starting to clear
② MW28	6:05	10.1	275	8.40	starting to clear
③ MW29	6:10	14.5	450	7.69	1st sample
④ MW29	6:20	14.5	550	7.52	big water produced
⑤ MW32	6:25	8.9	1560	7.26	clearing up
⑥ MW28	6:30	9.10	375	8.20	—
⑦ MW29	6:40	14.5	600	7.55	clearing up

Jo Ann Sherrin 8/30/88

73

8/31/88 Temp corrections
8/9/88Overcast day Mike & Tim &
Greg Oathout

Well#	Time	Temp	Conduct	pH	Remarks
⑤ MW32	8:00	8.9	1800	6.95	clear
④ MW28	8:10	9.10	450	9.80	clearing
⑥ MW32	8:15	8.9	1800	7.24	DONE
④ MW29	8:30	14.5	700	7.29	clearing
⑤ MW28	8:35	10.1	475	8.10	
⑤ MW29	8:50	14.5	725	7.33	shut down g remove blacktop
⑤ MW28	9:05	10.1	500	8.05	
④ MW28	9:30	10.1	510	8.03	clearing good
④ MW35	9:35	10.4	260	7.76	1 st sample
⑤ MW28	10:00	10.1	510	8.08	DONE trench clearing
④ MW35	10:05	13.4	300	7.62	very muddy
④ MW35	10:50	17.3	375	7.50	flushed
④ MW35	11:25	14.5	380	7.55	very muddy
④ MW29	1:45	20.1	775	7.34	cleaning up high temp. shut plastic note electric note
⑤ MW35	2:00	14.5	400	7.43	cleaning up
④ MW29	2:15	18.6	775	7.31	sat a while cloudy
⑤ MW29	2:25	14.5	760	7.26	mostly clear
④ MW35	2:30	14.5	450	7.38	DONE
④ MW42	2:50	18.4	250	7.61	clearing up fairly clear

John Shuman 8/31/88

74

7:00	start pumping MW32 & MW28
7:45	calibrated pH & conduct meters
8:15	Finished MW32 1 Barrel
9:00	Shut down MW29 needs to be flushed to remove any plastic & 1 or 2 more readings taken
9:10	Start hand pump in MW35
10:00	Finished MW28
	TOC MW29 = 3.5' ^{not long etc} plastic cone
10:55	Flush MW35 to clean out upper part of screen
11:10	Flushed MW35
11:30	Flushed MW29 to remove plastic etc.
12:40	Restart electric pump on MW29
1:00	Move to 30 MW42
1:30	Start pumping 30 MW42 is hand pump - will pump dry, then flush
1:55	Stop MW29 to get new barrel for water
2:05	Stop MW29 Start pumping MW29
2:30	Stop pumping MW29

John Shuman 8/31/88

75

Well #	Time	Temp	Conduc	pH	Remarks
MW42	3:20	174	225	7.65	
MW35	3:45	176	550	7.49	
MW42	5:15	174	185	7.62	
MW42	5:20	173	210	7.56	JS
MW42	6:40	173	250	7.59	a well dry cloudy

Jo-Lynn Sherwin 9/11/88

76

3:30	Gently flushed out MW42 twice
3:45	Stopped pumping MW35 - area closed, will need about an hour in the morning
5:55	Started pumping W hand pump in BMW43
6:45	Stopped pumping MW42
6:40	Stopped pumping MW43

Jo-Lynn Sherwin 9/11/88

Well #	Time	Temp	Cond.	pH	Remarks
77	9/1/31	Temp correction 88 9/1/88			
⑥ MW42	7:35	17.3	350	7.77	
⑦ MW42	7:55	17.3	350	7.57	
⑧ MW43	8:20	9.10	1125	7.05	
⑨ MW43	8:40	8.9	1075	6.91	
⑩ MW35	9:00	14.5	128	7.47	
⑪ MW43	9:35	18.1	1150	7.10	
⑫ MW35	10:30	13.4	400	7.45	cloudy
⑬ MW35	10:45	13.4	400	7.48	clearing
⑭ MW43	11:00	14.2	475	7.10	slut
⑮ MW35	11:10	14.5	475	7.31	muddy
⑯ MW35	11:30	14.5	400	7.32	a little cloudy
⑰ MW35	—	—	—	—	200E & 111 cloudy bottom
⑱ MW21	12:10	13.4	475	6.90	coiled down then are a little cloudy
⑲ MW21	1:15	12.3	675	7.22	cloudy
⑳ MW43	1:25	10.1	1125	6.89	muddy
㉑ MW21	1:45	13.4	725	7.05	1/2 sample after filtering
㉒ MW41	2:05	13.6	185	7.10	stirring
㉓ MW21	3:00	14.5	775	7.10	up mud
㉔ MW43	3:45	10.1	1150	7.07	
㉕ MW43	4:00	10.1	1160	6.90	
㉖ MW21	4:10	12.3	750	7.05	
㉗ MW41	4:25	12.3	180	7.10	

Go-Run Sherwin

9/1/88

9/1/88

78

7:00a	Start Work.	Mike Roddy
	Bill & John Anderson to do caps & wellhead	
	Raining day but not too cold	
	Well development - Mike Ties	
	Greg O. myself, Calibrated mot	7:30
7:15	Start pumping BG MW42	
7:20	Start pumping BG MW43	
7:55	Stop pumping MW42	
8:20	Start sampling MW43	
9:00	Start pumping MW35	
9:10	Stop pumping MW35	
9:40	Flush MW43	
10:30	Start pumping MW35	
11:35	Stop pumping MW35	
12:05	MW21 - check to see if clarity	
	O.K. Not really clear & black	
	plastic found.	
12:10	Lunch	
1:05	Pump MW21 muddy	
1:45	1:15 The pumping on MW43	
1:30	MW43 is starting to make	
	water & appears to be improving	
2:45	Set up on MW41 to hand pump	

Go-Run Sherwin 9/1/88

Well =	Time	Temp	Conduc	pH	Remarks
12	NW 41	4:45	14	180	6.68
13	NW 41	4:55	14	225	6.64 clearing up
14	NW 41	5:10	12	235	6.64 DONE
15	NW 21	5:45	17	775	7.14 DONE
16	NW 43	6:00	13	1175	6.90 DONE
Still muddy water coming up in 3rd pump of hand pump - only makes a pint of water every 15 min or so. Measurements taken in clean sample which is clean at end of pump.					

John Sherrin 9/1/85

not much water all mud flushed it starting to look good
3:00 Started pumping MW 2
4:45 New mercury thermometer
All temp readings need to be corrected by 1°
5:15 MW 41 Also not make a lot of water, & it's a little cloudy, but is stable - Stop develop-
6:00 Stop pumping MW 43
6:00 MW 40 Set up, flushing pump
6:25 Quit pumping
6:30 Quit for day

John Sherrin 9/1/85

9/2/88

Well #	Time	Temp	Conduc	pH	Remarks
81	9/2/88				

Well #	Time	Temp	Cond	pH	Remarks
① MW22	9:40	9	825	7.1	
② MW40	10:35	15	130	7.8	first flushed
③ MW22	10:55	10	1175	7.5	cleaning
④ MW23	11:05	11	1125	7.6	up
⑤ MW22	11:15	10	1000	7.62	
⑥ MW23	11:20	10	1140	7.64	
⑦ MW22	11:25	9	1050	7.55	
⑧ MW23	11:35	10	1150	7.57	<u>DONE</u>
⑨ MW40	12:15	17	185	7.86	
⑩ MW40	12:50	16	220	7.80	
⑪ MW22	1:10	10	1200	7.42	
⑫ MW24	1:20	15	475	8.53	perfectly
⑬ MW24	1:30	17	475	8.53	clear <u>DONE</u>
			electric pump on this well		
⑭ MW22	1:35	10	1200	7.45	
⑮ MW40	2:50	18	210	7.90	
MW15	3:05	18	360	7.02	clear
⑯ MW22	3:10	18	1225	7.10	clear enough

~~John Davidson~~ 9/2/98

88/26

7:00 Start work drizzling in the 70's. Mike & Tam from Graves decommission Mike Roddy to do detail work on wells.

7:30 Start pumping MW40

8:00 Start pumping MW21 - looks like it had never been touched. No barriers left at site. Very muddy.

9:00 Start pumping MW23

Calibrated instruments

9:30 Stopped pumping MW23

10:00 Flushed MW40

10:10

11:35 Stopped pumping MW23

12:55 Started pumping MW24


3:00 Stopped pumping MW23. MW40 Pumped some oil MW15 - pump is too rough to show it clear. MW4 is still quite muddy & needs more filter. The well doesn't decommission. It's too thick.

How well
for John Sherwin 3/24/50

This page intentionally left blank.

Q.2.4 Notebook 4, Field Technician

This notebook contains decontamination records, calibration records for the HNU meters, records of photographs taken, records of shallow soil sample collection at Site 3 and the third round of water level measurements. Forty nine pages of this book were used, the first entry is 27 July 1988 and the last entry is 27 September 1988. Most entries were signed by Kimberly L. Davis. A few pages are signed by Jo-Ann Sherwin.



Return to:


Name Robert S. McLeod
Engineering - Science, Inc.
Address 710 S. Illinois Ave., Ste F-103
Oak Ridge, TN 37830
Phone (615) 481-3420

Projects

This book is published on a fine 50% cotton-content ledger paper, specially treated for maximum archival service, and protected by a water resistant surface sizing.

Cambium
Distributors
3589 Broad Street
Chamblee, Georgia 30341
(404) 455-1927

1



Projects (continued)

Name
Address
Phone

100

Contacts

Maj. Joel Mann Duluth ANG (218) 723-7290
 Col. Don Sulwold HQ MN ANG (612) 296-4673
 Sgt. Jim Norton Duluth ANG (CE)
 Utilities work central X292
 Sgt. John Wedlund Facility Mgr. (CE) X408
 Bill Hayden ES Deputy PM (615) 481-3920
 Sgt. Harold Stevens, supply X293
 Larry Janssen HAZWRAP (615) 576 1967
 Tom Sturdivant HAZWRAP (615) 482-6601
 Enrique Gentzsch MPCA site response (612) 296 7803
 Elizabeth Gawrys MPCA site response (612) 296 7821
 Ed Grunwald ES H+S Manager (404) 325-0770
 Tom Oathandt North Star Drilling (612) 632-6552
 (H) (612) 632 3306
 Melanie Baltizore ES Berkeley Lab (415) 841 7353
 (H) (415) 937 5368
 Kathleen Kiad ES Berkeley Lab (H) (415) 939 9475
 Bruce Burke Utilities (218) 123-7294
 Graves ("Denny") Drilling 819-2026
 624-4349

Phy 2 Dec 7-27-84

Emergency Contacts



Base Main Gate Security 723-7290
 Fire Department 723-7235
 Poison Control 1-800-332-3873
 Medical Emergency
 Hospital - St. Lukes Hospital of Duluth
 Address: 915 East 1st St., Duluth, MN
 Phone: (218) 726-5555
 Base POL: Maj. Joel Mann
 CE MHA NC
 Work: (218) 723-7290
 Home: (218) 728-2633
 PM R. S. McLeod
 ES Oak Ridge, TN (615) 481 3920
 Apt # (615) 483-4613
 Home # (404) 953-9603
 H+S Officer: Ed Grunwald
 ES Atlanta, GA
 (404) 325-0770
Phy 2 Dec 7-27-84

5

~~Thurs. Phys. Lab. 11
M. J. 11
D. 11
V. 11
N. 11
10099
6/10/6~~

4

~~Thurs. Phys. Lab. 11
M. J. 11
D. 11
V. 11
N. 11
10099
6/10/6~~



7-27-88

1415: Completed decerning water level indicator as per R.I. Work Plan (see "Decernation Procedures" pp. 6-9 through 6-11, specifically, Section 6.6.4.2). Mr. Dennis Forsberg pointed out that a "paper trail" must exist for each piece of equipment, thus mandating the initiation of keeping this field notebook. Serial #: 10035, Slope Indicator Co. IMPORTANT NOTE: Decern procedure deviates from work plan in the elimination of the disposable soap-imregnated cloth step; a methanol rinse and a HPLC water rinse are the two steps employed.

1520: Arrived at Site 2. Prepared to measure water levels.

1535: Breeby went back to office to retrieve tetlon squirt bottles. Left Joanne at site.

1600: Arrived back at Site 2. John has joined Joanne. They are busy sieving out existing wells.

1630: Began surveying existing monitoring wells with Joanne due to inaccuracies noted on map.

1820: Completed surveying.

Kathy J. Davis 7-27-88

7-28-88

0730: Arrived at base. Organized field equipment.

0900: Headed out to Site 2^{up} to take water level measurements. (See Jo Ann Sherwin's notebook for details.) Water level indicator already decontaminated (see 7-27-88 notes, previous page)

1300: Completed Site 2 water level measurements.

Went to level C 1330.

1515: Headed out to Site 3 to take water

level measurements with Jo Ann Sherwin

1600: First, recalibrated ^{up} water level indicator. Dec 50014, HNU to 70.2 (Follow procedure in HNU manual, page 8-5.)

1730: Started Site 4.

1800: Water level indicator batteries more out.

Went back to office. Picked up batteries on the way back to motel.

Note: See Jo Ann Sherwin's notebook for all water levels and times.

Phyllis Z Dow 7-28-88

7-29-88

0645: Arrived at base. Calibrated

HNU to 23; followed procedure on

page 8-5 of HNU manual Dec. '85.

Detecter #500791, probe #50018. Jo Ann

Sherwin took this HNU to measure headspace of wells that she is measuring water levels on. (See J. Sherwin's notebook for further info on this activity.)

0845: Recalibrated HNU, Detecter #164716

Probe #501284 to 2.5 on span setting.

Followed procedure on p. 8-5 of manual

Dec '85, HNU.

0920: Jo Ann returned from buying more

supplies. I joined her to begin measuring

water levels at Site 4. (See her notebook.)

1130: Completed water level measurements.

Picked up supplies and met John Hardeman

+ Peter Riemasma at Site 2 (with drill crew).

Rest of afternoon: I assisted J. Hardeman

+ P. Riemasma as they collected soil

samples from Borehole #1 at Site 2

(See P. Riemasma's notebook for details.)

1700: Quail drilling due to approaching thunderstorm

Went back to office until 1800.

Phyllis Z Dow 7-29-88

12

7-30-68

0645: Arrived at office.

0700: Went to Site 2 with P. Riemersmi & J. Hardman to meet dull crew. Continued with BH-1, rest of A.M. (See P. Riemersmi's notebook for details.) I assisted in sample preparation.

1200: LUNCH (See P. Riemersmi's notebook for decon of wash pails.)

1300: Continued, started BH-2 in the FTA vicinity as well.

1610: Took samples to Pet Ex (closer at 1700 today).

1700: Went back to office.

1730: Left.

13

8-1-68

0605: Arrived at office. Ate breakfast, took notes, recharged HNU #506791-50018, and decontaminated wash pails as follows:

- (1) Scrubbed w/ Alconix
- (2) Rinse w/ potable water
- (3) Sprayed w/ methanol
- (4) D.I. water final rinse

0710: Headed out to BH-2, site 2.

0800: Completed BH-2. (See details in Peter Riemersmi's field book.) I decontaminated wash pails using procedure above, decontaminated water in the 55 gallon drums designated to store waste water. Completed decon at 0830.

0845: Drove to next site, a shallow well point location on Site 2. Bought buckets with fresh potable water with me.

Went on rest of drill until 0945. Then left to pick up John Sherman at airport.

1100: Returned to site briefly, then went back to office for lunch.

1210: Began assisting John Anderson with decon of augers, extensions, sleeves, etc. He had previously liquioxed them yesterday.

Phil Z Davis 8-1-68

Phil Z Davis 7-30-68

14

Today, he was steaming them again. Next, I applied a methanol rinse with the stainless-steel sprayer. Then, I applied a final rinse of DI water.

1400: Three guys from Woodward-Cline approached me. Wanted to know if we had any extra methanol. I told them "no." (I used last gallon the past hour.) Asked if we owned all supplies in office ("yes, except small box of tyres, etc on table") Wanted to know if we could show office. I suggested to seek out other space.

1410: Continued applying D.I. rinse to drilling parts.

1425: Finished decanning. John, is wrapping parts in vinyl.

Rest of afternoon: sat around and watched drillers put in well point.

1700: Left.

July 2, Davis 8-1-88

15

8-2-88

0605: Arrived at office. Deanned work pairs as outlined on page 13 lines 4-7 of this field notebook.

0715: Handed out to survey in monetary well locations per Bob McCleod's instructions. These will be drawn in on aerial photos Bob brought.

See Jo Ann Sherrin's notebook for details of survey.

1025: Handed out to site 3 to continue surveying.

1120: Completed Site 3. Went to Site 2, to continue surveying.

1230: Completed Site 2. Went to eat lunch.

~1500: Went to Site 4 to continue surveying.

See Jo Ann Sherrin's notebook for details.

1700: Completed site 4. Went to office.

1730: Left.

July 2, Davis 8-2-88

16

8-3-88

0630: Arrived. Prepared to go to Site 2 with Peter Klemerson, John Hardman & Bob McLeod.

0710: Change in plans per John Hardman's instructions. Stayed at office with Jo Ann. Worked on plotting up ^{existing} well ~~new~~ locations, rest of morning.

Afternoon: Watched Potosonic drilling operation.

1730: Left.

Q-185

17

8-4-88

0630: Arrived.

0800-1230: Observed random digging in supposed vicinity of Site 2's fire-train area #1.

Afternoon: Assisted in packaging of soil

samples for MW-12, Site 2. Four

samples total. See Peter Klemerson's notebook for details. Note: A small

error was noted in sample bottle labelling. Peter Klemerson left the "B" out of

"DANG-B-MW12-SS1" numbers. Therefore,

I labelled the chain of custody with the "B" as well, which deviated from the

R.I. Work Plan's labelling system outlined

on page

180. Left.

Phyllis L. Lin 8-3-88

Phyllis L. Lin 8-4-88

8-5-88

0630: Arrived. Calibrated HNU, docket # 16A716, probe # 501288. No change in span setting. Used Isobutylene with #9488-001588 lot #12 per calibration instruction in HNU manual, p. 8-5, Dec. '85.

0715-0847 Took 3 samples from MW-15 (see Peter Riemers' field book for details). Assisted in sample packaging.

0925: Completed sample packaging for MW-15. Rest of morning: reviewed Dames & Moore report, ran errands.

1300-1400: Drilled MW-18, MW-20 on Site 8.

There will be abandoned as boreholes since

the bedrock was encountered at same depth as existing wells they were to complement.

(See P. Riemers' Notebook for details.)

1600-1730: Prepared samples for Fed Ex.

1800: Left

Philly 2. A 8-5-88

19

8-6-88

0640: Arrived. Working with P. Riemers + J. Shorin.

0740: Calibrated HNU 16A716, probe 501288 to 326 using isobutylene, batch #9488.

061588, lot #12 per calibration instruction in HNU manual, p. 8-5, Dec. '85.

0800: Assisted in sample preparation on Site 8.

Also am taking HNU readings. This is

Well Point #16, so no soil samples.

Well Point #10

Depth HNU reading

0-5' 0 ppm

5-10' 0 ppm

10-15' 0 ppm

(Further reading recorded on P. Riemers' field log)

Began a photographic record at photos point of the RT.

Roll, picture #20: Site 8

top: 55-1, 0-5' (Well Point 16)

bottom: 55-2, 5-10' (left foreground)

Roll, picture #21, Site 8

Well point #10 drilling operation

With drillers John Anderson and Jim H.

Roll, picture #22, Site 8

Well point #10, left, 55-3, 10-15' bottom

Philly 2. A 8-6-88

- right: SS-3, 11-15' (bottom → top)
- Roll 1, picture # 23, Site 8
- Roll # 10, SS-4, 15-20' (left → right)
- Roll 1, picture # 24, Site 8
- WP # 10, SS-3, 10-15'
- 10-11' top, 11-15' bottom (left → right)
- Roll 1, picture # 25, Site 8
- WP # 10, SS-1 (top) SS-2 (bottom)
- SS-1 = 0-5', SS-2 = 5-10' (L → R)
- Roll 1, picture # 26, Site 8
- WP # 10, SS-5, 20-22.5' (left → right)
- time: 0919
- Roll 1, picture # 27, Site 8
- WP # 10, SS-6, 22.5-27.5' (left → right)
- time: 0942
- Roll 1, picture # 28, Site 8
- WP # 10, SS-6, 27.5-32' (left → right)
- time: 0952
- Roll 1, picture # 29, Site 8
- WP # 10, SS-7, 32-35' (left → right)
- time: 1021

1050: After testing the 30-40.5 sample, obtained erratic readings on HNU, Went back to office to check calibration. Determined that moisture in sample caused the readings, which steadily

Philly 2 Jan 81-6-88

increased from 0-50 ppm over 5-10 seconds. Calibration was still O.K.

- Roll # 1, picture # 30, Site 8
- WP # 10, SS-?, 35-40.5' (L → R)

time: 1114

- Roll # 1, picture # 31-32, Site 8
- WP # 10, SS-?, 40.5-45' (L → R)

time: 1125

- Roll # 1, picture # 33, Site 8
- WP # 10, SS-?, 45-47' (L → R)

time: 1141

NOTE: At all times through pages 19-21, WP # 10 should be WP # 10 D.

- Roll # 1, picture # 34, Site 8
- WP # 10 D - building well point

time: 1345

- Roll # 2, picture # 1, Site 8
- WP # 10 D - building well point

- Roll # 2, picture # 2 - Site 8

WP # 10 S - 0-5' time: 1530

- Roll # 2, picture # 3, Site 8

WP # 10 S, 5-10' time: 1530

(See Peter Riemer's notebook for details of WP # 10 S and WP # 10 D.)

Philly 2 Jan 81-6-88

23

Roll #2, picture #5, Site 8
 WP #105, 10-15' time: 1540
 Note different lithologies.
 - Roll #3, picture #6, Site 8
 WP #105, 15-20' time: 1558
 - Roll #3, pictures #7, 8, 9, Site 2
 "Hazardous Waste" dump site for
 55 gallon drums which were dug up
 by an unidentified front end loader.
 Ground Site 2, near the road on
 Friday, 8-5-88. Time: 1645.
 These pictures were taken after Jo Ann
 Sherrin & I measured distance from
 a well to a benthic on Site 2 (see
 J. Sherrin's notebook for details).
 1700: Last for day.

Philly 2 den 8-6-88

23

8-7-88 SUNDAY - NO WORK TODAY
 8-8-88
 0600: Arrived. Calibrated HNU #500791
 detector #500018 with 150kVt lane
 (94.7 ppm) supplied by Liquid Carbonics,
 batch #9488-061588, lot #12, per
 instructions in HNU manual, p. 8-5, Dec. '85.
 0600: Prepared to drill sample of road on
 Site 8, a deep shallow monitoring well pair.
 It will be assisting in soil sample collection.
 - Roll 2, Picture #14, Site 8
 MW-14, 0-5' left, 5-10' right
 bottom to top time: 0830
 0 5 10
 - Roll 2, Picture #15, Site 8
 MW-14 drilling operation
 John, Jeff, & Bill time: 0840
 - Roll 2, Picture #16, Site 8
 MW-14, 10-15' (bottom to top) time: 0900
 NOTE: Took duplicate of water table sample,
 SS-3.
 1015: Talked to Bill Hayden on telephone.
 He said that DANGB8-MW20-SS1 arrived broken
 in California - 1 L Amber. Also, DANGB8-MW20-
 SS4 was not on chain-of-custody sheet as
 Philly 2 den 8-8-88

Philly 2 den 8-8-88

It should have been. The chain of casing was started 8-5-88.

- Roll 2, picture # 17, Site 8, MW-14
SS-3, SS-4, SS-5, right (bottom) half
SS-3 and SS-4 are side by side die to
pwr recovery for a total of 15-25'
SS-5 is underneath; this picture shows
27'-30' time: 1100

- Roll 2, picture # 18, Site 8, MW-14
SS-3, SS-4, SS-5, left (top) half.
SS-3 and SS-4 are side by side due to pwr
recovery for a total of 15-25'
SS-5 is underneath; this picture shows 25-28'
time: 1100

- Roll 2, picture # 19, Site 8, MW-14
SS-5 continuation, 30-33.5' (L-R)
time: 1106

- Roll 2, picture # 20, Site 8, MW-14
33.5-35' + m. 1127. (L-R)
- Roll 2, picture # 21, Site 8, MW-14
35-39' (L-R) time: 1235

- Roll 2, picture # 22, Site 8, MW-14
39-44' (L-R), bed rock time: 1235
1240. Brake for lunch. Rest of afternoon, read own reports,
ran errands. Left at 1700.

Phibbs, L. Davis 8-9-88

8-9-88

0645: Arrived

0715: Decanned three stainless steel wash
pails as described on page 13, lines 4-7
of the field notebook.

0800: Went to Site 2 to assist Jo Ann
Shorwin in surveying in ≈ 30 locations
where front end loader dug in suppressal
vicinity of FT-1, See J. Shorwin's
notebook for details.

1150: Completed "porehole" locations for the
AM. Finished all

1200-1330: Ran errands, ate lunch
1345: Went to watch decontamination of drill
casing + core pipes.

First, truck was steam-cleaned. Then
pipe which had been previously decontaminated
was loaded on. I witnessed the decontamination
of (1) five last sections, (2) 2 feet sections
(3) 10 feet sections of outer casing, (1) 10 ft section
of inner core casing. Procedure:

- (1) Spray w/ Acigumex via steam cleaner
- (2) Spray w/ potable H_2O via steam cleaner
- (3) Spray w/ methanol with pesticide spray (stainless)
- (4) Spray w/ DI- H_2O

Phibbs, L. Davis 8-9-88

26

1530: Completed decan of pipes above, plus (3) 5 ft casing sections placed on plastic. Bill moved all clean pipe onto plastic placed on a pallet on ground, and covered. Next, approximately 80 feet more of pipe was decanned in the same manner, as outlined on the last 4 lines on page 25.

1630: Completed this set of pipes. Bill placed these on plastic with other pipes.

1700: Left

May 2. wk 8-9-68

27

8-10-88

0630: Arrived. Calibrated HNU # 500291) detector, probe #500018 with isobutylene (94.7 ppm) supplied by Liquid Carbonic batch # 9488-061588. Let #12, per instruction in HNU manual, p. 8-5, Dec. '85.

0800: Assisted in sample preparation from MW-19 and MW-16. MW-19 was not completed as a monitoring well since backhoe was encountered at the same depth as the existing "shallow" well. It was to be completed. See P. Riemersma's notebook for details.

- Roll #3, picture 1, Site 8

MW-16 drilling operation - John Anderson

Time: 1105

- Roll #3, picture 2, 3, Site 8

Scenery around MW-18

1200: Broke for lunch.

1300: Returned to MW-16. I continued to assist P. Riemersma as above.

- Roll 3, picture 4, Site 8

MW 16, 0-5', 5-7.5', 7.5-10' arranged from top to bottom.

- Roll 3, picture 5, Site 8

MW-16, 0-15', 16-20' to bottom

15-16' not in picture, but is the same

May 2 - Sun 8-10-88

- a) 16-20'.
- Roll 3, picture 6, Site 8
 - MW-16 - 20-21 $\frac{3}{4}$ ', 21 $\frac{1}{4}$ -23 $\frac{1}{2}$ ', 23 $\frac{1}{2}$ -25', arranged from top to bottom.
 - Roll 3, picture 7, Site 8
 - MW-16: 25-30', boulder.
 - Roll 3, picture 8, Site 8
 - MW-16: Bill, John Hardman, John Anderson

John is welding a broken piece, a common method for repairing lines this far.

1400: Want to buy Vermiculite for packing.
1445-1630. Prepared samples, Fed Exed out.

1645: Began plotting up points on Site 2.

1820: Left.

8-10-88

July 2 Jani

8-11-88

0630: Arrived. Calibrated MW detector #500791, probe #500018 with 150cm long gas supply, by Liquid Carbonic, batch #9488-06588, lot #112, per instruction in MW manual, p 8-5, Dec. 85. Reset span slightly to 3.20.

0900: Began WP-9D. I assisted Peter Remersma in sample collection (for lithology only), photographs and general errands. See P. Remersma's notebook for details.

- Roll 3, picture 9, Site 8

WP-9D, 0-6' (L-R) Note that picture caption indicates "0-5'" this is not correct. time: 0958

- Roll 3, picture 10, Site 8

WP-9D, 6-8.5' (L-R) Note that picture caption indicates "5-7.5'".

This is not correct. Time: 0959

- Roll 3, picture 11, Site 8

WP-9D, 8.5-11' (L-R) Time: 1001

- Roll 3, picture 12, Site 8

WP-9D, 11-14' (L-R) Time: 1014

- Roll 3, picture 13, Site 8

WP-9D, 14-14' (L-R) Time: 1015

July 2 Jani 8-11-88

30

- Roll 3, picture 14, Site 8
- WP-9D, 15-19 1/2' (L → R), Time: 1031
- Roll 3, picture 14, Site 8
- WP-9D, 19 1/2 → 23' (L → R), Time: 1032
- Roll 3, picture 15, Site 8
- WP-9D, 23-26' L → R, Time: 1033
- Roll 3, picture 17, Site 8
- WP-9D, 26-28' L → R, Time: 1057
- Roll 3, picture 18, Site 8
- WP-9D, 28-31' L → R, Time: 1105
- Roll 3, picture 19, Site 8
- WP-9D, 31-36' L → R, Time: 1106
- Roll 3, picture 20, Site 8
- WP-9D, 36-38' (no caption), Peter

R. is holding cross section of core, which was too firm to crumble, Time 1113

This cross section also is representative of what was contained in 38-41.

- Roll 3, picture 21, Site 8
- WP-9D, 38-41' (no caption), Peter
- Roll 3, picture 22, Site 8
- WP-9D, 43.5-46', Time: 1151 (L → R)

1230: Booked for lunch. Placed phone calls, read QA/QC comments and worked on new computer.

8-11-88

31

1445: Calibrated HAND detector #164716
 probe at 501288 using ISO body camera
 supplied by Liquid Carbonic (94.7 ppm)
 batch # 9488-061588 lot # 12 per
 instructions in HOU manual p. 8-5 Dec 85.
 Adjusted spec to 3.61 prepared to go
 to Site 8 with Jo Ann Sharvin and Mike
 Roddy to test 2A borehole locations from
 150' 2 weeks in July. I assisted Mike R.
 and J. Sharvin for 30 minutes then I
 went to assist Bill in sanding the
 paint out of the stamper steel monitoring
 well pipes.
 1715: Went back to office; prepared to leave
 1800: Left.

8-11-88

8-12-88

0635: Arrived. Heavy rain.

0800: Rain subsided. Drilled, began decoring Rotasonic drill rig, since last holes were punctured yesterday at Site 8. Following decoring, drilling will re-commence at Site 2.

0945: Completed decoring of the drilling rig. Procedures: (1) Steam clean with pitable water;
(2) Steam clean with lignine;
(3) Steam clean with pitable water.

Began steam cleaning well casing and core pipes. 90 ft. casing and 50 ft. core pipe on rack now.

1030: Completed decoring well pipe described directly above. Procedure described on last four lines of Volume 25.

1045: Calibrated HNU detector # 164716 probe

IF 501288 with 54.7 ppm 15% humidity

supplied by Liquid Carbonic, batch #

9488-061588 lot # 12 per instructions

in HNU manual, p. 8-5, Dec. '85. No adjustment

in span. This HNU will be used later today

during drilling operations at Site 2.

1100-1120: LUNCH

Phyllis Z. Davis

8-12-88

1200-1345: Remounted in downtown Duluth.

1400: Went to Site 2. Drilling, drilling due to missing connection.

1500: Began drilling a borehole which may be constructed into a monitoring well at FT-7.

Location on Site 2: I assisted Mike Kelly

and Peter Riemersma in gathering analytical

samples.

1700: Terminated drilling at this borehole

due to large boulders. Will discard

the one surface sample pulled from this hole.

Decided to drill new hole tomorrow in different location.

1730: Left.

Phyllis Z. Davis

8-12-88

34

8-15-88

0645: Arrived. Peter calibrated HNU.
 0715: Went to site 2. Began drilling now
 beside near one yesterday which was
 abandoned. I will be assisting in sample
 preparation. This is MW-58.
 0800: Postponed drilling due to lightning
 directly overhead.
 0845: Lightning subsided. Quickly gathered
 three samples in the derrick. I prepared
 samples for shipment while Peter Remmer,
 Mike Roddy, John Hardman, John Anderson
 and Bill - began building well.
 0845: Lightning returned directly overhead again.
 1130: I left site to go to office, other followed.
 1300: Lunch, then left for day.

Phil 2 d. 8-13-88

35

8-15-88

0640: Arrived. Peter Remmer cal. brail
 HNU. Some difficulty in getting a probe
 to work properly.
 0725: Went back out to MW-38. Site 2 - to
 complete building well. Missing stabilizers
 steel clamps for well screen stabilizers.
 0915: Began building well.
 - Roll #4. Picture 11, Site 2
 MW-38. General activity surrounding
 building of well. John Anderson, John Hardman,
 Bill - and Jeff Aus. Time 0920.
 0945: I went to run errands.
 1100: Returned. Frashed well rig was moving to
 MW-37 location.
 1200-1300 - LUNCH
 1300: I began assisting P. Remmer in
 soil sample collection + packaging on MW-37.
 1415: Completed taping soil samples. Took
 two duplicate - SS-5 on this well.
 - Roll #4, picture 12, Site 2
 MW-37 coies, 1 - 0-5', Far left;
 0-5' - 10', next 2 middle coies, 16 - 18.5',
 Far right coie. (Top of hole is bottom
 Bottom of hole is top of picture for each coie.)

Phil 2 d. 8-15-88

1430-1545. Built MW-37

1600. Moved rig to MW-39 site 2. I

continued to assist in sample collection.

1720. Completed packaging of samples. Went to Fed Ex.

1820. Left for home.

Robert L. Jones 8-15-88

8-16-88

0635. Arrived. Received Stambaugh buckets
as per procedure listed on page 13,
lines 4-7. Ran errands.

0930. Started drilling MW-40, Site 2.

I assisted Peter Riemers in soil
sample collection and packaging.

1145-1215. Lunch

1215. Drillers began installing well screen.

John Anderson, John Hademan & Mike

- Roll #4, Picturs 14, 15, Site 2

MW-40 sandpicking, John A., Peter R,
Mike.

- Roll #4, Picturs 16, Site 2

MW-40 borings 0-15'. Final core

is not in picture, which contains some
bedrock fragments.

1300. Begin moving towards well points 75 & 7D
on Site 2. Difficulty in access.

1400. I left site 2 to begin packaging
soil samples for Fed. Ex.

1515. Called Bill Hademan; he called earlier
desiring total # of samples taken thus far.

Told him ≈ 59 samples, 8 dups, rough estimate.
1530-1730. Packaged (3) MW-40 samples,

Robert L. Jones 8-16-88

(12) site 3 surface soil samples taken by J. Shorman and M. Reddy. (No drops)
 1230: Went to Red Ex.
 1800: Went out to site 2, WP-7D site to check on progress. Apparent to be finishing up, return to office w/ J. Shorman + M. Reddy. Shortly after 1830, left. J. Shorman + I stopped for supplies on the way home.

8-26-82

8-17-82

0600: Arrived. Deconail stainless steel buckets, 1 fence post diggers (2), various bands + spoons per procedure on page 13, lines 4-7.

0645: S. is 'as close ther'. Drillers began deconailing @ 0700. Procedure on list (lines p. 25).

0800: Driller completed deconailing J. Shorman, M. Reddy + J. Hardman headed out to site 2 to begin WP-7S. P. Riemann and I went to site 3 to continue gathering surface soil samples.

LOCATION	DEPTH	TIME OF DAY OF MONITORING SAMPLE	COMMENTS
DANGB3-SS-AT	1.7-2.0	0917	off, silty, sandy, few pebbles
DANGB3-SS-AS	1.9-2.0	0937	Black, organic rich soil
DANGB3-SS-BZ	1.8-2.0	1020	Green soil
DANGB3-SS-YZ	1.8-1.9	1037	"
DANGB3-SS-BZ	1.7-2.0	1140	"
DANGB3-SS-AZ	1.7-1.9	1206	Between AZ + BZ
DANGB3-SS-AZ	1.7-1.9	1232	Between AZ + BZ
DANGB3-SS-DZ	1.7-1.9	1511	1506
DANGB3-SS-DZ	1.8-2.0	1545	1537
DANGB3-SS-DS	1.4-2.1	1604	1600
DANGB3-SS-DS	1.8-2.1	1625	1623

8-17-82

- Procedure for gathering surface soil samples at site 3:
- Dig hole to approximately 2 feet with deconned fence post digger. ^{use tape measure calibrated to 1/16" of foot.}
 - When reach designated depth, continue digging, placing soil from hole into deconned stainless steel bowl. Record ~~th~~.
 - Immediately pack 4 oz. VOA bottle with soil from bowl, using deconned stainless steel spoon. ^{Record time.}
 - Mix contents of bowl with same stainless steel spoon, then place mixed soil into 1 L Amber bottle using same spoon. Fill $\approx 3/4$ of the way. Record time.
 - Place sealed bottles into ice cooler.
 - Decon fence post digger, brush and spoon per procedure on page 13, lines 4-7. Wrap in aluminum foil if they are not to be used immediately thereafter. Otherwise, allow to air dry before using again on next location.
 - Note: Sampler(s) are wearing disposable vinyl gloves and changing them after each sample.

1630: Prepared samples for shipment w/ P. Kienemann & J. Sherwin until 1800, then left.

8-17-88

8/18/88 windy M. Duddy & J. Sherwin, Sunny 41

LOCATION	DEPTH	Time of Turnout	Remarks
DANGB 35549	1'4"-1'6"	10:55	in a narrow creek
DANGB 35550	1'8"-1'11"	11:20	coarse, size gravel
DANGB 35551	1'9"-2'0"	11:45	gravelly sand
DANGB 35552	1'5"-1'7"	12:10	gravel water in hole
NOTE: This hole, DANGB 35551 was plugged			
SGC-2 this is the wrong location for			
SGC-2 according to the map and			
SGC-2 was already located on the			
ground corresponding to its location			
on the map. It has already been			
sampled. We therefore guess this			
flag is in error. We left this flag			
and added another flag. 55 D with			
the date, 8/18/88 added			
DANGB 35550	1'8"-1'10"	12:30	12:35
DANGB 35552	1'6"-1'9"	1:00	1:05
NOTE: 9'4" W of SG-52 in the			
grass just off the edge of the road.			
SG-52 is in the roadway			
finished at 1:15 p			

J. Sherwin 8/18/88

42

8/22/88

HNU Calibrated 800 detector is 164716

proton H 50.208 1.1 447 ppia out, 12.12

Supplied by Liquid Carbonic Birch = 7488-06588

list to 2

Note: battery light flicking on and off

Miles 2000

43

9/27/88

9.530 Clear, sunny, cloudy water
level measurements by myself

John Shuman 9/27/88

Well #	Depth to water	Total Depth	pad @ casing	protect or other features	Pull info
10-6W.C.	7' 11 ³ / ₈ "	15' 2 ¹ / ₂ "	2' 1 ¹ / ₂ "	8-4"	n 5" thick pad - n 2" off ground large logs around pad
10GWB	9' 11 ¹ / ₈ "	15' 1 ³ / ₄ "	2' 4 ³ / ₁₆ "	- 3 ³ / ₈ "	n 5" thick pad 3" - 5 ¹ / ₂ " off ground wooden posts set around pad n 5" thick pad - 1 ¹ / ₂ " 4" off ground wooden form-set around pad
2MWLH	8' 1 ¹ / ₈ "				
GW2A	5' 10 ¹ / ₈ "				
MW7	5' 2 ⁷ / ₈ "				
2MWHO	5' 9 ¹ / ₄ "				
2MW3F	4' 5"				outer protective cap as resting on inner casing cap
Continue with Mike Roddy					
MW5	3' 9 ¹ / ₂ "				
MW6	3' 33"				

Jo. Ann Shepwin 9/27/88

Jo-Cun Sherwin 9/2/85

46

Time well# Depth


11:17 8GW2C 7.91'
 11:18 MW4 7.0'
 11:24 2WP2D 3.01' } Protective caps are
 11:25 2WP7 3.75' } resting on inside
 11:34 2WPC 8.19'
 11:37 GW2B 4.96'
 11:39 2MW3B 4.57'
 11:43 MW2 11.25' well was unlocked - was

cut through - cut
 is started

11:45 MW1 15.0'
 11:48 ~~MW2E~~ 12.29'
 11:50 GW2D 13.41'
 11:55 2MW37 3.66' outside cap resting on
 12:11 2WP8 7.29' " " " " " "
 12:43 8MW43 12.40'
 12:50 8MW14 8.83'
 12:51 8MW15 9.66'
 12:54 8GWSC 6.39'
 12:57 8MW16 7.33' " " " "
 12:58 8MW17 7.83' "
 13:07 GW8-B 5.02'
 13:10 GW8-A 5.80' well was unlocked
 13:13 8WP10D 6.93' outside caps on inner
 13:14 8WP17 6.58'

Jo Ann Sherwin 9/27/88

47



1.82 add to 6.06 = 7.88
 1.63 " " " " +1.88 " " " " +2.22
 Jo Ann Sherwin 9/27/88

48

Well #	Time	Depth	Top of Butter Case	Top of Steel Case	Part thick
MW10	1321	5.40			no loose
5MW24	1322	4.40	1.87	1.93	18" ground back 3" up land well
MW8	1326	6.46			
MW9	1328	6.70	no under case		
4MW21	1329	6.99	2.05	2.25	.4
4WP120	1335	5.56	1.60	1.76	.3
4WP12	1336	5.02	1.60	1.70	.3
4WP130	1341	9.96			
4WP13	1342	8.96			
4MW22	1345	8.77			
6W4-D	1346	9.80			
4MW23	1349	7.96			
6W4-C	1350	10.50			
4WP140	1352	9.79			
4WP14	1353	8.62			
MW11	1355	7.40			
4WP150	1358	8.59			
4WP15	1359	7.74			
6W4-A	1432	4.66			
8WP11	1435	9.83			
8WP90	1438	8.99			
8WP9	1439	8.75			
4WP160	1444	4.50			
6W4-B	1448	5.04			
3MW27	1452	5.33			

met the surveyors & they are taking
all these measurements

J. Ann Sherwin 9/27/88

49

Well #	Time	Depth	Remarks
3MW26	14.54	6.98	
3MW25	14.55	6.84	
3MW29	14.58	5.79	
3MW35	15.00	5.62	
3MW30	15.05	8.29	
3MW31	15.08	9.58	
3MW32	15.12	9.11	
3MW33	15.15	7.75	
3MW34	15.17	6.62	
3MW28	15.20	2.88	
6W3-D	15.25	6.01	
6W3-B	15.28	8.97	
6W3-C	15.30	6.15	
6W3-A	15.56	11.66	
3MW42	16.57	3.67	

Q.2.5 Notebook 5, Sample Collection Log

This notebook contains sample collection procedures and times for the collection of surface water, sediment and ground-water samples. Ninety eight pages of this book were used. The first entry is 6 September 1988 and the last is 25 September 1988. The entries are signed by Kimberly L. Davis.

This page intentionally left blank.

Duluth ANGERS


FIELD BOOK

SAMPLE COLLECTION
LOG

Kim Davis

DISTANCES FROM SIDE STAKES FOR CROSS-SECTIONING

Roadway of any Width. Side Slopes 1 1/2 to 1.
In the figure below: opposite 7 under "Cut or Fill" and under .3 read 11.0, the distance out from the side stake at left. Also, opposite 11 under "Cut or Fill" and under .3 read 16.7, the distance out from the side stake at right.




Cut or Fill	Distance out from Side or Shoulder Stake																			Cut or Fill
	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	
0	0.0	0.2	0.3	0.5	0.6	0.8	0.9	1.1	1.2	1.4	0	1	2	3	4	5	6	7	8	9
1	1.5	1.7	1.8	2.0	2.1	2.3	2.4	2.6	2.7	2.9	1	2	3	4	5	6	7	8	9	0
2	3.0	3.2	3.3	3.5	3.6	3.8	3.9	4.1	4.2	4.4	2	3	4	5	6	7	8	9	0	1
3	4.5	4.7	4.8	5.0	5.1	5.3	5.4	5.6	5.7	5.9	3	4	5	6	7	8	9	0	1	2
4	6.0	6.2	6.3	6.5	6.6	6.8	6.9	7.1	7.2	7.4	4	5	6	7	8	9	0	1	2	3
5	7.5	7.7	7.8	8.0	8.1	8.3	8.4	8.6	8.7	8.9	5	6	7	8	9	0	1	2	3	4
6	9.0	9.2	9.3	9.5	9.6	9.8	9.9	10.1	10.2	10.4	6	7	8	9	0	1	2	3	4	5
7	10.5	10.7	10.8	11.0	11.1	11.3	11.4	11.6	11.7	11.9	7	8	9	0	1	2	3	4	5	6
8	12.0	12.2	12.3	12.5	12.6	12.8	12.9	13.1	13.2	13.4	8	9	0	1	2	3	4	5	6	7
9	13.5	13.7	13.8	14.0	14.1	14.3	14.4	14.6	14.7	14.9	9	0	1	2	3	4	5	6	7	8
10	15.0	15.2	15.3	15.5	15.6	15.8	15.9	16.1	16.2	16.4	10	1	2	3	4	5	6	7	8	9
11	16.5	16.7	16.8	17.0	17.1	17.3	17.4	17.6	17.7	17.9	11	2	3	4	5	6	7	8	9	0
12	18.0	18.2	18.3	18.5	18.6	18.8	18.9	19.1	19.2	19.4	12	3	4	5	6	7	8	9	0	1
13	19.5	19.7	19.8	20.0	20.1	20.3	20.4	20.6	20.7	20.9	13	4	5	6	7	8	9	0	1	2
14	21.0	21.2	21.3	21.5	21.6	21.8	21.9	22.1	22.2	22.4	14	5	6	7	8	9	0	1	2	3
15	22.5	22.7	22.8	23.0	23.1	23.3	23.4	23.6	23.7	23.9	15	6	7	8	9	0	1	2	3	4
16	24.0	24.2	24.3	24.5	24.6	24.8	24.9	25.1	25.2	25.4	16	7	8	9	0	1	2	3	4	5
17	25.5	25.7	25.8	26.0	26.1	26.3	26.4	26.6	26.7	26.9	17	8	9	0	1	2	3	4	5	6
18	27.0	27.2	27.3	27.5	27.6	27.8	27.9	28.1	28.2	28.4	18	9	0	1	2	3	4	5	6	7
19	28.5	28.7	28.8	29.0	29.1	29.3	29.4	29.6	29.7	29.9	19	0	1	2	3	4	5	6	7	8
20	30.0	30.2	30.3	30.5	30.6	30.8	30.9	31.1	31.2	31.4	20	1	2	3	4	5	6	7	8	9
21	31.5	31.7	31.8	32.0	32.1	32.3	32.4	32.6	32.7	32.9	21	2	3	4	5	6	7	8	9	0
22	33.0	33.2	33.3	33.5	33.6	33.8	33.9	34.1	34.2	34.4	22	3	4	5	6	7	8	9	0	1
23	34.5	34.7	34.8	35.0	35.1	35.3	35.4	35.6	35.7	35.9	23	4	5	6	7	8	9	0	1	2
24	36.0	36.2	36.3	36.5	36.6	36.8	36.9	37.1	37.2	37.4	24	5	6	7	8	9	0	1	2	3
25	37.5	37.7	37.8	38.0	38.1	38.3	38.4	38.6	38.7	38.9	25	6	7	8	9	0	1	2	3	4
26	39.0	39.2	39.3	39.5	39.6	39.8	39.9	40.1	40.2	40.4	26	7	8	9	0	1	2	3	4	5
27	40.5	40.7	40.8	41.0	41.1	41.3	41.4	41.6	41.7	41.9	27	8	9	0	1	2	3	4	5	6
28	42.0	42.2	42.3	42.5	42.6	42.8	42.9	43.1	43.2	43.4	28	9	0	1	2	3	4	5	6	7
29	43.5	43.7	43.8	44.0	44.1	44.3	44.4	44.6	44.7	44.9	29	0	1	2	3	4	5	6	7	8
30	45.0	45.2	45.3	45.5	45.6	45.8	45.9	46.1	46.2	46.4	30	1	2	3	4	5	6	7	8	9
31	46.5	46.7	46.8	47.0	47.1	47.3	47.4	47.6	47.7	47.9	31	2	3	4	5	6	7	8	9	0
32	48.0	48.2	48.3	48.5	48.6	48.8	48.9	49.1	49.2	49.4	32	3	4	5	6	7	8	9	0	1
33	49.5	49.7	49.8	50.0	50.1	50.3	50.4	50.6	50.7	50.9	33	4	5	6	7	8	9	0	1	2
34	51.0	51.2	51.3	51.5	51.6	51.8	51.9	52.1	52.2	52.4	34	5	6	7	8	9	0	1	2	3
35	52.5	52.7	52.8	53.0	53.1	53.3	53.4	53.6	53.7	53.9	35	6	7	8	9	0	1	2	3	4
36	54.0	54.2	54.3	54.5	54.6	54.8	54.9	55.1	55.2	55.4	36	7	8	9	0	1	2	3	4	5
37	55.5	55.7	55.8	56.0	56.1	56.3	56.4	56.6	56.7	56.9	37	8	9	0	1	2	3	4	5	6
38	57.0	57.2	57.3	57.5	57.6	57.8	57.9	58.1	58.2	58.4	38	9	0	1	2	3	4	5	6	7
39	58.5	58.7	58.8	59.0	59.1	59.3	59.4	59.6	59.7	59.9	39	0	1	2	3	4	5	6	7	8
40	60.0	60.2	60.3	60.5	60.6	60.8	60.9	61.1	61.2	61.4	40	1	2	3	4	5	6	7	8	9

For Curve Tables see end of book.

Return to: Robert S. McLeod
Engineering - Science, Inc.
710 S. Illinois Ave
Suite F-103
Oak Ridge, TN 3783
(615) 481-3920

The paper in this book is made of 50% high grade rag stock with a WATER RESISTING surface sizing.
KEUFFEL & ESSER CO.



2:

Contacts

Maj. Jod Means	Duluth ANG	218 723 7290
Col. Don Solwold	HQ MN ANG	612 296 4673
Sgt. Jim Norton	Duluth ANG (CE)	
	Utilities work control	X 292
Sgt. John Wedlund	Family Mgrs (CE)	X 408
Bill Hayden	ES Deputy PM	615 481 3920
Sgt. Harold Stevens	supply	X 293
Larry Jansson	HARWRAP	615 576 1967
Tom Sturdivant	HARWRAP	615 482 6601
Enrique Coetzsch	MPLA site response	612 296 7803
Elizabeth Gamrys	MPLA site response	612 296 7821
Ed Grunwald	ES H+S Manager	404 325 0720
Tom Oathead	North Star Drilling	612 632 6552
	(H) 612 632 3306	
Melanie Bultzone	ES Berkeley Lab	415 841 7353
	(H) 415 937 5368	
Kathleen Kidd	ES Berkeley Lab	(H) 415 939 9475
Bruce Burke	Utilities	218 123 7294
Graves (Danny)	Drilling	879-2026
		624-4344

3:

Emergency Contacts

Base	Main Gate Security	723-7280
Fire Department		723-7233
Poison Control		1-800-332-3073
Medical Emergency		
Hospital	St. Luke's Hospital of Duluth	
Address	915 East 1st St., Duluth, MN	
Phone	(218) 726-5555	
Base POL	Maj. Jrel Manns	
	CE MN ANG	
	Work: (218) 723-7290	
	Home: (218) 728-2633	
PM:	R.S. McLeod	
	ES Oak Ridge TN (615) 481 3920	
	Apt #: (615) 483 4613	
	Home #: (404) 953-9603	
H+S Officer	Ed Grunwald	
	ES Atlanta, GA	
	(404) 325-0776	

4

9-6-88

1030: Sharon Shulte, Joanne Beecher, and John O'Brien arrived at Duluth International Airport (DIAP).

1235: Peter Premarisa, Mike Rowdy and Kim Davis arrived at DIAP.

1600: Arrived at office (all six people) after running errands and eating.

1715: Began decontaminating six Teflon bailers, filtrate apparatus (2), Keck pump, tubing as per Appendix B of the P.I. Work Plan, Section 6.6.3, p. 6-10.

Exception: Plastic filter apparatus used to filter metals is decontam as such:

- (1) Wash with Loginox.
- (2) Rinse with potable water.
- (3) Rinse with 10% nitric acid solution.
- (4) Rinse with HPLC water.

1745: Sharon Shulte noted that, although decontaminating outdoors, a layer of black sooty material appeared to keep depositing on freshly decontaminated equipment.

1800: Decontaminated water level indicator (GEO) as per the R.I.W.P., App. B, Section 6.6, p. 6-10.

Friday 2 Jan 9-6-88

5

9-6-88

Lot numbers of various solutions used in decon and sample preparation:

(fish-scum-like) Lot #

- HPLC Grade Water: 883934, 880929

(fish-scum-like) 883937, 885028, 885079, 883940

- Optima Grade Methanol: 882613, 883342

- Nitric Acid, Reagent ACS, 69-2120, from Colorado (100%)

Scientific Instrument Supply Co. (C-P): 3E118D

- Hydrochloric acid, Reagent ACS

from COSCO: 3F03M

- Sulfuric acid, Reagent ACS from

Fisher Scientific: FL-02-0786

- pH 10.00 buffer from

Cole Parmer Instrument Co. (C-P): 8 2692

- pH 7.00 buffer from C-P: 8 2601

- pH 4.01 buffer from C-P: 8 2347

- Yellow Springs Instrument Co. (YSI)

3163 Conductivity calibrator,

10,000 micromhos/cm: A85104 065284 B32045D

1,000 μ mhos/cm: and } Expires 1-18-89

E48675 065280 B32045E

Expires 5-31-89

- Liquid Carbonic 94.71% isobutyl gas: batch-9488-061588, lot-12

and batch-9488-061588, lot-12

Friday 2 Jan 9-6-88

6

9-6-88

Let Number of Sampling bottles:
(All from J. Chem Research.)

Type

Lot #, QC #

1 L small min. 1/2 cimbors,

Cat. # 349-1000:	8201243	7431C
Additional lot #'s	8201203	7427C
8215323	8201173	7424C
8215343	8201213	7428C
8215063	8201223	7429C
8215123	8209143	7659C
8216143	8201253	7432C
8204083	8208183	7658C
8207143	8204143	7654C
8207163	8147123	4110C
8207183	8147093	4107C
8209043	8208173	7657C
8179133	8201233	7430C
	8208113	7651C

1 L polycarbonate bottles,

Cat. # 313-1000:

C8195183, C7308C

Additional lot #'s

8179163, 6118C

(placed under

washing column)

8179133, 6115C

8179173, 6119C

8179113, 6113C

C8141123, 4931C

7/2/89 J. Davis 9-6-88

7

9-6-88

Type

Lot #, QC #

Cat. # 313-1000 cont'd

8179153, 6117C

500 mL polycarbonate

8251333, 8251373

40 mL VOA vials,

S336.0040:

W8215373, W7756C

W8215353, W7754C

W8215383, W7757C

W8215333, W7752C

W8215343, W7753C

W8179013, W5635C

W8179023, W5636C

W8179033, W5637C

W8207183-7143-7153-7163-7173-7183-7193-7203

1900: Completed decan of all equipment

listed on page 4. Left.

9-6-88

7/2/89 J. Davis 9-6-88

9-7-88 Sharon Schultz, Peter Ramonson, Mike Kelly,
Kim Davis, John O'Brien, Joanna Butler
0700: Arrived at office. Arranged equipment
0730: Bill Hayden called. Mail mistake
samples to:
Metallurgy Inc. Trail
13715 Ryden North
Earle City MO 63045
Attn: Rich Mann
Toll (314) 298 8566
ES-Berkeley cannot run. Analysis will
not be 429, but calorimetric. Continue
to use salivic and parametric.
0745: Calibrated a HACH conductivity
TDS meter model #4600, serial
88070 054.
1,000 μ mhos standard: .973 μ S/cm \rightarrow 6.000 μ S/cm
10,000 μ mhos standard: 10.023 μ S/cm \rightarrow 10.000 μ S/cm
0810: Calibrated the Orion pH meter, model
SA 230, 2617 serial #.
Thermometer (morning) reads 18.5°C, probe reads 17.1°C
pH 7.00 standard: 6.65 \rightarrow 7.00
pH 10.00 standard: 9.99 \rightarrow 10.00 (adjusted slope)
0825: Prepared to HNU the (6) deionized water
prior to taking boiler rinse scale samples.
Why? Du: 9-7-88

9-7-88 Notes Background in office given is 4 ppm.
All barrels and caps registered at
background. Some black particles that
S. Shultz noted yesterday were visible on
barrels & caps.
0900-1000: J. Butler and K. Davis prepared
rinsate blanks.
1030: John Hardeman arrived.
1045: R. Davis placed phone call to Cole Parmer
to check on Coolers. Was told that they had
been back ordered, hence their delay.
1050: Called Melane Bulken in Berkeley.
Said she had given responsibility for making
travel blanks to "Pam". Said she would call back
1100-1200: Made up lists of analysis #s for
labelling, generally organized him to approach
Sampling, P. Ramonson, S. Schultz and
Mr. Kelly are at site & preparing a well,
1315: Joanna Butler and K. Davis went to NW-43,
a background well, P. Ramonson, S. Schultz
and Mike Kelly had just finished pouring when arrived
1330-1400: Ate lunch.
1400: Joanna Butler, J. Hardeman went to get additional
supplies from office.
Why? L. Davis 9-7-88

10

9-7-88

1430-1600: Obtained MW-43 and duplicate, "MW-50", bubblepacked, etc. Took picture of bottles.

1600: MW-43:

Temp: 10.2°C

conductivity: 1030 mS/cm (1030 μ mhos/cm)

pH: 6.25

1630-1730: Packed samples

1730: Drove to Feed Rd with samples:

MW-43 Samples, FB-1 UOA Dug 3 lines

MW-50 MW-43 duplicates

RR-1 Barber rinse samples

1815-1915: Made up labels for tomorrow.

Sharon Shultz decanted one barrel (the one

used at MW-43) using procedure on page

four (Appendix B in WP) with a 10% nitric

rinse before the final HPLC grab

water rinse. The filter apparatus was

decanted using procedure on page 45 lines

14-18.

1930: Joanna Butler decanted the barrel

that Pete Siemens and Mike Ralby

used to purge MW-42 using page

4 Appendix B procedure with 10% nitric

rinse. Note this procedure (which was

used on page 4 decantation of six

Ruby L Chen 9-7-88

11

barrels (nitric rinse was not needed on p. 4) will be returned to als the Decantation procedure from now on.

D

N

Ruby L Chen 9-7-88

12:

9-8-88 Bob Mendenhall

0700: Arrived at office

0730: Calibrated the black conductivity meter
described on page 5, lines 12-14.

Mercury thermometer reads 20°C, meter reads 19.7°C

1000: pH standard 1060 $\mu S/cm \rightarrow 1000 \mu S/cm$

10,000: pH standard 1070 $\mu S/cm \rightarrow 10,000 \mu S/cm$

0740: Diana Butler conducted HFS meeting.

0755: Calibrated Orion meter described on

page 5, lines 15-16. Temp 20.0°C

pH 7.00: 6.95 \rightarrow 7.00

pH 10.00: 9.89 \rightarrow 10.00

0820: Headed out to MW-42, a background

well that P. Ramasena + M. Reddy

purged yesterday (K. Davis, J. Baker, S. Shultz)

0830: Stopped outside gate and prepared

bottles.

Note: FB-2 is a Todd blanks for MW-42

0845: Arrived at well, took water level measurement,

but water level indicator was broken. Took picture

of bottles to be used. Bottles used today and

yesterday were in accordance to R.I. WP, Appendix

B, Table 6.2, page 6-4.

Only used bailer once with well water due to

poor recharge (usually rinse 2X).

Kathy L. Davis

9-8-88

13

9-8-88

0930: Took general parameters, measured

Temp: 11.0°C

pH: 7.72

Spec. Conductivity: 0.480 mS/cm (480 $\mu S/cm$)

Around this time, smelled exhaust fumes in air,

probably due to the 2 F-4's that took off

overhead.

0945: Packed van to leave.

1015: Completed wrapping all samples from

MW-42. J. Baker is purging bottles for

next site, MW-32. Am using this

well for matrix spikes samples.

1020: John Handman arrived at office with

first shipment of VOA travel blanks.

(Note: was supposed to arrive yesterday,

did not send any yesterday.) K. Davis

prepared these labels.

1040: Arrived at the third background well,

MW-32 (Site 3). Prepared to sample.

1130: Called Melvin. Bait zone to double

check on matrix spikes samples, due to

S. Shultz's concern that we were not

taking enough. Melvin confirmed.

Kathy L. Davis

9-8-88

14 9-8-88

that we need to take (2) 1 L
Ambers from each of the following
analyses: EPA 608, EPA 625, and EPA 418.1
for a total of (6) 1 L Ambers.

No extra sample is needed for metals
analyses; what we are gathering already
is sufficient for matrix spikes. This

matrix spike batch is taken every
20 samples. Also, no problem of holding times for this sampling.

155: K. Davis measured gross parameters
for MW-32:

Temp: 11.7°C
pH: 7.36

spec. conductivity: 1900 $\mu S/cm$ (1900 $\mu S/cm$)

1230: Left MW-32. Went to office to
organize after bubble picking etc.

1320-1400: CONCL

1410: Arrived at MW-14, Site 8. P.

Remmon & M. Reddy still purging MW-15

next to it. (team = J. Beale, K. Davis, S. Smith)

We will be taking field blanks (FB-3)

and a duplicate (DAMB-8 - MW51 - GW-1)

Took picture of bottles prior to sampling.

1420: P. Remmon & M. Reddy got back

stuck in MW-15. Left to fill slugs to knock

Shirley Z Jan 9-8-88

15

9-8-88

14:10:15

1450: Gross parameter readings, MW-14

temp: 12.3°C

pH: 7.03

spec. conductivity: 0.353 $\mu S/cm$ (353 $\mu S/cm$)

Note: Took MW-51, a duplicate
of MW-14.

1545: Finished up MW-14. Went back to
office.

1555: Decided to pick up three samples
collected thus far for Fed Ex. P.
Remmon & M. Reddy still purging
next well after MW-15.

1700: Completed picking samples. Prepared
to go to Fed Ex. (J. Beale & S. Smith with)

K. Davis remained behind and helped P. Remmon
& M. Reddy decan bailers as per Decan-1

procedure on page 11 and decan filter apparatus
as per procedure on page 4, lines 14-18.

1745: Made labels for tomorrow.

Note: The battery went out today.

MW-14: Samples, 1 TB-1

FB-2: blanks for MW-14 1st set of head
blanks

MW-32: Samples

Matrix Spikes (12) from MW-32

Shirley Z Jan 9-8-88

16

9-9-80

MW-14 samples

FB-3 blanks from MW-14

MW-51 duplicate of MW-14

1800: Lot 1.





27

9-9-80

0700: Arrived

0715: Calibrated Orion pH probe

described on page 85, June 17-18,

pH: 7.00 std: 7.09 → 7.00

10.00 std: 4.93 → 10.00

0720: Calibrated Hach conductivity/SDS

meter described on page 85, June 17-18,

1,000 $\mu\text{mhos}/\text{cm}$ std: 0.970 mS/cm → 1000 $\mu\text{S}/\text{cm}$ 10,000 $\mu\text{mhos}/\text{cm}$ std: 9.66 mS/cm → 10,000 $\mu\text{S}/\text{cm}$

Made out labels

This morning plan to sample MW-15,

which will have FB-4 associated with it.

Also, MW-17 which will have FB-5

associated with it.

0730-0805: Took BR-2 bailer

rinsate, Fe, Site & parameters,

0830: Arrived at MW-15. Prepared to

Sample. Team: Pete Riemann, Kim Davis,

Shun Shute, James Becker

0900: Took gas permeability readings, MW-15.

Water is cloudy and difficult to filter.

temp: 9.80C

pH: 9.07

open conductivity: 0.26 mS/cm (200 $\mu\text{mhos}/\text{cm}$)



18

4-9-88

Sharon Shultz noticed a bubble in the travel blank VOA bottle (TB-2).
 0945: J. Balen conducted a safety meeting
 0930: Went to MW-17. Took PB-S.
 0940: Sampled MW-17.

1020: Took gross parameter readings.
 Water at this well is very, very silty
 causing meters filtration to go blowby
 temp: 9.9°C

pH: 7.23

spec. conductivity: 0.67 mS/cm (670 μ hos/cm)

1100: Sampled MW-16, located next to

MW-17. First, Sharon Shultz decanted
 the filtration apparatus used on MW-16

using procedure on page 4, (lines 14-18).

(We have two filtration apparatus with us
 in Van; one is still dirty from MW-15.)

1120: Took gross parameter readings. Water

is same as MW-17.

temp: 10.2°C

pH: 8.62

spec. conductivity: 0.384 mS/cm (384 μ hos/cm)

1135: Went back to office to decant (3) bottles

Filtration apparatus using procedure on page 4, lines

14-18

19

4-9-88

14-18: K. Dixon continued filtering

MW-16 metric samples.

- Change of plans in sampling.

Went going to sample 2 men on

Site 4 today. However, cannot find

keys to these wells (Stage 2 Phase

II wells). Therefore we will move to

Site 4 and sample them. P. Reem

and M. Raddy are purging MW-21

now. (Site 4)

1200: S. Shultz decanted 2, barrels

using Decan-1 procedure on page 11.

1230-310 LUNCH

1318: Headed to Site 4, MW-21.

1330: Pulled MW-21 sample.

1338: Gross parameter measurements.

Water is very clear and free of silt.

temp: 12.6°C

pH: 7.78

spec. conductivity: 1.30 mS/cm (1300 μ hos/cm)

1345: Went to office, picked up supplies.

1400: J. Balen & K. Dixon took S. Shultz

to airport - she is departing for Atlanta

Headed to Site 4 to MW-GW8C

1430: Took sample from GW8C

Sharon Shultz 9-88

20

15.65 Took gross parameter readings:
Water moderately cloudy.

Temp: 15.4 °C

pH: 6.69

Spec. Conductivity: 0.98 mS/cm (980 μ mhos/cm)

P. Bremers + M. Naddy are having problems getting water from GW8-B. Therefore, since there are no more wells around Thorsen, will stop here.

Note: Took photos of all bottles today prior to sampling events.

15.451 Began wrapping samples, packing, etc.

1710: Handled Red Ex with following:

MW-15⁸ with FB-4 Field blank

MW-17⁸ with FB-5 Field blank

MW-16⁸

MW-21⁴

GW8C

BR-2 with Site 3 parameters

TB-2 - trail blank #2-19-7-88^{filled}

Friday 2 Dec 9-1-88

21

Note: Joann Rader called Berkeley

15.6 at 1630 to O.K. the Saturday delivery for these samples.

1745-1900: Decanned (2) for the appendix

as per page 4, lines 14-18; Decanned (5) barrels as per Decan-1 procedure on page 11.

Prepared bottles for tomorrow.

1900: Left.

Weather: Sunny, very breezy 20-30 mph gusts, 75 °F high.

~~9/11/2/88~~

Friday 2 Dec 9-1-88

22

9-10-88

0700: Arrival at office. Joanne Beeler

conducted H+S meeting (P. Remmer, M. Reddy,

K. Davis, J. O'Brien in attendance)

0735: Calibrated Orion pH probe described

on page 8, lines 17-18.

400 standard: 3.93 → 4.00

200 standard: 7.04 → 7.00

0745: Helped J. Beeler fill up BR-3

bailer inside VOA vial. We both noted a

heavy exhaust smell lingering in air; probably

from jet that just took off. She filled rest.

0750: Calibrated Hach conductivity probe

described on page 8, lines 14-16.

1500 $\mu\text{mhos/cm}$ std: 1.016 mS/sec → 1.000 mS/sec 10,000 $\mu\text{mhos/cm}$ std: 9.83 mS/sec → 10.000 mS/sec

0900: Handled out to Site 4, MW-22.

Taking a field blank FB-6 at this

well. (Team = Kim Davis and Joanne Beeler)

0915: Pulled sample from MW-22 -

Took picture prior to getting sample

0930: Gross paramecium measurements:

temp: 9.4°C

pH: 7.39

spec. conductivity: 1.26 mS/cm (1260 $\mu\text{mhos/cm}$)

Phyllis L. Davis 9-10-88

23

9-10-88

Water is slightly cloudy; not too bad to filter.

1000: Went to MW-21. Took picture of bottles.

→ NOTE: Yesterday, all references to MW-21 should be MW-23.

This is an error on the chain of custody although the bottles are all correctly labelled.

1015: Pulled MW-21 sample. John

Handman borrowed the conductivity and

pH meters, therefore we must wait for

him to return it before we can do

rest with. Finally, decided to just put

some sample in a bottle to measure

pH it conductivity a little later. Decided

to train operators with (1) nitric 10% rise, (2) HPLC run.

Note: MW-21 and MW-22 had been painted

earlier this morning and were slightly sticky

on the cap for the meter casing. No paint

odor was detected, however.

105: Went to MW-24.

Strong smell of JP-4 in air, probably due to

truck that is refueling about 75 feet east

Phyllis L. Davis 9-10-88

24

9-10-58

OK MW-24

1120: Pulled MW-24 sample after taking picture of bottles.

1135: Decanted Filtration apparatus using (1) 10% nitric rinse, (2) HPLC H₂O rinse.

1136: J. Handman finally returned pH of conductivity meter. Took readings:

MW21:

Water fairly clear.

pH: 7.01

temp: 20.2°C (warm temp due to sitting out)

conductivity: 0.733 mS/cm (733 μ hos/cm)

MW2A:

Water very cloudy, difficult to filter.

pH: 8.5

temp: 19.8°C (warm temp due to sitting out in bottle)

sp. conductivity: 0.730 mS/cm (730 μ hos/cm)

1200: Healed to drive to pick up 1" bailer to do GW4B.

1205: Left message at Berkeley Lab for Mechanic Balkzone that all MW-21's are C-O-C.

Yesterday should be MW-23.

9-10-58

25

9-10-58

1300: Went to GW8B, Site 8.

Note: While at office, decanted the new 1" bailer using Decan-1 procedure described on page 11.

1320: Took gross parameter readings.

Water very, very silty and difficult to filter.

temp: 12.2°C

pH: 7.45

sp. conductivity: 13.0 mS/cm (1300 μ hos/cm)

1500: Healed to GW8A after Decan-1

1" bailer using Decan-1 procedure described on p. 11.

Also decanted two filter-applicable using (1) 10% nitric rinse,

(2) HPLC H₂O rinse.

1510: Took pictures of bottles and pulled sample.

1535: Gross parameter readings.

Water same as in GW8B.

temp: 12.2°C

pH: 7.04

sp. cond.: 11.02 mS/cm (1020 μ hos/cm)

1600: Pulled samples

1640: Went to Field Ex with samples

See next page for list.

9-10-58

26

10:00

Samples shipped out today

BR-3 with site & parameters

FB-6 - MW22 VOA blank

MW-22

MW-21

MW-24

GW8

GW8B

WB-3

1705: Came back to office. Prepared to decom (13) 2" bailer and (1) 1" bailer. These will be decom

using Decom-1 procedure on page 11.

Decom (3) 2" filter apparatus as per

procedure on page 4, lines 14-15.

1840: left, after adding pressurizers to tomorrow's bottles.

Weather today: calm breezes, hazy skies, high of 70°F.

Phil 2 Dr

Phil 2. Done 9-10-84

27

9-11-84

0800: Arrived at office. Prepared ice

for cokers, organized schedule.

0910: Calibrated Orion pH probe

described on page 8, lines 17-18.

4.00 standard: 4.04 → 4.00

7.00 standard: 7.02 → 7.00

Temp probe reads 18.8°C, Hg thermometer = 18.9°C.

0925: Calibrated Hach SP conductivity

probe described on page 8, lines 14-16.

10.00 $\mu\text{mhos/cm}$ std: 1.02 mS/cm → 1.00 mS/cm 10,000 $\mu\text{mhos/cm}$ std: 9.83 mS/cm → 10.00 mS/cm

Temp reads 19.2°C, Hg thermometer = 19.2°C

From this point on, will use Hach probe to read temp. instead of Orion probe.

0900-0930: J. Beeler prepared BR-A

bailer rinsate assay site & parameters.

team: K. Davis, J. Beeler

1000: Went to GWTC site & to sample

1025: Took field blank, FB-6.7.

1030: Took sample from GWA-C.

Took duplicate, "MW51"

9-11-84

28

9-11-88

Note: Took picture of bottles prior to sampling.
1205: Gross parameter measurements.

Water very silty; difficult to filter
temp: 11.3°C

pH: 7.60

sp. conductivity: 440.192 mS/cm
(1.152 μ mhos/cm)

1235: J. Beeler decanned (1) filter
apparatus using 10% nitric rinses, then
HPLC H₂O.

1240: Moved to MW-9.

Binette, got stuck in ditch. Therefore,
ate lunch, called tow truck and made
labels.

K Davis decanned (1) additional filter
apparatus using 10% nitric rinses, then
HPLC H₂O. J. Beeler decanned the
1" bailer that we used on GW4C
to use on MW-9. Used Decan-1
procedure described on page 11.

1545: Pollard MW-9 sample after taking
picture of bottles. A field blank, FB-8,
was taken at 1535.

1645: Took gross parameter readings.

July 2, Daws 9-11-88

29

9-11-88

Water is very very silty and difficult
to filter. We suspect this is due to
all previously existing wells from Phase
II, Stage I and Stage II, which had been
developed and remaining uninteracted for
25 years.

temp: 15.7°C

pH: 6.74

sp. conductivity: 0.843 mS/cm (2.15 μ mhos/cm)

1730: Took BW4B sample after taking
picture.

1805: Gross parameter readings.

Water very very silty and hard to filter.

temp: 11.10°C

pH: 7.77

sp. conductivity: 0.429 mS/cm (1.09 μ mhos/cm)
1815: ~~1800~~ Continued to filter until 1900.

1900: Went back to office. Decanned all
bottles as per Decan-1 procedure on p. 11.
Decanned (6) filter apparatus: as described
on page 4, laws 14-18. Packed samples.
Cleaned office.

2045: Left. (Weather: sunny, breezy, 68°F.)

July 2, Daws 9-11-88

9-11-88

List of what want sent today:

BR-4 bailer rings w/ site 4 parameter

TB-4 ground blank

GW4C¹ with BR-4 ground blankMW-51¹ - dup of GW4C

FB-8 - field blank & MW-9

MW-9¹GW4B¹

MATRIX SPIKE (2) (441)

9-12-88

0715: Arrived. J. Beeler placed call to Sharon Smith to order more filter paper, white tape, 1 L polyethylene bottles, thermometer.

0800: Went to pick up supplies.

0830-0930: Made telephone calls

0930: Took BR-5, bailer inside. This mistake came from the 4th bailer only.

Since that will be the only one in use today (Only Phase II Stage I + II wells will be sampled today, which requires this small bailer), BR-5 was for

Site 4 parameter only.

1030: Henriquez contacted, requested

that MW-29 on site 3 be split with him. If time will try MW-23, next. Said that he would return after lunch.

Continued to make labels, work on written requests from O.R. office. M. Roddy +

P. Raman ran errands. this A.M.

- J. Beeler called Berkeley Lab to change chain of custody form 9-9-88 and to

ask where trip blanks were. M. Battersea

Robert Zden 9-12-88

Robert Zden 9-11-88

32

9-12-88

and Ron - told her that they shipped them 9-7-88 (that we received) and that we were to open them and add HCl preservative "preferably in our motel room" before shipping them. K. Davis called Sharon Shulte to discuss this and was told that this methodology would turn the trip blank into a field blank, essentially, and recommended very highly against this procedure.

12:10: K. Davis called M. Batten and expressed concern over holding times being exceeded on our trip blanks (total 9-7-88 and was told by M.B. and Ron - that there was no holding times on trip blanks. Terminated conversation at this point.

12:30: ^{K. Davis} Called Richard Westmuckland, Martha Muncie. Noted him of impending splits (2 samples) with all of analysis.

Also asked him what his methodology about trip blanks was. He said the lab shoule preserve the trip blanks from the start, and there is no danger of exceeding holding times.

He said that there was no way we could open a trip blank and add preservative without getting

Khory 2. Davis 9-12-88

33

9-12-88

Dubbles in the vials, and therefore should not be opened.

K. Davis kept writing on O.R. office's request for information.

1300: K. Davis delivered by phone all information to J. Sherwin.

1320: Henriquez Co. returned. We agreed to meet at Site 3 shortly.

1335: Calibrated Orion pH meter descent in p. & lines 17-18.

4:00 started: 4.04 → 4.00

7:00 standard: 6.98 → 7.00

Calibrated. High conductivity meter described on p. 8, lines 14-16.

1,000 $\mu\text{mhos/cm}$ standard: 1,008 $\mu\text{mhos/cm}$ → 1,000 $\mu\text{mhos/cm}$

10,000 $\mu\text{mhos/cm}$ standard: 9,986 → 10,000 $\mu\text{mhos/cm}$

High temp: 21.2°C Hg thermometer temp: 21.2°C

1400: Headed out to NW-29. Set up

bottles for Berkley and Mitei Miller and took picture. ^{K.D.} Attached Miller's ES.

Also getting FB-9 (field blank) and

Berkley is getting TB-5 (travel blank).

14:15: Began getting samples. Team: K. Davis, J. Beder, H. Gentsch

Khory 2. Davis 9-12-88

34

2-12-88

1540: Henrique left to check on Peter
Remington and M. Roddy. It turned
out Henrique only wanted VOA's

1600: Took gross parameter readings.
Water cloudy, but not too difficult to filter
temp: 19.0°C

pH: 7.24

Sp. Conductivity: 0.820 mS/cm (820 µmhos/cm)
1600-1715: Packaged samples

1715: Henrique left.

Note: Joel Munns approached us today
to ask when the 55 gal. drums would be
removed. (Soil drums need to be tested for
BP Toxicity and water drums are mostly
water onlyies.)

1730: Brought foling to Red Ex:

BBR-5 using site 4 parameters.

(This was before Henrique showed up and
changed our plan: to site 3, now 21)

(2) MW-29 - one to ES, one to Berkeley

TB-5 to ES

TB-9 to ES

Phyllis L. B. 9-12-88

35

Need to call Mitzi Miller or Richard
Westmarch to ask if they need a field
blank, which was inadvertently forgotten.

1730: P. Remington discussed the 2" back

used today vs. Decem-1 procedure on

P-11 and decided the (2) filter

apparatus using the procedure described

page 7, lines 14-18.

1815: Left. Weather: 65°F, cloudy, breezy

Phyllis L. B.

Phyllis L. B. 9-12-88

36 9-13-88

0715: Arrived. Made phone call to Oak Ridge. Sample team: J. Beale & K. Davis

0815: Calibrated Orion pH probe described on page 8, lines 12-15.

4.00 standard: 4.03 → 4.00

7.00 standard: 6.98 → 7.00

Calibrated Hach conductivity meter

described on page 8, lines 14-16.

1000 $\mu\text{mhos/cm}$ std: 1.073 → 1.000

10,000 $\mu\text{mhos/cm}$ std: 9.068 → 10.00

temp: 17.2°C Hy thermometer: 17.5°C.

0900: Handed out to NW-8, Site A.

0910: Took picture - team = K. Davis, J. Bech

0915: Began pulling samples

0925: While filling VOA vials, two

JP-4 trucks passed within 5 feet of

our table causing heavy diesel fumes

to be noticeable in the air.

0935: Poured sample to be P. 11 hand into

a clean container. Water was so murky,

that after 5 minutes, only top 1/2 inch

of container was settled out enough in

order to allow light to pass through

slightly.

9-13-88

37

Took picture of water from this well.

0945: Took gross permeability (See above for water description)

temp: 13.2°C → 14.2°C

pH: 6.49

sp. cond.: 0.558 ms/cm (55.8 $\mu\text{mhos/cm}$)

1035: Permeability (2) Filter apparatus?

using 10% nitric rinse and HPLC water.

The container used to hold sample in

order to allow settling will be decant

using Decant procedure - page 4,

lines 14-16 procedure.

Note: P. Remson & M. Roddy are

re-purging site A wells that they did

Sunday, and we were unable to get to

yesterday due to MPCA bay here.

1040: Went to NW-26, Site 3

(M. Roddy & P. Remson purged this one

yesterday at the request of Henning)

Control in atmosphere of sample, it

1055: Took picture of bottles

1100: Pulled sample

9-13-88

38

9-13-88

1115: Took gross parameter readings. Water very silty towards end of boring when we were sitting by the filter module.

Temp: 14.1°C

pH: 7.85

Sp. conductivity: 0.671 mS/cm (0.71 μ mhos/cm)

On this well, tried using 5.0 μ m pre filters before a 0.45 μ m filtering stage. We found that the 5.0 μ m filters were almost as slow as the 0.45 μ m filters.

1200-1330: Lunch, Decanned 1" bailer

using Decan-1 procedure on page 11.

Also decanned (2) filter apparatus using procedure on p. 4, lines 14-18. The

containers used to hold sample in order to settle prior to filtering was also decanned using the same procedure.

1345: Handed out to GW4A, Site 4

1400: As we were preparing to pour samples (took pictures beforehand), Johnson, Belton spilled nitric acid on arm. Went back to office.

John Zehn 9-13-88

39

9-13-88

to attend to

1420: Return to GW4A. Continuing to sample.

1500: Took gross parameter measurements.

Water very silty and difficult to filter.

Temp: 16.1°C

pH: 6.74

Sp. conductivity: 0.680 ~~1~~ mS/cm (0.80 μ mhos/cm)

Notes: Called Richard Westman (Tel. 9-1220) to see if samples arrived. He said

that he is sharing responsibility with

Armed ~~Force~~ ^{Maritime} (sp. foreign) and he may find them.

From now on, he said, only send parameters

that MP/CA collects. [I explained that we had already prepared bottles before realizing

that Henrique Gentil only wanted

VQA samples.] Also, it is not necessary

to send a field blank to Martha Monetta, as long as we retain one to send to ES Berkeley.

1540: Finished GW4A. Went to Decan

1" bailer using Decan-1 procedure on

page 11 and to decan (2) filter apparatus

and sample holder/settler using procedure

John Zehn 9-13-88

40

9-13-88

continued on page 4, lines 14-18.
Johnnie Beckel deceased.

1600: Hauled out to GWAD at site 4.

1620: Took sample (after taking picture).

1635: Took gross parameter readings.

Water is very very silty.

temp: 12.0°C

pH: 6.45

sp. conductivity: 1.066 mS/cm (1066 μ mhos/cm)

1245: Hauled back to surface to filter metals for this well and to pack the coders.

Going out today:

GW4A

GW4P

MW 8 (site 4)

MW 26 (site 3)

TB-6

1730: Went to Red Ex

1800: Prepared bottles for tomorrow

1835: Left.

Weather: Cool (60-65°F), Sunny.

sporadic breezes (0-25 mph)

Wind 2 Sw 9-13-88

41

9-14-88

0710: Arrived. Received phone call from

Bill Hayden. BR-3 boiler rinsed

sent out on 9-10-88 did not know

EPA 608's checked on chain of custody.

Told him it should have been checked!

0730: Talked to Bob McLeod. He said

to hold off on ordering bottles until

we are clear what MPCA wants

as far as (1) whether we should wait

for results before conducting 2nd sampling

round and (2) whether we will sample

all wells or just ones with "hits."

0800: K. Davis calibrated Orion pH meter

described on page 8, lines 17-18.

4.00 standard: 4.04 \rightarrow 4.00

7.00 standard: 7.00 \rightarrow 7.02

Calibrated Hach conductivity meter

described on page 8, lines 14-16.

1,000 μ mhos/cm std: 11.043 mS/cm \rightarrow 11.000 mS/cm

10,000 μ mhos/cm std: 9.78 \rightarrow 10.00 mS/cm

Hach temp: 16.8°C, Hg thermometer: 17.9°C

0815: P. Kienasim and M. Roddy prepared

BR-6 boiler rinse with site 3

parameters.

Wind 2 Sw 9-14-88

A2

9-14-88

0820: J. Beebe + K. Davis (sample team)
Went to MW-11, Site 4.

Note: We realized today that MW-26, Site 3 should not have been sampled.
MW-25 was purged next to it. Therefore MW-26 will be re-sampled and MW-25 will be re-purged. From now on, all purged wells will be marked and dated.

0830: ~~Prepared~~ Prepared to sample MW-11.

Took picture

0845: Pulled sample from MW-11

0910: Measured gross parameter

Water very silty, difficult to filter

temp 13.0

pH 6.90

sp conductivity: 0.1690 mS/cm (690 μ hos/cm)

0945: Went back to office. Decanned (3)

filter apparatus using 10% nitric rinse,

then HPLC grade water rinse. Decanned

1" binder used on MW-11 with Decon-1

procedure on page 11. Packaged (1) cooler and

sealed.

Theresa L. Davis 9-14-88

A2

9-14-88

1015: Took picture, pulled sample
at MW-10.

1100: Took gross parameters near well.
Water slightly cloudy, not filtered + filter
temp 17.2°C

pH 6.96

sp conductivity 0.1451 mS/cm (451 μ hos/cm)

1125: Went back to office. Called Kathleen Kidd to ask about Grand blent holding times ("no holding time"), whether Ron (KS Bally) was correct in saying one hour TB's before sending one out to preserve / HCL (no, the lab is supposed to preserve them before sending out a).

→ Kathleen said that a rolling cart used to transport samples collapsed yesterday, breaking an unknown number of samples.
From 9-12-88.

1200: LUNCH and errands.

1420: Went out to MW-25 and MW-26 (pair)

1500: Begun sample MW-25 at 1500 after

taking picture

Theresa L. Davis 9-14-88

44

9-14-88

1505: took gross parameter readings:
Water slightly cloudy, not too different
to filter. (Only used 10 filtering apparatus)

temp: 16.0

pH: 7.81

sp. Conductivity: 0.1694 mS/cm (694 μ mhos/cm)

1600: Took MW-26 sample after taking
precare. This sample has a duplicate
normal MW-53 scheduled for 1630.

1615: Took MW-26 gross parameter
readings:

Water very silty and difficult to filter.

temp: 17.7°C

pH: 6.80

sp. conductivity: 0.435 mS/cm (435 μ mhos/cm)

1615: Went back to pack samples and to
continue filtering metals.

1730: Went to Red Ex with:

BR-6 with Site 3 parameters

MW-11, Site 4

MW-10, Site 4

MW-25, Site 3

MW-26, Site 3

MW-53, dup of MW-26

Andy Z. 9-14-88

45

9-14-88

Sometime this afternoon, Melanie Bulteen
called to verify bottle breakage which
occurred at Berkeley yesterday. The
following broke:

GWAC: all 5 VOA vials

MW-29, Site 3: (2) 418.1

(2) 608

(2) 625

FB-9: (2) VOA vials

Peter talked to Mr. Bulteen and told
her ~~that~~ to not analyze MW-26
sent out yesterday due to the fact
that it was not purged. (We resampled
it today.)

Also, we took a duplicate of Gentic,
called MW-52. We are considering
just using that sample to serve as
GWAC for this VOA vial at this point.

M. Bulteen suggested to put all resampled
bottles on a separate chain of custody and
mark "re-sampled."

Andy Z. 9-14-88

46

9-14-88

1830: Decanted (2) filter apparatus
using procedure described on page 4.
11/15/14-16: All bailers used today
(2" and the 1") were deemed usable.

Decen - 1 procedure on page 11.

1850: Left.

Weather: Cool (75°F), sunny, slight br.

~~W. W.~~

9-14-88

47

9-15-88

0745: Arrived. Decided to resample

GW-4C. Catching on same papermate

0915: K. Daws calibrated Orion pH meter
described on page 8, lines 19-18.

4:00 standard: 4.03 → 4.00

7:00 standard: 7.01 → 7.00

Calibrall Hatch conductivity meter

described on page 8, lines 14-16:

6,000 $\mu\text{mhos/cm}$ std: 1.033 → 0.000 mS/cm

10,000 $\mu\text{mhos/cm}$ std: (see below) *

Hatch temp: 17.6°C

Hg thermometer temp: 17.5°C

* Decided to just use 1,000 $\mu\text{mhos/cm}$ std.

from now on, since most samples collected

this fall are in the 500-1500 $\mu\text{mhos/cm}$

range. The procedure specified in the Hatch

manual for this meter only uses one standard

(see page 14 of this manual, published by

the Hatch Company, 1987, 1988).

1005: Called Kathleen Kidd to tell her

to cancel analysis of GW4C remaining

bottles and call of MW52.

1015-1115: Picked up 80 coolers from

the Base loading dock and met John

Hardeman at airport

9-15-88

48

9-15-88 Sampling team: K. Davis, J. Beelee
 1130: Headed out to MW-29, Site 7
 to re-sample (2) EPA 418.1, (2) EPA 608
 and (2) EPA 625 1 L Amber bottles
 to replace ones that ES-Berkely broke.
 1135: Took picture, and pulled samples.
 1150: Took gross parameter readings.
 Temp: 17.0°C
 pH: 7.05
 sp. conductivity: 0.682 mS/cm (682 μ mhos/cm)
 1155: Decided to take Field Blank,
 FB-10 at this site (was not in picture).
 1200: Went to MW-27.
 1215: Took picture, then pulled sampler.
 Extremely slow in recharging. After
 fully VOA, well was almost dry.
 Ake lunch between 1230-1300.
 1300: Pulled 1 L Gum MW-27 before it
 went dry again.
 1400: J. Handman arrived on scene.
 Decided to leave bucket in well and
 check later due to lack of water.
 At this point, only have (5) VOA vials,
 and (2) 1 L meters, and (6) ambers
 1 L bottles which are filled 1".
 R. Z. 2. 8-15-88

49

9-15-88
 1415: Came back to office, decanted
 filtering apparatus with 10% water
 rinse and HPLC grade water.
 Placed phone calls.
 1530: Went back to MW-27. Still
 dry. Decided to go ahead and
 sample MW-33 (J. Beelee and John
 Handman) while K. Davis wrapped
 bottles, filled out C-O-C, etc.
 1615: Pulled sample from MW-33
 6.5 L vial picture.
 1640: Took gross parameter measurements.
 Water silty and difficult to filter.
 Temp: 16.8°C
 pH: 7.49
 sp. conductivity: 1.5362 mS/cm (1536.2 μ mhos/cm)
 1700: Came back to office and packed.
 1715: J. Handman & J. Beelee drove to
 Fed Ex; K. Davis remained at office
 to decan. Filtration apparatus to
 filter to using procedure outlined on
 page A, Nov 14-18.
 A/SO, K. Davis is rinsing out the (6) 1 L
 Ambers from MW-27 with HPLC H₂O
 to use tomorrow at MW-27.
 R. Z. 2. 8-15-88

SD

9-15-88

To Fed Ex today:

MW-27, Site 3 (just VOA's + metals)

MW-33, Site 3

TB-7

MW-29 (resampled (b) 1 L quarts from
breakage at ES lab)

FB-10 - field blank at MW-29 to

replace FB-9 that was broken.

1800-1900: Prepared bottles for tomorrow.

1400: Left.

Weather: Cool (65°F), cloudy; rain at

1400 and continued for rest of evening.

Doris

Wendy

Doris L. Davis 9-15-88

51

9-16-88

0710: Arrived. Raining heavily. Prepared
to take a bottle rinseate, BR-7

with Site 3 parameters. (J. Haden, P. Ramsey, Kelly)

0745: Calibrated Orion pH meter described

on page 8, lines 17-18.

4.00 standard: 4.03 → 4.00

7.00 standard: 7.07 → 7.00

Calibrated Hach conductivity meter

described on page 8, lines 14-16.

1,000 μ mhos/cm standard: 1,100 μ mhos/cm → 1,000 μ mhos/cm

Water temp: 16.6°C. 14g thermometer temp: 17.8°C

0845: Drive to GWAC to get sample

(due to bottle breakage) along with

the duplicate, MW-52. Still raining

heavily; windy. J. Haden helped

set up tarp over well and sampling

table.

NOTE: TB-8 (1) of the vials has a

bubble in it.

0945: Took picture of bottles, then

pulled GWAC, then MW-52 samples.

Sampling Team: P. Ramsey, K. Davis

Doris L. Davis 9-16-88

52

6-16-88

1100. Took gross parameters
measured

Water slightly salty, we will
filter back in office.

Temp: 67.3°C

pH: 7.45

Sp Conductivity: 1.102 mS/cm (1102 μ mho/cm)

1115-1145: Filtered metals at office.
Placed phone calls.

1230. Went to MW-27 to take good rest
of 1 L samples (2). Rain has subsided
somewhat; just misty now.

1245 (Call only) got 1 L Amber, EPA608
from this well (Took picture prior to sampling).
Well went completely dry after this.

1315-1400 LUNCH

1415: Dived up into 2 sampling lines
K. Davis & P. Rasmussen went to MW30.

J. Hardeman & M. Riddy went to MW34.
Before going, discovered filter apparatus
using 10% nitric rinse and HPLC
grade water.

1445: K. Davis took picture of MW-30
batteries prior to fully 1st sample.

Philip Z. Davis 6-16-88

53

1500: J. Hardeman & M. Riddy pulled
sample from MW-34 after taking
picture.

1515: Diving fill-up of bottles from
MW-30, accidentally poured sample
directly into metals bottles (about
200 ml each). We will pour this
out. Those bottles with HPLC grade
water, add 5 ml HNO₃ to each
and pour filtered sample into them.
(We are using same bottles due to
rapid depletion of polyethylene bottles.
This rapid depletion of polyethylene bottles
was observed before to store in filtered
sample prior to sampling, which was
not taken into account for when initially
ordered.)

1545: Took gross parameters readings MW-30
Water slightly cloudy, not too difficult
to filter.

pH: 7.38

Temp: 10.10°C

Sp Conductivity: 0.524 mS/cm (524 μ mho/cm)

Philip Z. Davis 6-16-88

SA

9-13-88

1400: Took parameter readings for MW-34, water very murky and difficult to filter

pH: 6.48 (2 meters deviating)

temp: 9.8

sp. conductivity 0.800 mS/cm (800 μ mhos/cm)

1610: P. Ravensma & K. Duns return to office to filter MW-34 and pack.

J. Hardman & M. Rodby continue purging site 3 wells.

Note: J. Hardman called Baskell

lab \approx 1000 this AM to warn Thosh

of impending Saturday shipment and

12 day hold day time. Secretary

took message since no one was available

to talk on phone.

1730: P. Ravensma and K. Duns went to Fed Ex with:

MW-30 site 3 TB-8

MW-34 site 3

GWAC site 4 re-samples

MW-52 re-sample of GWAC deep

BR-7 using Site 3 parameters

MW-37A just (2) 625 12 amber

Philly 2 when 9-16-88

SS

9-16-88

Weather today was driving rain this morning, subsiding to a mist, Temp: 60°F.

1930: Last, after decontamination apparently with 10% methanol, or HFC mix.

[Handwritten signature]

[Handwritten signature] 9-16-88

56
9-17-88

0710: Arrived.

0730: Calibrated pH meter described

on page 8, lines 17-18

Temp: 4.00 standard 3.99 → 4.00

pH: 7.00 standard 6.98 → 7.00

sp. conductivity

Calibrated Hatch sp. conductivity meter

described on page 5, lines 12-14.

1000 $\mu\text{mhos/cm}$ std: 1.000 mS/cm (1000 $\mu\text{mhos/cm}$)

Hatch temp: 17.9 - 17.9 thermometer: 18.2

0745: Made out labels.

0815: Divided up into 2 sampling teams

again. J. Hardeman, M. Ratley on one,

P. Riemann & K. Davis on other. We

are planning to sample GW3A, GW3B, GW3C

and GW3D, which are all clustered together.

0825: Found DANUB-BRT EPA#18.1 bottle

laying on table that was supposed to be

included in yesterday's shipment.

0845: K. Davis, P. Riemann went to GW3C

to begin sampling. We are taking FB-11

here.

Philip Z. Rea 9-17-88

57

9-17-88

0915: K. Davis & P. Riemann pulled

GW3C sample after taking picture.

FB-11 was pulled @ 0920.

0920: J. Hardeman & M. Ratley pulled

GW3B. They are taking a duplicate.

NW54, scheduled @ 1000.

1000: Took gross parameter readings for

GW3C. Water is too silty to even

begin filtering in the field. We are

pouring into bottles to allow settling.

Temp: 16.9°C

pH: 5.80

sp. conductivity: 0.173 mS/cm (173 $\mu\text{mhos/cm}$)

— Took gross parameter readings for GW3B.

Water same as above.

Temp: 11.3°C

pH: 6.18

sp. conductivity: 0.800 mS/cm (800 $\mu\text{mhos/cm}$)

1045: K. Davis & P. Riemann prepared bottles

for GW3A.

1100: K. Davis & P. Riemann took picture

Philip Z. Rea 9-17-88

58

9-12-88

of GW3A then sampled, and M. Reddy & J. Hardman took picture of GW3D and sampled.

NOTE: For this morning's sampling (GW3A, GW3B, GW3C, GW3D, MW52 & MATRIX SPIKE), bailers were left in wells from purging. We used these same bailers to sample. Therefore, we could not take bailer rinsewater as scheduled this AM. This would have been BR-8, which will be taken 9-19-88.

1145: P. Roman measured gross parameters at GW3A. Water cloudy, will filter back at office.

Temp: 11.4°C

pH: 7.18

SP Conductivity: 0.420 mS/cm (420 μ mhos/cm)

GW3D gross parameters: (water cloudy same as above)

temp 9.6°C

pH ~~6.3~~ 6.3

SP conductivity 720 μ mhos/cm

Phredy L. Davis 9-17-88

59

9-17-88

1200: Came back to office, M. Reddy & P. Roman documented the (A) stainless steel bailers used this morning.

Using Decan-1 procedure with the exception of the substitution of 5% nitric rinse for the 10% nitric rinse.

From whom an, this stainless steel bailer procedure will be called "Decan-2".

J. Hardman filtered samples.

K. Davis prepared chain of custody, packed and inventoried supplies.

1600: Finished filtering & packing - went to Fed Ex bldg.

GW3A

GW3B

GW3C

GW3D

MW54 dup of GW3B

MATRIX SPIKE (6 AMBERS)

FB-11

MW-27 - (2) 608's

1845: Prepared to leave.

Weather: Sunny, warm (75°F), no breeze.

Phredy L. Davis 9-17-88

60

9-18-88 - DAY OFF
9-19-88

0710: Arrived.

0720: P. Krenshaw calibrated the Orion pH meter described on page 8, lines 17-18.
7.00 standard: 6.98 → 7.00
10.00 standard: 9.84 → 10.00

He also calibrated the Hach conductivity meter described on page 8, lines 12-14.
1,000 μ mhos/cm standard: 0.993 → 1.000 μ S/cm

0800: Poured bailer rinsers from (3) Teklon bailers. BR-8, using side 3 parameters. These bailers will be used to finish off Site 3 today on MW-28, MW-31 and MW-35.

0830: J. Herdman & M. Reddy went to purge last 3 wells on Site 3. They are taking bailers that BR-8 was poured from & purge and will leave bailers in well for P. Krenshaw & K. Davis to sample with.

0930: K. Davis & P. Krenshaw prepared MW-31 bailers - this is sample ear this AM
9-19-88

9-19-88

0945: Pulled sample from MW-31 after taking picture.
1000: Took gross parameter readings. Water very very cloudy; therefore we will allow to settle before attempting to filter.
temp: 10.6 °C
pH: 7.82
sp. conductivity: 0.894 μ S/cm (894 μ mhos/cm)

1020: Prepared bailers for MW-28 & 1035. Pulled sample from MW-28 after taking picture.
1100: Took gross parameter readings. Although water was only slightly cloudy, was very difficult to filter.
temp: 11.5 °C
pH: 8.17

sp. conductivity: 0.518 μ S/cm (518 μ mhos/cm)
1130: Prepared bailers for MW-35. We are taking a field blank, FB-12 here.

9-19-88

62

9-19-88
 1145: Pulled sample from MW35
 after taking picture -
 1225: Crissi parameters readings -
 water slightly cloudy - Weir will
 filter a few / a day to settle
 for ~ 7 hours
 temp. 15.10°C
 pH 7.67
 sp. conductivity 0.236 mS/cm (236 μ hos/cm)

1300: Went back to office J. Becker
 has returned. P. Remosma & J. Becker
 started filtering the (3) Site 3 samples.
 K. Davis went to get lunch for some
 people. J. Hardman & M. Raddy
 determined backers used that morning
 using Decan-1 procedure

Note: At 0200 P. Davis called Kathleen
 Kidd ~~notified~~ to notify the lab of
 the inadvertent absence of BR-7
 48.1 bottle. R. Kidd said to include
 it with a note in today's shipment

Shelley L. D. 9-19-88

63

9-19-88
 1430: P. Remosma & K. Davis went
 to get (2) 48.1 1 L Amber bottles
 from MW-27, Site 3 at J. Hardman's
 request. Note: First started sample
 this well ~~on~~ (MW-27) on 9-15-88.
 The barrel has been in the well since
 9-15-88.

1445: Drove back to office to get labels.
 1500: Drove to MW-2, Site 2. Prepared
 bottles.
 1530: Pulled sample from MW-2 after
 taking picture.
 1545: Took Crissi parameter readings.
 Water is like chocolate milk -
 Temp: 11.6°C
 pH 7.06
 sp. conductivity: 0.991 mS/cm (991 μ hos/cm)

1605: Pulled MW-1 after taking picture.
 1625: Crissi parameters (water sample at 1625)
 temp 12.3°C
 pH 6.63
 sp conductivity 1.31 mS/cm (131 μ hos/cm)

64

9-19-88

1630-1730: F. Skered MW-1 and MW-2.
 began raining intensely (A. H. very wet)
 obscuring landmarks.

1745: Dove to feed E. 20 within:

BR-8 site 3 parameters

MW-28 } site 3

MW-31 } site 3

MW-35 }

FB-12 - taken at MW-35

MW-1 } site 2

MW-2 }

TB-8 - was supposed to be called "TB-9"
 since TB-8 was taken 9-16-88.

1800: J. Hurdant + M. Roddy Decanned:

buckers - Teflon used Dec 11, 1988

used. Dec 11, 1988 - (Dec 11, 1988, page 59)

1830-1930: Made labels

1930: Left. Weather: Cloudy, warm,

no breeze all day until 1700

when rained heavily until we left.

Robert L. Allen 9-19-88

65

9-20-88

0710: Arrived

0735: Calibrated Orion pH probe described

on page 8, lines 17-18.

7.00 standard: 7.01 → 7.00

4.00 standard: 3.88 → 4.00

Calibrated Hach conductivity meter

described on page 8 lines 12-14.

1,000 µmhos/cm std: 1,000 µmhos/cm → 1,000 µmhos/cm

Humidity: 17.4°C Hg. Hg. m. temp: 17.5°C

0800: J. Hurdant poured BR-9, bucket marked "5th"

0830: Hurdant to site 2, MW 30,

Sample team: L. H. Davis, B. Beeler

0945: Pullall sample after taking pictures.

0915: Took gross Nazareth reading.

Water very cloudy.

Temp 12.1°C

pH 6.40

SP conductivity: 0.362 mS/cm (362 µmhos/cm)

0930: J. Beeler sliced open finger to hide

cutting buckle rope off of buckle (hands

were numb from cold weather - GPF,

20 mph wind). M. Beeler took back

notes.

Level 20 - 9-20-88

66 9-20-84

0945: Reorganized sampling team is now P. Remmon + K. Davis. We could not get lock back on MW-37. Decided to get longer brass lock from another well and switch due to MW-37 lock brass too short. (well cap is too tall to get outer casing flush in sub-to lock). Left cap off of well, lockbody will return later to remedy situation.

1000: P. Remmon + K. Davis prepared bottles for 1015 sampling of MW-41. However, when we were ready to sample, realized that Johnson took off with keys to wells. Headed out to find keys.

1015: Recovered keys from survey car. 1030: Returned to well. Took pictures, pulled sample from MW-41.

1105: Gross parameter readings: water is almost completely clear. temp 9.8°C
pH 6.53

SP. conductivity: 0.390 mS/cm (390 μ mhos/cm)

July 2 Dec 9-20-84

67

9-20-84

Mike M. Leach returned. J. Harwood took J. Beebe to hospital. Mike is now purging MW-40 within sight of Peter Remmon + K. Davis.

1130: Prepared bottles for GW2E.

1150: Took sample from GW2E after taking picture

1205: Gross parameter readings:

water very silty, cloudy

temp 9.76°C

pH 6.83

SP. conductivity 0.385 mS/cm (385 μ mhos/cm)

1230: LUNCH

1330 Placed calls to order supplies.

1400: Went to MW-40 to sample.

Prepared bottles, ran back to office for supplies.

1500: Pulled MW-40 sample after

taking picture. We are taking a duplicate MW-55, at this well scheduled for

1530:

1545: Took gross parameter readings

July 2 Dec 9-20-84

68

9-20-80

Water is Supply Level.

Temp 11.90C

pH 7.66

Sp. Conductivity: 0.324 mS/cm (324, μ mb/cm)

1600: Filtered metals and pack

1745: Want to feed Ex with

MW-37

MW-41

GWZE and dup, ~~MW~~ ^{KE}

MW-40 and dup, MW-55

BR-9 using site 2 parameters

K. Pans

1900: Left to go to Target to buy supplies.

Weather: 50-55°F, gusts of wind

20-30 mph, cloudy

Note: Called K. Kidd @ 1700 to tell her to

Change TB-8 from 9-19-80 to TB-9.

She said that the lab, today, broke ~~on~~ a

still undissolved number of amber bottles

from "collapsey shelves in the refrigerator."

A. Kelly 2 Rm 9-20-80

69

9-21-85

0710: Arrived

0715: J. Hardman + J. Becker joined
BR-10, using site 2 parameters.

0725: Attempted to calibrate Orion

pH water described in page 8, lines 12-18.

4.00 standard: Could only get down to 4.83

7.00 standard: Could only get down to 7.51.

(Pointed fresh standards)

Decided that this meter is shot.

Calibrated Hach conductivity meter

described in page 8, lines 12-14.

1,000 μ mb/cm standard: 1,007 μ mb/cm

Hach Temp: 15.6°C, Hg temp 16.1°C

0830: Arrived at Site 2, GWZA. We will

pull a duplicate here, MW-56. Sampling team

is P. Riemersson + K. Davis. M. Reddy is

pulling. MW-7 with the 25' of our well.

Prepared labels for this sample, event.

0845: Begin pull, GWZA after taking

picture. MW-56 is scheduled for 0915

A. Kelly 2 Rm 9-21-85

70

9-21-58

and we can also pull a field blank, FB-13, scheduled for 0900.

NOTE: TB-10 has a ground bubble in one VOA vial.

0940: Took gross parameter readings.

Water is cloudy.

Temp. 12.0°C

pH 6.57

sp conductivity 0.456 mS/cm (456 μ mhos/cm)

1010: P. Remington & K. Davis moved to meet

well GWZC, site 2. Prepared bottles.

We will be taking FB-14 at GWZC.

FB-14 is scheduled for 1035.

1030: Took picture of bottles. Could not

sample right away due to the presence

of a big diesel truck idling about 40

feet east of GWZC. The truck left

around 1035, but there is still a big

USAF general running continuously at the

same approximate location. Sargent Denney

Philip L. Davis 9-21-58

71

9-21-58

said that the exhaust was exiting

on the other side of the ~~DEAN~~ road

TACAN facility about 75' east

of GWZC.

1100 Took gross parameter readings.

Water very very silty.

Temp. 11.2°C

pH 6.10

sp conductivity 0.190 mS/cm (190 μ mhos/cm)

M. Paddy is now acting as a go-between

for P. Remington & K. Davis, delivering bottles

to the office for J. Beeson to filter.

1110: Moved to MW-1. Began preparing bottles.

1130: Took picture, then pulled sample

1140: Took gross parameter measurements

Water very very silty.

Temp. 11.3°C

pH 6.26

sp conductivity 0.608 mS/cm (608 μ mhos/cm)

Philip L. Davis 9-21-58

72

9-21-88

1200-1300. Lunch

1300-1400. P. Riemann + M. Reddy

decontaminated bottles (2) used

Decon-2 procedure. Kim prepared
bottles for this afternoon and placed
them out.1400. Arrived at ~~about~~ GWRD, Site 2.

Sampling team = John Sherman, who

just arrived from Oak Ridge, and

K. Davis. (M. Reddy + P. Riemann

are purging elsewhere on Site 2.) Prepared
bottles for GWRD

1415. Pulled samples after taking pictures.

First picture, larger water bottle, SC.

took another J. Sherman took picture

of site in ground.

1500. Gross parameter measurements.

Water pretty silty, but appears to be

settling out O.K.

Temp 10.7°C

pH: 6.09

SP conductivity: 0.875 mS/cm (875 μ hos/cm)

1520: Went to MW-39. Prepared bottles

Thoby 2. Done 9-21-88

73

9-21-88

1545: Pulled sample from MW-39

after taking pictures.

1615: Took gross parameter measurements

bottle fairly clear

Temp 11.7°C

pH: 6.59

SP conductivity: 0.650 mS/cm (650 μ hos/cm)

1620: Hauled back to office. Had great

dinner with Jeffery GWRD, so only

sent 1 1/3 liters. Johnnie Beale

called Kathleen Kidd to ask about this

and 1/2. Kidd said to send 2/3 liter

tomorrow.

1745: Hauled to Fed Ex with:

GWRD and duplicate MW-36 (Site 2)

FB-13 taken at GWRD

TB-10

GWRD

FB-14 taken at GWRD

MW-4

GWRD

MW-39

BR-10 with site 2 parameters.

Thoby 2. Done 9-21-88

74

9-21-58

1810: Returned to office. J. Shuman prepared bottles for tomorrow. K. Davis helped P. Riemersma decan bottles.

Tetlin bottles were decanted using Decan-1 procedure and stainless steel bottles were decanted using Decan-2. (Decan-1 is described in p. 11 and Decan-2 is described on page 54.)

1900: Left.

Weather today: 50°F, in the AM, not much breeze, rising to 65°F and sunny in the afternoon.

Phyl Z. 9-21-58

75

9-22-58

0710: Arrived.

0730: K. Davis calibrated the Oron pH meter described on page 8, lines 17-18.

400 standard: 3.23 → 4.00

700 standard: 6.98 → 7.00

Calculated the Hach conductivity meter described on page 51, lines 12-14.

1,000 pH/psd: 0.993 → 1.000 mS/cm

Arch temp: 23.9 Hy. Humid. temp: 24.0

0840: J. Shuman & K. Davis, Sampling team arrived at NW-7, Site 2.

(P. Riemersma & M. Roddy are purgery e/scholar on Site 2.) Prepared bottles

0840: Left Site 2. J. Shuman refused to work without application of insect repellent.

0850: J. Shuman placed call to Robert Thoren, FES - Atlanta. He okayed the usage of

insect repellent as long as it is not on the hands touching bottles.

0915: Returned to NW-7. Took picture and pulled samples.

0950: Took gross parameter readings. Water fairly clear.

Phyl Z. 9-22-58

7b

9-22-88

temp: 13.0°C

pH: 7.27

sp. conductivity: 0.748 mS/cm (748 μ mhos/cm)

1030: Prepared bottles for MW-6. We will be taking a MATRIX SPIKE set here, scheduled for 1105.

1100: Took picture of bottles, then pulled sample from MW-6.

1130: Took gross parameter readings - water is pretty cloudy.

temp 13.7°C

pH 7.07

sp. conductivity: 0.503 mS/cm (503 μ mhos/cm)

1145: Prepared bottles for MW-5. We will be taking a field blank, FB-15 at this well, scheduled for 1230.

1200: Took picture pulled sample from MW-5.

1230: Took FB-15.

1235: Took gross parameter readings. Water is typically cloudy, as are most non-ES wells.

9-22-88
9-22-88

77

9-22-88

temp: 12.7°C

pH: 7.40

sp. conductivity: 0.523 mS/cm (523 μ mhos/cm)

1245: Prepared bottles for MW-38, Site 2.
1315: Took picture, then pulled sample from MW-38.

1335: Took gross parameter measurements. Water is clear, tho get a little air-bailly continued.

temp: 13.7°C

pH: 7.61

sp. conductivity: 0.501 mS/cm (501 μ mhos/cm)

1345: Finished up. Lack enough bottles to do next sample and Van has mob-functioning starter.

1400: Jumped van. Handed to office

1415-1515 LUNCH

1530: Preparing CWZB bottles, site 2.
1545: Took picture then pulled sample from CWZB.

1615: Gross parameter readings: Water pretty clear. Tri-salts and of 15 mg of bottle.

9-22-88
9-22-88

78

9-22-88

Temp: 14.7°C

pH: 6.96

Sp Conductivity: 1081 $\mu S/cm$ (1081 $\mu mho/cm$)

Note: TB-11, the travel blank

one of the 40 mL VOA vials had a large bubble in it.

Note: While sampling at GW2B, could detect a faint drum of diesel fumes from the generator at the TACAN facility approximately 250 ft north of GW2B.

1700: John Anderson resampled the EPA 418-1's for GW8C and MW8 which the lab broke 9-20-88.

1730: Headed to feed EX with TB-11

MW-7, site 2

MW-6, site 2 with MATRID SPIKE

MW-5 with FB-15, site 2

MW-38, site 2

GW2B, site 2

RESAMPLE: 418-1's for GW8C + MW8-

July 2 9-22-88


78

9-22-88

1500: Returned to office. Prepared bottles and labels for next day

1900: Ctd.

Weather: Cool, cloudy, rainy, mist on and off throughout day. High of 71.60°F



July 2 9-22-88

80

9-23-58

0700: Arrived. Prepared to do surface water sample and sediment sample by (J. Hardaway, J. Beiler, K. Davis)

M. Reddy & Jean Sherman are going to Site 10 to pump and sample the shore wells there.

0749: Calibrated Orion pH meter described

on page 8, lines 17-18

4.00 standard: 4.26 to 4.00

7.00 standard: 6.95 to 7.00

Calibrated Hach conductivity meter described

on page 9, lines 12-14

1,000 $\mu\text{mhos/cm}$ standard: 1,009 mS/cm (could not reduce to 1,000)

Hach temp: 16.2°C 17.6°C, Hg thermometer = 18.2°C

0810: Decanned (2) stainless steel buckets and

(1) stainless steel angur using

(1) Lysine scrub

(2) Potable rinse

(3) Methanol rinse

(4) HPLC water rinse.

This will be called "Decan-3" from here on.

9-23-58

81

9-23-58

0845: Headed out to SL-5, a backcountry

surface water site

0900: Packed SL-5 (sampling team =

J. Hardaway, K. Davis & J. Beiler)

0925: Gross perovnick measurements =

Temp: 11.6°C

pH: 6.77

Sp. Conductivity: 0.458 mS/cm (458 $\mu\text{mhos/cm}$)

0930: Drive to SL-4, a backcountry site. We are going to take a duplicate

here, called SL-25. John H. is

taking stream flow measurements here using

the Pyming fluorometer. Note: He could

not measure flow at SL-5. Stop at

0945: Packed SL-4 sample.

1015: Packed SL-25, Dup (scheduled time)

1020: Gross perovnick measurements =

Temp: 10.2°C

pH: 7.12

Sp. Conductivity: 0.261 mS/cm (261 $\mu\text{mhos/cm}$)

1025: Took picture of SL-4 location

1030: Went out to Site 4, SL-11, J. Hardaway

left sampling team = K. Davis & J. Beiler.

9-23-58

82

9-23-88

1045: Pulled SL-11, Site 4.

1050: Gross parameter measurements:

Temp 11.6°C

pH: 6.46

Sp conductivity: 0.401 mS/cm (401 μ hos/cm)

Took picture of site SL-11.

Note: A strong odor of JP-4 was noted at this ~~site~~ ^{upstream} site along with a oily sheen on the water surface.

1055: Went to SL-12, Site 4, approximately 100 yards east of SL-11 (upstream).

1100: Pulled SL-12 sample. J. Beeler took picture of K. Davis.

Gross parameter measurements:

Temp: 12.9°C

pH: 7.01

Sp conductivity: 0.396 mS/cm (396 μ hos/cm)

Note: Strong odor of JP-4 was noted here.

But not quite as strong as SL-11.

There was also an oily sheen at SL-12.

The sediments at SL-11 & SL-12 were sticky and black, with strong odors associated with them.

Phil L. De 9-23-88

83

9-23-88

NOTE: After each sample, taken this AM, the streamless start'ng or bowl and spin was done using Decon-3 procedure described on page 80.

1200-1300: CONUC

1300: Prepared bottles for afternoon.

1330: Kathleen called. ES: Berkeley called &

Said that red addition bottles were found

in refrigerator freezers. No samples had

not been per lunch as 2 bottles

DANUB-SLOC and DANUB-DIW.

1400: Talked to Bill Hayden. Said that

the DANUB-SLOC was really for all

the analyses, not just Hg, so go ahead

and SLOC.

Also, the EP Toxicity test will be for

the 8 REPA metals, then EP Toxicity.

The analysis # is 261.2A.

Rest of afternoon: Packed samples, filled.

J. Bherme & M. Raddy examined surface

water sites and did flow measurements

Phil L. De 9-23-88

84

9-23-51

1730: Went to Ford Ex with:

SL-5

SL-4 & dep, SL-25

SL-11A

SL-12

1800: J. Barker & K. Davis prepared

bottles for weekend's sampling and

cleaned, inventoried, packed supplies.

2400: Left.

Weather: Sunny & cool (high 60°F), breeze.

~~9-24-51~~

9-23-51

85

9-24-51

0710: Arrived, divided into 2

Sampling teams. J. Shannon & M. Reddy are Shuply background ^{soil samples} sites SL-1

SL-2 and SL-3 with FB-16

and TB-12

J. Barker & K. Davis are going to stand with Site 1 surface water sites.

J. Barker determined standardized buckets using Dec 13/1980

0740: K. Davis collected Oregon pit made described on page 8, lines 17-18.

400 standard: 3.87 → 4.00

700 standard: 6.99 → 7.00

Next, calibrated Hach conductivity meter

Described on page 8, lines 2-14.

1000 µhos/cm standard: 1.005 mS/cm

Hach temp: 9.9°C 11, thermometer: 20.2°C

0840: K. Davis & J. Barker prepared bottles

for SL 13 (0900) and SL 26, dup, (0920).

Note: Due to the lack of water at SL-13,

we moved SL-13 slightly west of what

9-24-51

9-27-52

is shown on map. This location is 15' east of drainage directly north of JP-4 building tank #3.

0900: Pulled SC-13. Did not take picture since we gave the camera to M. Reedy & J. Sharin. Noted dead worms in stagnant water at surface water sampling location. This area is surrounded by cat tails, which hinder the stream flow. Also, there is a heavy sheen on surface of water.

0920: Pulled SC-26 (scheduled time).

0945: Gross parameter measurement.

Water does not filter easily due to coarse floccy material.

temp. 10.3°C

pH: 6.63

sp. conductivity: 0.997 mS/cm (592 μ mhos/cm)

0945-1030: Continued filtering. Very, very slow. Went back to office to try to call J.

Hardison to see if he accidentally went home to George yesterday with crucial

Reedy & Sharin 9-24-52

9-28-52

missing Ruying water part. (This part is still missing even though office was thoroughly inventoried last night.) Not listed in telephone directory, and could not get number.

1045: Headed to Site SC-14, Site 4.

Note: The fraction the bottles say is 1000 although it will be 1100 before sample.

1100: Pulled sample from SC-14. Water too shallow to get good sample, but took anyway. May little flow.

1105: Gross parameter measurements:

temp. 11.9°C

pH: 6.94

sp. conductivity: 0.348 mS/cm (348 μ mhos/cm)

1115: Poured FB-17, field blank.

1130: Headed to SC-15. Prepared bottles.

for SC-15. Pretty good flow, with deep water.

1200: Pulled SC-15 sample (Site 4)

1215: Gross parameter measurements:

temp: 14.3°C

pH: 7.23

sp. conductivity: 0.667 mS/cm (667 μ mhos/cm)

Reedy & Sharin 9-24-52

88

9-24-58

1245: Returned to office. Filtrated, packed, lunch. J. Shuman + Mr. Roddy sampled

(2) background sites SC-11 and SC-2.

1430: Returned to field. Mr. Roddy + J. Shuman went to get SC-3, a background site.

Mr. Davis + J. Beeler went to site 8.

1445: Prepared bottles for SC-17, site 8

(K. Davis + J. Beeler). Mr. Roddy had

drug hole yesterday. We will try to

sample water from this hole - pulled sample at 1450

1505: Gross parameter measurements:

Temp: 14.8°C

pH: 6.98

Sp. Conductivity: 0.459 mS/cm (459 μ mhos/cm)

1520: Arrived at SC-18. N. Roddy dug

hole yesterday, but there is not enough

water to pull sample. Therefore we will

just pull sediments at 1530.

1530: Pulled sediment sample. Very difficult

to dig. Did not take pH/conductivity measurement

since we didn't take water sample.

1545: Filtered SC-19. Decided to pull

duplicate, SC-27 scheduled for

1630.

1600: Pulley SP-19 sample.

9-24-58

89

9-24-58

1615: Took gross parameter measurements

Temp: 18.4°C

pH: 6.37

Sp. Conductivity: 0.281 mS/cm (281 μ mhos/cm)

Water is especially dirty due to string

of sediments in shallow hole.

1625: Took field blank, FB-18.

1630: Scheduled time for SC-27.

1632: Drove back to office. Realized

that there was no way we would

make the 6700 field Ex shipment.

J. Shuman + Mr. Roddy had 2 boxes

prepared containing:

FB-12 - background

FB-16, taken at background

SC-17

SC-22 - no nitrate or phosphate

SC-23 - no nitrate or phosphate

SC-24 - no nitrate or phosphate

SC-25 - no nitrate or phosphate

Went to Field Ex with these.

1700: Continued filtering, metals, packing

1800: J. Shuman + Mr. Roddy left.

2100: K. Davis + J. Beeler went to

Duluth Airport Air Freight reception

area with:

Philip L. De 9-24-58.

90

9-24-58

FB-17 taken at site A

FB-18 taken at site S

TB-13 - for site S

SL-14, site A (no metals yet)

SL-13 & SL-26, dup, site A

SL-15, site A

SL-17, site S

SL-18 (sediment only), site S

SL-19 & dup, SL-27, site S (no metals yet)

SL-1 metals

Also, J. Beiler prepared EP Tox bottles
(3 1 L Amber) to take back to
Atlanta ES lab with her tomorrow.

Weather today: Morning, cloudy, cool, 60°F,
gusts 20-30 MPH. Afternoon sunny, warmer,
60°F, windy still.

2200: Lab.

Robert P. Davis 9-24-58

91

9-25-58

2730: Arrival (J. Beiler & Davis)

J. Beiler packed personal artifacts.

K. Davis' gear things: chain of custody

and gunnily strapped up: office.

2945: K. Davis took J. Beiler to airport

1045: K. Davis returned from airport.

M. Ruddy arrived. Went to site

SL-1 and SL-2 (K. Davis & M. Ruddy)

measurements with the Pyping flow meter.

1310: Returned to office. Placed gun

to Base Security to get into site 3

to pull the sampler. No answer. Note:

Called earlier this morning and yesterday and

also got no answer.

1330: K. Davis & M. Ruddy went to site

4 to resample SL-14 for metals.

Since they were misplaced yesterday, Note:

M. Ruddy also resampled SL-1 and SL-2

metals. While we were there today, since he

occasionally filtered the ones gathered

yesterday with a 5.0 µm filter instead of

a 0.45 µm filter.

1400: K. Davis returned. Continued to pack.

Robert P. Davis 9-24-58

9-24-58

1430: began to rain. (This means the
sampling tomorrow, possibly.)
1500: Mike left. I dump stayed in
pick. Mike found old SC-14, 11th
circuit. K Davis left.
Weather: Sunny, wof in AM, windy,
drizzly & cloudy starting at 1400
and continuing towards 2100

~~Mike~~

Mike J. Davis 9-24-58

93

9-26-58

1200: K. Davis, who is keeping this log,
came in. Mike die to doctor visit.
Mike Pickley & J. Shannon came in
before the AM. and pulled the
following samples:
SC-6 side Z
SC-7 side Z
SC-20 Dip side Z
FB-20, side Z
1300: Mike & J. Shannon went out to
side 3 and pulled
SC-10 & dip SC-28
1530: Called Kathleen Kidd (K. Davis)
Asked if:

- received our large stamp
- we should replace SC-11 and SC-2
which were already sent with 500
filling
- She said she would call back. Also
she verified that there is nothing to
resample BR-7.

Afternoon: K. Davis remained in office and
filled pack
Mike J. Davis 9-26-58

9-20-58

1000: SL-10 and SL-29 filtering

extremely slowly.

1640: Talked to Kathleen Kiedel

Said ~~the~~ metals SL-1 and SL-2 with 45 min filtration and clearly mark "refilled." It is OK to send metals in day or two later.

Check with PM on unfilterable samples. Also, ES Berkeley has not received air cargo shipment yet.

1:50: Fed Exed out the following

SL1, SL2, SL3 ~~to~~ Nitrate & Rad

SL7, SL6, SL29 (DUP) Nitrites site 2

SL8 site 3 (except for ^{no metals} portion unchanged)

SL9 site 3 (no metals)

SL28 site 3 dup

FB-19 site 3

FB-14 site 3

SL1 & SL2-B6 metals, refilled

SL10 site 3 (except for ^{no metals} portion air cargo)

SL6 site 2

SL7 site 2

SL29 Dup, site 2

SL14 site 4 metals

FB-20 site 2

9-20-58

9-20-58

FB-15 site 2

Air Cargoed:

All soils: SL7, SL8, SL9, SL28

SL10, SL6, SL7, SL29

SL-10 site 3. Airbags: EPA 4101, 608, 625

SL8 VOA's

For all pH & conductivity & temp records for samples collected today, refer to "Sampling: Pure Reagents" Field Notebook.

1:50: Mike & Jo Stenwick left

1930: K. Davis left to send air cargo boxes

(2) out.

Weather: Partly cloudy, cool 55°F

Around 1400, a heavy fog fell on airport

which will cause the air cargo to arrive

9-20-58 Since no planes are land of takeoff

tonight.

Note: K. Davis called Berkeley lab and 1400

to see if air cargo shipment arrived. They said

it just arrived but the person I talked

expressed concern over where we are going to

put it.

9-20-58

96

9-27-88

0710: M. Reddy + J. Shemin arrived.
 0730: K. Davis arrived.

M. Reddy + J. Shemin prepared bottles
 while K. Davis placed phone calls to

Bill Hayden + J. Barber.

0830: J. Shemin left to check out of
 motel.

0845: M. Reddy + K. Davis went to Site 3
 SL-10 to pull MATRIX SPIKE

0905: Took sample for Site 4 SL-16
 (M. Kelly, K. Davis). Took pictures.

0910: Gross parameter measurements.

Water is fairly muddy.

temp: 10.9°C

pH: 7.0 (7.7) 6.78

sp. conductivity: 0.455 mS/cm (455 μ S/cm)

0945: Return to office.

M. Reddy filtered, K. Davis packed.

NOTE: TB-16: One vial has a giant
 bubble in it.

1000-1400 M. Reddy + J. Shemin

took 300 random water level measurements.

K. Davis filtered + packed.

MM 2 9-27-88

97

1430 M. Reddy took J. Shemin to

airport. M. Reddy then sampled

DATA-SCC 4 - that E's Bank is
 broken. Took duplicate.

1730: Went to Red Ex. mtg.

TB-16 (site 4)

SL-16 (no mtg)

MATRIX SPIKE

SCC 4 and dup (RESAMPLE)

M. Kelly, K. Davis then packed

up to 2300.

2300: Left.

Weather: Partly cloudy, cool (55°F)

MM 2 9-27-88

MM 2 9-27-88

9/8

9-23-55

0900: K Davis arrived. Continued

packing. Preparation SL-16 methyl

for 1. Fed Ex. Preparation all

instrumentation for Fed Ex.

0745: Called M. Sudl Mains about

disposal of trash. Got Captain

Nickerson

0750: J Mains called back. T's sandy

men + truck

0800: M Reddy arrived. Continued packing.

0845: K Davis went to Fed Ex with

(2) HAND's + OVA — U.S. Army Lab

Biosensor experiment — T. Minter

Explosion — 1st. Antenna

Gorge comb + bellows — HAZCO

SL-16 methyls — ER Berkeley

0910: Returned. Loaded boxes for

air cargo. Took leave

0930: Returned. Loaded seats into vans.

Went to A.P.

1040: Left for Knoxville.

Philip A. De 9-28-58

Q.2.6 Notebook 6, Sampling Purge Records

This notebook contains purge records for the monitoring wells. All wells were purged within the prior 24 hours of being sampled. The first entry is 7 September 1988 and the last entry is 28 September 1988. One hundred nineteen pages were used. The pages after page 61 are not numbered. Entries were made by Peter Reimersma and Mike Roddy; the pages are not signed.

DULUTH ANGE

SAMPLING

FORGE RECORDS


PETER RIEMERSMA

MIKE RODDY

DISTANCES FROM SIDE STAKES FOR CROSS-SECTIONING

Roadway of any Width. Side Slopes 1 1/2 to 1.

In the figure below opposite 7 under "Cut or Fill" and under 3 read 11.0, the distance out from the side stake at left. Also, opposite 11 under "Cut or Fill" and under .1 read 16.7, the distance out from the side stake at right.




Cut or Fill	Distance out from Side or Shoulder Stake										Cut or Fill
	0	.1	.2	.3	.4	.5	.6	.7	.8	.9	
0	0.0	0.2	0.3	0.5	0.6	0.8	0.9	1.1	1.2	1.4	0
1	1.5	1.7	1.8	2.0	2.1	2.3	2.4	2.6	2.7	2.9	1
2	3.0	3.2	3.3	3.5	3.6	3.8	3.9	4.1	4.2	4.4	2
3	4.5	4.7	4.8	5.0	5.1	5.3	5.4	5.6	5.7	5.9	3
4	6.0	6.2	6.3	6.5	6.6	6.8	6.9	7.1	7.2	7.4	4
5	7.5	7.7	7.8	8.0	8.1	8.3	8.4	8.6	8.7	8.9	5
6	9.0	9.2	9.3	9.5	9.6	9.8	9.9	10.1	10.2	10.4	6
7	10.5	10.7	10.8	11.0	11.1	11.3	11.4	11.6	11.7	11.9	7
8	12.0	12.2	12.3	12.5	12.6	12.8	12.9	13.1	13.2	13.4	8
9	13.5	13.7	13.8	14.0	14.1	14.3	14.4	14.6	14.7	14.9	9
10	15.0	15.2	15.3	15.5	15.6	15.8	15.9	16.1	16.2	16.4	10
11	16.5	16.7	16.8	17.0	17.1	17.3	17.4	17.6	17.7	17.9	11
12	18.0	18.2	18.3	18.5	18.6	18.8	18.9	19.1	19.2	19.4	12
13	19.5	19.7	19.8	20.0	20.1	20.3	20.4	20.6	20.7	20.9	13
14	21.0	21.2	21.3	21.5	21.6	21.8	21.9	22.1	22.2	22.4	14
15	22.5	22.7	22.8	23.0	23.1	23.3	23.4	23.6	23.7	23.9	15
16	24.0	24.2	24.3	24.5	24.6	24.8	24.9	25.1	25.2	25.4	16
17	25.5	25.7	25.8	26.0	26.1	26.3	26.4	26.6	26.7	26.9	17
18	27.0	27.2	27.3	27.5	27.6	27.8	27.9	28.1	28.2	28.4	18
19	28.5	28.7	28.8	29.0	29.1	29.3	29.4	29.6	29.7	29.9	19
20	30.0	30.2	30.3	30.5	30.6	30.8	30.9	31.1	31.2	31.4	20
21	31.5	31.7	31.8	32.0	32.1	32.3	32.4	32.6	32.7	32.9	21
22	33.0	33.2	33.3	33.5	33.6	33.8	33.9	34.1	34.2	34.4	22
23	34.5	34.7	34.8	35.0	35.1	35.3	35.4	35.6	35.7	35.9	23
24	36.0	36.2	36.3	36.5	36.6	36.8	36.9	37.1	37.2	37.4	24
25	37.5	37.7	37.8	38.0	38.1	38.3	38.4	38.6	38.7	38.9	25
26	39.0	39.2	39.3	39.5	39.6	39.8	39.9	40.1	40.2	40.4	26
27	40.5	40.7	40.8	41.0	41.1	41.3	41.4	41.6	41.7	41.9	27
28	42.0	42.2	42.3	42.5	42.6	42.8	42.9	43.1	43.2	43.4	28
29	43.5	43.7	43.8	44.0	44.1	44.3	44.4	44.6	44.7	44.9	29
30	45.0	45.2	45.3	45.5	45.6	45.8	45.9	46.1	46.2	46.4	30
31	46.5	46.7	46.8	47.0	47.1	47.3	47.4	47.6	47.7	47.9	31
32	48.0	48.2	48.3	48.5	48.6	48.8	48.9	49.1	49.2	49.4	32
33	49.5	49.7	49.8	50.0	50.1	50.3	50.4	50.6	50.7	50.9	33
34	51.0	51.2	51.3	51.5	51.6	51.8	51.9	52.1	52.2	52.4	34
35	52.5	52.7	52.8	53.0	53.1	53.3	53.4	53.6	53.7	53.9	35
36	54.0	54.2	54.3	54.5	54.6	54.8	54.9	55.1	55.2	55.4	36
37	55.5	55.7	55.8	56.0	56.1	56.3	56.4	56.6	56.7	56.9	37
38	57.0	57.2	57.3	57.5	57.6	57.8	57.9	58.1	58.2	58.4	38
39	58.5	58.7	58.8	59.0	59.1	59.3	59.4	59.6	59.7	59.9	39
40	60.0	60.2	60.3	60.5	60.6	60.8	60.9	61.1	61.2	61.4	40

For Curve Tables see end of book.

KEUFFEL & ESSER CO.


The paper in this book is made of 50% high grade rag stock with a WATER RESISTING surface sizing.

KEUFFEL & ESSER CO.




[illegible][illegible]

V



LV



Stabilization of purging Parameters

pH $\pm .1$
 Conductivity ± 10 microhmhos
 Temperature $\pm 1^{\circ}\text{C}$

VI

9/7/88

7:08 Arrived at base, cool weather with blue sky
 ES Personnel

Mike Roddy
 Peter Riemersma
 Sharon Schultz
 John O'Brien
 Jo Anna Beeley

PLAN Mike Roddy and Peter Riemersma
 are going to start purging back
 ground

Calibrate Meters

- HNO meter calibrated Asset NO. 500791
 Probe NO. 500018 Span setting 4.72
 Calibrated by Peter Riemersma

- Calibrated Cole Palmer conductivity meter
 Model 9977-99 series no. 8020 80116
 Standard 1000 microhmhos 960 - 1000
 Standard 10,000 microhmhos 9800 - 10,000

- Calibrate ORION Research Model 5A 230 pH meter
 to 7.0 pH standard

2

9/7/88

adjust 7.06 to 7.00 with calibration

Knob 9.76

adjust 9.2 to 10.0 with slope knob

8-10:53 Prepared equipment for sampling

Went to Base Civil Engineering to pick

up supplies, picked up purging supplies

Plan to do BG MW 43 SE of FAA tower

BG MW 42 West of Site 3

BG MW 32 at Site 3

Load up van

Arrive at Background MW 43

HMV reading of borehole 3.5 ppm

Background 3.5 ppm

- water level reading to top of

Casing

13.12 TOC

- Bottom of well, no apparent

silt on bottom

- Well volume calculation

22.28 - 13.12 = 9.16 water depth in well

correction $9.16 \times 1.63 = 14.93$ gallons = 1 volume

9.16 x 1.63 = 14.93 gallons = 1 volume

Pump used Keck Geophysical Instruments

Sampling Pump 81

Serial No 103

Model Sp 81A

.166' 9/7/88

3

7.16 14.93

H²H

1.63

3

2748

549.60

916.00

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

1493.06

8.11.43 Pump on, pump at surface water level

is being lowered as water level declines

8.11.45 Pump off water level at 18.5 TOC

Water sample taken at 11.44 at 2 1/2 gallons purged

pH 7.11 micromhos/cm

Temperature 12.8 °C

conductivity 1075

Pump on 1150.86

Pump off 1150.40 1 gal/bn removed

12.12 Switch pH probe and recalibrate

calibrate to 7.0 adjust from 6.94 to 7.0

calibrate to 10.0 adjust from 9.74 to 10.0

12.20 Pump on water level at 12.80 TOC

water sample taken for measurements - clear water

12.23 Pump off water level 16.5'

pH 7.16

Temperature 14.9 °C

conductivity 925

12.38 Change pH meter 6.77 to 7.0

Use Serial 3191 adjust 11.89 to 10:00

A

9/7/88

1248	Pump on	water level at 13.0
1352	Water sample,	Pump off water level at 16.5
	conductivity	990
	temperature	13.6
	SAS	pH 6.90
	ES Personnel working on this	
	Mike Roddy	
	Peter Rumsma	
	with instruction by Sharon Schultzy	
1320	Pump on	water level 13.16
1323	Pump off	water level 16.5 sample taken
	slight cloudiness	
	temp	13.9 °C
	conductivity	960
	pH	6.80
1332	Pump on	water level 14.5 13.5
	water sample taken after 1 gallon discharge	
	total water withdrawn 3 gallons	
	temp	13.2 °C
	conductivity	1050
	pH	6.70
1355	Pump on	water level 13.4
1358	Pump off	water level 16.5
	temp	14.2
	conductivity	1150
	pH	6.52

9/7/88

5

1403 Resal brake adjust 1125 to 1000

Conductivity meter

1406 Pump on water level 13.6 13.50
 1407 Pump off water level 16.5 4 gallons have
 been pumped

temp 13.6 16.5

conduct 960 1040

pH 6.63

Pump on water level 13.6

Pump off water level 16.5 Parged 5 gallons

temp 12.7

conduct 1060

pH 6.73 6.69

Take pump out of Background MW 43

Took Mike to town to pay ticket

Went to copy well logs at Bear

Civil Engineering, Went to try to find
 wellers at site to get keys.

TIME

1724 Arrive at BG MW 42 billions of mosquitoes

Background 3.5 ppm

Borehole HNU 3.5 ppm

Initial water level before pumping to top of

casing 6.08 TOC

Team Members: Peter Rumsma & Mike Roddy

9/7/88

6

9/7/88

Bottom of well 14.6

approx. 3-13

5:35 Took out one bailer full

water level at 702 no. 10 using pressure visible

well volume = $8.52 \times 1.63 = 13.9$

Well volume = 4.17 gallons

5:40 PM water level 6.66 before bailer

sample taken

after bailer samples taken 10.52 TOC

approximately 2 gallons of water withdrawn

conductivity

temp

pH

water looks to very slightly cloudy but

otherwise clear

6:16 water level before bailer

water level after bailer

total water withdrawn

water quality: very slightly cloudy

conductivity

temp

pH

No insect repellent used, blood loss

sustained with severe mental anguish

9/7/88 Peter E Ramerman

9/7/88

7

6:45 water level before

water level after

Total water withdrawn 3.0 gallons

water quality: very slightly cloudy

conductivity

temp

pH

6:55 water level before

water level after

Total water withdrawn

water quality: same as above

conductivity

temperature

pH

7:07 water level before

water level after

Total water withdrawn

water quality: same as above

conductivity

temp

pH

Leads 1 lb

Decon bailer used for NW 42

9/7/88 Peter E Ramerman

9/7/88

SUMMARY

- 1) PURGED BACKGROUND MW43 FOR 2 hrs 54 minutes for removal of 3 well volumes (5 gallons)
- 2) PURGED BACKGROUND MW42 FOR 1 hour 43 minutes for removal of 3 well volumes (~4.3 gallons)
Conductivity, pH, and Temperature had stabilized as defined on page VI in front of this book
- 3) We decided to use bailer to purge due to slow recharge and easier ability to discern barrier between wells than the pump.
- 4) Mike Roddy and Peter Riemersma received instruction in purging parameters from Sharon Schulte. They worked on MW42 as a team.

9/8/88

PLAN FOR THE DAY

Peter Riemersma and Mike Roddy

will purge background MW32 at Site 3 and then purge 4-5 wells at Site 8

7:08 AM Arrive at office

Calibrate Cole Palmer conductivity meter

Model adjust 980mm to 1000

adjust 9950mm to 10,000

HNU ASSET NO. 500791 calibrated per work plan

Calibrate Orion Research Model 5A 230

pH meter

adjust 6.97 to 7.00

adjust 9.73 to 10.00

Decantimeter water-level indicator

Pick up bailer discontinued 9/6/88

Prepare to move to BGMW 32

Mike Roddy and Peter Riemersma attended

Health and Safety Meeting

8:06 Have to go get key to MW from Drillers at Site 2

8:30 Arrive at MW 32, Site 3

HNU reading background 38 ppm

HNU reading of casing hole 38 ppm

8:38 Initial water level before bailing 9.88'

10

9/8/88

856	859	859	904	906	
btm of the well at 19.8'	total well water 19.72-9.85 = 9.87 feet	l well volume = $9.87 \times 1.63 = 1.60$ gallons	3 well volumes = 13.48 gallons	can screened 7-17' can drop water	down to 14.5'
took 4 builer full out	water level after bailing 10.95'	total water withdrawn 1 gallon	water quality: poor, very cloudy, no odor	conductance 7,000 m	temperature 10.1°C
				pH 7.25	
				Note: Cannot see btm of 150 ml beaker through water sample, note silt at btm of cup	
				initial water level 9.52' before	
				water level after bailing 11.5'	
				water quality cloudy, same as above	
				total water withdrawn 2 gallons	
				conductance 2000	
				temp 9.6°C	
				pH 7.50	
				Note: sediment on bottom of cup	

9/8/88

11

923	924				
initial water lvl	9.90'				
final water level	11.0				
water quality	same as before				
total water withdrawn	3.25				
conductance	2000				
temp	9.9°C				
pH	7.34				
water 540' cloudy w/ sediment					
928	929				
initial wtr level	10.20				
932	final wtr lvl	11.71			
water quality	same as above				
total water withdrawn	4.25 gallons				
conductance	2000				
temp	9.5°C				
pH	7.31				
939					
initial wtr level	10.20				
final wtr	11.20				
water quality	same as above				
total water withdrawn	5 gallons				
conductance	2000				
temp	8.9				
pH	7.37				
949	lower site				
950	Arrive at office to discuss				

12

9/8/88

bailer and water level indicator per work plan procedure	
1015	Arrive at HW 15 S.H.S
	HW reading of borehole after recalibration of zero 0 ppm
1018	initial water level before pumping 10.22 TOC
	Final H ₂ O level
	total water withdrawn
	btm of well 17.40
	1 well volume = $7.18 \times 163 = 1.170$ gallons
	3 well vol = 3.51 gallons
1024	final H ₂ O level 10.24 (water quickly recharged)
	total water withdrawn 1 gallon
	water quality: cloudy, some suspended sed.
	conductance 320
	temp 11.9
	pH 6.97
	Water cloudy, unable to see bottom of 150 mL
	vial some sediment at bottom
1035	initial water level 10.24
1037	final water level 10.32
	water quality some as before
	total water withdrawn 2 gallons
	conductivity 320
	temp 11.7

9/8/88

13

	pH 7.698
1042	initial H ₂ O L 10.24
1044	final H ₂ O L 10.32
	water quality same as before
	total H ₂ O withdrawn 3.5 gallons
	conductivity 320
	temp 12.0 °C
	pH 6.97
1049	initial H ₂ O L 10.24
1052	final H ₂ O L 10.28
	water quality
	total H ₂ O withdrawn
	conductivity 350
	temp 11.6 °C
	pH 6.99
	Note Very rapid recharge - appears to reach equilibrium height almost instantaneously
1100	Back to office to decom- bailer and water level indicator
1119	Arrived HW 14 (Deep)
	HW of borehole 0 ppm
1121	water level before pumping 9.50 TOC
	btm of well 12.96, 3 ft feel at btm

14

9/8/88

1 well volume = $33.4 \times 1.63 = 5.44$ gallons

3 well volume = 16.33 gallons

Start bailing well back - 4 gallons

out

final H₂O level 24.30

water quality slightly cloudy - clear

total H₂O withdrawn 4 gallons

conductivity 190

pH 8.35

temperature 9.6

Note Water looks clear with no apparent sediment. As always we are using a dedicated bailer line

1159 initial water level 21.12

1211 final water level 30.48

water - water quality cloudy, more cloudy

total H₂O withdrawn 7.0 gallons

conductivity 200

pH 8.84

temp 9.7

initial water level 27.50

final water level 33.76

water quality cloudy

total amt. water withdrawn 10 gal

9/8/88

15

conductivity 190

pH 8.62

temp 10.0

1241 leave for lunch, wait for well to recharge. Back from lunch

1330 initial H₂O level 23.501339 final H₂O level 28.06

water quality slightly cloudy

total H₂O withdrawn 11.5 gallons

conductance 185

pH 8.60

temp 9.8

Note Can barely see bottom of 15' pipe with

with water in it, no noticeable odor

1353 initial H₂O level 24.7814102 final H₂O level 31.82

water quality same as above

total H₂O withdrawn 19.04 gallons

conductance 190

pH 8.62

temp 10.0°C

initial H₂O 30.44final H₂O

water quality

total H₂O withdrawn

16

9/8/86

1408-1451 line to bailer fell off and slope water indicator, which was below bauler became stuck next to bailer at 37' we were tried to lift the slope indicator up. We tried to use a slug to bump the stuck bailer loose but were unable to do anything but push the bailer further down the well. Upon further attempts to unloosen it, the water indicator broke off at 5' and remains in the well, so, in summary, a 3 foot teflon bailer and the bottom 5' of the slope indicator remain in the well. The indicator contains plastic and metal

1514 Went to office and picked up new bailer and water level measuring device

MOC to MW17

1526 HNU of borehole 0 ppm
 initial water level before bailing 8.32
 depth to btm. of well 14.76
 well volume = $6.44 \times 163 = 1.05$ gallons
 well volume = 3.17 gallons

1533 Fin. final H₂O level 10.88
 water quality cloudy
 total amt of water withdrawn 1.5 gallon

17

9/8/86

conductivity 8550 S40
 pH 7.18
 Temp 10.1°C

Water looks cloudy with lots of sediment suspended
 1539 initial water level 9.08
 1541 final water level 10.95

water quality - slightly somewhat cloudy

total amt water withdrawn 2.5 gal
 conductivity 575
 pH 6.88
 Temp 9.4°C

Water has small amount of clay sediment at the bottom

1553 initial water level 8.83
 1556 final water level 10.78

water quality slightly cloudy
 total amt of water withdrawn 3.25

conductivity 610

pH 7.13

Temp 9.4°C

1606 initial H₂O level 8.78

1609 final H₂O level 10.82

water quality slightly cloudy

total amt of water withdrawn 4.5 gallon

18

9/8/88

conductivity 610

pH 7.15

temp 9.4

Finish purging MW 17

Recontaminated 4 barrels, filter setup and water level indicator per

work plan

Go to bring seat to airport

Leave office

SUMMARY

PURGE BGHW32

PURGE Site 8 MW 15

PURGE Site 8 MW 14 ~ 3 hours

PURGE Site 8 MW 17 ~ 1 hour

Dropped bailer down MW 14 and broke lower 5' of line of water indicator off, also remaining in well

9/9/88

19

7:01 AM arrive at office

Calibrate Cole - Palmer Conductivity meter model 1484-10.

Adjust 990 mhos to 1000

Adjust 9600 mhos to 10000

Calibrate Orion Research model SA 230

pH meter & thermometer

read 7.00 for 7.00 solution

Adjust 9.98 to 10.00

Calibrate temp reading

18.5 mercury thermometer read 18.504

Temperature readout on Orion Research model

SA 230

HNU Model Assett 50091 calibrated to

work plan specifications

7:39 Mike Roddy is going to scope out

the surface water and soil sampling sites

with Bob McLeod, Peter Klemm

is going to help with groundwater

sampling

7:39-9:16 Help prepare equipment for sampling

over

20

9/9/88

9:00 Peter Remington 15 at Site 8 MW 1.6
to pump the well.

MW of cinder hole with cap removed
previously by drillers.

9:24 depth to top of water before bailing 8.25' to
total depth of well = 32.6'

well volume = $24.39 \times 1.63 = 3.98$ gallons

3 well volumes = 11.93 gallons

9:31 Final H₂O level 21.35'
total water withdrawn 3.5 gallons
water quality slightly cloudy
conductance 350

pH 9.22
temperature 8.4°C

Note can see bottom of 150 ml vial with
water in it

Slow recharge 7.77 initial H₂O level 18.83
9:50 final H₂O level 21.40

total water withdrawn 4.5 gallons

water quality same as above
conductance 410

pH 8.79
temperature 8.20

Don't know if this is a good sample or not

32-10-22

9/9/88

21

9:53 initial H₂O level 20.41

10:01 final H₂O level 23.31

total water withdrawn 5.5 gal
water quality same as above

conductance 410

pH 8.14

temp 8.9

10:10 initial H₂O level 21.58

10:15 final H₂O level 23.38

total water withdrawn 6.5 gallons

water quality same as above

conductance 410

pH 8.21

temp 8.6°C

Purging complete at 6.5 gallons as
all parameters have stabilized and

well reaching slowly. 6.5 gallons

is about 1/2 well volume

10:36 leave site MW 1.6

11:22 Arrive at MW 23 Site 4

level indicator, try to get key

11:29 Arrive at MW 23 Site 4

Had to skip previous MW at Site 8

because the keys were unavailable

22

9/7/88

the bot monitor well lid was removed
by Shullens = reading by HANCOFF-
the barometer was 0.1 ppm

11:31 initial water level before 18.59

total well depth (soft botm) 36.00

final water level

total water

l well volume is $27.41 \times .163 = 4.47$

3 well volume is 13.40

11:48 final water level 12.33

total water withdrawn 5 gallons

conductivity

pH 7.46

temp 11.2

water quality: slightly cloudy

initial H₂O level 9.63final H₂O level 12.75

water quality: very slightly cloudy

total water withdrawn 9.5

pH 7.42

temp 10.5

conductivity 1310

23

9/9/88

12:08 initial H₂O level 9.0612:17 final H₂O level 12.02

water quality: clear 14.5 gallons

total water withdrawn 14.5 gallons

pH 7.44

temp 10.8

conductivity 1310

12:23 leave site 4 MW 23 Pump complete

12:23 - 1330 lunch and decommission H₂O indicator

13:31 GNB-C, previous work

Peter R. and H. K. R. on it

backhoe reading 0.1 ppm

13:36 initial reading before bailing 7.76

dim of well

soft at 14.50

final reading

water quality

total water withdrawn

1 well volume = $11.71 \times .163 = 1.913$ gal

3 well volume = 5.74 gallons

1:44 final water reading 8.78

water quality: slightly cloudy

total water withdrawn 1 gallon

pH 7.10

conductivity 910

temp 15.0

24

9/4/88

1353 initial H₂O reading 8.00
 1359 final H₂O reading 8.92
 water quality cloudy
 total amt water withdrawn 3.0 gallon
 conductivity 980
 temp 14.8
 pH 7.04

1708 1353 initial H₂O reading 8.00' 8.15
 1359 final H₂O reading 8.92' 9.08
 water quality clear to cloudy later
 total amt water withdrawn 3.0 gallon
 conductivity 990
 temp 15.2
 pH 7.08

Purge complete Go to office
 Decanned boiler and water barrel
 indicators per work plan

1433 Arrived at MW GW-8B
 HNU of borehole Oppin

1436 initial water level 6.83
 1518 final water level 7.62
 water quality so slightly cloudy
 total amt H₂O withdrawn 2.5 gallons

9/4/88

25

conductivity 690 700
 temp 15.0
 pit 7.34
 bottom of well (21.83) soft feel at bottom
 1 well volume = 15 x 1.63 = 2.49 gallons
 3 well volumes = 7.5 x 7.48 gallons
 Slow purging results in inability to get below
 past top of screen. We have only about
 a foot of water to bail from.
 Peter Klevenstein Auked to John Handman
 who said like p. wrens well had two inch
 greens. Bob McLeod explained how to
 do stream flow measurement
 action ka-dim?
 stream 1' 1' 1' 1' 1' depth 1.6 to the water depth

1540 initial H₂O 6.95
 final H₂O
 water quality
 total amt H₂O withdrawn
 conductivity
 temp
 pH

1545 Abandon purge of GW-8B
 due to slow recharge and inability

26

9/9/88

to get barrel before top of screen

1613

Purged at Site 4 MW 22

H₂O of borehole 0 ppm; windy

top of water before barrel 9.59g

bottom of well (soft) 36.45

well volume 26.91 x .163 = 4.39

well volume 13.16 gallons

1628

final water level 25.25

water quality cloudy

total water withdrawn 5 gallons

conductivity 1270

pH 7.64

temperature 8.5°C

1643

initial water level 15.00

1657

final water level 26.11

water quality cloudy

total water withdrawn 18 gallons

conductivity 1250

pH 7.60

temperature 9.0

27

9/9/88

1722 initial water level 14.33

1731 final water level 25.02

water quality slightly cloudy

total water withdrawn 14

conductivity 1410 1240

pH 7.72

temperature 8.5°C

Purge complete

1731-1844 Decom 5 barrels

been water level instructions

clean out soon

we checked all barrels with H₂O

and wrapped them up in aluminum

foil

1901 left office

Summary

Purged MW 16 Site 8

Purged MW 23 Site 4

Purged GW 8-C

Attempted to purge GW-8-B

28

9/10/92

7:00 AM arrive on site

Calibrate Cole-Palmer conductivity meter
model 1484-10

Peter Kummerow and Mike Roidy to Perry Site

Find Site 8 wells today.

Calibrate Orion glass electrode model SA230

pH meter & thermometer

Serial # 3191

Read 18.0 on thermometer and

18.0 on mercury thermometer

Adjust 6.98 to 10

Adjust pH 6.94 to 7.00

Calibrate Cole-Palmer Model 1484-10

Serial No. 7092005

with 1000 std adjust 1550 to 1000

with 10,000 adjust 9050 to 10,000

Calibrate HNV to standard isobutyl

Adjust 50071 probe to span setting 4.74

739

Arrive at HiW 21 Site 4

HNV reading of casing hole 9 ppm

bairing and water level indicators were

observed near the end of yesterday.

7:46

initial water level before boring 758

depth to bottom of well (solid) 22.58

9/10/92

29

1 well volume is $15 \times 163 = 2.45$ gallons

3 well volumes is 7.34 gallons

initial H₂O level same as at 7:467:56 final H₂O level 9.48

water quality very cloudy

total water with drawn 3 gallons

conductivity 720,000 835

pH 8.58

temp 9.8

Water very cloudy with significant sediment

8:01 initial water level 7.99

8:06 final water level 10.25

water quality cloudy, better than before

total water with drawn 5 gallons

conductivity 770

pH 7.16

temp 12.1

Good Recharge in this well

8:16

initial H₂O level 7.92

8:21

final H₂O level 10.11

water quality cloudy to slightly cloudy

total water with drawn 7.5 gallons

conductivity 780

pH 7.24

30

9/10/88

temp	13.0	
8.31	initial H ₂ O level	7.98
8.35	final H ₂ O level	9.74
	water quality	slightly cloudy
	total water withdrawn	9 gallons
	conductivity	780
	temperature	13.7
	pH	7.17
8.42	Lease Site	
	Decon boiler and water level under	
	Boiler Decon Procedure always used	
	SDAP	
	WATER WASH/ELINE	
	HNO ₃	
	HALC-RINSE	
	Method	
	HALC-Rinse thorough	
	Checks with H ₂ NH	
9.09	ARRIVE at MNV 24 Site 4 in Park Farm fence	
	borehole H ₂ N reading	0.99m
9.16	initial water level before boring	5.48
	depth to bottom of well (Chard)	37.5
	1 well volume	32.02 x 163 = 5.212
	3 well volume =	15.65 gallons

31

9/10/88

9.2.6	final H ₂ O level reading	16.00
	water quality	clear
	total water withdrawn	5 gallons
	conductivity	600
	temp	10.3
	pH	8.32
9.2.8	initial water level	14.01
9.3.6	final water level	18.67
	water quality	slightly cloudy
	total water withdrawn	9.5
	conductivity	750
	temp	9.3
	pH	8.46
	Good recharge	
9.4.5	initial water level	17.29
9.5.2	final water level	15.35
	water quality	slightly cloudy
	total water withdrawn	12.0
	conductivity	790
	temp	9.0
	pH	8.61

32

9/10/88

10.00	initial water level	9.57
10.07	final water level	13.71
	water quality	slightly cloudy
	total water withdrawn	15.145 gallons
	conductivity	790
	temperature	10.0
	pH	8.80
10.12	initial water level	13.71
10.14	final water level	14.52
	water quality	almost clear
	total water withdrawn	17.0
	conductivity	840
	temperature	8.6
	pH	8.70
10.18	initial water level	14.32
10.23	final water level	16.21
	water quality	almost clear
	total water withdrawn	18.5
	conductivity	760
	temp	8.8
	pH	8.8 8.66
Note heavy sediment volume probably related to conductivity 10.		

9/10/88

33

10.26	initial water level	15.30
10.30	final water level	17.51
	water quality	slightly cloudy
	total water withdrawn	19.5
	conductivity	770
	temp	8.7
	pH	8.72
10.41	leave site: clean 1" bailer and water level	
	Arrive at GW-88	Site 8
10.43	initial water level before	7.07
	total depth to bottom of well	21.83
from page 25 3 well volumes is 7.48 gallons		
We now have 1 inch bailer to use down the		
well since 2 inch bailer was unable to		
go below top of screen		
11.18	Final Ho. level	9.85
	water quality	very cloudy
	total volume removed	2.5 gallons
	bailer added to purge with 1" bailer	
	temp	11.3
	conduct	630
	pH	7.98

34

9/10/88

1122	initial H ₂ O level	7.55
1129	Final H ₂ O level	9.03
	water quality	very cloudy, much sediment
	total water withdrawn	4 g
	conductance	670
	temp	11.9
	pH	7.57
1130	initial H ₂ O level	9.01
1143	final H ₂ O level	9.16
	water quality	cloudy
	total water withdrawn	6 gallons
	conductance	680
	temp	12.1
	pH	7.63
1144	initial H ₂ O level	9.14
1154	Final H ₂ O level	9.27
	water quality	cloudy
	total water withdrawn	7.75
	conductance	640
	temp	11.5
	pH	7.77
Note heavy sediment volume probably interfered with consistent conductivity measurements		

35

9/10/88

1201	leave site	
1215	RRS 13:15 lunch	
1321	Arrive at GW 8A Site B	
	time remaining off base hole = 0.72	
1323	initial reading before basing	6.70
	begin of well (hard)	15.17
	level volume = 8.47 x 1.63 =	11.38
	3 well volumes =	41.9
1335	final H ₂ O level	8.75
	water quality	cloudy
	total water withdrawn	11.5 gallons
	conductivity	960
	temp	12.5
	pH	7.39
1336	initial H ₂ O level	8.36
1344	final H ₂ O level	10.12
	water quality	cloudy
	total water withdrawn	3.5
	conductivity	1010
	temp	11.6
	pH	7.35

36

9/10/88

1349	initial H ₂ O level	9.02	
1353	final H ₂ O level	9.92	
	water quality	cloudy	
	total water withdrawn	4.5	gallons
	conductance	1010	
	pH	7.41	
	temperature	11.4	
	Good Recharge		
1357	Lane Site		
	Acorn Under and	water level indicator	
1423	Harvie Site	GW4-C Site 4	
1429	water level before boiling	11.01	
	bottom of well (Soft)	22.66	
	well volume = 11.65 x .163	= 1.9	gallons
	well volume	= 5.7	gallons
1442	final H ₂ O level	11.26	
	water quality		
	total water withdrawn	1.5	gal
	conductance	1120	
	pH	7.94	
	temp	11.1	

37

9/10/88

1444	initial H ₂ O level	11.15	
1457	final H ₂ O level	11.27	
	water quality	cloudy	
	total water removed	3.5	
	conductance	1120	
	temp	10.1	
	pH	7.86	
1550	initial H ₂ O level	11.18	
1510	final H ₂ O level	11.36	
	water quality	very cloudy	
	total water removed	5	gallons
	conduct	1110	
	temp	9.8	
	pH	7.79	
1512	initial H ₂ O level	11.21	
1519	final H ₂ O level	11.30	
	water quality		
	total water removed		
	conduct	1100	
	temp	9.4	
	pH	7.74	

Peter R. goes to van around for John

Hardeman Mike Robby continues purging.

9/18/88

1600 arrive at MW 9 - site 4
 HNU Kicken & baseline O₂ -
 Mike Raddy top of water before bubbling 7.13
 bottom of well 15.60 → bottom hand
 1 week volume = $8.47 \times 1.63 = 13.8$ gallons
 3 week volume = 41.4 gallons
 (spec final time for bubbling)

water level initial	total water withdrawn	water quality	pH	conductance
7.13/12.20	1 1/2 gallons	Very cloudy	7.04	16.10/14.0
8.34/12.08	2 1/2 "	Very cloudy	7.04	16.45/16.49
8.37/11.83	3 1/2 "	Very cloudy	7.05	17.16/17.20
8.76/11.92	4 1/4 "	Very cloudy	6.95	17.41/17.44

note: Slow recharge

17:50 leave site

17:58 - 18:25 Decant into field gear

18:25 - 18:45 Discus what needs to be done

18:45 leave office

Summary

Purged MW 21, MW 24, Site 4
 GW 4-6, MW 9

GW-8B, GW-8A, Site 8

9/11/88

10:00 Peter Riemersma and Mike Raddy
 arrive at site to purge additional
 wells. Windy clear blue sky.
 JoAnna and Kim arrived earlier
 to do boiler rinses.

Callibrate Cole Palmer Conductivity
 meter Model 1484-10 SN 7092005
 adjust 10.75 to 10.00
 adjust 9600 to 10000

Callibrate Orion Research model SA 230
 temperature calibrated with mercury thermometer.

Adjust pH 6.90 to 7.00
 pH 9.01 to 10.00

Callibrate HNU 5000791 per work plan
 same as yesterday's calibration procedure

40

9/11/88

10:25 arrive at GW40

HNU reading at borehole \rightarrow 0 ppm

top of water before bail 10.67

bottom of well 26.08 surrounding soil1 well Volume = 1541 \times 163 = 2.513 well Volumes = 251 \times 3 = 7.53

Note well has apparently suffered some frost heave

water level initial/finish	total water withdram	PH	bailing		Temp °C	Conductance mhos
			start time	finish time		
10.67/11.75	2 gal	6.49	10:36/10:54		9.2 °C	750
11.32/11.67	4 gal	6.46	10:57/11:08		8.3	850
10.98/11.58	6 gal	6.30	11:17/11:30		8.5	880
10.83/11.52	7.5 gal	6.48	11:40/11:51		9.2	890
11.36/11.54	8 gal	6.70	11:56/12:01		8.8	900

note: good recharge

finish 12:04

lead site 12:06

Dean Sampling Apparatus 12:10-12:23

9/11/88

41

12:29 arrive at GW40B

HNU reading at well \rightarrow 0 ppm

top of water before bailing - 6.21

bottom of well - 23.29 much bottom1 well Volume = 1708 \times 0.163 = 2.783 well Volume = 2.78 \times 3 = 8.34 gallons

12:41 - 13:50 help get Silver Van unstuck

water level initial/finish	total water withdram	water quality	PH	bailing time		Temp °C	Conductance
				start	finish		
6.21/12.75	3 gal	very cloudy	8.12	13:54/14:12		11.2	370
11.16/12.33	5 gal	very cloudy	8.38	14:16/14:28		10.4	380
10.58/11.55	7 gal	very cloudy	8.18	14:33/14:43		9.8	380
8.75/9.16	8 gal	very cloudy	8.06	14:49/14:58		9.7	390

finish 14:59

leave site 15:05

bunch 15:18

16:09 back from lunch

equipment 16:24 decon samples

A2

9/11/88

10:32

arrive at MW-11

HNU reading at well → 9:00 pm

initial water level reading before boiling 8.19
 bottom of well 16.68 → hand bottom

well volume = $8.49 \times 0.163 = 1.38$

3 well volumes = $1.38 \times 3 = 4.15$

note PVC well casing

water level initial/final	total water with down	water quality	pH	Boiling start/finish time		Temp °C	conductance mhos
				start	finish		
10 8.19/10.16	1 1/2 gal	cloudy	7.35	16:42	16:49	13.0	640
10 10.10/12.31	2 3/4 gal	cloudy	7.17	16:52	16:58	11.9	640
11 11.33/13.08	3 3/4 gal	cloudy	7.36	17:27	17:30	11.9	640
11 12.08/13.67	4 1/4 gal	cloudy	7.25	17:53	17:56	11.6	630

finish 17:59

18:03 leave site

Decon Sampling Equipment 18:07 - 18:17

9/11/88

A3

18:18 arrive at GW4-A

HNU

initial water level reading before boiling 5.36

bottom of well 21.00 muddy bottom

well volume = $15.64 \times 0.163 = 2.55$

3 well volumes = $2.55 \times 3 = 7.65$

water level initial/final	total water with down	water quality	pH	Boiling time start/finish		Temp °C	conductance
				start	finish		
5.36/5.70	3 1/2 gal	cloudy	6.74	18:29	18:42	10.9	650
5.48/5.75	6 gal	cloudy	6.61	18:46	18:54	10.3	650
5.58/5.80	8 gal	very cloudy	6.6	18:56	19:05	9.9	650

finish 19:10

Decon sampling equipment 19:12 - 19:10

leave site 18:12

Sampling

Purged GW4-B, GW4-A
 MW 67

44

9/12/98

Arrive 7:00 AM Discuss day plans; raining outside.
Sampling slow due to long filtering of water
- Calibrate Cole Palmer conductivity
meter same as yesterday

adjust 1050 to 1000

adjust 9400 to 10,000

- Calibrate pH meter ORION
research model SA 230

adjust 6.90 to 7.00

adjust 8.85 to 10.00

- Calibrate HNU 5000791 per work plan

Arise 500018 Spar setting 4.34

Pick up Coolers at Base

8:45 Arrive at Site 4 MNR

Bottom of well (Soft) 15.58

1 well volume = $8.5 \times 1.63 = 1.385$

3 well volume = 4.16 gallons

HNU of borehole approx.

Peter Rimmerman and Mike Raddy

on the gorge team. Kim Davis

and JOAN on sampling.

9:45 Leave Site MNR

down water and water level indicators

9/12/98

MW-8 Purge

45

water level initial/final	Bailing TIME start/finish	total water withdrawn	water quality	pH	Temp	Conductivity
7.08 / 10.48	8:58 / 9:04	1.5 gallon	very cloudy	7.85 7.5*	13.7	405
8.33 / 10.30	9:08 / 9:13	2.5 gallon	very cloudy	6.36 6.7	13.4	410
7.99 / 9.72	9:19 / 9:24	4.25 gallon	very cloudy	6.30	13.4	400
PURGE complete						

* recalibrated pH meter from 7.45 to 7.00

46

9/12/88

9:45-12:02 Shopping for supplies, bought
poker knives, wine

When we came back to Anna and Kim
saw that Enrique from MPCA came by
and wants to sample MW 29 at Site 3

1208 Arrive at MW 29 Site 3

Have reading of casing hole 140m

14.64 = First depth to bottom of well

Well volume = $7.97 \times 16.3 = 1.3$ gallons

Well vol = 3.9 gallons

Well purge

1240 Leave MW 29

Go to Fed Express to drop off
packages for Kim and Joanna

12:55-1:45 Lunch

9/12/88

Site 3

MW 29 47

Water level Initial/Final	Bailing time Start/Finish	Total water Withdrawn	Water quality	pH	Temp	Conductivity
6.67 / 7.07	1220 / 1223	2.0 gallons	almost clear	7.00	15.7	1800 615
7.02 / 7.30	1225 / 1229	3.5 gallons	almost clear	6.96	15.1	1800 615
6.76 / 7.56	1233 / 1234	5.0 gallons	almost clear	6.89	15.5	610

Purge Complete

9/12/88

1801 Leave office for the day

9/13/88

51

7:10 AM Arrive at office Since we are purgers
in head of sampling, H. Keir and Peter
R. are going to do important work
until Kim R. and J. ANNA complete
sampling some additional wells

Calibrate Cole Palmer multi-sensor on
yesterday
adjust 977 1060 to 1000
adjust 9400 to 10,000
Calibrate Olson Research Model SA 230
adjust 6.57 to 7.00
adjust 9,579 to 10,000

Calibrate HNU model Asset No. 51000791
per work plan

Run errands consisting of dropping off
package picking up table pack, Callup Oak Ridge

Office Initial water level 8.76 well volume
total well depth 16.68 calculation
3 well volume is 4.15 on page

Work went to Feb X to get Helmut of John
instruments properly checked and rechecked
Since it was unable to go down yesterday
on its latest condition

9/13/84

12:14 leave MW 11 Site 4

12:36 Arrive at Site 4 + 4A

total depth of well 21' much

3 well volumes from previous calculation 7.65 gal


MW 11 purge info on left of this page

13:20 leave site - drive back to office

13:30 lunch

14:20 back from lunch

14:23 - 14:48 clean



9/13/84

53

MW 11

conductivity

Temp

pH

water quality

total water withdrawn

pumping time

water level raised/lowered

MW 11

8:36 / 10:0	10:43 / 10:48	1 gal/min	cloudy	7.18	12.1	6.30	640	MW 11
9:01 / 11:49	11:11 / 11:16	2 gal/min	very cloudy	6.88	11.3	640	652	MW 11
10:03 / 12:00	11:52 / 11:56	3.5 gal/min	very cloudy	6.98	11.8	652	640	MW 11
11:06 / 13:04	12:05 / 12:09	4.5 gal/min	very cloudy	7.03	12.1	640	690	MW 11
5:41 / 6:02	12:50 / 13:57	3 gal/min	very cloudy	7.01	12.4	690	640	MW 11
5:00 / 5:08	13:01 / 13:06	5 gal/min	very cloudy	6.80	11.7	640	640	MW 11
15:08 / 15:08	13:07 / 13:14	7.7 gal/min	very cloudy	6.85	12.3	640	640	MW 11

56

9/13/88

18:10 prepare bottles for next day
18:38 leave site

Summary for the Day

Pumped MW-11
GW4-D
MW-10

9/14/88

57

7:10 AM Arrive at Site

Calibrate Conductivity Meter - Cole Palmer
Model 1484-10 Serial No. 7092005

adjust 1100 to 1000

adjust 9500 to 10000

Calibrate pH Meter Model SH230

Serial No. 3191

adjust temperature with thermometer

adjust 6.98 to 7.00

adjust 9.88 to 10.00

HNU Calibration Asset No. 500791

Span Setting 4.82

7:30-9:30 Mike R. and Peter R. do BR-6
borehole rim site samples

9:49 Mike R. and Peter R. arrive at Site 3

Mike R. is going to do MW26

Peter R. is going to do MW25

there are paired wells

MW25 from previous calculation 3 well volume = 5.7 gal

MW26 btm of well at 15.33

1 well volume = $7.96 \times 1.63 = 1.30$

7/14/88

well	MW 85 (Pete Richmond)	Bailing time	total water	water quality	pH	temp	conductivity
MW 85	10:01 / 10:18	10:01 / 10:18	1.5 gal	slightly cloudy	7.69	12.8	635
	9:51 / 10:15	10:09 / 10:22	30 gal	slightly cloudy	7.33	12.0	630
	10:33 / 11:25	10:29 / 10:35	10 gal	cloudy	7.30	12.8	640
	11:00 / 11:22	10:53 / 10:58	6.5 gal	cloudy	7.35	12.8	650
MW 86 (Mike Roddy)							
	9:37 / 9:48	9:53 / 9:59	1.5 gal	partly cloudy	7.25	14	450
	7:38 / 7:45	10:08 / 10:12	3 gal	partly cloudy	6.82	14.4	450
	7:38 / 7:47	10:17 / 10:24	5 gal	partly cloudy	6.73	14.2	440
Purse							
Completed							

9/14/88

MW 26

HNW of well → opp in
initial water level reading 7.37
bottom of well = 15.33
11:00 - 12:15 Decon 2 barrels, one for the purge
team and one for the sampling
team Decon 1" barrel for the
sampling team. Went for phone
call at 11:00 left about
accident as described in Kim Reno
sampling fieldbook on the desk
and time. This information is needed
to plan our sampling strategy for the
afternoon.
12:15 - 13:27 Talked to Melane at the Berkeley
Lab. They had a vehicle breakdown
a car not and some bottles were
broken. Some wells samples, though
some bottles were broken. The lab will
be able to get by with what they have
however for MW 26 sampled
9/12/88 and GW 4C sampled
9/12/88

15.33
7.37
7.96

60

9/14/88

9/11/88 several bottles were broken and these wells need to be re-sampled. Justed below are the bottles that had to be refilled. I talked to Bob Richard who said we should re-sample for only those bottles broken. He also said to call Richard Westwood about the hole only sampling VOA's at MW29.

DANGB-4-GW4C-GW1 5 VOA VOA's

DANGB-3-MW29-GW1 2 418.1 liter bottles
2 1 liter bottles 608DANGB-FB9 2 VOA bottles
2 1 liter bottles 608

1327-1505 Bob went on supply buying errand and bought vermiculite for packing samples
tweezers for removing filter paper

yellow ryp lock plastic bags for shipping
1000' feet of black nylon rope

1505-1549 Lunch Break

1549 Arrive at MW29

item of borehole 0.9 ppm
3 well volumes from page 46 = 3.9 gallons

9/14/88

MW29 G1

MW27

water level initial / final	Boring time start / finish	total water withdrawn	water quality	pH	conductivity	temp
6.75 / 7.20	553 / 557	1 gallon	slightly cloudy	6.86 7.71	680	17.7
6.82 / 7.34	1603 / 1606	3 gallons	almost clear	6.51	730	15.9
6.91 / 7.24	1609 / 1611	4 gallons	slightly cloudy	6.50	740	16.0
MW27			MW27			
8.50 / 12.37	1642 / 1644	1 1/2 gallons	slightly cloudy	6.53	580	15.0
11.00 / 12.05	1729 / 1732	2 1/2 gal	slightly cloudy	6.92	600	12.2
11.23 / 13.50	1752 / 1756	2 1/2 gal	cloudy	7.08	610	11.5
note: very slow recharge						

9/14/88

Note from 1345-1327 I talked to
 volume at the Berkeley lab about
 not emburying MW26 as it had been
 accidentally sampled from an unpurged
 well.

1435 F. line at MW27 SIK3

HWS of borehole Oppm

btm of well 14.68

3 well volumes as 3.15 gallons from
 calculations on page 48

large permeable on page 61

This well recharges very slow and
 it is taking quite a lot of time to get
 even 3 gallons out

1800 Leave MW27

decontainers

1845 Leave office

9/15/88

7.30 Arrive at office pretty cloudy skies

Kim Davis

Peter Cummings

John A. Becker

Mike Roddy

- Mike R. calculate How Asset stable
 span setting 4.28

- Orlin R. R. Palmer Conductivity
 meter Serial No. 7092005

adjust 1075 to 1000

adjust 8000 to 10,000

- Orlin R. R. Palmer PH meter model SA 230

adjust 6.80 to 7.00

9.90 to 10.00

temperature checked

7.30-9.54 Found out that we have to send
 insurance forms for auto accidents
 to CNA office in Minneapolis

I we write our own and Oak Ridge office
 numbers as contact points. We sent one
 copy of the accident reports FedEx to
 Carol Palmer and one copy (the original) by first class US mail

9/15/88

15.15 arrive at MW 33, 34

MW 33 initial H₂O level 9.41 TOC

bottom of well 14.82 hard bottom

1 well volume = $5.41 \times 163 = .88$

2 well volume = $0.88 \times 3 = 2.64$

H₂O of well 33 → 0 ppm

MW 33 initial H₂O level 9.25 from TOC

bottom of well 24.80 hard bottom

1 well volume = $13.55 \times 163 = 2.2$

3 well volume = $2.2 \times 3 = 6.6$

H₂O of well 33 → 0 ppm

MW 34 is very slow recharge

MW 30 turn of borehole 0 ppm

water level before bailing 9.38

bottom of well 17.92

1 well volume = $8.54 \times 163 = 1.39$

3 well volume = $1.39 \times 3 = 4.17$

9/15/88

H₂O

MW 30

water level	bailing time	total H ₂ O	water	pH	Temp	conductance
initial / final	start / finish	concent	quality		°C	
9.38 / 12.76	17:48 / 17:42	13.4 gal	cloudy	8.12	9.3	450
11.35 / 13.50	17:53 / 17:55	3 gal	cloudy	8.03	9.2	460
11.50 / 12.98	18:09 / 18:12	4.1 gal	cloudy	7.92	9.1	470

purge complete

18:18 leave site

18:25 Decon sampling equipment

19:25 leave office for the day

W

9/15/83

to CHIA

P.O. Box 9332

Minneapolis, MN 55440

ATTN: Claudia dept

We picked up FedEx packages

including boxes and forms on how

to do stream flow measurements

0.51039 pi. w. boxes for base supply

11:44 arrive at GW 4C

HW at above 11.08

initial water level measurement 11.08

bottom of well 22.66 mdsy. bottom

well volume = 11.58 x 0.163 = 1.9

3 well volumes = 1.9 x 3 = 5.7

12:42 finish up lease GW 4-C

12:42-1:30 PM lunch

1:30-3:10 PM decom. structures. Shovel buildings

pick up contents from base supply

1:52Z start bailing MW 3H

9/15/88

in MW

GW 4C

bailing time

Water level initial/finish	Start/finish	Total water w. below	Water quality	pH	Temp °C	Conductance
11.08/11.35	11:53/12:04	1 3/4 gal	slightly cloudy	7.47	10.8	1240
11.24/11.37	12:07/12:15	4 gal	slightly cloudy	7.63	10.6	1190
11.25/11.48	12:24/12:38	6 gal	slightly cloudy	7.60	10.6	1180
	purse completed					

MW 3H

Water level MW 3H (Peter Riemann)

Water level initial/finish	Bailing time start/finish	Total water w. below	Water quality	pH	Temp °C	Conductance
19.25/14.80	15:39/15:46	1 1/2 gal	cloudy	7.33	8.9	1520
14.30/18.30	15:49/15:53	3 1/2 gal	cloudy	7.48	8.3	1510
16.50/15.50	15:57/16:02	5 gal	cloudy	7.49	8.2	1580
15.80/19.15	16:03/16:07	6 gal	cloudy	7.46	7.9	1650
End						

MW 3H (Mike Paddy)

Water level initial/finish	Bailing time start/finish	Total water w. below	Water quality	pH	Temp °C	Conductance
9.41/12.02	3:15Z/1:58Z	3 1/4 gal	clear			
11.00/13.02	1:53Z/1:53Z	1 1/4 gal	slightly cloudy	7.28	10.3	420
11.04/13.42	1:59Z/1:59Z	1 1/4 gal	cloudy	7.72	9.3	540
11.71/13.42	1:59Z/1:59Z	2 1/4 gal	cloudy slightly	7.45	9.5	610
11.75/13.62	1:59Z/1:59Z	3 1/2 gal	cloudy	7.44	9.7	740
11.78/13.33	1:59Z/1:59Z	2 1/4 gal	cloudy	7.51	9.6	730

9/16/88

7:05 AM Arrive at office, weather is rainy and it rained all night

— Cole Palmer Conductivity Meter

Model 1484-10 S/N 7092005

adjust 1260 to 1000

adjust 9500 to 10,000

— Orion Research PH meter model

SA 230 Serial NO 3191

adjust PH 6.96 to 7.00

adjust PH 9.66 to 10.00

— Calibrate HNU Asset NO 500791

Probe NO. 500018 to 97% Isooctylene

Span setting 1.28

PLAAC

Kim Davis and Peter Remmersma are going to sample GW4-C at Site 4

Mike Roddy and John Hurdman

are going to purge some wells

Johann Beeler is leaving on a plane at 10:40 this morning

9/16/88

12:00-8:45 do boiler rinse-sample

0855-0935 help set up sampling station

0940-10:10 run errands for Samplers and hold down tarp

10:30 arrive at Site 3

GW3-C initial water level 8.50

Bottom of well 21.35

HNU offset

well volume = $12.93 \times 0.163 = 2.04$

well volume = $2.04 \times 3 = 6.12$

GW3-B

14 ft water level 10.20

bottom of well 22.0

HNU offset

well volume = $12 \times 0.663 = 7.96$

well volume = $7.9 \times 3 = 23.7$

9/16/88

1:50 - go back to office to help
samplers - decon bilers

13:00 Go to lunch

14:05 back from lunch
Decon filtering devices
Help samplers

15:18

GW3-A

Initial water level 10.30

Bottom of well 8.33

Well volume = $8.03 \times 0.163 = 1.3$

3 Well volume = $1.3 \times 3 = 3.9$

Water level Initial/Final	Bailing Time Start/Finish	Total water pumped	Water Quality	pH	Temp °C	Conductance mhos	Well
8.50 / 19.0	11:29 / 11:33	2 gal	very cloudy	7.35	9.4	300	GW3C
11.92 / 17.32	16:22 / 16:25	3 1/4 gal	very cloudy	7.82 8.05	9.2	420	
15:10 / 20.02	18:18 / 18:20	4 1/2 gal	very cloudy	7.69	9.2	440	
10.20 / 11.6	10:52 / 11:58	2 gal	very cloudy	7.53	10.2	700	GW3B
11.3 / 12.4	11:04 / 11:07	4 gal	very cloudy	7.49	10.1	700	
10.95 / 11.4	11:16 / 11:20	6 gal	very very cloudy	7.46	9.7	700	

surge completed

9/16/88

9/16/88

15:28 arrive at GW3-D

HVU of well - n. at done rain

initial water level 6.64

bottom of well 19.16

1 well volume = $12.52 \times 0.163 = 1.9$

3 well volume = $1.9 \times 3 = 5.7$

GW3-D

water level initial / final	boiling time start / finish	water withstand	water quality	pH	temp °C	conductivity microhm/cm
6.64 / 14.82	17:25 / 17:29	2 gal	very cloudy	7.80	10.1	720
7.77 / 12.80	17:42 / 17:45	2 gal	very cloudy	7.54	9.6	730
8.66 / 12.75	17:54 / 17:57	5 gal	very cloudy	7.48	9.6	720
9.59 / 11:32	18:02 / 18:03	5 gal	very cloudy	7.50	9.7	720
		purge completed				

GW3-A

water level initial / final	boiling time start / finish	water withstand	water quality	pH	temp °C	conductivity microhm/cm
10.30 / 6.40	17:30 / 17:32	1 gal	very cloudy	—	—	—
13.60 / 15.16	17:47 / 17:50	2 gal	very cloudy	7.73	9.5	350
13.75 / 15.25	18:06 / 18:08	3 gal	very cloudy	7.73	9.4	370
13.75 / 15.50	18:23 / 18:25	4 gal	very cloudy	7.67	9.6	360
		purge completed				

9/16/88

18:38 back at office

help prepare bottles for next

day

19:20 leave site

9/17/88

7:10 arrive at office

Ken Davis

Peter Riemersche

Mike Roth

John Henderson

Calibrate HNU model PI 101

ASISCT # 500791 probe in 500018

Span setting 2.0 Calibrated with

94.7 ppm isobutylene supplied by

Liquid Carbon

Calibrate Cole-Palmer conductivity

meter serial NO 7092505

Adjusted 970 to 1000

Adjusted 9200 to 10000

Orion Research PH meter model SA 230

Centred on 7.00

temperature checked

13800 ~~help~~ = 17:15

help sample wells - no lucks
Purged

9/19/88

7:10 AM arrive on site

Calibrate HNU model p3 101
asset # 500751 probe # 5005018
Span setting 3.5 Calibrated with
942 ppm Isobutylene supplied by
Liquid Carbonic 9488-06588

Calibrate Calc-Palmer conductivities
probe Serial # 7092005
adjust 1050 to 1000
adjust 9400 to 10000

Calibrate Orion Research model
SA 230
adjust 6.38 to 7.00

Temperature checked

Weather conditions rainy & cool

9/19/88

8:05 start at NW 31

HNU of Well = 11 ppm

Initial Water Level 10.21

bottom of well 7.55

Well Volume = $7.34 \times 0.163 = 1.2$

Well Volume = $1.2 \times 3 = 3.6$

NW 31

Water level	Boiling Time	total H ₂ O	water	pH	Temp	Conductivity
Initial / Final	Start / End	Well / Surface	Quality			PC
10.21 / 11.30	8:20 / 8:22	11.4 gal	cloudy	7.44	10.2	860
11.5 / 12.10	8:23 / 8:24	24 gal	cloudy	7.21	10.2	840
12.00 / 12.30	8:25 / 8:26	34 gal	cloudy	7.62	9.8	860

purge completed

8:35 arrive at NW 28

Initial H₂O level 3.34

Bottom of well 14.83

Well Volume = $11.49 \times 0.163 = 1.87$

Well Volume = $3 \times 1.87 = 5.61 \text{ gal}$

9/14/88

MW28

Water level	Barling's Time	Initial/Final	Total H ₂ O Withdrawn	Water Quality	pH	Temp °C	Conduct
3.34 / 9.25	8:42 / 8:45	13.45 gal	13.45 gal	slightly cloudy	8.18	11.9	510
7.00 / 11.00	8:50 / 8:52	3.2 gal	3.2 gal	slightly cloudy	8.01	11.5	510
6.35 / 10.01	9:23 / 9:25	3.6 gal	3.6 gal	cloudy	8.16	11.3	510
7.00 / 9.60	9:39 / 9:40	5.2 gal	5.2 gal	cloudy	8.19	11.2	520

purge completed

Water level	Barling's Time	Initial/Final	Total H ₂ O Withdrawn	Water Quality	pH	Temp °C	Conduct
MW35							
5.43 / 10.50	9:12 / 9:14	1.5 gal	1.5 gal	slightly cloudy	8.16	14.2	150
6.60 / 9.53	9:47 / 9:48	3.3 gal	3.3 gal	slightly cloudy	8.18	14.8	160
7.60 / 10.00	9:53 / 9:54	4.9 gal	4.9 gal	slightly cloudy	7.82	14.5	175
8.50 / 10.00	10:03 / 10:04	4.6 gal	4.6 gal	slightly cloudy	7.68	14.5	185

MW35

Water level	Barling's Time	Initial/Final	Total H ₂ O Withdrawn	Water Quality	pH	Temp °C	Conduct
Initial water level							
bottom of well							
well volume =							
3 well volumes =							

9/14/88

Water level	Barling's Time	Initial/Final	Total H ₂ O Withdrawn	Water Quality	pH	Temp °C	Conduct
10.35							
Initial water level							
bottom of well							
well volume =							
3 well volumes =							

Water level	Barling's Time	Initial/Final	Total H ₂ O Withdrawn	Water Quality	pH	Temp °C	Conduct
12.29 / 17.11	10:45 / 10:48	2.4 gal	2.4 gal	very, very cloudy	7.62	10.3	820
17.00 / 17.50	10:50 / 10:53	5.5 gal	5.5 gal	very, very cloudy	7.60	10.7	950
17.20 / 18.00	10:55 / 10:59	7.8 gal	7.8 gal	very, very cloudy	7.54	10.9	1000

purge completed - note heavy sediment load in water

Water level	Barling's Time	Initial/Final	Total H ₂ O Withdrawn	Water Quality	pH	Temp °C	Conduct
11.12							
Initial water level							
bottom of well							
well volume =							
3 well volumes =							

9/19/88

MW1

Water level	Initial/Final	Build-up Time	Total H ₂ O withdrawn	Water quality	pH	Temp °C	Conduct
1526/170	11:18/11:22		2 gal	very very cloudy	7.78	12.1	950
1700/1960	11:23/11:25		4 gal	very very cloudy	7.62	11.8	1080
1800/2233	11:28/11:38		5 gal	very very cloudy	7.68	11.6	1090
2200/2215	11:38/11:39		5 gal	very very cloudy	7.59	11.4	1110

purge completed

finish up 1:46

lunch 1:50 - 12:35

12:35 pickup bottom A.B. at Alapaha

12:00 Decom build

14:05 arrive GW2-E

initial water level 12.58

bottom 20.0

lowest value = 7.22 * 0.163 = 1.18

3 well volumes 1.18 * 3 = 3.54

9/19/88

GW2-E

Water level	Initial/Final	Build-up Time	Total H ₂ O withdrawn	Water quality	pH	Temp °C	Conduct
2148/1537	14:13/14:15		1 gal	very very cloudy	7.16	12.0	1440
1530/1610	14:17/14:19		2 gal	very very cloudy	7.12	11.1	1480
1400/1685	14:26/14:28		3 gal	very very cloudy	7.11	11.3	1450

purge complete

14:37 arrive at GW2-D

H₂O of well → 0 ppm

initial water level 13.75

bottom of well 23.42

well volume = 9.87 * 0.163 = 1.59

3 well volumes = 1.59 * 3 = 4.74 gal

9/19/88

6W2-D

Water level	beginning	Time	Total H ₂ O withdrawn	Water quality	pH	Temp. °C	Conduct. mhos
Initial/Final	Start/End						
13:35/22:00	14:43/14:46		21 gal	very cloudy	7.03	15.2	760
14:00/22:50	16:45/16:47		33 gal	very cloudy	7.53	16.0	840
last note day	9:20/9:24		purge 30	com-punged on		9/20/88	
13:39/23:00	9:02/9:07		47 gal	very cloudy	7.40	10.3	880
22:40/23:50	21:16/21:16		5 gal	very cloudy	7.30	9.9	870

14:58 move on to NW 37

HNude well = Oppr

initial water level 4.16

bottom of well 18.07

well volume = $13.91 \times 0.163 = 2.27 \times 3 = 6.81 \text{ gal}$

NW 37

Water level	beginning	Time	Total H ₂ O withdrawn	Water quality	pH	Temp. °C	Conduct. mhos
Initial/Final	Start/End						
4:16/12:25	15:06/15:10		2 gal	slightly cloudy	7.62	17.8	360
6:00/13:25	16:28/16:33		5 gal	very cloudy	7.71	18.1	360
7:00/12:10	17:36/17:39		6 gal	very cloudy	7.81	18.6	350

purge completed

9/19/88

to pick up

pet.tera and some capers

16:15 get red van stuck at 6W2-D

16:25 get van unstuck

17:00 arrive at NW 41

HNude well - Upper

initial water level 10.25

bottom of well 14.50

well volume = $4.25 \times 0.163 = 0.69 \times 3 = 2.07 \text{ gal}$

NW 41

Water level	beginning	Time	Total H ₂ O withdrawn	Water quality	Temp. °C	Conduct. mhos
Initial/Final	Start/End					
10:25/12:11	17:08/17:12		24 gal	slightly cloudy	7.56	16.7
14:50/13:25	17:51/17:16		14 gal	slightly cloudy	7.61	16.5
12:10/13:50	17:51/17:24		2 gal	slightly cloudy	7.76	15.9

purge completed

finish up leave site 17:40

17:55 - Accumulate bags for next day

18:55 leave site

9/20/88

7:06 AM arrive on site

Calibrate Cule - Volume - Conductivity

meter serial # 20512025

adjust 1350 to 1000

adjust 4000 to 10000

Calibrate Orion Research model

SA230

adjust 7.54 to 7.00

adjust 9.20 to 9.90 all the higher

Temperature checked in well

Calibrate HNU model PI 10.

asset # 500791 probe # 50038

span settings 4.2 calibrated with

94.7 ppm Isobutyl alcohol

Liquor Carbonic batch # 9488 - dist 58

lot # 12

weather - cloudy, wind and windy

9/20/88

9:15

finish painting 602-0

9:30 arrive at HNU 40

9:33 Jantone S. shows up with 3

seriously lacerated fingers; take her back

to office to get instructions to take her

to the hospital - J. Hardness says he will

take her to the hospital

9:55-10:30 clean barrels and water-kick

indicator

11:00 arrive at HNU 40

PMU of well # 7 open

initial water level readings 4.54

bottom of well 114.58

Well volume = $110.4 \times 0.103 = 11.64$

Well volume = $11.64 \times 1.3 = 14.92$

9/20/88

MW 70

Water level	Boring Time	Total H ₂ O withdrawn	Water quality	pH	Temp °C	conduct numbers
Initial/Final	Start/Finish					
4.54 / 3.00	11:01 / 11:13	1.54 gal	ok - w/ clouds	7.25	13.0	320
6.92 / 10.16	11:21 / 11:22	3.24 gal	ok - w/ clouds	7.20	12.8	340
2.90 / 9.53	11:49 / 11:51	4.63 gal	ok - w/ clouds	7.27	12.1	400
9.14 / 9.92	12:00 / 12:00	5.94 gal	ok - w/ clouds	7.20	12.3	410

purge completed

12:03 leave Bunker

12:18 back at field office discuss water level indicator

12:30 leave

13:30 back from lunch

14:01 arrive at GW2-C

HW of WCI = 0.99

Initial water level readings 10.10

bottom of well 2.40

Well Volume = $13.94 \times 0.163 = 2.27$

Well Volume = $2.27 \times 3 = 6.81$

9/20/88

GW2-C

Water level	Boring Time	Total water withdrawn	Water quality	pH	Temp °C	conduct numbers
Initial/Final	Start/Finish					
10.10 / 14.25	17:14 / 17:23	2.15 gal	Very cloudy	6.80	10.9	170
6.92 / 16.00	17:35 / 17:35	5.5 gal	Very cloudy	6.71	10.4	175
1.40 / 18.00	17:48 / 17:52	7.5 gal	Very cloudy	6.81	10.9	180

purge completed

15:14 arrive at MW 4 - note PVC well

HW of WCI = 0.99

Initial water level 8.16

bottom of well 2.16

Well Volume = $14.0 \times 0.163 = 2.28 \Rightarrow 2.28 \times 3 = 6.84$

Water level

Initial/Final	Boring Time	Total water withdrawn	pH	Temp °C	Water quality	conduct numbers
Start/Finish	Start/Finish					
9.86 / 11.40	15:25 / 15:25	2.1 gal	6.97	12.2	Very cloudy	700
9.40 / 11.10	15:35 / 15:38	5 gal	6.94	11.7	Very cloudy	720
9.00 / 11.00	15:45 / 15:48	7 gal	6.91	11.5	Very cloudy	740

purge completed

15:58 leave site

16:15 discuss boundaries of field office

9/20/88

16:43 arrive at G102-A

HNW of well - opp-

initial water level 7.16'

bottom of well 12.50

1 well volume = $5.34 \times 0.163 = 0.87$

3 well volume = $0.87 \times 3 = 2.61$

G102-A

Water level	Drilling Time Start/Finish	Total Water Withdrawn	Water quality	pH	Temp °C	Conduct mmhos
7.16/8.16	16:50/16:51	1 gal	Almost cloudy	7.28	13.3	500
8.08/8.20	16:53/16:54	2 gal	slightly cloudy	7.26	13.3	490
8.20/8.50	16:57/16:58	3 gal	slightly cloudy	7.21	13.3	490

purge complete

17:04 leave well site

17:08 arrive at MW 7

HNW of well - opp-

initial water level - 6.16

bottom of well 12.08

1 well volume = $15.92 \times 0.163 = 2.59$

3 well volume = $2.59 \times 3 = 7.78$

9/20/88

MW 7

Water level Initial/Final	Drilling Time Start/Finish	Total Water Withdrawn	Water Quality	pH	Temp °C	Conductivity mmhos
6.16/21.53	17:16/17:21	2.4 gal	cloudy	7.54	11.5	800
6.59/21.10	18:33/18:37	5.5 gal	slightly cloudy	7.50	11.6	740
7.16/20.70	18:40/18:43	7.4 gal	clear	7.48	11.8	730

done on 9/21/88 - purging - failed

17:43 decide to stay to purge more water

Tomorrow - very slow recovery

17:55 back at field office - clean bailers and other equipment

18:55 leave field office

9/21/88

7:03 AM arrive on site

Calibrate Cole-Palmer Conductivity

meter Series # 7012005

adjust 1050 to 1000

adjust 9700 to 10000

Calibrate Orion Research Model

SA 230

Adjust 6.91 to 7.00

Adjust 9.30 to 10.00

Temperature checked

Calibrate HNU model PT 101

asset # 50074 probe # 50008

span settings 4.9 Calibrator with

4.7 ppm Isobutylene supplied

liquid Carbonic batch # 9488-06588

lot # 12

9/21/88

8:28 arrive at ~~point~~ MW7

attempt to resume purge

data entered in table for MW7 on 9/28/88

Very slow recharge

8:40 help Sam place to go get needed samples for the

9:10 Aid in bottle preparation

10:00 take bottles to fire office for filling and

10:40 pick up samples

10:50 back to help Sam

11:46 Aid in the shipping of bottles & MW7

12:08 go to lunch

13:00 back from lunch

check supply computer

14:00 arrive at MW 39

need to get bailer type for

samples

9/21/88

HNW of well → 0 ppm

initial water level 490
bottom of well 1686

1 well volume = $11.96 \times 0.63 = 1.95$
3 well volumes = 5.85 gal

MW 39

Water level initial/final	Boiling Time start/finish	Water withdrawn	water quality	pH	Temp °C	Conduct mhos
490/9.00	14:30/14:37	2 gal	cloudy	7.01	12.8	490
700/8.61	14:39/14:42	4 gal	cloudy	6.97	11.9	560
726/9.33	14:48/14:52	6 gal	cloudy	7.02	11.9	570

purge completed

15:00 leave site

take bottles back to Field Office
for samples

15:38 arrive at MW 38

HNW of well - 0 ppm

initial water level 469

bottom of well 17158

1 well volume = $12.81 \times 0.168 = 2.17$
3 well volumes = $2.17 \times 3 = 6.51$

9:00 return

9/21/88

MW 38

Water level initial/final	Boiling Time start/finish	Water withdrawn	water quality	pH	Temp °C	Conduct mhos
469/12.00	15:44/15:53	2 gal	cloudy	7.19	13.6	420
650/12.75	16:06/16:07	3 gal	cloudy	7.45	13.8	450
1050/13.83	17:21/17:25	4 gal	clear	7.36	11.9	470
1370/14.92	17:57/17:58	6 gal	slightly cloudy	7.34	11.3	470

purge completed

MW 5

Water level initial/final	Boiling Time start/finish	Water withdrawn	water quality	pH	Temp °C	Conduct mhos
383/13.75	16:28/16:36	3 gal	cloudy	7.51	11.6	500
967/17.58	16:57/17:03	4 gal	cloudy	7.52	11.3	500
1291/17.23	17:33/17:36	8 gal	cloudy	7.58	10.4	5100
1616/17.83	17:45/17:47	9 gal	cloudy	7.49	10.8	490

purge completed

16:16 start at MW 5 note PVC well

initial water level 383

bottom of well 2286

1 well volume = $14.43 \times 0.63 = 9.10$

3 well volumes = $9.10 \times 3 = 27.30$

HNW of well → 0 ppm

17:52 leave site note slow recharge

9/21/88

18:10 arrive at MW7 to complete purge

18:20 leave MW7 purge completed
see table on 9/20/88 for data

18:35 back at Field Office
Dean Surpless assigned

19:00 leave site

9/22/88

7:08 A.M. arrive on site

Calibrate CEC - Palmer Conductivity
meter Serial # 7092003

adjust 1000 to 1000

adjust 9400 to 10000

Calibrate Orion Research Model
SA 230

Adjust 652 to 7.00

Adjust 934 to 10.00

Temperature checked

Calibrate HNU model P11 201

Asset # 500741 probe # 500018

Span Setting Calibrated

units 94.7 ppm Iso butylene

supplied by Highwind Carbon

batch # 9488 - 061588 lot # 12

9/22/88

8:00 arrive at G6V2-13

H.N.V. of well - 0.22

initial water level 4.83'

bottom of well 14.25

lineal volume = $9.42 \times 0.163 = 1.54$

3 well volume = 4.62

Water level	Initial / Final	Bail Time Start / Fin	Total Water		pH	Temp °C	Conductivity mmhos
			With Pump	Without Pump			
4.83 / 5.16		8:13 / 8:17	1 1/2	1 1/2	7.07	13.7	1050
5.04 / 5.25		8:19 / 8:22	3	3	7.13	14.0	1050
5.20 / 5.33		8:24 / 8:26	4 1/2	4 1/2	7.17	13.8	1060
			Purge Completed				

0834 leave well

MW6

H.N.V. of well

initial water level 2.22

bottom of well 19.16

lineal volume = $15.94 \times 0.163 = 2.6$

3 well volume = 2.6 x 3 = 7.8 gal

9/22/88

Water level	Initial / Final	Bail Time Start / Fin	Total Water		pH	Temp °C	Conductivity mmhos
			With Pump	Without Pump			
3.22 / 13.08		8:50 / 8:55	2 1/2 gal	2 1/2 gal	6.88	13.3	480
7.00 / 11.75		9:12 / 9:18	4 1/2 gal	4 1/2 gal	6.85	13.4	470
6.00 / 13.08		9:13 / 9:18	6 1/2 gal	6 1/2 gal	7.02	13.4	480
6.50 / 13.25		9:25 / 9:30	8 1/2 gal	8 1/2 gal	7.06	13.3	480

Purge completed

9:50 leave site

10:48 back at field office to clean sampling equipment and get necessary equipment for site 10

Arrive at SITE 10 3 wells

GW10A GW10B, GW10C and one

duplicate GW10D will be sampled One 1 liter

poly bottle preserved with HNO₃ will be

sampled for each well and duplicate

Mike Roddy and Peter Kiersma will be

wearing - tyvek suits and booties

- gloves

- hard hats

- safety goggles

9/22/85

One stainless steel barrel will be left at the site. This barrel is dedicated to Site 10.

11:35 Run water samples back office get jump cables to get other Van started

12:20 Purge Van gets stuck

12:35 Purge Van gets unstuck - go to Budget Rent a Car to find out where better is in Pissaw Van

14:00 other Van started

14:15 go to Site 10 to find well location

15:00 take Peter M. to airport

15:30 back at field office clean equipment

16:00 arrive at GWS-C

17:00

Initial water level 5.89

Bottom of well 9.42

Water volume = $13.53 \times 0.163 = 2.21$

Swim volume = 6.63

GW8-C		Total		Water		pH		Temp		Conductivity	
Water level	Bailing Time	Water	Temp	pH	Temp	Conductivity					
Initial	Start/Finish	Take	Over								
5.84/9.80	16.11/16.14	2.5 gal		very cloudy	14.4	8.8	14.4	850			
9.60/10.05	16.15/16.15	5 gal		very cloudy	13.9	8.8	13.9	850			
10.05/10.50	16.20/16.23	6.5 gal		very cloudy	13.7	8.8	13.7	850			
purge completed											
16:32	Arrive at MWS	note PUC well									
	HMV of well										
	Initial water level	5.91									
	bottom of well	15.66									
	Water volume =	$9.70 \times 0.163 = 1.58$									
	Swim volume =	4.74									
MWS											
Water level	Bailing Time	Water	Temp	pH	Temp	Conductivity					
Initial	Start/Finish	Take	Over								
5.96/10.16	16.35/16.37	1.2 gal		very cloudy	15.9	6.83	15.9	380			
8.90/9.92	16.39/16.43	3 gal		very cloudy	14.7	6.94	14.7	380			
9.05/11.20	16.45/16.48	4.3 gal		very cloudy	14.3	6.85	14.3	380			
16:51	Leave well site										
17:05	take EPA H/S	Sample from GW8-C									

9/22/88

17:13 Take sample 418.1 from MW-8

17:20 back at field office

start decontamination's field equipment

17:53 prepare bottles and discuss

surface water samples and sediment

samples

18:45 leave field office

9/23/88

7:04 arrive on site

Calibrate HNU PI IN

asset # SA0179 probe # 500018

span setting 3.8 calibrate with

94.7 ppm isobutylene supplied by

liquid Carbonic batch # 9488-04588

lot #12

Calibrate Cole-Parmer conductivity

meter Serial # 7052035

adjust 100 to 700

adjust 9600 to 10000

Calibrate Orid-Resant Model SA238

pH and Temperature meter

adjust 6.92 to 7.00

Adjust 9.50 to 10.00

Temperature checked

10:00 - 11:00 Decan. Sampling equipment

11:02 arrive at GW10-A

HNH at well - 0.9pm

Background radiation $< 0.1 \text{ mR/hr}$

initial water level

7.29

batter of well

23.00

level value = 15.71 $\pm 0.162 = 2.56$

mean value = 2.56 $\pm 0.3 = 7.68$

Water level initial/final	Bilings Time start/finish	Total flow oz	Water quality	PM	Temp °C	Conductivity mhos
7.29/10.56	11:07/11:12	2.6 gal	slightly cloudy	7.12	9.8	560
8.36/14.08	11:20/11:22	5 gal	cloudy	7.00	9.9	550
10.00/12.66	11:28/11:32	7 gal	cloudy	6.53	9.8	550

purge completed

note water in real time readings off less

than 0.1 mR/hr

note purge water contained in 55 gallon drum

11:45 collect sample GW10-A

11:50 leave site 10

Base 4

Site Personnel Mike Ruddy 111210 0002

John Sherrill 111210 0003

11:54 cannot leave area for security

Police have road blocked off - police white

F-4 has gun repaired - Air Force does not

want us to drive in front of F-4 while

gun is jammed

12:14 permitted to Air Force to proceed

12:30 arrive back at field office

12:45 go with J. Henderson to do

stream flow measurements

13:00 attempt to

1330-1415 do stream flow measurements

at site 1

9/22/88

14:20 go to base supply to
pick up milk and Civi Eng to
make photocopies

14:40 back at Field Office - clean out
rental car

14:50 go to Civi Eng to make copies
or check off custody forms

15:30 back from Civi Eng

15:55 go to site to do stream
flow measurements

decide to use pygmy flow meter

16:45 Dan complete pygmy in place
stream diversion 3.5 ft across

0.85' deep at bank to 0.3' deep
in middle

read 1916 on pygmy flow meter

check to see if possible to collect
surface water samples

9/23/88

7:00 - 17:20 dig holes for water to accumulate in
for water to accumulate in

17:25 back at Field Office - clean up

17:55 leave office

9/24/98

7:18 arrive at field office

Calibrate Cole. Palmer Conductivity meter

Serial # 7092005

adjust 950 to 1000

adjust 9400 to 10000

Calibrate Orion Research Model SA230

adjust 702 to 7000

adjust 9.44 to 10.00

Temperature checked

8:30 arrive at SL-1

attempt to do skin film measurement

decide to wait until morning to

do it

9:11 collect a water sample and

pellet sample

9:15 collect sample DIVERS-SL-1-

9:30 so get filter, export & deionize

equipment

09:36 RS-SL-1-SW

pH 6.56

Temperature 11.6

Conductivity 110

Sample for water analysis collection about 1 1/2' below the surface

10:31 arrive at DIVERS-B6-SH-SW

10:40 Field blank 16 dune

10:45 Collect water and sediments for site DIVERS-B6-SH-SW

pH 6.65

Temperature 11.7

Conductivity 205

Sample for water analysis collected about 1 ft below the surface

11:38 back at office - start filter

metals = 200, preparing sample for shipment

13:00-13:30 lunch break

9/24/84

13:35 leave for background site L-7

13:50 arrive at L-7 weather - clear, warm, breezy
Decide to take sample below the dam

14:05 Sample taken 1' below the surface and 6 ft from bank on side the closest to the road

pH 7.45
Temp 14.0 °C
Conductivity 255 μ mhos

14:50 leave site 14:50

14:55 arrive site 2

15:00 Sample Barrels 1, 2, 3 for
EP Toxicity Samples
note barrel found to contain water of uncertain origin

15:30 arrive at SL
Dig hole for water to collect in

9/24/84

15:40 leave SL

16:00 back at field office - start filter
note - preparing samples for shipment

16:15 go get ice

16:25 back - continue doing filtering
packing supplies

18:28 leave field office

9/25/88

10:30 AM arrive on site

10:45 leave to do stream measurements at SL1

12:15 finish stream measurements at SL2

13:30 collect field office begin filter metals

15:00 Finish filter metals start decontamination

equipment

15:30 leave field office

9/26/88

7:10 AM arrive on site

prepare bottles to take to site 1 and prepare labels

Calibrate HACH conductive STDs meter

model 44600

980 mS/cm at 100

Temperature checked

Calibrate Orion Research meter SA230

Adjust 8.00 to 7.00

Adjust 9.02 to 10.00

Temperature checked

8:25 leave field office

8:40 stop at Airport

9:00 leave airport

9:08 arrive at SL1

9:30 sample 2 SL1 - note low or no stream

flow - swampy or marshy section

10:00 collect 2 SL2 - duplicate sample of

2 SL6

9/26/88

Measurements for 25.6 and 25.25

PM 7.14

Conductivity 0.390 mS/cm

Temperature 12.5°C

10:45 collected sample 2SL7

from small stream about

2 ft wide and 4 ft deep

Note: stream was flowing at the time the sample was taken

PM 7.57

Temp 12.0°C

Conductivity 0.390 mS/cm

11:08 leave Site 2

11:15 back at field office

decide what needs to be taken to site 3

11:30 - dis back at site 3 for surface water to accumulate in

9/26/88

12:00 pick up ice.

12:15 - 13:00 lunch

load van up for site 3 and dead

Sampling equipment

13:20 go to Target to get fish

13:50 arrive at 3SL10 and 3SL28 (Oyster)

14:00 Take sample 3SL10

Do field Blank FB-19

14:20 Take sample 3SL28 Discharge of 3SL20

Site notes: standing water no flow bottom covered with decaying leaves and plant matter

PM 6.72

Temp 12.7

Conductivity 0.649 mS/cm

leave 3SL10 15:05 - drop bottles off at

field office

15:20 arrive at 3SL8

9/26/88

15:30 collect 3SL's sample
 Sample collected from nearby area
 Standing water no visible stream flow

Temp 70.3
 13.0°C

Conductivity 0.204 mS/cm

16:08 Finish 3SL's Stand on 3SL's

16:45 Collect Sample 3SL's

Note: stagnant water, shallow < 0.4 ft
 narrow < 2 ft

Temp 13.9
 pH 6.72

conduct 0.514 mS/cm

16:46 leave site 3SL's

16:55 back at field office
 for shiner - help filter samples

17:55 Take samples to Fed X

9/26/88

18:20 back from Fed X resume filters
 and decan equipment
 19:01 leave site for the day

9/27/88

7:17 arrive on site

begin calibration

Calibrate HACH conductivity / TDS meter

model 44100

adjust 0.985 to 1.000

adjust 9980 to 10000

Temperature checked

Calibrate Orion Research Model SP230

Adjust pH 7.13 to 7.00

Adjust pM 9.94 to 10.00

Temperature meter checked

8:30 leave field office to collect

final surface water and sediment

sample and nitrite spike sample

notes are in sampling results

8:50 back at field office

begin filtering

samples

base supply

10:50 go to site to pick up field

envelope and then over to site

to do water level measurements

9/27/88

12:30 back at field office - decide to do

background water test - from site 8 and 4

14:10 - 14:30 lunch break

14:30 - 15:30 water level measurement

15:30 take water samples to airport

15:50 back from airport - testing measurements

Go to site 3 to collect soil sample SKC4

and duplicate sample

16:50 go to Blum 42 for final water

level measurement

17:15 back at field office - start filtering

and packing samples and packing equipment


22:30 leave site for the day

9/28/88

08:10 arrive on site finish packing up
equipment

10:00 leave for airport

10:45 leave dealership



This page intentionally left blank.

Q.2.7 Notebook 7, Slug Test Notes

This notebook contains notes taken while the aquifer slug tests were being performed. The first entry is 9 September 1988 and the last is 10 September 1988. Twelve pages were used plus a scratch page on the back cover. The pages are not numbered. They are signed by John O'Brian.

This page intentionally left blank.

7

Cambium

FIELD BOOK

101595

41 8 1/2

Projects

DULUTH AIR NATIONAL GUARD
OR 001-02

SUG TESTING

SUG A diameter 1.20" length
SUG B diameter 1.20" length

Name John O'Brien

57 Executive Park

Address Atlanta, GA

Phone 404/325-0770

Cambium
Distributors
3589 Broad Street
Chamblee, Georgia 30341
(404) 455-1927

This book is published on a fine 50% cotton-content ledger paper, specially treated for maximum archival service, and protected by a water resistant surface sizing.

Project Manager	Bob McLeod
-----------------	------------

Project Manager	Bob McLeod
-----------------	------------

Field	Team Leader	0
Field	Team Leader	0

John	Hardeeman	904/325-0770
------	-----------	--------------

Slur Test Technician 00

John Obrien 404/325-0770

Slugs	Test Equipment	00
-------	----------------	----

HERMIT Environmental Data Logger

Model SE 1000B In-Situ, Inc.

mode	#	SE/1000 B	#

Serial #	1KB-964
----------	---------

Thursday
9-8-88

SFO

* Note:

Slugs were deconned as
specified in the Minnesota
AUG work plan, Appendix B
page 6-10 prior to testing
each individual well.

0700 Arrived at Duluth AUG,
deconned slugs via the
Minnesota Air National Guard
Base Duluth International
Airport, Duluth, Minnesota
Work Plan, Appendix B
Page 6-10.

0745 Participated in health and
safety lecture given
by on-site health and
safety officer, Jenna Becker.

1331 Site B, MW 25, SING-A
Below Static H₂O level 4' 9.5"
Ground level 2 Total well depth 16'

1345 Start test MW 15, step 0
Below Static H₂O level 4' 6.5" = SFO
Ground 2 Total well depth 12' 9" = 9-8-88

1427 Start Test 0: step 1 (MW 25)

Thursday
9-8-88

John O'Brien

Site 3	MW 26	SLUG A
Start Test 1	Step 1	(mw 26)
Static H ₂ O Level	4' 6.5"	
Total Well Depth	12' 9.0"	
Start Test 1	Step 1	(mw 26)
End Test		
Site 4	MW 22	SLUG B
Static H ₂ O Level	6' 8.0"	
Total Well Depth	31' 0"	
Start Test 2	Step 0	(mw 22)
End Test 2	Step 0	(mw 22)
Start Test 2	Step 1	(mw 22)
End Test 2	Step 1	(mw 22)
Left	Depth	Aug

John O'Brien

Friday
9-9-88

John O'Brien

1026	Site 2	GWA-E	SLUG B
Static H ₂ O Level	11' 4.5"		
Total Well Depth	19' 8.5"		
Start Test 3	Step 0	(GWA-E)	
End Test 3	Step 0	(GWA-E)	
Start Test 3	Step 1	(GWA-E)	
End Test 3	Step 1	(GWA-E)	
Static H ₂ O Level	8' 2.5"		
Total Well Depth	29' 11.0"		
Start Test 4	Step 0	(mw 16)	
End Test 4	Step 0	(mw 16)	
Start Test 4	Step 1	(mw 16)	
End Test 4	Step 1	(mw 16)	

Saturday
9-10-88

John O'Brien

1148 Site 3 MW 34 slug A

Below ground surface
Static H₂O Level 6' 8.0"
Total well depth 12' 5.0"

1221 Start Test 7 stop
1251 End Test 7 stop

1351 Start Test 7 stop
1311 End Test 7 stop

NOTE:
Due to reference value
being inadvertently reset, the
values of Test 6 stop 1 and stop
are incorrect.

Saturday
9-10-88

John O'Brien

1243 Site 3 MW 33 slug A

Note:

Site 3 MW 33 has recovered from
earlier (1048) slug test and therefore
this well will be re-tested
in order to regain the data lost
previously today.

static H₂O level 6' 8.0"
Total well depth 12' 5.0"

1318 Start Test 8 stop

1348 End Test 8 stop

1348 Start Test 8 stop

1418 End Test 8 stop

1500 Left Duluin Ave

~~Station 23~~

66
76
2

2'6"
9 20"
7 22"
2'6"
9'2"
9'1.5" 72
70

4022
9'4"
2'6"
3 25
250
6
6'8"
36
26
210

1005
30
65
2'8"
10 10.5 32.7
8 25 30
29.11"

2'10"
5
3
2 2"
15 6
2 10
13 6 13
12.5

[2'6"]
4'2"
5'4"
32'6.5"
30.05"

Q.2.8 Field Drilling Records

The following lithologic logs are the field notes on the core lithology, sampling and HNV readings for all deep boreholes. They were recorded by Peter Riemersma and Mike Roddy.

This page intentionally left blank.

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B-BG mw 32 8'	DRILLING STARTED: 8/29/85
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/29/88
PROJECT NO: OR001	DRILLING METHOD: <i>Rotasonic</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: <i>Mike S. Ruddy</i>	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		60%		Boulder - moved out of way by drillers Clay, mottled tan and brown, some silt, some 1/4" to 2" pebbles, dry, plastic, firm	HNU of sample 2' ppm
0-1					
2-3 1/2					
3 1/2-5				Clay, brown, some silt, abundant 1/4"-2" pebbles, dry, plastic, firm	
5-7 1/2		100%		Clay, brown, same as 3 1/2-5	HNU of sample 2' ppm
7 1/2-10		100%			
7 1/2-10				Gabbro, gray, massive probable boulder.	HNU of sample 2' ppm
10-14 1/2				Clay, brown, some silt, abundant 1/4"-1/2" pebbles, moist to wet firm	HNU of sample 2' ppm
14 1/2-22				Clay, same as 10-14 1/2	HNU of sample 2' ppm
14 1/2-18				Sand, brown, some silt and clay, abundant pebbles 1/4" to 3", wet soft	
18-20				Sand and gravel, brown, abundant pebbles 1/4"-3", wet, soft (washout?)	
20-22.5					
TD 22.5'					

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG Background MW42A	DRILLING STARTED: 8-18-1988
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5				Clay, light brown to brown, some silt, some pebbles, little sand, fine, dry to slightly moist, Firm to very firm	How of sample 1 ppm
5-10				Clay, brown, some silt, some gravel, angular, little pebbles, slightly moist to 9 1/2'	How of sample 1 ppm
11-13				Concrete, powdered, white and ash like, some pebbles	
				MW 42A abandoned at 13'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

Abandoned

WELL/BORING ID: DANG Background MW42	DRILLING STARTED: 8-18-1988
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		SS 1 100%		<i>light brown</i> clay , some silt, & little pebbles 1/4-2" diameter, very loose, very dry	HAV of sample 21.0 ppm
5-7.5				clay and silt, brown, some gravel, angular, little pebbles, very firm, slightly moist, some red ^{granite} rock fragments up to 1" diameter at 7-7.5', gives soil reddish brown color	hit hard drilling zone at 7.5', maybe concrete
7.5-10'				Boulder, granite, quartz, plagioclase. <u>Abandoned at 12:24</u>	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANG Background MW42	DRILLING STARTED: 8-18-1988
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-18-1988
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: P.	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		SS1 100%		Silt clay and silt, brown, and with black organic rich lenses in upper 6"; some sand, fine at 2-5'; loose from 0-2', wet from 2-5', slightly moist from 0-2, firm	H ₂ O of sample < 1 ppm water table est. at 2'
5-10				Silt, brown, some clay, firm to very firm, some gravel and pebbles up to 3" diameter, slightly moist	H ₂ O of sample < 1 ppm
10-15.5				clay, mottled brown and black, organic rich in black lens, some silt, pliable, soft, very moist to wet, so from 10-12', trace pebbles Silt, some clay, some gravel and pebbles very fine dense and hard, clay to very slightly moist 12.5-15.5'	H ₂ O of sample < 1 ppm
				TD @ 15.5' at 13:30	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE ____ OF ____

WELL/BORING ID: DANGB-BG-MW 43	DRILLING STARTED: 8-18-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-18-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E. Remersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY (%)	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		100% SSI		Peat, dark brown to black, some clay, brown, pliable, dry 0-1 1/2' slightly moist to moist from 1 1/2-5' little silt	
5-15				Peat, dark grey to black, some clay, brown, probably occasional tree plant roots, moist to very moist, natural organic odor, from 5-12.5', Peat is easily pliable and soft Peat is mottled brown and black from 12.5-13.5, with some clay Gravel and Sand, brown, fine to coarse, angular to subrounded, some clay, pebbles, rounded, 1/2-2" diameter 13.5-14.5', wet, loose clay, brown, little silt, soft, pliable 14.5-15'	
15-24				clay, brown, some silt, little pebbles 1/4-1" diameter, soft TP @ 24'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANG -2-BH1	DRILLING STARTED: 7-29-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 7-30-88
PROJECT NO: OR001	DRILLING METHOD: Hollow stem auger
DRILLER: North Star Drilling Co.	SAMPLING METHOD: split spoon
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-2'	14-21-18-14	40% SS-1	X	Clay, brown with black mottled areas, stiff, micaceous, some silt. Strong oily smell with dark black areas more odorous. Sample dry.	HB = ANN reading in bi-axial zone HA = ANN reading at top of auger tube 1:39 PM HB 0 ppm 2:01 PM HA no reading
2-4'	4-11-10-10	40% SS-2	X	Clay, same as above oily odor	ANN reading of split spoon tip is 150 ppm - sand to soil
4-6'	16-35-22-22	REX AS 25% recovery SS-3		Clay, same as above oily odor	2:40 HA 7 ppm HB 0 ppm split spoon headspace ANN of 4-6' was 175 ppm from small sample
6-8'	9-5-9-8	30% SS4	X	Clay sandy, silty, brown med to dk brown, micaceous DANG - strong hydrocarbon odor. At base of split spoon get some stiff grey clay - plastic.	3:01 PM HA - 0 ppm Split spoon headspace 225 ppm
8-10'	1-4-12-25	SS 5	X	Clay silty, sandy, grayish green. Top 18" grades into a dark brown sandy silty clay w/ strong fuel odor.	ANN - A 0 ppm split spoon headspace 175 ppm stopped work at 8 17:00

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF 2

WELL/BORING ID: DANG 2 - BH 1	DRILLING STARTED: 7-29-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 7-30-88
PROJECT NO: OR001	DRILLING METHOD: <i>Hollow Stem Auger</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD: <i>split spoon</i>
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

SAT.

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
10-12'	10-28-20-25	75% SS6	X	clay, some silt, little sand, fine, trace pebbles, dark brown with light grayish-green mottled areas, petroleum odor strong, wet sample	HA 45 ppm HB 41 ppm split spoon headspace reading 5 ppm
12-14'	8-9-17-27	75% SS7		clay, dark brown, some silt, lower 1' has trace pebbles, upper 6" has thin cm thick <u>Sand</u> , medium-coarse, pebbly, laminations, slight petroleum odor, moist, weak firm consistency	HA 30 ppm HB 41 ppm split spoon headspace 5 ppm
14-16'	11-27-12 inch sample refusal	100% SS-8		Clay and Silt, clay, some sand, some silt, dark brown, sand is fine to medium, little trace pebbles 1/4" to 1" diameter moist to wet, no odor, 8.0 @ 16' auger refusal	HA 110 ppm HB 41 ppm split spoon headspace - no reading - 0 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANG2 BHZ	DRILLING STARTED: 7-30-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-1-88
PROJECT NO: OR001	DRILLING METHOD: <i>Follow Stem Auger</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD: split spoon
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: <i>Peter Riemersma</i>	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-2'	11-10-12-20	SS-1 60%	X	Clay, some silt, pebbly with 1/8" to 1/2" diameter, dark brown with black mottled areas, firm, dry, strong hydrocarbon odor	split spoon headspace 90 ppm w/ HNU HA 180 ppm HB 0 ppm
2-4'	17-22-16-18	SS-2 75%		Clay, same as above with increased number of pebbles, size of pebbles 1/2 to 2 inch diameter, dry, strong petroleum odor	
4-6'	4-9-10-15	SS-3 80%		Clay, same as above, rare wood fragments, some pebbles 1-2 inches, strong odor. Some sandy silt layers 1/2 inch thick	HA 70 ppm split spoon headspace 40 ppm
6-8'	10-15-8-6	SS-4 50%	X	Clay, same as above, strong petro. ferrous odor, pebbles common, dry, firm. At very base of spoon got some organic rich planty material - peat	HA 10 ppm HB 4 ppm split spoon headspace 400 ppm
8-10'	3-5-4-9	SS-5 40%		Peat and clay, upper brown to black, loose, upper 3/4" is peat with plant fragments, lower 3/4" is clay, firm, rare 1/8" pebbles, moist	HA 150 HB 0 ppm split spoon headspace 300 ppm
10-12'	4-7-14-13	SS-6 80%	X	Silt, dark brown, some clay, soft, little pebbles common, strong petroleum odor, moist to wet	HA 35 ppm HB 0 ppm split spoon head

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANG 2 BH-2	DRILLING STARTED: 7-30-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-1-88
PROJECT NO: OR001	DRILLING METHOD: Hollow Stem Auger
DRILLER: North Star Drilling Co.	SAMPLING METHOD: split spoon
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
12-14	8-6-18-21	85%	SS 7	Silt, brown, some clay, little sandy trace pebbles, very moist, almost all saturated. Some dark black plant rich areas (peat)	HA 4ppm HB 0ppm Spoon spoon headspace is 35ppm
14-16	8-20-11-13	SS 8 70%		Silt, brown, some sand, fine to medium, some clay, firm, rare plant fragments, very wet, water in spoon, slight petroleum odor, some pebbles	HA 3ppm HB 0ppm Spoon spoon headspace ending is 5ppm
16-18	12-23-25 auger split spoon 18" refusal down	SS 9		Silt, brown, some sand fine to coarse, firm, lower 4" dry silt and clay, slight petroleum odor, moist to wet	HA 60ppm HB 1/2ppm SS headspace 5ppm
18-20	s			Sample attempt failed due to boulder in the way	HA 40ppm HB 0ppm
20-				Boulder still in the way	HA 5ppm HB 0ppm
20.5-	spoon down 4" before refusal	SS 10		Sand, dark brown, fine to medium, some clay, some silt, pebbles 1/8 to 1/4" common, to wet, no petroleum odor	8-1-88 HA 15ppm HB 0ppm
21.1				Auger refusal, interpreted as bedrock TD 21.1'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG2 - MW 12	DRILLING STARTED: 8-4-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-4-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter Riemersma + Jo Ann Sherwin	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-2'		651 100% X		clay, brown, some silt, dry, no odor	HA of sample 1 ppm
2-4' 5'		1086 552		clay, same as above with pebbles 1/4-1" diameter slightly moist	HA of sample 1 ppm
5-11' 5'		1086 553 33% sample compressed 3' out of 10		clay and silt, brown to dark brown, little sand, few pebbles, firm, slightly moist, no odor. Pebbly zone in lower 6' of the core, damp with some sand and little clay; Probably lost lower 3'	HA of sample 1 ppm HB = 0 ppm water table estimate at 12'
15-20		1000% 554 5		Silt, brown, some clay, firm, little small pebbles, in bottom 2', moist Silt and Gravel in upper 3', gravel composed of pebbles from 1/4-1" diameter very firm and hard, very moist, some dark gray colored areas Color is grayish brown 5YR 3/2	HA - 0 ppm HB - 0 ppm Streaks of clayey silt Color N3 dark gray at about this depth
20.3' - 23'		3' of bedrock		cored bedrock, 3' of dark, mafic hornblende, pyroxene, some quartz, quite heavy, competent TP 23'	HB - 0 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG 2 MW-13	DRILLING STARTED: 8-5-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-5-88
PROJECT NO: OR001	DRILLING METHOD: Rotary
DRILLER: North Star Drilling Co.	SAMPLING METHOD: continuous coring
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: P. Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-2		100% SS1	X	Clay, dark brown, in upper 1', abundant root and plant fragments some silt, loose, slightly moist (from rain) Silt in lower 1', some clay, firm, little pebbles	sample HNU - oppm
2-5					
2-5		SS2		Silt, some clay, brown, scattered pebbles ^{1/4"-1"} , very firm slightly moist	HB - oppm
5-15		100% SS3		Silt, brown, and clay, pebbles 1/4" to 3/8" diameter, several areas at 7-7 1/2', 8-8 1/2' of Sand fine-grained, some clay, clump entire. Sample is clump and very firm except for bottom 1-1 1/2' where we get a little sand; fine-grained, pebbly, loose, wet. From 5-15' seems to coarsen downward, increase in amt of sand	HNU of sample - oppm
15-19.5'		14'-15' SS4	X	Bedrock	Rough drilling at 15' cored bedrock K 15-19.5'
				TD 19.5'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANGB2-MW37	DRILLING STARTED: 8-15-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-15-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: P. Riemersma + M. Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		100% SSI		Clay, ^{v brown} some silt, trace sand, fine pliable, soft, moist to slightly moist	AN of sample 1.5-2.0 ppm
5-16				Clay, brown, some silt, ^{little} some gravel and pebbles 4g-1" diameter, firm, moist from 5-5 1/2, slightly moist 5-16	Hnu of sample < 1.0 ppm
16-18.5'				Sand, brown, fine to coarse, some gravel, little clay, loose, wet 16-16'8" Clay, some as above, 5-16, little pebbles, moist 16'8"-18 1/2', some pebbles up to 5' diameter Bedrock, 18-18 1/2', etc	Hnu of sample 1.9 ppm
				TD @ 18 1/2'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE ____ OF ____

WELL/BORING ID: DANGB 2- MW 38	DRILLING STARTED: 8-13-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-13-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS:	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		60% SS1		Clay, ^{brown} some silt, little sand, ^{fine} trace pebbles, firm, slightly moist	Hum of sample < 1 ppm
5-10		100% SS2		Clay and Silt, brown, little sand, fine, ^{little} same gravel, firm slightly moist	Hum of sample < 1 ppm
10-15.5		200% recovery SS3		10'-10"2" Gravel and sand, fine-course, wet, loose, rock fragments clay and Silt, brown same as 5-10'	Hum of sample < 1 ppm
15.5-19		100% SS4		Clay and silt, same as above	
19-20'				Bedrock,	
				rd @ 20'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANG82 - MW38A	DRILLING STARTED: 8-12-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-12-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter Riemersma and Mike Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		60% SS1	got upper 2-2 1/2' m recovered	Clay, brown, some silt, a little pebbles, rounded 1/4-1", slightly moist, firm	H ₂ O of sample < 1 ppm
5-10		100% SS 2		^{brown} Silt, some clay, some pebbles, Firm to very stiff, moist to dry (8 1/2-10) Some pebbles up to 4"	H ₂ O of sample < 1 ppm
10-15 13.5		100% r. extruded		Silt, some clay, same as 8 1/2-10' interval, very stiff, dry to slightly moist	H ₂ O < 1 ppm H ₂ A < 1 ppm but something hard (boulder?) at 13.5'
13.5-16 16-16' 8"				Boulder, gabbro, dark gray-black color Gravel, fine to coarse, some coarse sand, angular to sub rounded, loose, minerals include rock fragments and rounded pebbles ABANDONED @ 25'	

Q346

ENGINEERING-SCIENCE DRILLING RECORD

w
PAGE 1 OF

WELL/BORING ID: DANGB 2 - MW 40	DRILLING STARTED: 8-16-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-16-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E. Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5	60% 0-3 1/2 SS1			^{brown} clay, little silt, pliable, firm, moist 0-3 1/2 with Sand, brown, some gravel, two inches thick at 3'-3'2", dry to slightly moist	Hnu of sample < 1 ppm
5-15.5	100% SS2			clay, brown, some silt, pebbles 1/4" - 1/5" diameter common throughout this interval, trace sand, fine, moist to slightly moist, pliable, wet fine sand at 14.5-15.5	Hnu of sample 0-1.5 ppm Hnu of sample 15-15.5 < 1 ppm
15.5-17	SS3			clay, same as above, small 1" long 1/2" thick oolitic sand, fine-medium Bedrock, 16'3" - 17'	
				TO @ 17'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANGB2 MW 41	DRILLING STARTED: 8-17-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-17-88
PROJECT NO: OR001	DRILLING METHOD: Roto sonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike Roddy	WATER LEVEL DATE:
SIGNATURE: Mike Roddy	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		80%		Clay, brown, little silt, abundant pebbles 1/4" to 3". Dry to moist. 4-5' gray clay layer, firm, very tight.	HNU of sample LC ppm
5-7'		100%		5-7' silt, brown, little sand and clay, abundant pebbles 1/4" to 3" wet.	HNU of sample LC ppm
				8-9' clay, brown, some silt, little abundant pebbles 1/4" to 3", wet.	
				9-12' silt, brown, some clay, little sand, abundant pebbles 1/4" to 3" moist to wet	
				12-15' clay, brown, little silt, firm to very firm, moist, abundant pebbles 1/4" to 3"	
15-20'		80%		clay, brown, some silt, firm, moist, abundant pebbles 1/4" to 4"	HNU of sample LC ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANGZ WP-6	DRILLING STARTED: 8-1-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-3-88
PROJECT NO: OR001	DRILLING METHOD: Hollow Stem Auger
DRILLER: North Star Drilling Co.	SAMPLING METHOD: split spoon
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-2	6-11-15-16	SS-1 80%		Silt, some sand, some clay, some silt, light brown, upper six inches dark brown, loose, rare pebbles, upper 6 inches root fragments, dry, no odor	Oppm split spoon heads pace
5-7'	6-10-18-32	SS-2 80%		Clay, some silt, medium to dark brown, w/pebbles to > 15". At base is a dark brown to black coarse grained sand. slightly damp, no odor	Oppm split spoon heads pace HA - oppm
10-12		no sample split spoon recovery			HA - oppm
10-12'	11-14-24 -6 for 2"	SS-3 70%		upper 10' of spoon CLAY, moderate brown STR 3/4, some sand, pebbles, black heavy minerals (hornblende?) common, slightly damp and sand, in lower 8" dusky yellowish brown 10YR 2/2 LkK looking) medium to coarse, pebbly, subangular quartz and black accessory minerals, sand is net, We found 1 inch angular pebble 802	move 7' W to new location samples termed WP6-2 HA 0 ppm HB 0 ppm Water at 10.5'
15-17'				No split spoon taken due to rocks TD at 25.4	HA 41 ppm HB 41 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANGB2LWP7	DRILLING STARTED: 8-17-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-17-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike Roddy	WATER LEVEL DATE:
SIGNATURE: Mike Roddy	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		80%		Clay, brown, some silt, plastic. Organic fragments - ^{thin} peat layer at 1" approximately 8" thick moist to wet 0-5', pebbles 1/4" to 3" common	HNU of sample < 1 ppm.
5-8'		100%		Clay and silt, ^{fine sand} brown, plastic to firm. abundant pebbles 1/4" to 3", moist to wet. Alternating clay layers with 6"-8" thick with coarser silt, some sand, abundant gravel layers between. Coarse layers are saturated	HNU of sample < 1 ppm.
8-11'		100%		8-9' Sand, brown, little silt and clay, abundant gravel 1/4"-2" wet-saturated	HNU of sample < 1 ppm.
11-15'		100%		9-10' Clay, brown, abundant pebbles, moist, sand, brown, little silt abundant pebbles 1/4"-2", wet 11-12' sand, brown, little clay and silt, pebbles 1/4"-3" abundant, wet 12-15' Clay, ^{80%} brown, firm, abundant pebbles 1/4" to 3", moist to damp	HNU < 1 ppm.

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANG B2 WP 8	DRILLING STARTED: 8-17-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-17-88
PROJECT NO: OR001	DRILLING METHOD: - Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike Roddy	WATER LEVEL DATE:
SIGNATURE: Mike Roddy	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		90%		Clay, brown, little silt, soft, some pebbles 1/4" to 2".	HNU of sample < 1 ppm
5-8'		100%		Tan brown 0-3 1/2', dark brown 3 1/2'-5'	
8-12'		100%		Clay, brown, little silt, soft. Some pebbles 1/4" to 2", moist.	HNU of sample < 1 ppm
12-14'		100%		Clay, brown, some silt, little sand, abundant pebbles 1/4" to 4", moist to damp.	"
14-15'		100%		Silt, brown, some clay, little sand, abundant pebbles 1/4" to 4", wet	"
15-18'		100%		Gabbro, gray, massive, pebbles bottom?	"
				Gabbro, gray, massive bedrock	"

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANGBZ WP 7D	DRILLING STARTED: 8-16-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-16-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLE BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		100% SS 1		<u>Clay</u> , brown, little silt, some organic plant fragments, 0-1' moist, pliable <u>Peat</u> , black, 1-2' moist <u>Clay</u> , some silt, little sand, fine, pebbles 1/4"-3" common, wet from 3-5', to very moist, thin sand lens appear saturated	Hnu of sample < 1 ppm
5-15'				5-10' <u>Clay</u> and <u>Peat</u> , brown and black, mottled, some silt 5-6', very moist, firm <u>Clay</u> , some silt, some pebbles, same as clay from 3-5", very moist 6-7' <u>Sand and Gravel</u> , fine to coarse, gravel is angular to subrounded, little clay, loose, wet, from 7-9 1/2' some pebbles 1/4-4" diameter <u>Silt</u> , d. brown, some clay, trace pebbles, slightly moist, very firm to dense <u>Sand and Gravel</u> , layer fine to coarse, same as sand and gravel layer above, 13.8-14.0 but increasing pebbles to 30%, wet <u>Silt</u> , same as silt from 9 1/2-13, 14-15'	Hnu of sample < 1 ppm Hnu

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF 2

WELL/BORING ID: DANG52 WP 7D	DRILLING STARTED: 8-16-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
15-23.4'		100% 55		Gravel, fine to coarse, angular, some pebbles, wet, loose, some sand; 15-15 1/2'	from of sample 1 ppm
23.4'-25'				Silt, d. brn, same clay, some pebbles, rounded diameter up to cobble size 4", slightly moist, very firm (very stiff). - becomes moist at 18' with increase to little sand, fine - is dry at 22-23.4', very hard few pebbles,	
25'-29'				Silt and Clay, brown, some pebbles 1/4-1"; rounded to angular, dry to slightly moist, very firm to hard,	
29-33'				Bedrock 26 1/2-29', cobbles from 26 1/2'- Bedrock	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B3 MW29	DRILLING STARTED: 8/30/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/30/88
PROJECT NO: OR001	DRILLING METHOD: Reverse
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S. Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		80%		Clay and silt, brown, trace sand, abundant pebbles 1/4" to 4", moist to wet, soft	FINO OF sample Lippen
5-16		90%		clay and silt, same as 0-5	FINO OF sample Lippen
5-7					
7-14				Clay, brown, little to some silt, abundant 1/4" to 4" pebbles wet, firm	
14-16				Sand, brown, little gravel, some silt, trace clay, soft, wet, abundant 1/4" to 3" pebbles	
				TD 16'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B3 MW25	DRILLING STARTED: 5/26/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/26/88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike Ruddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		80%		Clay, brown, some silt, trace sand, abundant 1/4" to 1/2" in diameter pebbles, soft, moist to wet	HNU of sample < 1 ppm
5-15		100%			
5-14				Clay and silt, brown, trace to little sand, abundant 1/4" to 1/2" pebbles, soft to firm, wet	HNU of sample < 1 ppm
14-15 1/2				Sand, brown, some clay and silt, abundant pebbles 1/4" to 2", soft, wet	
14 1/2-15				Same as 5-14	
15-18		100%		Gabbro, gray, massive, coarse-grained intrusive rock, plagioclase with minor pyroxene and opaque metallic mineral	HNU of sample < 1 ppm
				TO 18'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B3HW30	DRILLING STARTED: 8/21/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/26/88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S. Rodda	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5.5		80%		Clay and silt, brown, trace sand abundant 1/4" to 1/2" pebbles, moist to wet, soft to firm, gabbro boulder from 1 1/2" - 2 1/2"	HNU of sample 21 ppm
5 - 6.5		100%		Clay and silt, mottled brown and gray, wet, firm, abundant 1/4"-1/2" pebbles: boulder 5 3/4" - 6 1/4"	HNU of sample 21 ppm
6.5 - ^{nsc} 9		100%		Gabbro, gray, massive, coarse grained plagioclase, opaque metallic and minerals	HNU of sample 21 ppm
9 - 15		100%		Silt, brown, some clay, little sand, abundant 1/4"-1/2" pebbles soft-firm, wet	HNU of sample 21 ppm
15 - 17.5		80%		Silt, brown, some clay and sand abundant 1/4"-1/2" pebbles, soft, wet Similar to 9-15 T.D. - 17.5 Ft	HNU of sample 21 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B3 MW 26	DRILLING STARTED: 8/26/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/26/88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD: <i>Roto Sonic</i>
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: <i>Mike S Roddy</i>	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		60%		Clay, brown, little to some silt. abundant pebbles 1/4" to 1/2" in diameter moist-wet, soft	HNU of sample L ppm
5-14.5		100%		2nd gravel layer ^{above sand} between 4-4.5' Clay and silt, brown, trace to little sand, abundant 1/4" to 1/2" pebbles, wet, soft-firm	HNU of sample L ppm
				TD 14.5 ft	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG 33 MW 27	DRILLING STARTED: 8/24/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/24/88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		80%		Clay and silt, gray to brown (1-2)	HNU of sample.
0-2				Trace sand, occasional pebble 1/4"	2 ppm
2-5				2" Wet to moist, soft	
				Clay, brown, mottled, little to some	
				silt, occasional pebbles 1/4"-2"	
				moist to wet, soft	
5-15		100%		Clay, brown, some silt, abundant	HNU of sample
				pebbles 1/4" to 4" in diameter,	2 ppm
				wet, firm to very firm	
				TD 15'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B3 mw 28	DRILLING STARTED: 8/27/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/27/88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S. Reddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		80%		Clay, black, little silt, moist soft	HNU of sample L1 ppm
0-1'					
1-4'				Clay, mottled gray and brown, little silt, occasional 1/4-2" pebbles, moist, soft	
4-5'				Clay, brown, some silt, abundant 1/4-2" pebbles	
5-11.5'		100%		Clay and silt, brown, trace sand, abundant 1/4" to 1/2" pebbles, moist to wet, soft to firm	HNU of sample L1 ppm
11.5-12.5'		100%		Gabbro, gray, massive, very coarse grained, some chloritic alteration, probably a breccia	HNU of sample L1 ppm
12.5-15'		50%		Clay and silt, brown, trace sand, abundant 1/4" to 1/2" pebbles, moist firm to very firm	HNU of sample L1 ppm
				TO 15'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE () OF ()

WELL/BORING ID: DANG 13 MW 31	DRILLING STARTED: 8/27/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/27/88
PROJECT NO: OR001	DRILLING METHOD: Rotary
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S. Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		80%	ss 1	Clay and silt, tan brown, little sand abundant pebbles 1/4" to 1/2" in diameter, soft, moist to very moist	HNU of sample < 1 ppm
5-7 1/2'		100%		Clay and silt, brown, trace sand, abundant 1/4" to 1/2" pebbles fine, moist	HNU of sample < 1 ppm
7 1/2'-15'		15%	ss 2	Clay and silt, brown, trace sand, abundant 1/4" to 1/2" pebbles, wet soft-fine	HNU of sample < 1 ppm
15-18'		80%	cutting	Boulder from 7 1/2' - 8 1/2'	HNU of sample < 1 ppm
15-16'				Sands and gravels, gray, fines washed away	
16-18'				Gabbro, gray, massive, coarse-grained plagioclase, Pyx, melilite opaque metallic minerals probably K-feldspar	
				TW 18'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG 3 mw 33	DRILLING STARTED: 8/27/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/27/88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S. Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5 0-1		60%		Clay and silt, black, abundant 1/4" to 2" pebbles, abundant organic matter, soft, moist	HNU of sample 21 ppm
1-5				Clay and silt, brown, abundant 1/4" - 3" pebbles, firm, moist	
5-15 5-12		100%		Clay and silt, brown, trace sand, abundant 1/4" to 2" pebbles, moist to wet (10-12), firm	HNU of sample 21 ppm
12-15				Silt, brown, some clay and sand, abundant 1/4" to 3" pebbles, wet, firm	
15-21		100%		Silt, brown, some sand and clay, abundant 1/4" to 3" pebbles, firm, wet	HNU of sample 21 ppm
21-24 21-21.5		70%		Sands and gravels, gray-brown, fines washed out by drilling	HNU of sample 21 ppm
21.5-24				Gabbro, gray, massive probably bedrock	
				TD - 24'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B3 MW 34	DRILLING STARTED: 8/29/85
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/29/85
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S. Ruddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		75%		Clay, brown, little to some silt, abundant 1/4" to 3" pebbles, soft moist	HNU of sample 21 ppm
5-15 5-7		100		Clay, brown, some silt, abundant 1/4" to 3" pebbles, soft moist	HNU of sample 21 ppm
7-13				Clay and silt, brown, trace of sand, abundant 1/4" to 3" pebbles, soft to firm, moist to wet	
13-15				silt, brown, some clay, trace sand, abundant 1/4" to 3" pebbles, firm, wet TD 15'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B3 MW 35	DRILLING STARTED: 8/25/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/25/88
PROJECT NO: OR001	DRILLING METHOD: 12 in. sonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S. Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5 0-2		80%		Sand, black-brown, some silt, trace clay, abundant pebbles 1/4" to 4", moist to wet, soft	HNU of sample L'ppm
2-5				Clay, brown, some silt, abundant pebbles 1/4" to 4", wet, soft	
5-11.5		85%	SS3	Clay, brown, some silt, trace sand, abundant pebbles 1/4" to 4", wet, firm to very firm	HNU of sample L'ppm
11.5-14'		80%		Gabbro, gray, massive, coarse-grained, intrusive rock - boulders	HNU of sample L'ppm
14-15'		Lost			
15-16'		80%		Clay, brown, some silt and sand, abundant pebbles 1/4" to 4", wet, firm, similar to 5-11.5	HNU of sample L'ppm
16-17'				Sand, brown, some silt, little clay, abundant 1/4-3" pebbles, soft wet, metal notations found in core	
17-17.5'				Gabbro, bedrock? TO 17.5'	

ENGINEERING-SCIENCE DRILLING RECORD

Abandoned

PAGE 1 OF 1

WELL/BORING ID: DANG B3 MW 35	DRILLING STARTED: 8/25/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/25/88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S Ruddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		60%	SSI	Silt, brown, some sand, little clay, abundant pebbles 1/4" to 3", moist	HNU of sample 21 ppm
0-2				soft	
2-3			SSZ	Sand, brown, some silt, trace clay, abundant pebbles 1/4" to 4", wet	
				soft	
3-5				Clay, brown, little to some silt	
				trace sand, abundant pebbles 1/4" to 4", moist to wet, firm	
5-6.5		100%		Silt and clay, ^{brown} little sand, abundant pebbles 1/4" to 4", wet, firm	HNU of sample 21 ppm
6.5-7.5		100%		boulder? chloritically altered Gabbro, trace sulfides	
				TD 75 ft	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B4 mw 21	DRILLING STARTED: 8-20-1938
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD: <i>Rotasonic</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER: <i>Mike Roddy</i>	STATIC WATER LEVEL:
GEOLOGIST: <i>Mike Roddy</i>	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		40%		<u>Sand and silt</u> , brown, soft little to some clay, soft pliable, wet from 3-5 ft.	HNU 21 ppm
5-15		100%		<u>Sand</u> , brown, some silt and clay, little pebbles 1/4"-2", soft, pliable, wet.	HNU of sample 21 ppm
5-6				<u>Clay</u> , brown, little silt, few pebbles 1/4" 1", soft, wet	HNU of Auger and borings zero 21 ppm
6-8				<u>Silt and clay</u> , brown, little sand, abundant pebbles 1/4"-2", soft, wet	
8-10				<u>Sand</u> , brown, some silt and clay, abundant pebbles 1/4" to 2" wet, soft	
10-11				<u>clay</u> , brown, some silt, soft, abundant 1/4"-3" pebbles, wet	
11-12				<u>Silt and clay</u> , brown, abundant pebbles 1/4" to 2", wet, soft	
12-13				<u>clay</u> , same as 11-12'	
13-15				<u>Clay</u> , brown, little to some silt, abundant pebbles 1/4" to 2", moist, STIFF	HNU of sample 21 ppm
15-19		100%		<u>Bedrock</u> , ^{possible} narrow sand and gravel layer just above it.	HNU of sample 21 ppm
19-22.5		100%		<u>Bedrock</u> , ^{possible} narrow sand and gravel layer just above it. rather, fine crystalline, massive, coarse grained intrusive rock, plagioclase laths from 1/4" to 5/8", pyroxene possible sulfides	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANGB-4-MW 22	DRILLING STARTED: 8-20-1988
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-20-1988
PROJECT NO: OR001	DRILLING METHOD: <i>Rotary</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: <i>Peter E. L. ...</i>	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'8"		SSJ 70%		<i>Peat</i> , black, some organic material, moist, plant roots	H ₂ O of sample < 1.0 ppm
5-15 5'8"-15'8"				<i>Clay</i> , mottled gray and brown from 5-7', brown from 7-15', little silt, <u>no</u> gravel or pebbles, plastic, firm, very moist from 5-8', moist to from 8-15'	H ₂ O of sample < 1.0 ppm H ₂ O of auger borehole 150 ppm H ₂ O of breathing zone < 1 ppm water table est 5' 8:49 AM H ₂ O of auger hole < 1.0 ppm Breathing zone < 1.0 ppm
15-25 15'8"-25'8"				<i>Clay</i> , brown, little silt, no gravel or pebbles, plastic, firm, 15-21 <i>Sand</i> , fine, layers 1-2" thick at 18.5 and 19.5, wet <i>Silt</i> , some clay, brown, 3" <i>Sand</i> , fine layers at 22.2, 23, 23.5, no gravel or pebbles, wet, loose	H ₂ O of sample < 1.0 ppm
25-31 25'8"-31'8"				<i>Silt</i> , some clay, some gravel and pebbles 1/4-1" diameter, firm to moist, <i>Sand</i> , some brown, fine, some silt, some clay, wet 30.5-31	H ₂ O of sample < 1.0 ppm

Change in depth when table height was measured

PAGE 2 OF 2

WELL/BORING ID: DANGB-4-MW22	DRILLING STARTED: 8-20-1988
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-20-1988
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
22-35 318"				Bedrock	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANGB-4-MW23	DRILLING STARTED: 8-18-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD: <i>Rotary</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: <i>Rev. E. Riemersma & Mike Roddy</i>	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		80% ^x SS1		Clay and silt, brown, some gravel and pebbles 1/4-1", loose, slightly moist, 0-4' Peat, small roots and plant material visible, damp, 4-5'	Hdr of sample < 1 ppm
5-15'		SS2		Peat, same as above 5-7' Clay, mottled green and brown, little silt, pliable, firm in core, 7-7 1/2' Clay, same as above but brown, and some silt 7'6" - 7'9" ^{brown} ^x Clay, some silt, some sand, fine, wet, loose, 7'9" - 8'1" Clay, brown, little silt, pliable moist to very moist, trace pebbles 8'1" - 13'5" Silt, and Sand ^{PER} same as fine to medium, ^{little} some clay, very moist. loose 13'5" - 14'	Hdr of auger hole 0 ppm borehole zone 0 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF 2

WELL/BORING ID: DANGB-4-MW23	DRILLING STARTED: 8-18-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-18-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter + Mike	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
15-25		100% SS3		Silt, brown Clay, brown, some silt, trace little pebbles 1/4-1" diameter, firm moist from 19-21.5, slightly moist from 21.5-25, number of pebbles increase downward	Thru of sample < 1 ppm
25-31		85% SS4		Silt, brown, some sand and clay, little some pebbles 1/4" to 4" diameter, moist to wet, soft	Thru of sample < 1 ppm
25-27				Sand, brown, little silt and clay, Abundant pebbles 1/4" to 2", wet, soft,	Lab sample labeled SS3
31					
27-30					
30-31					
31-33'10"			Bedrock		

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B4 - MW 24	DRILLING STARTED: 8/24/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/24/88
PROJECT NO: OR001	DRILLING METHOD: <i>Roto Sonic</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: <i>Mike S Roddy</i>	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5 0-3 1/2		50%		<u>Sand</u> , brown, some clay and silt. Some pebbles 1/4" to 2" in diameter. Wet to moist, soft.	HNU of sample < 1 ppm
3 1/2-4 4-5				<u>Sand</u> , brown, trace silt and clay, wet, soft.	
5-15 5-8		90%		<u>Clay</u> , gray, little silt, firm, moist to wet.	HNU of sample < 1 ppm
8-12				<u>Clay</u> , brown, little silt, little sand, abundant pebbles 1/4" to 4" in diameter, soft, wet.	
12-13				<u>Clay</u> , brown, little silt, trace sand, abundant pebbles 1/4" to 3", moist to wet, firm.	HNU of sample < 1 ppm
15-25		100%		<u>Clay</u> , brown, some silt, little sand, abundant pebbles 1/4" to 4" in diameter, wet, firm.	HNU of sample < 1 ppm
25-33' 0"		50% 60%		<u>Clay</u> , brown and gray mottled appearance, some silt, little sand, abundant pebbles 1/4" to 2".	HNU of sample < 1 ppm
33' 10"-37'				<u>Gabbro</u> , ^{gray} massive, massive, intrusive rock. - probably bedrock. Chloritic alteration along fractures.	HNU of sample < 1 ppm
				TO 37'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANGB-4-WP11D	DRILLING STARTED: 8-11-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-19-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		80% 551		Clay, brown, some silt, abundant pebbles 1/4-2' diameter, Peat, dark brown to black layers 1" thick within interval firm, slightly moist, upper 6" of interval is Peat	thru of sample x 1 ppm may be fill material
5-7		100%		Peat, dark brown to black, small plant fragments, soft, moist no pebbles	but something hard at 7' thru of sample x 1 ppm
7-15.5				Peat, same as above, 7-9', wet Silt, brown, some clay, trace pebbles, stiff, moist with very moist zones 9-12.8' Sand, fine-medium, little silt, ^{some RR} little clay, 2" thick from 12.8-13.3, sand (1/2" thick) 13.3' to 17.5', loose, pebbles Silt, same as 9-12.8' to 15.5'	
15.5-23.5				^{brown} Silt, some clay, some gravel and pebbles, very firm to stiff, slightly moist 15.5-17.5' Sand, green-brown, ^{gray} fine to medium, trace clay, little silt, sub angular, loose, moist, 17.5-17.7' Silt, same as 15.5-17.5' to 23.5' bottom 4" is moist to very moist abundant pebbles up to 2"	sand is from disintegrated rock

ENGINEERING-SCIENCE DRILLING RECORD

PAGE ____ OF ____

WELL/BORING ID: DANGB-4 WP 11D	DRILLING STARTED: 8-19-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-19-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
23.5-24.3		100%		Bedrock, TD 24.3'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANGB-4-WP 12 S	DRILLING STARTED: 8-22-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-22-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		50% 0-25		<u>Clay</u> , brown, organic fragments some silt, moist 0-1' <u>Silt</u> , ^{brown} some clay, dry to slightly moist, some pebbles 1/4-1" firm to hard 1-2.5'	Two of sample 1.1
5-10				<u>Clay</u> , brown, some sand, fine, soft, wet, little silt 5-7' <u>Clay</u> , black-dark gray, little silt, pliable, soft, 7-7.5' moist, <u>Clay</u> , mottled brown and dark grey, little silt, little ^{small} pebbles, pliable, little sandy fine moist 7.5-9 <u>Silt</u> , ^{brown} some clay, some pebbles 1/4-1" diameter, some sand, fine, very moist, firm 7-10'	Two of sample 2.1

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF

WELL/BORING ID: DANGB-4-WP12.5	DRILLING STARTED: 8-22-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-22-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
10-18'				<p>Clay, brown, some silt, little pebbles, very moist, 10-11'</p> <p>Silt, same as 9-10', brown abundant rounded pebbles 1-3" in diameter, some gravel</p> <p>Slightly moist, firm to very firm</p> <p style="text-align: center;">TP at 18'</p>	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE ____ OF ____

WELL/BORING ID: DANGB-4-WP 12 D	DRILLING STARTED: 8-22-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E. Riemersma	WATER LEVEL DATE:
SIGNATURE: <i>Peter E. Riemersma</i>	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLE BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
15-25		100%		Silt, brown, some clay, abundant pebbles and gravel, diameter from 3/4 - 3", most are slightly more rounded, firm, 15-24' 6" decrease to little clay from 20-24'	Have CF sample < 1.0 ppm
25-31.3'		100% poor recovery appears to be similar to that above		Sand, brown, fine, some silt, little clay, some pebbles, very moist, 24' 6" - 25', base Same as above, note poor recovery	
31.3'-34" 11				Bedrock, granitic appearance	

71
 41.2
 6.1
 34"

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANGB-4-WP 12 D	DRILLING STARTED: 8-22-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-22-88
PROJECT NO: OR001	DRILLING METHOD: <i>Rotasonic</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		50% SSI (2-2.5)		^{brown} Clay, some silt, abundant pebbles 1/4-1/2", dry, very firm to dense	it: v illuv of sample <1.0ppm
5-15				Clay, brown some silt, same as above 5-6, slightly moist Sand, brown, fine, some silt, moist, stiff 6-6'6" Clay, greenish blue, little silt, pliable, moist, trace sand, fine, soft 6.5'-7.5' Clay, brown, some silt same as 5-6', 7.5-8' Clay, mottled brown, green and red, some silt, little sand, dense, fine to medium, moist to very moist, disintegrated rock, firm 8-10.5' Silt, ^{brown} some clay, pebbles and gravel abundant, some sand, fine, moist, 10.5-11.5' Clay, brown, some silt, ^{abundant} pebbles, rounded up to 3" diameter, slightly moist, firm to very firm	thru of sample < 1.0 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WP

WELL/BORING ID: DANG E. -4-13 S	DRILLING STARTED: 8-22-1988
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E. Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0- 5 10 11		60%		<p><u>Clay</u>, brown, some silt, some pebbles, 1/2-2" diameter, black layer at 6", slightly moist 0-10'</p> <p><u>Sand</u>, brown, fine, some clay 10-11</p> <p>TD 11.5'</p>	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WP

WELL/BORING ID: DANGB-4-13D	DRILLING STARTED: 8-22-1988
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E. Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		80%	2-8'	<u>Silt</u> , ^{brn} some clay, little pebbles, firm, slightly moist 0-3' <u>Peat</u> , black, organic rich 3-4' <u>clay</u> , <u>Silt</u> , same as silt above from 0-3'	
5-15'		100%		<u>clay</u> , mottled brn and grey, some silt, firm, moist 5-6' <u>Sand</u> , ^{light} brown, fine, some clay, little silt, <u>wet</u> , in loose-firm, little gravel 6-10' <u>clay</u> , brn-with gray, little silt, very plastic, soft, moist 10-15'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF 2

WP

WELL/BORING ID: DANGB-4-13D	DRILLING STARTED: 8-22-1988
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-27-1988
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
15-21				<p>Silt, brown, some clay, little sand, fine, in lenses, soft to firm, moist 15'-17'</p> <p>clay, brown, little silt, friable, soft, moist 17-18'</p> <p>Silt, same as 15'-17' above, some pebbles, 1/4-2", rounded, 18-21'</p> <p>some little gravel, little sand, fine</p>	11 min. sample 21.0 pp m
21-25				<p>Bedrock</p>	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANGB-4-WP14D	DRILLING STARTED: 8-23-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-23-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter Riemersma Mike Ruedy Jo Ann Herwig	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LB.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		60% 0-3		Silt and clay, brown, little pebbles 1/4-1" diameter, slightly moist, very firm to hard. Two inch (2") <u>Peat</u> , black from 2' to 2'2"	Hand sample 0 ppm
5-15		100%		Silt, same as above, 5-6 Sand, brown, fine to coarse, little gravel, little clay, wet, loose 6-8.5 Clay, dark brown, little silt, moist to very moist, pliable, firm 8.5-15'	Hand sample 11 ppm
15-21.5 24				Clay, same as above but moist 15-18 ft 21 Clay, brown, little silt, little gravel and pebbles, some pebbles 1/2-3" diameter, same Sand, fine, laminations throughout interval, 1-2" thick PER 8-23-88 Sand and clay, brown, little silt, little gravel and pebbles, wet to very moist, loose, some pebbles 1/2-3" 21-24'	Hand sample 0 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE ____ OF ____

WELL/BORING ID: DANGB-WP 14 S	DRILLING STARTED: 8-23-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-23-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: P. R. Kinnear, Mike Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		60% 0-3		Silt and clay, brown, some pebbles, 1/4-2", Peat layer, 2-3" thick at 2.5-2.7, slightly moist	Hand of Sample 2 ppm
5-12		670% condensed		<p>silt and clay, mottled brn and black, same as above, 5-6</p> <p>Sand, brown, fine-course, some gravel, little clay, loose, wet, gravel layer at 8' about four inches thick, 6-10</p> <p>clay, dark brown, little silt, gritty, Firm, moist, 10-12</p> <p style="text-align: center;">_____ TD at 12'</p>	Hand of Sample 2 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF 2

WELL/BORING ID: DANG3-4-WP14D	DRILLING STARTED: 8-23-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
24-27.5				Bedrock, TD 27.5'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B4 - WP15 S	DRILLING STARTED: 8/23/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S. Rodde	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5' 0-1'		60%		Q-1 Sand and silt, brown, a number pebbles 1/4" to 2" in diameter. moist, soft, friable.	HNU of sample 41 ppm
1-5'				peat, black, very soft moist	
5-12		100%		clay, brown to tan, ^{some silt} abundant pebbles 1/4" to 3/4" in diameter. moist to wet, soft	HNU of sample 41 ppm
12-17		80%		clay, brown, little silt. Occasional pebbles 1/4" to 2" in diameter. moist to wet, firm	HNU of sample 41 ppm
				TO 17'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG B4-WP15 D	DRILLING STARTED: 8/23/88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8/23/88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Mike S Roddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	AMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5' 0-1'		80%		0-1 Sand and silt, brown, abundant pebbles 1/4" to 2" in diameter, moist, soft, pliable	HNU of sample 21 ppm
1-4' 4-4 1/4' 4 1/4-5'				peat, black, very soft, moist Sand and clay, brown, soft, moist pliable clay, brown, some silt, trace sand, soft, moist, occasional pebbles 1/4" to 2" in diameter.	
5-15'		100%		clay, brown, some silt, abundant pebbles 1/4" to 1" in diameter, lower 5' firm, upper soft soft, moist.	HNU of sample 21 ppm
15-25'		90%		clay and silt, brown, trace sand, abundant pebbles 1/4" to 3" in diameter. Wet, firm to very firm.	HNU of sample 21 ppm
25-29'		0%			
29-31.5'		100%		Gabbro, gray, holocrystalline massive, coarse-grained intrusive rock, plagioclase, pyroxene, trace opaque metallic minerals TD 31.5 Ft	HNU of sample 21 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE ____ OF ____

WELL/BORING ID: DANGS-4-WP 16 D	DRILLING STARTED: 8-18-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD: <i>Rotary</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E. Remersma Mike Raddy	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		100% SSI		<p><u>Sand and Gravel</u>, black, fine to coarse sand, some silt, loose, surface fill, slightly moist 0-1 1/2</p> <p><u>Silt and Sand</u>, fi brown, fine, some clay moist, loose, pebbles 1/4-4" diameter 1 1/2-2 1/2</p> <p><u>Sand</u>, brown-black, fine-medium, little clay, <u>wet</u>, loose 2 1/2-3</p> <p><u>Clay</u>, brown, some silt, plant roots, probably marks end of fill</p> <p><u>Peat</u>, black, soft, moist</p> <p><u>gray-black clay</u>, trace silt, pliable, soft, moist</p>	<p>Am of sample < 1 ppm</p> <p>water table at 2 1/2'</p> <p>Fill to 3'</p>
5-14		100% SSI		<p><u>clay</u>, brown, little silt, very soft, pliable very moist from 5-8, moist from 8-10, slightly moist from 10-14 trace pebbles from 5-10 some pebbles (abundant) from 10-14 firm from 10-14</p>	<p>Am of Sample or < 1 ppm</p> <p>1/4-1 1/2" diameter</p>
14-2x 17'				<p><u>Clay</u>, brown, little silt, pliable, soft moist, 14-16.8', massive some silt at 16-16.8', trace pebbles</p> <p><u>Sand</u>, brown, fine, very moist, loose 16.8-17'</p>	<p>hit rock at 14'</p> <p>Am of sample 2.0 ppm</p>

ENGINEERING-SCIENCE DRILLING RECORD

PAGE ____ OF ____

WELL/BORING ID: DANG B-4 WP 16D	DRILLING STARTED: 8-18-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
17-20 ^{ft}				Sand and Gravel, brown, little silt little clay, wet, sand and gravel is fine to coarse, some pebbles 2" diameter 17-20	THW < 1.0 g/m
20-22				Silt, some clay, brown, pebbles up to 2" diameter	
22-23.5				Silt, brown, some clay, some pebbles and gravel, hard, slightly moist to dry	THW of sample < 1 ppm
23.5-24.4'				Bedrock TP at 24.4'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANG 8 MW 14	DRILLING STARTED: 8-8-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-9-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD: continuous
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		70% (3 1/2) SS1	0-1' x	clay, brown, ^{some} gravel 1/8 - 1/2" diameter, moist in upper 1', dry from 1-9' loose [Fill]	Hand sample of c/p/m HB 0 p/m
5-10		SS2		clay and silt, ^{brown} some little gravel, to 7', dry, loose, some plant fragments at top Silt, some gravel, up to 35%, some some clay, wet, loose some pebbles up to 4" diameter in this interval	Hand sample of c/p/m Driller says hit water at 10' Sample wet at 7'
10-15		SS3		Sand and Gravel, brown to dark brown, little medium-coarse grained, angular quartz and rock fragments, interclay; wet, loose, pebbles 1/4 - 3" common to 12' Silt, ^{some} sand, fine-medium, ^{some} some clay, ^{some} 1" gravel and sand lamination, wet, slightly firm, (12-15'), pebbles 1/2" diameter	HA 0 p/m HB 0 p/m
15-20.5		SS4 (3') 30%		clay, ^{brown} some silt, no pebbles or gravel, wet-slightly wet, pliable sand, medium fine, at estimated 16-16 1/2', some clay and silt, wet, interval sampled - 15-18	Don recovered due to wet sample clogging out through drill bit

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF 2

WELL/BORING ID: DANG 8 MW14	DRILLING STARTED: 8-8-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-9-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
25-33.5		100% SS5		Clay, ^{brown} little silt, trace fine-med sandy pebbles 1/4" - 1", wet, pliable sand is rounded	HA 0 ppm HB < 1 ppm HA HB Hw of sample at 3 locations < 1 ppm
33.5-35		SS6 100%		Clay, brown little silt, trace pebbles, wet to 34', loose, pliable ^{ly, silty} Clay, brn, little gravel, dry, firm 34-35', some pebbles	Harder drilling
35-39		SS7 100%		Clay, brownish red, some silt, ^{little sand} some pebbles 1/2" - 3", trace ^{granular, some} rock fragments slightly moist 35-36 dry, firm 36-38 moist, pliable 38-39	Hit boulder at 35' Hw of sample 0 ppm
39-42		SS8 100%	^{38' x 38-40'} Lab sample Sand from 37-39 1/2'	Sand and Gravel, ^{gray} coarse, subangular to angular, loose, from 39-39 1/2', some pebbles 1/2" - 1" Bedrock ^{to 42'} upper 6" fragmented	
42-44				Bedrock, gubbers TD 44'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG 8 MW/15 (shallow)	DRILLING STARTED: 8-9-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-9-88
PROJECT NO: OR001	DRILLING METHOD: Rotary
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'		100% SS1		Clay, ^{little} silt, brown, to light brown from 2-5, some pebbles 1/8" diameter, upper 2' loose with organic remains, lower 3' (3-5') firm, all dry except for upper 1' moist due to recent rain	Hum of sample 0 ppm
5-10'		100% SS2		Clay, brown, ^{little pebbles} silt, dry, 5-6' Sand and Gravel, to medium-coarse, angular, sand, quartz and rock fragments including feldspar, mafic minerals, wet, some little clay, some pebbles 1/2-1", rounded, 6'-10'	Hum of sample at three locations 0 ppm
10-15'		SS3 100%		Sand and Gravel, same as above, to from 10-12.5', loose Clay, brown, some silt, plastic, firm, from 12.5-14.5'	Hum of sample 0 ppm HB 0 ppm
15-20'		SS4 60%		Sand, fine to coarse, some clay, angular little pebbles 1/4-1/2", 14.5-15' Clay, brown, little silt, very plastic, very moist, TD 20'	Hum of sample <1 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANGB & MW16	DRILLING STARTED: 8-10-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-10-88
PROJECT NO: OR001	DRILLING METHOD: <i>Pulsasonic</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: <i>Peter E. Riemersma</i>	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		70% SS1		<i>black</i> <i>little silt</i> Peat, (clay and organics), 0-2' moist dry, 2-5, wet, very loose,	Hum of sample approx
5-10		SS2 100%		Peat, same as above to 6.5' Clay, little brown, little silt, pliable, wet, ^{trace} pebbles (6.5-10') no odor	Hum of sample at
10-15		SS3 100%		Clay, dark brown, little silt, some organics, as above, pliable, wet Sand, brown, fine to medium, trace coarse, trace gravel, ^{some} clay, 14-15, loose, wet	Hum of sample range from 0-3 ppm
15-20		SS4 100%		Clay, dark brown, little silt, pliable, moist wet, same as 10-14, trace pebbles 1/4 - 1/2" diameter	Hum of sample range from 0-3 ppm
20-25		SS5 100% elongated core recovery		<i>brown</i> Silt, some clay, little sand, fine 20-21 3/4, pure pebbles, very moist Sand and Silt, ^{some} 21 3/4-25, some clay, fine grained sand, trace pebbles	HA 8 < 1 ppm Hum of sample 3 ppm at one location 41 ppm at another
25-30		SS6 80%		Gravel, ^{1 1/4"} coarse, some sand, medium - coarse, total sand 1', from 28.8-30 28.8-30, Cored 2 1/2' of boulder gravel composed of rock fragments, angular, and quartz, feldspar, mafic minerals Boulder - appears to be same comp. as gabbro in bedrock	hit boulder at 28' 26.5' boulder is from 25.2-26.7-28.1

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANG68 HW16	DRILLING STARTED: 8-10-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-10-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
30-33.66'				Bedrock, TD 33' 8"	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANG B MW 17 Site 8	DRILLING STARTED: 8-10-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-10-88
PROJECT NO: OR001	DRILLING METHOD: <i>Rotasonic</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		100% SS 100%		<i>(clay)</i> <i>Pect, dark brn blk, organic material, plant fragments, dry 0-2', moist 3-5',</i>	<i>HA & V sample reading 0 ppm</i>
5-10				<i>Silt, some clay (35%), brown, firm, very moist to wet no pebbles, pliable</i>	<i>HA 41 ppm HB 41 ppm</i>
10-15				<i>Sand, some clay fine-med, some clay (25%) no gravel or pebbles 9 1/2' - 10'</i> <i>brown clay, some silt, wet, some pebbles, increase in silt in lower 2' with little sand, fine</i> <i>TD @ 15'</i>	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

SITE 8

WELL/BORING ID: DANG 8 MW 18	DRILLING STARTED: 8-5-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-5-88
PROJECT NO: OR001	DRILLING METHOD: <i>Ret-sol, L</i>
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E. Riemersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5'	SS1 <i>AB</i>	80%	*	Silt and clay, brown, little sand, numerous small pebbles and rock fragments 1/4" to 4" diameter, dry,	<u>Fill</u> H ₂ O of sample <1 ppm
5-15'	SS2	recovered 4' of 15' - 25%	*	Silt and Gravel, brown, in upper 1' of split core, probably from interbed 8-11' wet, some sand, firm little clay,	H ₂ O 0 ppm H ₂ A <1 ppm windy day
15-19'	SS3 14-15		*	Clay, brown, lower 3' of sample, some silt, little pebbles, dry, very firm, Bedrock, pieces are fractured into 3" pieces + 19'	Expected water table at ~ 8'

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF

WELL/BORING ID: DANGB8 MW 19	DRILLING STARTED: 8-10-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-10-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD: continuous core
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		SS 1 60%		dark brown clay, some silt, little sand, fine, slightly moist, no pebbles or gravel	Hand sample < 1 ppm
5-10		SS 2 100%		Silt, brown, some clay, (some sand at 7-8') very moist to wet from 5-10', Firm, some pebbles 1"-3" diameter. Wet at 7-8' sandy zone	Hand sample at 3 areas < 1 ppm
10-13.5		SS 3 9-10' 100%		Bedrock, core,	HA < 1 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG8 MW20	DRILLING STARTED: 8-5-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-5-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		100% SS1	6-2x	clay, brown, some silt, rare or trace pebbles, dry, very firm	
5-6.5		SS2 100%	6-8x LAB	Silt, brown, some sand, ^{fine} little clay, ^{1 some} 1/4-1/2" little pebbles, very damp - almost wet	0-6.5' gradual increase in amt of sand and silt
6.5-15'		SS3		^{fine} Silt, some sand, brown, little clay, little pebbles, <u>wet</u> , Firm to 8' then	Thin sample of fine Estimate top of water table at 6.5'
15-20.5'				clay, brown, some silt, little pebbles, <u>damp</u> to 9' then	Thin sample clippings
15-20.5'		SS4		Silt, some sand and gravel, fine to coarse sand, some rock fragments up to 5" diameter to 15' very damp, very firm. Some thin fine-medium sand lenses up to 5" thick in this section	
15-20.5'				Silt and clay, brown, some pebbles 1/8" - 3" randomly distributed, firm, damp, btm 2" bedrock	Thin 1/8" of sample
20.5-23.5'				Bedrock, corrod 3' into it - gabbro, competent, dark: grey-green	
				TD 23.5'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 2

WELL/BORING ID: DANG8 WP9D	DRILLING STARTED: 8-11-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-11-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-6'			30% SS1	Clay, light brown, little silt, organics, from 0-6", firm Peat, 6" black, organic rich, from 6" to 18" dry to slightly moist	Hum of sample oppm
6-10'			100% SS2	Clay, brown and black, some peat, moist, 6-7' 6-7' Sand and gravel, some pebbles, pebbles Sand, fine to coarse, wet, pebbles may be 1-3" diameter, color of interval 6-8" gray, 7-8.5 dark	Hum of sample 2.1 ppm
10-12'			100% SS3	clay, brown, little gravel, little pebbles, 8.5-11' moist Clay, brown, pliable, wet, 11-12'	Hum of casing AA oppm HB oppm
12-18'			100% SS4	Sand and Gravel, medium to coarse, some pebbles 1" to 3", angular, quartz and rock fragments, loose, wet, 12-13 1/2' Clay, same as 11-12' but from 13 1/2-16, some pebbles, silt, some clay, brown, pebbles 1/4-2" diameter 16-18', wet, moist, firm Gravel and sand, same as 12-13', from 18-18 1/2', wet Clay, same as 13 1/2-16, little silt, from 18 1/2-21, very moist Clay and silt, brown, some pebbles, 1/4-2", little sand, fine 21-26' pliable, very moist	Hum of sample 4.1 ppm
18-26'					Hum of sample oppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF 2

WELL/BORING ID: DANG WP 9D	DRILLING STARTED: 8-11-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-11-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST: Peter E. Remersma	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
26-36		90% SSS		^{brown} Clay, some silt, little pebbles 1/4", plastic, wet to very moist, 26-28' Silt, some brown, some silt, some clay, little pebbles, slightly gravel, little pebbles, slightly rock fragments moist, firm 28-31'	Hand readings of samples 3 ppm - maybe moisture in bag
36-41		100% SSS		Silt, brown, some sand, fine, little clay, little gravel and pebbles, slight, moist, firm Silt, brown same as above with some gravel, dry, very firm - difficult to break	Hand readings of sample 0-2 ppm
41-46		100% SSS		^{brown} Sand, fine-medium, little clay, quartz sand, small rock fragments make up the sand, wet, loose, 41-41 1/2'	
46-54				Silt, brown, same as 36-41 interval, dry, hard, some pebbles and some gravel Boulder, ^{some} gabbro, 46-48', 47 1/2' Sand and gravel, coarse, some silt layers 49 Silt layers with coarse sand, 48'-50 1/2', 47 1/2'-48 1/2' wet, 49-49 1/2', 50 Clay, some silt, 50 1/2'-51', firm, slightly moist Sand and Gravel as above 47 1/2'-49' from 50-51' Bedrock, 51 1/2'-54' 50	

TDE 54

ENGINEERING-SCIENCE DRILLING RECORD

PAGE ____ OF ____

WELL/BORING ID: DANG 8 ^{WP} 9 S	DRILLING STARTED: 8-11-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-11-88
PROJECT NO: OR001	DRILLING METHOD: Rotasonic.
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		50%		Peat, more dark brown to black, numerous plant root fragments, loose, dry	
5-15		100%		Sand and Gravel, dark grey, fine-coarse little clay, <u>wet</u> , loose 5-6'	
				Clay, some silt, ^{trace} little pebbles, very moist, becoming siltier down, 6-12 1/2'	
				Sand, some clay, some gravel, rock fragments fine-coarse, wet, 12 1/2-14 1/2'	
				Clay, some silt, some pebbles 1/4-2" 14-15', very moist	
15-21				silt, little clay, some pebbles & little gravel, slightly moist 15-18'	
				Clay, same as 14-15', 18-21'	
				TD @ 21'	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 1

WELL/BORING ID: DANG 8 ⁴⁴ / _{WP} 10 (shallow)	DRILLING STARTED: 8-6-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-6-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		100% SS1		Clay, some silt (35%), brown, scattered black organic rich areas, dry, firm, trace pebbles up to 2" diameter	Hum of sample 21 ppm Upper 6' probably fill
5-16'		100% SS2		clay, ^{brown} same as above to 6', ^{down to black} Peat, organic plant material, soft, loose, wet, little clay, trace silt, no pebbles (dep env. swamp) (bog)	Hum of sample 0 ppm
10-15		SS 3 80% compacted		Clay, dark brown, abundant plant fragments in top 1' of interval clay, dark gray to black, no plant fragments, trace silt, or natural organic odor, faint laminations to 12'	Hum of sample 0 ppm
15-20		SS4 80%	probably missing 1 1/2' of gravel coarse sand, wet	Sand, with fine to coarse, some clay, some silt, to 13', wet Gravel (13' to 14'), some sandy, fine to coarse, trace clay, wet, loose silt, (14-15'), some silt, brown, clay moist, firm silt, brown, ^{some clay} little pebbles 1/4-1/2", or moist, firm to 17 1/2' Silt, brown, some clay trace pebbles 17 1/2' to 19'; dry clay ^{19' to 20'} little silt trace pebbles & slightly moist TD @ 20'	Hum of sample 0 ppm HA 0 ppm HB 0 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 1 OF 3

WELL/BORING ID: DANG 8 WP10 D	DRILLING STARTED: 8-6-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED: 8-6-88
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
0-5		SS1 90%		Clay, brown, pebbles 1/4 to 1" diameter common (20% of core) some silt dry, probably fill material	Hum sample is 0 ppm
5-10		SS2 90%		Clay, same as above, but last 6" (9 1/2 - 10) ^{part} is woody and plant layer. May represent end of fill and old soil layer. Core becomes <u>moist</u> at 8' (change from dry)	Hum of sample is 0 ppm HA 0 ppm HB 0 ppm
10-15'		SS3		Clay , Silt, brown, some clay, rare small pebbles, very organic rich with small plant fragments, loose <u>Wet</u> from 10-14' Last 14-15' is clay, some silt, pebbles common 1/8 - 1/2" <u>damp</u> to slightly moist	
15-20		SS4		Clay, some silt, brown, pebbles common, 1/4 to 3" diameter, very firm, slightly moist clay appears to be rock flour	casing HA - Filled with water increasing HB - 0 ppm Hum of sample 2 ppm
20-22.5		SS5		Sand, brown, fine, some clay, in top 4" (20-20.3') wet, loose Silt and Clay, brown, pebbles common 1/4 - 2", very firm, slightly moist	

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 2 OF 3

WELL/BORING ID: DANG 8 WP 10 D	DRILLING STARTED: 8-6-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW L.S.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
22.5-32		100% SS6		^{brown to dark brown} Silt, some sand, fine to medium, gravel ^{little} little clay, very wet 22.5-23.3' Silt and clay, brown, little sand some pebbles, 1/4 - 5" diameter slightly moist, very firm, interval 23.3 - 27.5'	How of sample at three locations 0 ppm 2 ppm 3 ppm Cottrell moisture is on inside of core bag
27.5-32		100% SS6 SS6		clay, some silt, brown, small 1/8" rock fragments and pebbles common, very firm, slightly moist Pebbles can get up to 5" diameter	How of Sample 0.1 ppm
32-35		100% SS7		Same as above ^{angular} small rock ^{1/8" diameter} fragments and pebbles, one very angular and can be up to 5" diameter slightly moist to very dry	How of Sample 2 ppm 3 ppm
35-40.5				Silt and some clay, ^{little} some sand, fine to coarse, ^{little} gravel, angular, 60 pebbles rounded to angular, 1/4 - 2" diameter, from 35-37 moist to wet 37-40.5 ^{interval} slightly moist with trace gravel, little sand some clay	HA 0 ppm HB 0.1 ppm
40.5-45				Silt, brown, little clay, some fine- med sand and gravel, large cobbles 4" diameter at 40.5-41' and scattered in rest of core. <u>wet to moist</u> , see small, angular rock fragments common	How of sample < 1 ppm

ENGINEERING-SCIENCE DRILLING RECORD

PAGE 3 OF 3


WELL/BORING ID: DANG 8 WP 10D	DRILLING STARTED: 8-6-88
LOCATION: Duluth ANGB/Duluth, Mn.	DRILLING COMPLETED:
PROJECT NO: OR001	DRILLING METHOD:
DRILLER: North Star Drilling Co.	SAMPLING METHOD:
LOGGER:	STATIC WATER LEVEL:
GEOLOGIST:	WATER LEVEL DATE:
SIGNATURE:	WATER LEVEL DATUM:

DEPTH IN FEET BELOW LS.	SAMPLER BLOWS	PERCENT RECOVERY	LITHOLOGY	SAMPLE DESCRIPTION	WELL CONSTRUCTION
45-47.5		100%		Bedrock, gabbro upper 5' is fractured, rest is in 1 1/2' pieces TO 47.5	

Q.2.9 Notebook 8, Field Team Leader Notebook No. 2

This notebook contains notes of the Field Team Leader for work done during February, 1989. The notes are on the second ground water sampling round at Site 10 and also contain the water level measurements taken at that time. Seventeen pages were used. The first entry is 25 February 1989 and the last is 28 February 1989. The pages are signed by Jo Ann Sherwin

This page intentionally left blank.



Ben Meadows

LEVEL BOOK

101596

101596

101596

101596

101596

(218) 722 7542 Fed-X, Duluth 1.
(Mary Pat) # 1196-4207-8

RETURN TO:

Robert S. McLeod
Engineering Science
710 S. Illinois Avenue.
Suite F-103
Oak Ridge, Tennessee 37830


(615) 481-3920



The paper in this book is
made of 50% high grade rag stock with
a WATER RESISTING surface sizing.

DISTANCES FROM SIDE STAKES FOR CROSS-SECTIONING

Roadway of any Width. Side Slopes 1 1/2 to 1.
In the figure below opposite 7 under "Cut or Fill" and under 3 read 11.0, the distance out from the side stake at left. Also, opposite 11 under "Cut or Fill" and under 1 read 16.7, the distance out from the side stake at right.



Cut or Fill	Distance out from Side or Shoulder Stake																			Cut or Fill
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	
0	0.0	0.2	0.3	0.5	0.6	0.8	0.9	1.1	1.2	1.4	1.5	1.7	1.8	2.0	2.1	2.3	2.4	2.6	2.7	1.4
1	1.5	3.2	3.3	3.5	3.6	3.8	3.9	4.1	4.2	4.4	4.5	4.7	4.8	5.0	5.1	5.3	5.4	5.6	5.7	2.9
2	3.0	4.7	4.8	5.0	5.1	5.3	5.4	5.6	5.7	5.9	6.0	6.2	6.3	6.5	6.6	6.8	6.9	7.1	7.2	4.4
3	4.5	6.2	6.3	6.5	6.6	6.8	6.9	7.1	7.2	7.4	7.5	7.7	7.8	8.0	8.1	8.3	8.4	8.6	8.7	5.9
4	6.0	7.7	7.8	8.0	8.1	8.3	8.4	8.6	8.7	8.9	9.0	9.2	9.3	9.5	9.6	9.8	9.9	10.1	10.2	7.4
5	7.5	9.2	9.3	9.5	9.6	9.8	9.9	10.1	10.2	10.4	10.5	10.7	10.8	11.0	11.1	11.3	11.4	11.6	11.7	8.9
6	9.0	10.7	10.8	11.0	11.1	11.3	11.4	11.6	11.7	11.9	12.0	12.2	12.3	12.5	12.6	12.8	12.9	13.1	13.2	10.4
7	10.5	12.2	12.3	12.5	12.6	12.8	12.9	13.1	13.2	13.4	13.5	13.7	13.8	14.0	14.1	14.3	14.4	14.6	14.7	11.9
8	12.0	13.7	13.8	14.0	14.1	14.3	14.4	14.6	14.7	14.9	15.0	15.2	15.3	15.5	15.6	15.8	15.9	16.1	16.2	13.4
9	13.5	15.2	15.3	15.5	15.6	15.8	15.9	16.1	16.2	16.4	16.5	16.7	16.8	17.0	17.1	17.3	17.4	17.6	17.7	14.9
10	15.0	16.7	16.8	17.0	17.1	17.3	17.4	17.6	17.7	17.9	18.0	18.2	18.3	18.5	18.6	18.8	18.9	19.1	19.2	16.4
11	16.5	18.2	18.3	18.5	18.6	18.8	18.9	19.1	19.2	19.4	19.5	19.7	19.8	20.0	20.1	20.3	20.4	20.6	20.7	17.9
12	18.0	19.7	19.8	20.0	20.1	20.3	20.4	20.6	20.7	20.9	21.0	21.2	21.3	21.5	21.6	21.8	21.9	22.1	22.2	19.4
13	19.5	21.2	21.3	21.5	21.6	21.8	21.9	22.1	22.2	22.4	22.5	22.7	22.8	23.0	23.1	23.3	23.4	23.6	23.7	20.9
14	21.0	22.7	22.8	23.0	23.1	23.3	23.4	23.6	23.7	23.9	24.0	24.2	24.3	24.5	24.6	24.8	24.9	25.1	25.2	22.4
15	22.5	24.2	24.3	24.5	24.6	24.8	24.9	25.1	25.2	25.4	25.5	25.7	25.8	26.0	26.1	26.3	26.4	26.6	26.7	23.9
16	24.0	25.7	25.8	26.0	26.1	26.3	26.4	26.6	26.7	26.9	27.0	27.2	27.3	27.5	27.6	27.8	27.9	28.1	28.2	25.4
17	25.5	27.2	27.3	27.5	27.6	27.8	27.9	28.1	28.2	28.4	28.5	28.7	28.8	29.0	29.1	29.3	29.4	29.6	29.7	26.9
18	27.0	28.7	28.8	29.0	29.1	29.3	29.4	29.6	29.7	29.9	30.0	30.2	30.3	30.5	30.6	30.8	30.9	31.1	31.2	28.4
19	28.5	30.2	30.3	30.5	30.6	30.8	30.9	31.1	31.2	31.4	31.5	31.7	31.8	32.0	32.1	32.3	32.4	32.6	32.7	29.9
20	30.0	31.7	31.8	32.0	32.1	32.3	32.4	32.6	32.7	32.9	33.0	33.2	33.3	33.5	33.6	33.8	33.9	34.1	34.2	31.4
21	31.5	33.2	33.3	33.5	33.6	33.8	33.9	34.1	34.2	34.4	34.5	34.7	34.8	35.0	35.1	35.3	35.4	35.6	35.7	32.9
22	33.0	34.7	34.8	35.0	35.1	35.3	35.4	35.6	35.7	35.9	36.0	36.2	36.3	36.5	36.6	36.8	36.9	37.1	37.2	34.4
23	34.5	36.2	36.3	36.5	36.6	36.8	36.9	37.1	37.2	37.4	37.5	37.7	37.8	38.0	38.1	38.3	38.4	38.6	38.7	35.9
24	36.0	37.7	37.8	38.0	38.1	38.3	38.4	38.6	38.7	38.9	39.0	39.2	39.3	39.5	39.6	39.8	39.9	40.1	40.2	37.4
25	37.5	39.2	39.3	39.5	39.6	39.8	39.9	40.1	40.2	40.4	40.5	40.7	40.8	41.0	41.1	41.3	41.4	41.6	41.7	38.9
26	39.0	40.7	40.8	41.0	41.1	41.3	41.4	41.6	41.7	41.9	42.0	42.2	42.3	42.5	42.6	42.8	42.9	43.1	43.2	40.4
27	40.5	42.2	42.3	42.5	42.6	42.8	42.9	43.1	43.2	43.4	43.5	43.7	43.8	44.0	44.1	44.3	44.4	44.6	44.7	41.9
28	42.0	43.7	43.8	44.0	44.1	44.3	44.4	44.6	44.7	44.9	45.0	45.2	45.3	45.5	45.6	45.8	45.9	46.1	46.2	43.4
29	43.5	45.2	45.3	45.5	45.6	45.8	45.9	46.1	46.2	46.4	46.5	46.7	46.8	47.0	47.1	47.3	47.4	47.6	47.7	44.9
30	45.0	46.7	46.8	47.0	47.1	47.3	47.4	47.6	47.7	47.9	48.0	48.2	48.3	48.5	48.6	48.8	48.9	49.1	49.2	46.4
31	46.5	48.2	48.3	48.5	48.6	48.8	48.9	49.1	49.2	49.4	49.5	49.7	49.8	50.0	50.1	50.3	50.4	50.6	50.7	47.9
32	48.0	49.7	49.8	50.0	50.1	50.3	50.4	50.6	50.7	50.9	51.0	51.2	51.3	51.5	51.6	51.8	51.9	52.1	52.2	49.4
33	49.5	51.2	51.3	51.5	51.6	51.8	51.9	52.1	52.2	52.4	52.5	52.7	52.8	53.0	53.1	53.3	53.4	53.6	53.7	50.9
34	51.0	52.7	52.8	53.0	53.1	53.3	53.4	53.6	53.7	53.9	54.0	54.2	54.3	54.5	54.6	54.8	54.9	55.1	55.2	52.4
35	52.5	54.2	54.3	54.5	54.6	54.8	54.9	55.1	55.2	55.4	55.5	55.7	55.8	56.0	56.1	56.3	56.4	56.6	56.7	53.9
36	54.0	55.7	55.8	56.0	56.1	56.3	56.4	56.6	56.7	56.9	57.0	57.2	57.3	57.5	57.6	57.8	57.9	58.1	58.2	55.4
37	55.5	57.2	57.3	57.5	57.6	57.8	57.9	58.1	58.2	58.4	58.5	58.7	58.8	59.0	59.1	59.3	59.4	59.6	59.7	56.9
38	57.0	58.7	58.8	59.0	59.1	59.3	59.4	59.6	59.7	59.9	60.0	60.2	60.3	60.5	60.6	60.8	60.9	61.1	61.2	58.4
39	58.5	60.2	60.3	60.5	60.6	60.8	60.9	61.1	61.2	61.4	61.5	61.7	61.8	62.0	62.1	62.3	62.4	62.6	62.7	59.9
40	60.0	61.7	61.8	62.0	62.1	62.3	62.4	62.6	62.7	62.9	63.0	63.2	63.3	63.5	63.6	63.8	63.9	64.1	64.2	61.4

Pentecost Publishing Company
P.O. Box 5078 Tallahassee, FL 32314
(904) 578-4151

2: Contacts:

Maj. Joel D Manns DAV6B 218.723-7290
 Col. Don Solwold Hq. MWAAG 612-296-4673
 Sgt. Jim Morton D.ANG (CE)
 (Utilities) work control x 292
 Larry Janssen Hazwrap 615-575-A67
 Tom Sturdivant Hazwrap 615-482-6601
 Enrique Gentzsch MPCA 612-296-7823
 Elizabeth Gawrys MPCA 612-286-7821
 Ed. Grunwald HHS Mgr ES 404 325-0770
 Fire Dept. Bldg 103 218 723-7470

Emergency Contacts		3.
Base Main Gate Security	723-7280	
Fire Dept	723-7233	
Poison Control	1-800-332-3073	
Medical		
Hospital: St. Lukes Hospital of		
915 East 1st St.	Duluth	
Duluth, MN		
218 726-5551		
Base POC	Maj. Joel Manns	
	CE MN ANG	
	W 218-723-7290	
	H 218-728-2633	
Prop. Mgr.	R.S. McLeod ^{N 615} 481-3920	
	H 615-482-9385	
FAA City Key to Gate	727-2960	
	2151	

4.

08/25/89

2:00p arrived Duluth.
 Picked up bailers,
 survey meter, insulated
 gloves and other material
 that was shipped. Checked
 to see everything was
 there. Charging HNU
 meter. Will go to
 hanger to organize
 the rest of the material,
 and then to the store
 to buy a few odds
 and ends such as
 aluminum foil.
 Personnel: Jo Ann Sherman
 and Ted Volokay.
 Overcast temperature in
 upper twenties, lower 30's
 5:45 returned to hanger and

Jo Ann

Sherman 2/25/89

5.

designed the bailers and
 water level measurement
 tools. Prepared for tomorrow
 morning.

Jo Ann Sherman 2/25/89

9:	98	22/26/89			Water level	98 29/12/89	10
		break for lunch and			Location	Time	depth from
		very cold.			MS 9/1/86		check
		12:30	dear and		2-MW 41		7' 8.4"
		water level measurement tools			2-A 08		
		1:45	left hanger for GW 10-A.		2-A 08 7-GW 2A	3:35	4' 10.5"
		will take a duplicate			2-MW 42	3:45	8' 0.2"
		sample there and call it			MW 7	3:50	9' 0.55"
		GW 10-D			MW 6	only water in car as	3' 3.36"
		The sun is out so it looks			and can't	go any further.	Stick up
		warmer, but it is still very			2 1/2' cut at 11m	51m only	
		windy & very cold.			about 1' deep hole. Probably		
		Conduc	Temp		prayer at ground level		
		7.634	7.16		2-MW 39	4:05	7' 6.2"
		7.66	7.3		MW 5	4:15	6' 9.8"
		Readings are for duplicate			2-MW 28	4:25	9' 3.5"
		There are			GW 2-B	4:30	5' 8.5"
		per 10-C, samples			2-MW 37	4:40	6' 5.25"
		of water put out in our			2-MW 40		
		for 1/2 hr before reading temp.			not kind at 11m at 11		
					Column shown 2/26/89		

11					Sunny	2/27/89	not windy	12
under the pile of snow								
that the snow blower								
has blown when clearing								
the road. There was a								
flag that we dug around								
maybe 1 1/2 foot down. But								
we could not find								
evidence of this well.								
Finished about 5:00 and								
went back to the hangar								
to prepare the samples								
for shipment. Will								
ship tomorrow.								
Left hangar 6:00 p								
Can't get to wellson pad -								
snow too deep. by buoy markers								
GW 3-A								
12:00 p								
11' 11.75"								
3 MW 31								
12:10 p								
8' 9.9"								
3 MW 30								
12:20 p								
8' 9.4"								
BG MW 32								
12:30 p								
10' 0.2"								
3 MW 34								
12:40 p								
8' 3.5"								
3 MW 33								
12:43 p								
8' 2.2"								
Go down Sherwin 2/26/89								

13	14
Location	Time
GW 3-C	12:55p
GW 3-B	1:02p
3-MW 2S	1:33p
3-MW 3S	1:37p
GW 3-D	2:50p
GW 3-C	3:19p
WP 7D	3:33p
WP 7	3:46p
AW 7 MW-48	3:54p
WP 6	4:02p
1W 2	
MW 1	
GW 2E	
Cloudy	
getting cold	
Go down	

12:10th

13'2.6"

7'9.2"

4:16

4:38

GW 2-D

WP 8

Shipped samples by FedEx, decanned barrels

Took inventory, left hangar at 6:15p

This was MW 4. Mistake realized when compiling data for draft report. After we bought a shovel we went back & found this hole. A tall plow may have marked its vicinity. Go down Sherwin 5/15/89

9'1.5"

8'3.25"

10'11.25"

14'0.3"

10'12.9.75"

10'7.5"

11'8.5"

11'11"

Go down Sherwin 2/27/89

15	2/28/89				2/28/89	16
Ted Volsky, Jo Ann Sherrin						
10° cloudy, snowing lightly						
Over an inch since						
yesterday. It's supposed						
to stop later this morning						
and get colder						
location	time	depth		location	time	depth
3-MW 14	8:26a	10' 3.0"		MW 10 no. bore	12:00	7' 6.2"
3-MW 15	8:30a	10' 6.8"		4-MW 20	12:02	6' 6.75"
3-MW 16	8:45a	8' 5.25"		MW 3	12:06	8' 5.7"
3-MW 17	8:47a	8' 3.0"		108 Lunch break		
GW 3-C	9:07a	10' 2.34"		108-11147	2:25 ^{12:00} 12:00	3' 5.5"
4-WP 18D	9:16a	5' 10.9"		4-MW 21	2:48	8' 10.5"
GW 4-B	9:15a	6' 2.4"		MW 9	3:50	8' 9.5"
4-WP 11	9:40a	10' 5.6"		4-MW 22	3:05	10' 1.6"
3-WP 9D	9:46a	10' 1.4"		GW 4-D	3:10	11' 4.7"
3-WP 7	9:50	9' 14.7"		GW 4-E	3:20	11' 9.7"
				4-WP 13D	3:37	12' 4"
Jo Ann Sherrin	2/28/89			Jo Ann Sherrin	2/28/89	

17	2/23/57	18
<u>location</u>	<u>time</u>	<u>depth</u>
4-WP 13	3:45	10' 4.25"
4-MW 23	3:52	9' 6.8"
4-WP 15	4:12	10' 2.2"
4-WP 15D	4:20	10' 9.25"
GW 4-A	4:44	6' 4.5"
- Couldn't find:		
4-WP 14		
4-WP 14D	{ all under too-	
MW 11	{ much snow to	
be found.		
Sent equipment off by		
Fed. Ex. Left airport at		
5:30 p. Done for this trip.		
Go-Lan Shornum 2/28/59		